THE

INDIAN FORESTER

A MONTHLY MAGAZINE

OF

FORESTRY,

AGRICULTURE, SHIKAR & TRAVEL.

COMMITTEE OF MANAGEMENT:

F B MANSON CONSERVATOR OF FORESTS,
R McINTOSH, M A DEPUTY CONSERVATOR, AND E P STEBBING,
F L S, F E S, DEPUTY CONSERVATOR.

EDITED BY

J W OLIVER, A G. HOBART-HAMPDEN,
AND E P. STEBBING, F L S.

VOL. XXIX (1903).

Allahabad:
PRINTED AT THE PIONEER PRESS

1904

INDEX TO THE INDIAN FORESTER.

VOLUME XXIX.

1903.

A PAGE.

Afforestation in Ireland 426
Allen, D H.—Notes on Hopea odorata 498
America—Forestry in ... 323, 390, 443, 500
American Bureau of Forestry 258
Analysis of Soil in Sal Forests 213
Application of section 67 of the Forest Act... ... 114
Arbor Day—Institution of—in the Central Provinces ... 409
Arboricultural Society—Tour of the English—in the North of France, August 1902 217
Assam Manual on the powers of Forest Officers to compound offences 460
Athletic Sports at the Imperial Forest School, Dehra Dun 40

B

Bahr-el-Ghazal (Sudan)—Forest Exploration in ... 401
Bamboos—"Double-barrelled" 507
Bambusa polymorpha—Flowering of ... 244, 513
Barber, C. A.—Report on Spike Disease in Sandalwood in Coorg 21
Birbal, Forest Ranger—Ripening of Cones of Pinus longifolia 407
Board of Scientific Advice 280
Bombay—Forest Flora of—Review of 283
Botany and the Forest Officer 453
Brandis, Sir Dietrich—Treatment of the Sandal tree ... 3
    Ditto —Chloroxylon Swietenia ... 18
    Ditto —Teak in Evergreen Forest ... 187
    Ditto —Harry Charles Hill 309
    Ditto —Notes on Gelsemium elegans and the Bamboo Fungus of Burma 404
British Forestry 155
Broillard, Charles 562
Brown, Enos—A Redwood Lumber Plant 251
Bruce, C. —A peculiar type of Teak Forest 20

PAGE.

Bryant, F. Beadon—Shrinkage in Timber during flotation 455
Burma—England to—*viâ* Canada, Japan and China 257, 357
Do. —Notes on Gelsemium elegans and the Bamboo Fungus of 404
Butler, Dr. E. J.—Report on 'Spike' disease among Sandal-wood trees ... ...(Appendix Series)
Ditto —A Deodar disease in Jaunsar (Appendix Series)

C

Castilloa Elastica—Experiments on the Latex and Rubber from 123
Ceylon Forest Report for 1901 38
Channer, F. F. R —The Harcourt Working-plan ... 194
Charles Broilliard 562
Chemical Analysis of the Rubber of Wrightia tinctoria and Ficus infectoria 406
Chestnuts—Sweet—in India 190
Chettier, S. K.—Manual of Indian Timbers, letter on ... 194
Ditto Tanning extract from the heartwood of Xylia dolabriformis 408
Chir (Pinus longifolia) Twig Borer 564
Chloroxylon Swietenia 18
Cirencester—Forestry at 425
Ditto —Dr. Schlich and Forestry at 584
Commercial Side—Our neglected 241, 516
Ditto Value of Mhowra (Bassia latifolia) Seeds ... 543
Compound Offences—The Assam Manual on the Powers of Forest Officers to 460
Cooper's Hill as a Training College for the Imperial Forest Service 373, 509
Cordite Rifles in Indian Forests 460, 568
Corrigenda to Mr. Mercer's Timber Tables 517
Coventry, B. O.—Fungus destructive to Deodar ... 451
Ditto Chir (Pinus longifolia) "Twig Borer" ... 564
Coventry, E. M.—Ripening of Cones of Pinus longifolia 276, 572
Craddock, W. H.—Waterfalls of the Southern Shan States 471

D

Damage to Babul Trees by Fomes pappianus ... 216
Ditto Teak by drought in the Panch Mahals ... 263
Dead Elephant 249
Death of Mr. R. H. B. M. Dobrée, Assistant Conservator of Forests 340
Deodar—Fungus destructive to 451
Dickinson, Mr. F. B.—Obituary 577
Different Species of Indian Silver Fir 21
Dobrée, Mr. R. H. B. M.—Obituary 340

PAGE.

Double-barrelled Bamboos 507
Dr. Schlich, F.R.S., and Forestry at Cirencester ... 584
Dunstan, Wyndham R.—Quarterly Report on the Imperial Institute 31
Dyer, Sir W. T. Thiselton—Grass for Paper Manufacture 245
Ditto —Botany and the Forest Officer 453

E

Editorials—
  The late Mr. H. C. Hill 1
  The American Bureau of Forestry 258
  Cooper's Hill as a Training College for the Imperial Forest Service 373
  The Training of Forest Officers 495
Effect of Leaf Covering on Soils 238
Do. of Forest Fires on Insect Pests 75
Elephant—A Dead 249
England to Burma *via* Canada, Japan and China 287, 357
Eucalypts for Fuel 584
Evergreen Forest—Teak in 187
Experiments on the Latex of Castilloa Elastica ... 123

F

Fauna of British India 471
Fellings—Improvement—in Deodar and Blue Pine Forests 337
Fernandez, E. E.—Damage to Babul Trees by Fomes pappianus 246
Ditto —The Treatment of Hardwickia binata, 517
Fibres—Rubbers and 475
Finn, F.—Indian Pheasants and their Allies, 116,205,293,415,531
Fires—Forest 93
Fire Protection in the Teak Forests of Lower Burma ... 554
Fischer, C. E. C.—Our neglected Commercial Side ... 516
Ditto Wild Beasts and Magic 576
Fisher, W. R.—Sweet Chestnuts in India 190
Fliche, Mons.—Retirement of 254
Flowering of Bambusa polymorpha ... 244 513
Fomes pappianus—Damage to Babul Trees by ... 246
Forest Act—Application of section 67 of the— ... 114
Forest Administration Reports—Reviews on—
  Hyderabad Assigned Districts, 1900-01 33
  Bengal, 1900-01 35
  Ceylon, 1901 38
  Nizam's Dominions 40
  British India, 1900-01 81
  Punjab, 1901-02 195
  N.-W. Frontier Province, 1901-02 201

PAGE.

Forest Administration Reports—Reviews on—
  Burma, 1901-02 202
  Andamans, 1901-02 352
  Madras, 1901-02 355
  Baluchistan, 1901-02 411
  United Provinces and Oudh, 1901-02 463
  Coorg, 1901-02 467
  Assam, 1901-02 527
Forest Department—Indian—Recollections of the early days of, 1858—1864 312
Forest Destruction by Insects in Norway .. 129, 191
  Do. Exploration in the Bahr-el-Ghazal (Sudan) ... 401
  Do. Fires 93
  Do. Indian—Insect World in an—and how to study it ... 6, 57, 99, 141, 178, 229, 266, 334
  Do. Flora of Bombay, 2nd Edition 283
  Do. Flora of New South Wales 285
  Do. Officer—Botany and the 453
  Do. Officer—Training of 437, 495
  Do. Questions—On certain important ... 487, 566
  Do. Reserve—Notes from an American 320
  Do. School—Athletic Sports at 40
  Do. School—Prize Day at 365
Forester—Lumberman and the 538
Forestry 306
  Do. at Cirencester 425
  Do. British 155
  Do. in America 323, 390, 144, 500
  Do. in Sarawak 583
  Do. —President Roosevelt on 301
  Do. —Proposed School of—for Wales 584
  Do. —The Home Timber Trade and ... 473,535,578
  Do. The Institution of Civil Engineers on ... 89
  Do. Transvaal 253
Forests—Indian 421
  Do. Kheri Trans-Sarda (United Provinces) 379
  Do. Madras—What should they yield ... 440,549
  Do. of India and their Management 368
  Do. Working of State—in Russia 482
French, Mr. H.D.D.—Obituary 461
Fuel—Eucalypts and 584
Fungus destructive to Deodar 451
  Do. Notes 211

G

Gamble, J. S.—Grass for Paper Manufacture... ... 189
  On certain important Forest Questions ... 487
Garonne—Navigability of the 148

PAGE.

Gazettes ... ... i to xcvi.
Gleadow, F.—Progress in the United States 69
Do. Forest fires 93
Do. The Harcourt Working-plan. Translation by 111
Do. The Application of section 67 of the Forest Act. 114
Do. The Unity of Sylviculture 135
Do. Navigability of the Garonne 148
Government of India on the Madras Forest Administration Report of 1901-02 462
Grass for paper manufacture 80, 189, 245, 279

H

Harcourt Working-plan 111, 194
Hardwickia binata—Treatment of 517
Harry Charles Hill 309
Hart, G. S.—Shrinkage in Timber during flotation ... 456
Hemle, N —Jaunsar Working-plan 575
Hill, Mr H C.—The late 1
Hill, Harry Charles 309
Home Timber Trade and Forestry ... 473, 535, 578
Hopea odorata—Note on 498

I

Imperial Institute—Quarterly Report on 31
Improvement Fellings in Deodar and Blue Pine Forests ... 337
India—Fauna of British—Hymenoptera Aculeata, Vol. II, 471
Do. Forests of—and their Management 368
Indian Forests 421
Do. Museum Notes, Vol. V., No. 3 286
Do. Pheasants and their Allies 116, 205, 293, 415, 531
Insect Pests—Effect of Forest fires on 75
Insects—Forest Destruction by—in Norway ... 129—191
Insect World in an Indian Forest (continued from page 431, Vol. XXVIII, No. 12)—6, 57, 99, 141, 178, 229, 266, 334
Institution of "Arbor Day" in the Central Provinces ... 409
Do. of Civil Engineers on Forestry 89
Ireland—Afforestation in 426

J

Japanese Wood Pulp Trade 584
Jarrah Sleepers 584
Do. Wood—Australian—Resistance of to fire ... 425
Jaunsar Working-plan 575

PAGE.

K

Kashmir—Large Trees in 152
Kheri Division, Oudh—Notes on a Tour through ... 159
Do. Trans-Sarda Forests (United Provinces) ... 379
Kongu (Hopea)—Note on—in the Tinnevelly District ... 429

L

Lac in Guzerat and the Konkan 153
Large Trees in Kashmir 152
Leete, F. A.—The Kheri Trans-Sarda Forests (United Provinces) 379
Ditto Mercer's Tables showing cubic contents of logs 517
Lumberman and the Forester 538
Lumber Plant—A Redwood 251
Lushington, A. W.—Treatment of the Sandal Tree ... 113
Ditto Unusual development in leaves of Soymida febrifuga 340
Lushington, P. M.—Percentage of Essential Oil in Sandalwood 19
Note on Kongu (Hopea) in the Tinnevelly District ... 429

M

Madras Forest Administration Report of 1901-02—Resolution of Government of India on 462
Magic—Wild Beasts and 576
Manson, F. B.—The Institution of Civil Engineers on Forestry 89
Manual of Indian Timbers 150, 194
McDonell, J. C.—Ripening of Cones of Pinus longifolia ... 573
Mercer, L.—On certain important Forest Questions ... 566
Mills—Paper—in British India 482
Monophlebus Scale Insect in the Kheri Sal Forests ... 277
Monro, F. V.—Improvement Fellings in Deodar and Blue Pine Forests 337
Muriel, C. E.—Forest Exploration in the Bahr-el-Ghazal (Sudan) 401
Ditto "Double-barrelled" Bamboos 507

N

Navigability of the Garonne 148
New South Wales—Forest Flora of—Review of ... 285
Note from the Myodwin Teak Plantation 458
Notes from an American Forest Reserve 320
Do. on a Tour through the Kheri Division, Oudh ... 159
Do. on Gelsemium elegans and the Bamboo Fungus of Burma 404

PAGE.

Notes on Indian Trees—
    I.—Notes on Kongu (Hopea) in the Tinnevelly District, Madras 420
    II.—Notes on Hope odorata 498
Notes on the Forest Nursery and Plantations in the Panch Mahals 505
Notice to Subscribers 257
Nursery and Plantations in the Panch Mahals—Notes on the 505

O

Obituary—
    H. C. Hill, Inspector-General of Forests ... 1
    R. H. B. M. Dobrée, Assistant Conservator of Forests 340
    H. D D. French, Officiating Conservator of Forests ... 461
    F. B. Dickinson 577
On certain important Forest Questions .. 487, 566
Our Neglected Commercial Side 241, 516
Our Specialist-in-Chief on "Spike" 423

P

Paper Manufacture—Grass for 80, 189, 245, 279
Paper Mills in British India 482
Pearson, Col G F.—Recollections of the early days of the Indian Forest Department, 1858—1864 312
Pearson, R. S.—The Training of Forest Officers ... 437
    Ditto Damage to teak by drought in the Panch Mahals of the Bombay Presidency ... 263
    Ditto Notes on the Forest Nursery and Plantations in the Panch Mahals ... 505
Peculiar Type of Teak Forest 20
Percentage of Essential Oil in Sandalwood 19
Pests and Blights of the Tea Plant 413
Pheasants—Indian—and their Allies 116,205,293,415.531
Pinus longifolia—Ripening of Cones of ... 276,407,572
Preservation, Seasoning and Strengthening of Timber ... 580
President Roosevelt on Forestry 301
Prize Day at the Imperial Forest School, Dehra Dun ... 365
Professor Bailey on the want of a State Forest ... 128
Progress in the United States 69
Proposed School of Forestry for Wales ... 584

R

Radcliffe, E.—The different species of Silver Fir ... 21
    Ditto Susceptibility of Silver Fir to damage from fire 339
Rao, M. Rama—Root Parasitism of the Sandal Tree ... 386

PAGE.

Rapid Ageing and Fireproofing of Wood 41
Recollections of the early days of the Indian Forest Department, 1858 to 1864 312
Redwood Lumber Plant 251
Relations of Forestry to Zoology 582
Report on "Spike" disease among Sandalwood trees in Mysore and Hunsur Taluks 340
Report on "Spike" disease in Sandalwood Trees in Coorg... 21
Resistance of the Australian Jarrah wood to fire ... 425
Retirement of M. Fliche 254
Rifles—Cordite—in the Indian Forests ... 460,568
Ripening of Cones of Pinus longifolia ... 276,407,572
Rogers, C. Gilbert—Cooper's Hill as a Training College for the Imperial Forest Service 509
Root-parasitism of the Sandal Tree 386
Rubber of Wrightia tinctoria and Ficus infectoria—Chemical analysis of 406
Rubbers and Fibres 475
Ryan, G. M.—Lac in Guzerat and the Konkan ... 153
Ditto Commercial value of Mhowra (Bassia latifolia) Seeds 543

S

Sal Forests—Analysis of Soils in 213
Sandal Tree—Root parasitism of the 386
Do Treatment of the 3, 113
Do. Spike in 300
Sandalwood—Percentage of Essential Oil in 19
Sandalwood trees—Report on "Spike" disease in—in Coorg, 21
Sandalwood trees—Report on "Spike" disease among—in Mysore and Hunsur Taluks 340
Sarawak—Forestry in 583
Schinn, Charles Howard—Notes from an American Forest Reserve 320
Scientific Advice—Board of 280
Seeds—Commercial value of Mhowra (Bassia latifolia) ... 543
Shan States—Southern—Waterfalls of the 471
Shrinkage in Timber during Flotation ... 338,455
Silver Fir—Susceptibility of—to fire 339
Silver Fir—The different species of Indian 21
Sleepers—Jarrah 584
Soils—Effect of leaf covering on 238
Soymida febrifuga—Unusual development in leaves of ... 340
Spike in Sandal trees 300
Spike—Our Specialist-in-Chief on 423
State Forest—Prof. Bailey on the want of a 128

PAGE.

Stebbing, E. P., Insect World in an Indian Forest and how to study it ... 6,57,99,141,178,229,266,334
Ditto Effect of Forest Fires on Insect Pests... ... 75
Ditto Forest Destruction by Insects in Norway ... 191
Ditto The Monophlebus Scale Insect in the Kheri Sal Forests 277
Ditto A Note on the Sandalwood boring Insects of Madras (Appendix Series)
Ditto A Note on the Casuarina Insect Pests of Madras, (Appendix Series)
Ditto A Note on the Preservation of Bamboos from the attack of the Bamboo beetle or "Shot-borer," ... (Appendix Series)
Susceptibility of the Silver Fir (Abies Webbiana) to damage from fire 339
Subscribers—Notices to 257,543
Sweet Chestnuts in India 190
Sylviculture—Unity of 135

T

Tables, Mercer's, showing cubic contents of logs—Corrigenda to 517
Tanning Extract from the heartwood of Xylia dolabriformis 408
Tea Plant—Pests and Blight of (Review) ... 413
Teak—Damage to—by drought in the Panch Mahals of the Bombay Presidency 263
Teak Forest—A peculiar type of 20
Teak Forests of Lower Burma—Fire-protection in ... 554
Teak in Evergreen Forest 187
Teak Plantations—A note from the Myodwin .. 458
Thompson, G. W., Grass for Paper manufacture ... 80,245
Ditto Chemical Analysis of the Rubber of Wrightia tinctoria and Ficus infectoria 406
Timbers—Manual of Indian—Review of 150
Timber—Preservation, seasoning and strengthening of ... 580
Timber—Shrinkage in—during flotation ... 338,455
Tour of the English Aboricultural Society in the North of France 217
Trade Circulars 54,91,130,157,214,255, 307,369,427,483,541,585
Training of Forest 437,495
Training College—Cooper's Hill as—for the Imperial Forest Service 373,509
Transvaal Forestry 252
Treatment of Hardwick's binata 517
Treatment of the Sandal tree 3,113

PAGE.

Trees, Indian—Notes on I.—Kongu 429
II.—Hopea odorata 498
Tulloch, J. C.—Shrinkage in Timber during flotation ... 338
Twig-borer—Chir (Pinus longifolia) 564

U

United States—Progress in the 69
Unity of Sylviculture 135
Unusual development in leaves of Soymida febrifuga ... 340

W

Walker, H. C.—Fire protection in the Teak Forests of Lower Burma ... 554
Waterfalls of the Southern Shan States 471
Watson, H. W. A—A Dead Elephant ... 249
What should the Madras Forests yield ... 440, 549
Wild Beasts and Magic 576
Working of State Forests in Russia 482
Working-plan—Jaunsar 575
Working-plan—The Harcourt 111, 194
Wood Pulp Trade—Japanese 584
Wood—Rapid Ageing and Fireproofing of 41

X

Xylia dolabriformis—Tanning extract from the heartwood of 408

Z

Zoology—Relations of Forestry to 582

APPENDIX SERIES.

Report on 'Spike' disease among Sandalwood Trees, by Dr. E. J. Butler, M.B., F.L.S., Cryptogamic Botanist to the Government of India.

A Note on the Sandalwood boring Insects of Madras, by E. P. Stebbing, F.L.S., F.E.S., Officiating Superintendent, India Museum.

A Note on the Casuarina Insect Pests of Madras, by E. P. Stebbing, F.L.S., F.E.S.

A Deodar Disease in Jaunsar, by Dr. E. J. Butler, M.B., F.L.S.

A Note on the Preservation of Bamboos from the attacks of the Bamboo beetle or "Shot-borer," by E. P. Stebbing, F.L.S., F.E.S.

THE
INDIAN FORESTER.

Vol. XXIX.] January, 1903. [No. 1.

The Late Mr. H. C. Hill.

IT is with extreme regret that we record the death on November 7th, after only a few days' illness, of Mr. Harry Charles Hill, Inspector-General of Forests to the Government of India.

Mr Hill left India in April last on nine months' leave, and when the news of his death was telegraphed, letters written as late as the 31st October, apparently in the best of health and spirits, had just been received from him announcing his intended return to India at the close of the present month.

By his untimely death the Forest Department has been deprived of a Head whose high professional attainments, great administrative capacity, energetic temperament and very wide experience it could ill afford to lose; while many of us mourn the loss of a warm personal friend. He was the embodiment of a Forest Officer who combines and maintains to the end an undiminished enthusiasm for his work with a keen love of sport.

Mr. Hill, who was born in 1852, was selected for the Indian Forest Service in 1869, and received his professional training at Nancy. He joined in Oudh in December 1872, and after a short period of service in that province, was attached for two years to the Forest Survey Department. He was then transferred to Burma, where he became Conservator of Forests of the Tenasserim Circle in 1881. In 1883 he was transferred to the charge of the Pegu Circle, and in 1885 to Lahore as Conservator of Forests of the Punjab. This post he held till 1887, when on the annexation of Upper Burma he was appointed to the forest charge of that province, being at the same time *ex officio* Secretary to the Chief Commissioner of Burma in the Forest Department of Upper Burma. In 1889 he officiated as Inspector-General of Forests, and on return from furlough in 1893 became Conservator of the Central Circle of the North-West Provinces. In 1895 he again officiated as Inspector-General. In 1898 he returned to Burma as Conservator of the Western Circle, and in the following year was appointed Conservator of the School Circle and Director of the Imperial Forest School, which post he shortly afterwards vacated in order to act as Inspector-General of Forests. In 1899 he was deputed for six months to the Straits Settlements to advise the Administration in regard to forest matters in that colony, and on return to India he succeeded Mr. Ribbentrop as Inspector-General of Forests in 1900. While on leave some years ago Mr. Hill prepared for H. M.'s Commissioners of Woods, Working Plans for the Forest of Dean and the High Meadow Woods,—plans according to which these forests have since been managed.

The *Gazette of India* of the 12th December contains the following notification:—

"The Governor-General in Council has received with much regret the intelligence of the death in England, on 7th November, of Mr. Harry Charles Hill, Inspector-General of Forests.

"Mr. Hill entered the Forest Department in December 1872, as Assistant Conservator, and after officiating on several occasions as Inspector-General of Forests, was finally confirmed in that important post in November 19 0. Much of his earlier service was spent in Burma, where the arduous task fell to him of organizing and developing an efficient system of forestadministration in the Upper Provinces after their annexation. As Inspector-General, his wide experience of Indian Forestry was of great value to the Government of India.

Mr. Hill's premature death removes one who worthily filled a responsible office, and the Governor-General in Council desires to place on record his sense of the loss which the public service has sustained."

Treatment of the Sandal Tree.

BY SIR DIETRICH BRANDIS, K.C.I.E., F.R.S.

MR. BARBER'S paper on the sandal tree in the *Indian Forester* of September last has interested me. That this tree is a root parasite was established in 1871 by the late John Scott, then Curator of the Royal Botanical Garden, Calcutta, in a most important paper on *Loranthaceæ* and other parasites. (Journal of the Agricultural and Horticultural Society, Calcutta, Vol. II, p. 287). This paper has not received the attention in England which it deserved. Mr. Barber himself apparently had not seen it when he wrote In other countries, however, it has been fully appreciated. Count Solms Laubach, who in 1867 had published his researches on *Thesium* and *Osyris*, both root parasites of the Order *Santalaceæ*,* gave in the *Botanische Zeitung* for 1874 (pp. 128 and 144) a full account of Scott's paper, including a translation of that portion which relates to *Santalum*. The microscopic examination by Count Solms Laubach of Sandal haustoria sent him by Mr. Scott, whereby its roots attach themselves to the roots of other plants, showed a structure in all essential points identical with that of the haustoria of *Thesium*. In Engler und Prantl Naturliche Pflanzenfamilien (*Santalaceæ*) III 1. 204, and in the article on *Santalum album* of Kohler's Medizinalpflanzen (Vol. III) a detailed review of Scott's researches will be found. In 1872 and 1873, when I was working at Kew on the Forest Flora of North-West and Central India, Scott's paper of 1871 was not known to me, and the reviews mentioned above appeared much later.

It will interest the readers of this paper, that Charles Darwin had a very high opinion of John Scott's scientific work, while he was a gardener at the Edinburgh Botanical Gardens, before going out to India. (Letter to Asa Gray, December 1861, in *Life and Letters of Charles Darwin*, III, 300.)

Scott established the root connection between *Santalum album* and species of *Saccharum*, *Bambusa*, as well as a number of palms. To palms he paid special attention, because he had noticed sandal trees growing with unusual vigour in the vicinity of *Arenga*. Among Dicotyledons he examined the root connection with two species of *Heptapleurum* and *Inga dulcis*.

In regard to *Heptapleurum*, the following extract from Mr. Scott's paper is worth quoting here:—

"With the *Araliaceæ* I had most demonstrative evidence: *firstly* in a vigorous old tree of sandalwood growing in the vicinity of a large specimen of *Heptapleurum umbraculiferum*, which I had occasion to cut out. A few months after this I was surprised to find the tree nearly destitute of leaves and altogether in a most unhealthy state, though for some time, after the ivy wort had been removed, no changes had been observed. This, however, was probably due to the strong vitality of the ivy wort's roots, which may have remained fresh for weeks after the stems had been cut out. The tree has since made poor and weak growths, though always yielding an abundance of flowers; and now—the fourth year—it seems to be acquiring fresh vigour, probably from having formed new root attachments. The *second* case was of a young tree, 15 feet in height, and growing from the midst of a bush of *Heptapleurum venulosum*. The latter having been cut out, the young sandalwood tree shortly after lost the whole of its foliage and was for fully two years afterwards in a most unhealthy state."

---

* [illegible] Graf zu Solms Laubach, [illegible] Phanerogamen, in Pringsheim Jahrbucher für wissenschaftliche Botanik VI. 509.

If I correctly understand Mr. Barber, he has established the root connection of *Santalum* with *Casuarina* and *Lantana*. Hence it is evident that the sandal tree lives and thrives while its roots are in intimate connection with the roots of many other plants belonging to different orders and having different structure and organization. Foresters in Mysore and Coorg have long known by actual experience, that the tree thrives well when growing in company with *Casuarina* and *Lantana*. But they have also known that it flourishes when growing in hedges and among shrubs where no *Casuarina* or *Lantana* is near.

The sandal tree most probably takes up a large proportion of those mineral substances which it requires, not directly from the soil, but through its haustoria from the roots of those plants with which it lives. It is well known that plants do not take up indiscriminately all substances which are offered to their roots in a soluble state, they have the power of selecting those substances which suit them best. The majority of trees and shrubs, for instance, leave soda salts alone and take up instead potassium salts from the soil. The coffee bush takes up a large proportion of magnesia, the bamboos take up enormous quantities of silica, and tobacco extracts lithium from soil, in which this element is present in the most minute quantities. Doubtless, therefore, there are only certain species which are capable of furnishing those mineral salts which sandalwood requires. But we have seen that these species are very numerous, and that they belong to a large number of different natural families.

It is also probable that the sandal is not wholly dependent upon its companions for the supply of the mineral salts it requires. Some root parasites, I believe, are entirely without these fine hairs on the last ramifications of the roots which, by attaching themselves firmly to the minute particles of the soil, with the aid in many cases of acids secreted by them, take up mineral substances from the soil. It will be important to ascertain whether *Santalum album* has effective root hairs or not, for on this fact depends the question, to what extent the tree has to rely upon its companions for part of its nourishment.

Mr. Barber's communication is, I trust, the forerunner of important publications regarding this subject. He is familiar with the methods of anatomical and physiological research, and though the fact of the root union of the sandal tree with numerous species has been established beyond doubt, many questions remain to be solved. On the present occasion I would mention two questions of great practical importance: *First*, has the tree effective root hairs, and is it capable of taking up directly from the soil a portion of the food it requires? *Second* which species are the most useful companions of the sandalwood?

Readers of this paper will doubtless be struck by the fact that *Casuarina equisetifolia* is not a native of the Western Peninsula, and that *Santalum album* only made the acquaintance of its present useful companion about 30 or 40 years ago. The experience of the plantations near Bangalore show, I understand, that the union with this species is most beneficial to the sandal tree. On the Nilgiris in 1882, chiefly near Coonoor, the woods of *Acacia melanoxylon* were attacked on a large scale by Indian species of *Loranthus*, whose acquaintance the Australian *Acacia* had not previously made. In this case however the *Loranthus* did serious injury to the *Acacia*,—it killed many trees I believe.

In the plantations near Bangalore, Mr Pigot informs me that the *Casuarina* trees all die off together, when aged about 25 years, and that fears are entertained for the sandal after the loss of its companion. An underwood of *Lantana* might be tried, but apparently it is feared that it may prove a dangerous friend, that it may outgrow the sandal and smother it. There would not, however I suppose, be any difficulty if matters are methodically managed, in periodically cutting back the *Lantana* and thus compelling it to grow as underwood under the sandal trees.

If my memory does not fail me, *Cassia auriculata (Tangedu)* is frequently found associated with sandal in Mysore and Coorg. If so, experiments should be made to sow the two together. This species of *Cassia* is a valuable plant, hence I mention it. Also the seed of other shrubs or trees found in places where sandalwood grows should be sown with it experimentally. Foresters in Mysore, Coorg and adjoining districts of the Madras and Bombay Presidencies will know how to make these experiments. One point is important,—such experiments must be under uninterrupted control by a competent and intelligent Forester. Hence they must be made in a garden or in a forest nursery. Provided these experiments are continued steadily with system and method, they will show in a few years which companions suit the sandalwood best, and then I fully anticipate that the progress of sandal plantations will be steady and satisfactory. Misfortunes, such as the spike disease, will always happen, but the spruce and pine forests of Germany continue to flourish in spite of the ravages of the *Nun* and of *Gastropacha Pini*.

Like the oak, the larch and other trees, which require much light, the sandal thrives best when the ground is covered by a dense underwood, and the fact of its being a root parasite makes such underwood a necessity. But it must have room to develop a crown, and that crown must be exposed to the light. These facts, I believe, are now universally acknowledged, and if they are steadily borne in mind by those who have to cultivate this important tree, the result doubtless will be favourable

By self-sown seedlings the sandal tree propagates itself so readily that all the present trouble might have been avoided if a sufficient area of sandalwood bearing tracts had been set aside as Reserved Forest and had been efficiently protected against fire and grazing. Many years ago, I well remember, this plan was strongly advocated by the Government of India. However, as far as I know, no action except on a very small scale was taken in this direction by the local authorities. Under these circumstances there is no help for it, sandalwood must now be raised by sowing and planting on a large scale.

The Insect World in an Indian Forest.

By E. P. Stebbing, F.L.S., F.E.S.

(*Continued from Vol. XXVIII, p.* (431.)

Part III.

Order III.—*HYMENOPTERA.*

In the adult insect there are four membranous wings present, which have no scales upon them, are usually transparent and never very large, the hinder pair being smaller than the front ones; the cells formed by the nervures in the wing are irregular in size and form and never very numerous (less than twenty on the front, than fifteen on the hind wing). Mandibles are conspicuous even when the other parts of the mouth form a proboscis or sucking tube. The females are furnished at the extremity of the body with either a saw, sting, or ovipositor; these parts may be either withdrawn into the body or may be permanently protruded. Metamorphosis is complete. In the pupal stage the parts of the perfect insect are seen nearly free, each covered with a very delicate skin.

The Order *Hymenoptera* includes the wood-wasps, saw-flies and gall-flies; the numerous tribes of the Ichneumon flies and Chalcid flies and the ants, bees, and wasps. It is a large Order, in which a very large number of species remain to be discovered and described, and this is especially the case in India. In the adult insect the head is short and broad and deeply constricted off from the prothorax and never sunk into it; sometimes it is attached to this latter by a stalk-like process. The mandibles are powerful biting organs and the proboscis is at times of some length, it being used for sucking up sweet liquids into the mouth. The prothorax is but feebly developed, the dorsal portion being separated from the ventral half, the former being firmly fused to the mesothorax, whilst the lower portion (with the first pair of legs) is movable. Meso- and meta-thorax are usually immovably united, but in the saw-flies and wood-wasps they are freely movable. The legs have large coxæ and the trochanter is often divided into two joints (in the *Tenthredinidæ*, *Uroceridæ*, *Cynipidæ* and *Ichneumonidæ*); the tarsus is five-jointed, the first joint being longer than the following ones. The upper and lower wings are connected by a row of small hooks which fix on to the stout curved edge of the front wing, the two wings on one side thus acting as one piece. In all but the *Tenthredinidæ* and *Uroceridæ* there is a deep constriction between what appears to be the thorax and the body.* The abdomen is thus said to be *stalked*. The eggs when being laid pass through the hollow stabbing or boring apparatus at the end of the body of the female, in many cases a prick or cut being made in an animal or plant with this instrument for the reception of the egg. This apparatus may also serve as a sting (*e.g.* in the wasp). The grubs are usually white in colour and blind; only in the *Tenthredinidæ* and the *Uroceridæ* do they resemble the caterpillars of the *Lepidoptera* (butterflies and moths). The larvæ often form cocoons to pupate in. One of the most remarkable facts connected with this Order is the prevalence of parthenogenesis (or the production of young by the female without the concurrence of the male) in a considerable number of widely separated species. In some members of the Order it is believed that the reproduction is entirely parthenogenetic. In the gall making *Cynipidæ* parthenogenesis is frequently accompanied by alternation of generations, a generation consisting of two sexes being followed by another consisting entirely of females, which in its turn gives rise to a bi-sexual generation.

This Order consists of two very distinct Sub-orders dependant upon the manner in which the abdomen is joined on to the thorax, *viz* :—

I.—*Hymenoptera Sessiliventres.*—Insects with the abdomen broad at the base, its first segment not completely joined to the thorax.

II.—*Hymenoptera Petiolata.*—The abdomen connected with what appears to be the thorax by the slender joint forming a marked constriction between the apparent thorax and the abdomen.

I.—HYMENOPTERA SESSILIVENTRES.

The abdomen is not stalked but is nearly continuous in outline with the thorax. Trochanters are divided into two portions.

---

* This constriction really occurs in the first abdominal segment and not in the thorax. This first abdominal segment is firmly fixed to the thorax, and the constriction occurs between it and the second segment of the body.

The saws or boring apparatus at the end of the body of the female are concealed or only just visible. The larva has three pairs of thoracic legs and often numerous abdominal ones. The food is vegetable, some species feeding in galls on plants, others in the interior of twigs, whilst others again bore into and live in the hard wood of trees and shrubs The majority, however, live upon the leaves of plants. Those which live in wood resemble coleopterous larvæ in appearance, whilst the species living and feeding upon leaves resemble the leaf eating lepidopterous caterpillars.

FAMILY CEPHIDÆ (THE STEM SAW-FLIES).

Slender insects with a weak integument and slender antennæ. The female bears a saw at the end of her body. The larvæ live in the stems of plants or in the tender shoots of trees and shrubs.

Little is known about these insects in India. One, however,—an unknown species—has been found boring into the bases of the young new needles of the deodar in the spring. The needles develop on the branches in small rosettes, and if these be examined when attacked by this minute insect, they will be seen to have swollen up at their bases in such a manner that the needles coalesce at the bottom A closer examination shows that the swelling is convex on the outside, concave on the inner one, and in this small concave elliptical depression a tiny orange grub will be found. This is the larva of this small cephid. The irritation set up by its feeding operations causes the swelling at the base of the needle, and from four to six weeks are spent in this stage of its existence. The pupal stage is a short one. and about the middle of June or beginning of July the tiny brilliant metallic blue flies issue. The length of this insect is $\frac{1}{16}$th of an inch only. The attacked rosettes turn yellow and die, and occasionally a considerable amount of defoliation is accomplished in this manner on young saplings.

FAMILY SIRICIDÆ OR UROCERIDÆ (WOOD-WASPS).

Large insects of bright conspicuous colours; the female is provided at the extremity of the body with an elongate, cylindrical, boring instrument. Antennæ are filiform and elongate; the abdomen has eight dorsal plates, and the tibia of the front leg is provided with a spur; the anal lobe of the posterior wing is large. The larvæ live in wood, in which they gnaw long winding passages; they are blind yellowish-white grubs, with three pairs of short thoracic legs, but have no abdominal legs.

Until the present year our Indian Forest *Siricidæ* were unknown. The life-history of a *Sirex* sp., a magnificent insect not unlike the well-known and oft-quoted *Sirex gigas* of Europe, has been recently discovered and partially worked out by the writer and will be described shortly here.*

---

* *For a fuller account see 'Departmental Notes on Insects that affect Forestry,'* No. 2, p. 151, and plate VII.

Sirex sp. is a large handsome insect, the general colouring of the male being a deep metallic blue, green, and rich chestnut, the wings having a coppery sheen on them. The female is a deep metallic green on its upper surface. The grub is stout, thick, canary yellow in colour and about 1½ inches in length. The pupa is unenclosed in any cocoon, being pale yellow in colour.

The female lays her eggs in the wood of dead spruce (*Picea Morinda*, Link in the North-west Himalayas, drilling holes into the tree by means of the auger and drilling apparatus at the end of her body. The larvæ on hatching out bore winding galleries in the wood, these galleries having no apparent definite direction. The grubs evidently spend more than a year thus boring in wood, larvæ of various sizes being obtainable at any time. The larval tunnels are tightly packed with the wood sawdust passed through the body of the boring insects. When full fed the larvæ change to pupæ at the end of their tunnels with no special preparation, and the pupa is thus found lying naked at the end of the boring, the only free space unblocked with wood refuse in which is that occupied by it. The larvæ pupate about June, and fully developed imagos emerge in July. When ready to leave the tree the mature sirex bores its way out by a circular boring, an eighth of an inch in diameter, drilled in the wood by means of its powerful mandibles, and it invariably chooses the shortest route to the outside, the gallery having, however, usually a slight upward direction.*

This insect is capable of doing the most serious injury to timber, as the winding galleries of the larva and the exit holes of the mature insect riddle the wood and make it useless for anything save firewood. Further study of the habits of this insect may show that it attacks other coniferous trees.

Two, if not three, as yet undescribed and unnamed species of the wood-boring *Xyphidriides* which belong to this family have also been recently found boring into spruce in a manner very similar to that pertainable to the sirex. They are not unlike the latter, but can be recognised by having an exserted head, the latter being separated from the thorax by a well-marked neck. They are also smaller.

FAMILY TENTHREDINIDÆ (SAW-FLIES).

This is an important family, but little is known about its members in India and practically nothing about their habits. The perfect insects have a superficial resemblance to a large blue bottle fly, but can be distinguished by having the four wings instead of two; there are no spurs on the front tibiæ of the legs. The larvæ are very like caterpillars, having three pairs of thoracic legs and six to eight pairs of abdominal ones; in this they differ from lepidopterous caterpillars, which never have more than five pairs of abdominal legs. Saw-fly larvæ feed exposed on the leaves of plants in the same way as caterpillars, or they may live in galls, etc.

---

* *Vide* a note on the habits of the larvæ and adults of *Sirex* and *Thalessa* by the author in *Nature* of August 21st, 1902.

I have said that the life-histories of these insects have been very little studied in India until recently, but one or two crop-feeding forms being known. Within the last year, however, three species, as yet unnamed, have been found feeding upon coniferous trees in the North-west Himalayan forests. Of these one infests the deodar, a second the spruce, and the third the silver fir. Observations made on their habits show that they all feed upon the spring crop of needles of these trees, pupating some time in July. The larvæ are bright green in colour and about an inch or a little over in length. When feeding they take up a very characteristic position, which greatly aids in their recognition, for they coil the lower end of the body round the leaf upon which they are feeding. When full grown they change to pupæ within small light brown elliptical cocoons, the covering of which is of parchment-like consistency, which they attach to a needle. In the case of the silver fir saw-fly the larva pupates at the beginning of July, the mature fly issuing about the middle of the month. These coniferous saw-flies require careful study, as it is not improbable that they will play a not unimportant rôle in the forest as their management becomes more intense.

Almost every year a plague of green saw-flies make their appearance on rose bushes in the Dehra gardens and strip many bushes of their leaves. The cocoon formed is attached to the plant by a fairly long silken cord.

II.—HYMENOPTERA PETIOLATA.

The hind body is connected with the thorax by means of a deep constriction, so that there appears to be a stalk between it and the thorax. This stalk may be long or short, but is always resent. This sub-order is divided into three series—

1. PARASITICA OR TEREBRANTIA, including the families *Cynipidæ*, *Chalcidæ*, *Ichneumonidæ*, and *Braconidæ*.
2. TUBULIFERA—comprising the *Chrysididæ*.
3. ACULEATA—including the families *Apidæ*, *Diploptera*, *Fossoria* and *Formicidæ*.

SERIES I.—*Parasitica* or *Terebrantia*.

The trochanters (the second joint of the leg) are of two pieces, and the female is furnished with an ovipositor at the extremity of her body.

FAMILY CYNIPIDÆ (GALL-FLIES).

Small insects in which the abdomen is short and compressed, with an ovipositor arising from the ventral surface. The wings have only a few cells in them and have no stigma (a black patch) on the anterior margins of the upper wings. The antennæ are straight and are composed of a few (12—15) joints. The larvæ live in galls, either singly or several together. The female bores into the living portions of plants (stems, leaves, buds) by means of the spine at the end of the abdomen, and deposits an egg in the hole thus made; later on the plant tissue swells up in different ways owing to the irritation set up by the larva feeding upon the tissues. The different forms of gall thus arising are characteristic of different species of insect. In many species a regular alternation of a parthenogenetic and a true sexual generation exists, the two generations being dissimilar and causing galls of very different appearance.

Little is known about the life-histories of gall-flies in India, and the study of this interesting family greatly needs some energetic workers.

FAMILY CHALCIDIDÆ (CHALCID FLIES).

These differ from the last family in having elbowed antennæ consisting of from seven to thirteen joints The wings are without a system of cells in them. The insects are frequently of brilliant colour, and remarkable form. They are mostly parasitic upon caterpillars, and have been reared from several forest defoliating caterpillars in India, and probably tend to keep these pests in check to some extent. Undetermined species of this family have recently been found parasitic upon the larvæ of *Polygraphus*, *Pityogenes*, and *Scolytus* bark boring beetles in Blue Pine and Deodar trees, and as our knowledge of these insects increases, it will doubtless be found that they are as beneficial in the forest as they are in agriculture.

FAMILY ICHNEUMONIDÆ (ICHNEUMON FLIES).

The ichneumons are insects with a long slender body and many-jointed antennæ. The wings have a well-developed series of nervures and cells in them. The female has usually a long protruding ovipositor. These insects are parasitic in their larval stages. The egg is deposited by the mother in the body of the caterpillar. The larva on hatching out is a little white legless grub, which feeds upon the fatty tissues of his host, the latter eventually dying of exhaustion, though it may have sufficient strength to turn into a pupa first. When full-fed the ichneumon spins itself up into a cocoon, which may be attached to the body of the dead caterpillar or may be free inside the pupal case of the host. It often happens that two or three eggs are laid upon the caterpillar by the ichneumon fly and then several cocoons are obtained from the dead caterpillar or from the pupa into which it has changed.

This family thus performs a very important service in the forest by keeping down defoliating larvæ and wood boring pests and in fact insect pests of all kinds. At the same time it is also injurious to some extent owing to the fact that it also lays its eggs and kills off useful predaceous and parasitic insects.

The members of the genera *Rhyssa* and *Thalessa* are among the most remarkable of the Ichneumon flies. These insects have ovipositors of three to four inches in length, and are parasitic upon species of the family *Siricidæ* which, as above described, live in solid wood. The following is a note on a portion of the life-history[*] of an undetermined species of *Rhyssa* or *Thalessa* which is parasitic upon the *Sirex* sp. already described as infesting spruce in the North-western Himalayas. The mature insect appears on the wing about the beginning of June. The female is a fairly large handsome insect, black with yellow spots upon the thorax and a pink spot on either side of each segment of the body. The insect is one inch in length with an ovipositor of one and-a-half inches. Dead mature insects have been found in some numbers in spruce riddled by the *Sirex* sp, the tunnels in which the ichneumons were found communicating with the sirex larval ones in such a manner as to leave no doubt that the former was parasitic upon the latter. The larval and pupal stages of the ichneumon have not yet been found. There can be little doubt that this parasite is of the greatest service in keeping down the numbers of the sirex. It appears to itself suffer when the wood wasp larva has gone very deep into the wood, as the perfect ichneumon fly has then apparently not sufficient strength to bore its way out of the tree, and dies in the wood after having gone a certain distance.[†]

FAMILY BRACONIDÆ (BRACON FLIES).

These insects are very similar to the ichneumons. The antennæ consist of many (nearly always more than 15) joints, and the wings have a moderate number of cells in them. They can be distinguished from the ichneumons by the fact that the hind body has a much less degree of mobility of its segments and the upper wings differ, the series of cells running *across* the wing being only three in the Ichneumonides, whereas they are four in the Braconids, and a centre cell behind 2 and 3 is divided transversely into two in the former, but is undivided in the latter. If these distinguishing characters are remembered the two families can always be distinguished from one another.

---

[*] *Vide* a note on 'The habits of the larvæ and adults of *Sirex* and *Thalessa*' by the author in *Nature* of August 21st, 1902.

[†] For a fuller account see' Departmental Notes on Insects which affect Forestry' No. 2, p. 155, and plate VII, fig. 2.

The habits of this family are similar to the last, it being believed that they are nearly all parasites. Usually they attack larvæ, but they are bred in great numbers from pupæ and occasionally from imagos of other insects. The family requires careful study in India, where its members are probably of the very greatest service both in the forest and in the field. The writer has recently bred out bracon flies from two scolytid bark-boring pests—*Scolytus major*, M. S. and *S. minor*, M. S.—which infest deodar trees in the North-west Himalayas. The flies appear to lay their eggs in or on the larvæ of the scolytus.

SERIES 2.—*Hymenoptera Tubulifera.*

Trochanters undivided; the hind body consisting of from three to five visible segments; the female with an ovipositor, which is usually retracted and envelopes a fine pointed style. The larvæ usually live in the cells of other *Hymenoptera.* This is a small group in comparison with *Parasitica* and *Aculeata* and is not of importance here. One family is recognised.

FAMILY CHRYSIDIDÆ (RUBY WASPS).

Insects usually of glowing metallic colours, with a very hard, coarsely-sculptured integument; antennæ are abruptly elbowed. The abdomen is of peculiar construction and allows the insect to roll itself up into a ball.

SERIES 3.—*Hymenoptera Aculeata.*

Trochanters undivided; abdomen consisting of six or seven visible segments; female has a retractite sting. The bees, ants and wasps are included here.

FAMILY APIDÆ (BEES).

Usually very hairy insects, with elbowed antennæ; the parts of the mouth are elongated to form a protrusible proboscis; the tibiæ and tarsi of the hind legs are usually broad.

Some bees are social, *i.e.*, they form colonies of males, females, and winged workers, which are barren females. Other bees are solitary. In the social bees there is usually only a single fertile female in each nest, and when a new one is hatched the colony divides to form a new swarm. The bees build combs of wax arranged perpendicularly, consisting of layers of hexagonal horizontally-placed cells, closed at one end. The larvæ occupy some of these cells, whilst others are occupied by the workers or used as storage cells for honey and pollen. The queen or fertile female lives in a special large cell. The honey is carried by the bees to the comb in the crop, whilst the pollen is kneaded up and carried in a depression in the tibia of the leg, which is surrounded by hairs and called the basket; this basket only occurs in the workers.

In India there are several common colonial bees. *Apis dorsata*, the big bee which builds large nests consisting of a single comb, either suspended to the under side of the branches of lofty trees or placed amongst rocks (this is the bee present at the Marble Rocks near Jubbulpore). It can be recognized by its size and elongated body. Its sting in the hot weather is very poisonous, even causing death when inflicted in numbers. *Apis indica*, a smaller bee which forms smaller nests in hollow trees, holes in walls, etc., and the small bee, *Apis florea*, which is about the size of a small house fly, and builds a single comb in the open upon branches of trees, etc., its honey being peculiarly sweet though small in amount. The wax and honey of *Apis dorsata* is sold in Indian bazars, as is also that of *A. indica* to a smaller extent. In parts of the country a certain amount of forest revenue is derived from this source. Besides the various species of *Apis* there are several species of *Trigona*, a group of small stingless bees which build in old walls, the nest being formed chiefly of chewed resin.

The *Bumble-bee* is closely related to the common bees; it lives in small colonies in nests in holes in the ground; each colony is founded by one large female, which lives through the winter.

The females of many *Solitary bees* hollow out small cavities in the earth or in wood or build cells of mud, pieces of leaves, etc. In these cells they store pollen or honey and lay one egg in each and then close up the cell. The larvæ on hatching out feed upon the store of food thus provided. Amongst solitary bees the commonest forms in India are the mason bees, *Megachile*, and the carpenter bee, *Xylocopa*. The mason bees build cells of leaf or mud, and are to be seen at work in verandahs, out-houses, etc., in dry weather in many parts of India. They store the cells with honey or pollen and deposit an egg in each cell and carefully close it up, leaving the larva to develop by itself. The *Xylocopa* contain some of the largest and most powerful of the bees. They are often black or blue-black in colour, and several of them bore into dry timber, and for this reason are called 'carpenter' bees. An Indian species bores into and riddles timber, such as beams and rafters of houses, tea-factories, etc., forming cells in the wood. Serious consequences occasionally follow the attacks of the *Xylocopa*, and a case came to the writer's notice where the roof of a large tea-factory in the Duars had to be entirely replaced owing to the damage done to it by carpenter bees.

FAMILY DIPLOPTERA (VESPIDÆ)—(WASPS).

The wasps have a simple trochanter and angled antennæ, reniform eyes and long projecting mandibles; the body is stalked and the insects are provided with a sting; the most distinguishing feature is to be found in the wings, which are plicate, *i.e.*, folded longitudinally down the middle when the insect is at rest.

Some of the wasps are solitary, others—amongst them the genus *Vespa*, which contains the paper-wasps and hornets—are social and live in colonies consisting of males, females, and workers (the latter being barren females furnished with wings), and they build ingeniously constructed nests, consisting of a paper-like substance composed of chewed wood or bark. These nests consist of one or more horizontal combs, each composed of a number of prismatic hexagonal cells open at their lower ends. These contain the larvæ, which thus hang head downwards. The whole nest may be surrounded by a firm or loose covering. The larvæ are fed upon chewed insects The whole population of the nest dies in the late autumn, with the exception of the young fertilised females. These survive the cold weather months and found a new colony in the spring, the completion of which is accomplished later by the workers which the female brings up. The adults feed chiefly upon sugary matter and fruit.

The commonest Indian wasps are *Polistes hebræus*—a small yellow wasp with long legs, common in verandahs—*Vespa affinis* and *Vespa velutina*—which build large nests in the forest—and *Vespa magnifica*—a large insect building in hollow trees and possessing a powerful sting.

Solitary wasps form cells in branches of trees in a similar manner to the solitary bees, and stock them with living insects or spiders, which they sting and paralyse. Having stocked the cell the female then lays an egg on the helpless inmate, closes up the cell and then dies. On hatching out the larva feeds upon the stock of living and fresh material thus provided for it by the female. A common one in parts of India may be seen stocking its mud cells with a green caterpillar.

FAMILY FOSSORIA—(SAND WASPS).

Smooth-bodied insects, often with long legs and very like wasps, from which they are distinguished by having their antennæ curled and not elbowed. The front wings are not longitudinally folded. In habits they resemble solitary wasps, constructing either cells of clay or burrows in the ground or tunnels in the wood and stems of plants. In these they place the paralysed insects, laying an egg in each.

Others again, the *Scoliidæ*, which are hairy insects, frequently of large size, form no special receptacles for their young. They are parasitic, and lay their egs in the larvæ of other insects, which they first sting and paralyse in the position in which they find them in their homes. These wasps are therefore to some extent beneficial.

FAMILY FORMICIDÆ (ANTS).

The antennæ are elbowed and the ants can be distinguished from other *Hymenoptera* by the fact that they have a constriction in the stalk which joins the abdomen to the thorax. The trochanters are undivided. The individuals of each species are usually of three kinds :—males, females, and workers ; the latter have no wings, but the males and females are usually winged, though the females soon lose their flying organs. They live in communities of various numbers, the majority being workers. The larvæ are helpless maggots, fed and tendered by the workers or by the female. The pupæ are enclosed in silken cocoons, these being the so-called ant's eggs, which may be seen in fine weather exposed on the top of the nest to the warmth of the sun's rays.

Ants build nests which consist of passages and chambers dug out in earth and rotten wood, stumps of trees, etc., or they build in leaves which they fasten together. The burrowing ones generally pile up the earth they dig out in hillocks above the surface level.

The two most important sub-families of the ants are the *Formicides*, which have only one knot in their peduncle, the abdomen being not usually furnished with a sting, and the the *Myrmicides*, with two well-marked knots in the peduncle, the abdomen being usually furnished with a sting. The large yellow bamboo ants *Œcophylla smaragdina*, Fabr., with yellow workers and green males and females—which builds nests in trees by joining the leaves together, and is plentiful in many parts of India, and the large black ant—*Camponotus*—which constructs its nests in the ground and is a common example of the *Formicides* *Camponotus* attacks other ants, and is to be found in attendance upon *Aphidæ* and *Coccidæ*. One of them has been found sucking the sugary secretion emitted by the Dun sal *Monophlebus* Scale. Amongst the *Myrmicides* may be noticed a large fierce ant, *Sima rufo-nigra*, called the sepoy ant in Madras from its colouration, with a red thorax and black head and body. It makes its nest in dead wood, and is often found in old longicorn borings in sandalwood trees in Coimbatore and Mysore. Its sting is very painful. The common red ant of the plains of India, *Solenopsis gemminatus*, which lives in large colonies in nests in the ground, under stones, etc. It constructs partially covered ways across roads and is often to be seen carrying off dead insects. It has been reported as attacking potatoes and may be found to do damage in nurseries ; a largish ant with reddish head and dark abdomen called *Holcomyrmex scabriceps*, Mayr., which is a granary ant and builds its nests in the ground and stores up grass and other seeds. Quite large heaps of grain are collected by these insects, which they may feed upon or simply allow to ferment and then feed upon the sugar contained in the fermenting :

Some ants are in the habit of keeping Aphidæ (plant lice) in their nests, which they use much as we use cows, sucking up the sugary secretions they emit.

USEFUL HYMENOPTERA.

The *Hymenoptera* contain several families of useful insects which tend to keep injurious insect pests, both in the forest and field, in check. It must, however, be borne in mind that the good is in some cases almost counterbalanced by the fact that the same families contain insects which are parasitic upon, and therefore keep in check, our useful insect friends. In spite of this, however, in the case of serious increases in the number of an insect pest, such as a plague of caterpillars, man is often deeply indebted to his hymenopterous allies. In this respect the *Chalcidæ* without doubt contain numbers of insects of great use, and their further study will well repay the trouble expended on it. Undetermined species have been already found attacking bark-borers, such as the Blue Pine *Polygraphus*, *Pityogenes*, and the deodar *Scolytus* beetles, and this is but a commencement in the great field ready for exploration. The next family of use to man are the *Ichneumonidæ* or ichneumon flies, which are *par excellence* a parasitic group, and more especially attack the caterpillars of *Lepidoptera*. Numerous wild silkworms are subject to these attacks, and amongst forest defoliating caterpillars kept in check by them may be mentioned *Lymantria* (several species), *Dasychira*, *Acronycta*, *Hyblæa puera*, etc. Future observations will add many more to the list. The family are of use also in keeping the wood-boring grubs, both coleopterous and hymenopterous, in check, the genera *Rhyssa* and *Thalessa* being of particular importance in this respect. A species of one of these genera is parasitic upon the Indian spruce sirex. The *Braconidæ* or supplementary ichneumon flies as they are sometimes called, resemble in habits the *Ichneumonidæ*, and they are of interest in the forest, since already species have been found parasitic on the larvæ of the *Scolytus* deodar bark-borers, and researches will probably show that there are many other similar cases.

The *Apidæ* must be classed amongst the useful *Hymenoptera*, not on account of any predatory habits, but owing to the fact that they furnish man with certain products, such as honey and wax, which add to his food and comfort. There is yet another and important part played by this family in Nature. Bees undoubtedly help largely in the distribution of pollen, and therefore in the fertilization of the flowers of trees and shrubs, and consequently in the continuance of vegetable growth. It is not improbable that the family is of great service to the forester in this way.

The *Diploptera* (wasps) and the *Fossoria* (saw-wasps) both paralyse and lay their eggs in caterpillars and other insects, and therefore are of some use in keeping down pests. The sand-wasps also attack grasshoppers, probably several times their own bulk, and lay their eggs in them.

Little is known about the *Scoliidæ* in India, but in Madagascar a species lays its eggs in the rhinoceros beetle (*Oryctes*) which attacks palms. It may be found that a species infests and keeps in check the *Oryctes* in India when it is a serious pest at times.

Amongst the *Formicidæ* present available information does not show that they are of much use. The bamboo ant, *Œcophylla smaragdina*, feeds largely upon caterpillars, and so is possibly of some use in keeping down defoliating pests.

Taken as a whole, the order may be looked upon as one of considerable use to man.

II.—CORRESPONDENCE.

Chloroxylon Swietenia.

Flindersia, a tropical Australian genus of trees and shrubs, with one species in New Caledonia and one on Ceram Island, and *Chloroxylon* (monotypic) are classed under *Rutaceæ* (sub-order *Flindersioideæ*) by Engler in Engler u. Prantl Naturliche Pflanzenfamilien, III. 4. 111, 170. Doubtless there are strong arguments in favour of this arrangement As Mr. Lushington points out in his late communication on *Chloroxylon*, the leaves have pellucid glands and are aromatic, not bitter. Further, the stamens are free; a character which Kanjilal, in his most useful key to the Natural Orders, properly uses to separate *Rutaceæ* and other Orders from *Meliaceæ*; they are connate only in two species of *Atalantia* and more or less connate in *Citrus*, while they are free, among Indian *Meliaceæ*, only in *Walsura robusta* and *Cedrela*.

On the other hand, there are many points of resemblance between *Cedrela* and *Chloroxylon*, and there is this important fact, that *Flindersia*, which undoubtedly is closely allied to *Chloroxylon*, has a cup-shaped disc, enclosing the ovary, similar to what we find in most Meliaceous genera.

Chloroxylon is one of the numerous instances which illustrate the imperfections of our present arrangement of phanerogamous plants. Our Natural Orders must be regarded as a makeshift only. A non-natural system of species and genera might be built up, not by using length and breadth of the sheet on which we write, but by employing the three dimensions of space. Such a system of phanerogamous plants would resemble a huge building in which *Chloroxylon* would occupy a corner, surrounded on all sides, as well as above and below, by allied genera.

When *Indian Trees* sees the light, which I hope will be some time next year, my young friends in India will see that in some important cases I have been compelled to adopt an arrangement different from that of the *Genera Plantarum* and the *Flora of British India.* In the case of *Chloroxylon* I did not think such a deviation from the English standard works necessary, but only added a remark pointing out the strong argument for the arrangement adopted by Engler.

I congratulate Mr. Lushington that, evidently without knowing Engler's work, he has arrived at the same conclusion as this distinguished botanist.

D. Brandis.

Percentage of Essential Oil in Sandalwood.

In my notes on the sandal tree, which were published in the 'Stray Leaves' of the *Indian Forester* in 190[illegible], I stated that, in my opinion, the richness of the wood in oil was dependent rather on the elevation and exposure than on the soil.

I had then found sandal growing freely in a tank bed in the Erode Taluq at an elevation of about 700 feet. I found no trace of heartwood either in the stem or roots, and a billet, when subjected to an analysis, did not contain even a trace of essential oil.

I have now had an opportunity of examining the growth in the Tinnevelly district, where the tree is noticeable in two localities. At Courtallum the tree is fairly abundant between an elevation of 700 and 900 feet. In this locality no big trees are found. In the Alagarkovil valley of the Srivilliputtur forests the tree is to be found growing freely at an elevation of 900—1500 feet with a fair percentage of big trees. In order to test the quality of the wood grown at this low elevation, I had twelve trees, which were grown between 900 and 1200 feet, cut and cleared. From them I obtained 5mds. 14lbs. of scented wood. The wood was of a light yellowish brown and very deficient in scent. The wood sold at a rate of Rs. 3-12 per maund, which was a far better price than I expected to realise. Three of the billets, selected haphazard, were subjected to analysis and yielded respectively 0·24, 0·54, 0·46 per cent. of essential oil.

In 1896 whilst at North Coimbatore I had two billets, grown at what I consider the most favourable elevation, viz., 2500 to 3500 feet, analysed. One gave 1·94 and the other 2·44 per cent. of essential oil.

There seems, therefore, to be a regular gradation in the richness of the wood dependent on the elevation, and it would be interesting if this could be put to the test in a district which is really rich in sandal.

At the same time there seems to be a limit reached at about 3500 feet, though in North Coimbatore, at Osahatti and elsewhere, sandalwood is growing well at higher elevations. I believe that some fellings have been recently undertaken in Coimbatore at these higher altitudes, and it would be interesting if the results were published giving the quality of the wood obtained and its richness in oil.

PALAMCOTTAH :
11*th November* 1902.

P. M LUSHINGTON,
Deputy Conservator of Forests.

A Peculiar Type of Teak Forest.

I SEND an extract from my diary, as someone may be able to answer the question as to how this peculiar kind of teak forest came to be formed, as so far I am still at a loss to explain it.

"Girdled 63 trees to-day; the teak forest in this creek (the Kugyi) is of peculiar formation known locally as 'waiks.' These waiks are islands of teak always far apart in the moist jungle bordering the creek.

"The moist jungle is never more than a few hundred yards broad, then gives place to hills covered with Engdaing.



c = creek E = Engdaing. M = Moist forest, evergreen.



//// Teak |||| moist.(Evergreen Forest) E═══Engdaing.

"The maps, section and plan will explain what I mean. The trees are of gigantic size, as it is useless in my opinion having a tree of 13 feet girth and over. Seedlings are totally unrepresented, and saplings none or very scarce. Same may be said for second and third class trees. It is astonishing to me how the teak originally got here and only in these 'waiks.' Why not all along the moist forest? as I have seen similar forest in the Chindwin, only the teak there was not in spots like here, *i.e.*, the Nampanan creek, Sanda Reserve."

I should note that these "waiks" usually contain trees mainly of the same size, as subsequently I came on to "waiks" of teak containing hundreds of thousands of saplings (these waiks are well known and have names): it is true these were near villages, and all the old trees had been cut out, but in the waiks of gigantic trees only now and then a stump would be found showing where some extra-fine giant had been extracted, long ago, to make a boat hull.

C. BRUCE,

Mogok. *Deputy Conservator of Forests, Ruby Mines District.*

The occurrence of a different type of forest in the valley to that on the neighbouring hills is, we expect, due to geological conditions, the beds of laterite which generally accompany "Engdaing" having probably been eroded in the valley.

The 'waiks' of teak have long been a puzzle: perhaps they are the remains of an older type of forest, which is being gradually encroached on by the evergreen type —HON. ED.

The different Species of Indian Silver Fir.

IN the September number of the *Indian Forester* Mr. Upendranath Kanjilal writes on the first line of page 335:—"where Silver Fir in both its forms predominates". I believe that there is some doubt as to whether there are two different kinds of Silver Fir or not. Mr. Kanjilal has evidently studied the question, and more people besides myself interested in forestry would like to know if this point has been settled.

BARAMULLA, KASHMIR:
November 8th, 1902.

E. RADCLIFFE.

III.-OFFICIAL PAPERS AND INTELLIGENCE.

Report on Spike Disease in Sandalwood Trees in Coorg.

No. 541, dated 24th July 1902.

From—C A. BARBER., Esq, M.A., F.L.S., Government, Botanist, Madras,

To.—The Secretary, Board of Revenue, Madras.

I HAVE the honour to forward the following report upon the "spike" disease in the Coorg sandalwood trees.

2. As will be known to you, I was only able to spend a short time on the spot, and although this would frequently be amply sufficient to determine the cause of a plant disease, there are a

number of points in the present case which have not been elucidated. The result of my studies has been to trace the disease to the roots, but the exact cause of this diseased condition has not been determined. A number interesting facts have been collected regarding the life-history of the sandalwood, and these should put any future observer in a better position to clear up the mystery, especially if he has a laboratory equipped for cryptogamic work.

3. The disease seems to be of recent origin. It so happens that, from the appearance of the branches, it is possible to tell whether a dead tree has died of "spike," and as only the dead trees are collected for the sandalwood of commerce, it is probable that the disease, if of long standing, would have been noticed before. However that may be, the first reference to it is, I believe, the detailed report of Mr. McCarthy, the present Deputy Conservator of Forests in Coorg. To all appearance "spike" has only made itself felt during the last four of five years, and during that time has swept the sandalwood trees from whole tracts, especially where, from artificial planting or other causes, the trees are near together.

A.Progs. (Working Plans) June 1900, Nos. 9-12.

4. The steady progress from plant to plant, the complete destruction of all plants, excepting very young ones, in attacked areas, and the frequent immunity of isolated trees seem to point most decisively to the presence of a definite communicable disease, and not to peculiar phase of growth due to conditions of weather or soil. From certain facts it would appear to be contagious, whereas in some cases it is difficult to see how the affected trees could have touched each other. The determination as to whether the disease is contagious or infectious would add a good deal to the ease with which it could be diagnosed and prevented.

5. Upon my arrival at Fraserpet, the spot selected for my study of the disease, a very careful analysis was first made of the external above-ground characters of the affected trees. The following is the description published by Mr. McCarthy :—"The new shoots and leaves of a tree, instead of presenting the graceful appearance natural to the species, begin to grow out stiff and straight: the leaves also stand up stiff and erect like bristles, and as their arrangement is opposite and alternate, the shoot looks like a spike with four lines of erect leaves growing down it, something like a chimney brush. There is no discernible change in the new axis, except that it grows out stiff and straight. As regards the leaves, in the first place the distance between the alternate pairs is greatly decreased, then the petiole and blade are tip to tip in one straight line, and lastly the blade is shorter, narrower and more pointed. However, there is no sign of spot or sickness in the leaf substance. As the disease progresses, the new leaves become still smaller, narrower, more pointed and fewer each

successive year; until the new shoots present the appearance of fine spikes bearing 4 rows of fine bristles. After this the tree rapidly dies off."

6 This is an excellent and accurate description. But as the best description in words are not always easy to understand, I have appended a series of photographs and poisoned herbarium specimens which may be consulted as well.

7. I shall first describe the appearances in old and young trees recently attacked by "spike," and, after that, a young or old tree in the last stage of the disease. The first photograph represents an old, luxuriant tree, only recently attacked. It appears extremely healthy and full of foliage, but a close inspection shows that many of the branches are peculiarly formed. The latter have a feathery appearance, the leaves are smaller, narrower and more pointed; they are closely arranged on the branches, and there are no flowers. These are the spiked branches. It is to be noted that such a tree is not uniformly attacked all over. Certain branches, frequently widely separated, are seen to be completely spiked, while the neighbouring ones are normal. In fortunate cases it is possible to detect the commencement of the disease in a branch. Parts of it are spiked and barren: others normal and flowering (see herbarium specimen No. 3). In such branches it is generally possible to detect cases of phyllody, the inflorescence giving place to a tuft of leafy shoots and the flowers often being deformed, some or all of the sepals, petals, stamens or pistils being changed to small green leaves.

8. There appears to be no necessary connection between the parts of the tree which shows "spike." Healthy trees are occasionally met with in which there is no appearance of the disease other than a tuft of small leaves at the ends of one of the branches Sometimes too small branchlets, at different points, simultaneously develope the small, crowded leaves—just as in witches' brooms—while at other times—and this is the case in the tree photographed—one-half of the tree is more or less spiked, while the other half produces flowers and fruits as usual.

9. There are certain points in which a young tree just attacked differs from the old, well-grown tree just described. It is less usual for the individual branches to show such marked differences among themselves. The lower leaves of a branch are normal, while the upper ones show the appearance of "spike" and phyllody. Thus you may frequently find a young tree, the whole of whose branches have normal, large leaves below, with small spiked tufts at the ends (see photograph No. 4). The period during which the whole tree becomes involved is probably far shorter in these cases, and a young plantation, where "spike" has entered, becomes rapidly destroyed and shows in the clearest manner the various stages of the disease.

10. From all accounts the progress of the disease is very rapid, and the transition from a luxuriant tree, with many healthy leaves upon it, to the case of advanced disease about to be described may be merely a matter of months; but exact observations are wanting on this point.

11. The following are the characters of a young or old tree where the disease is well developed and in an advanced stage. At a distance the tree appears to be dead and leafless, or perhaps better, it appears to be pronouncedly deciduous, reminding one strongly of an English tree in winter A nearer inspection shows that there are many leaves scattered over the tree at the ends of the stiff branches, but they are very small indeed and form little brush-like terminal tufts. The branches are, however, full of sap. The leaves are very different from the normal, healthy ones, exhibiting in an exaggerated manner the form of those on the feathery branches already described. A student confronted for the first time with healthy and diseased sandal trees would at once pronounce them to be different species.

12. A marked character of all the diseased plants which I have examined is the absence of any external appearance suggesting the presence of any parasite, animal or vegetable. It is true that, at first sight, the idea of witches' brooms suggests itself. "But there are many respects in which the present disease differs from these, especially in the fact that the whole tree is surely, though perhaps slowly, affected, and that the abnormal appearances are not confined to single branches. There is also the most perfect regularity in the leaf formation, and there are no deformities anywhere to be seen.

13. The absence of flowers was the first point to be investigated. The occurrence of phyllody is one of the most puzzling parts of the disease. This peculiarity is frequently due to excess of nutrition, whereas any injury to the roots most generally results in a great development of flowers and fruits. But the phyllody in this case is not accompanied by increased luxuriance. The leaves, on the other hand, become successively smaller, until the leaf surface is insignificant as compared with that of healthy plants. The causes which induced phyllody in garden plants cannot therefore be considered here. It is more probable that in this case, as will be seen directly, the excessive and rapid formation of leaves points to an attempt on the part of the plant to cure itself of a grave disease.

14. There appears to be no absolute rule as to the period at which the sandalwood flowers. But, when it does, it is usual for each branch to end in an inflorescence, and, further, for each of the latter to end in a terminal flower. It is obvious that when a flower bud is formed at the end of a branch, no further growth would possibly take place until another vegetative shoot could

replace it, and this does not, I think, usually take place until the flower has developed and formed its fruit. There is thus a considerable resting period, at any rate from leaf formation, in the normal life-history of the tree. Supposing through some reason the formation of flowers were to be prevented, this resting time would not be available, and leaf after leaf would be formed in rapid succession. It might well be that, just as in the case of a temperate plant deprived of its winter's rest by being introduced into the tropics, excessive leaf formation might result in ultimate exhaustion. And the sign of this exhaustion would be seen in the decreasing size of the leaves.

15. It is well known, however, that phyllody is also caused by the attacks of various parasites. Different fungi attacking the tissues of a plant, cause the flowering branches to develope into leafy, barren ones. In fact a case has been noted of this, occurring in a Thesium, one of the sandalwood's nearest allies, and like it, a root parasite. A microscopic examination was therefore made of the vegetative shoots and their young tissues in spiked plants. There was no evidence at all of any attack, nor was any foreign body found in the cells.

16. But this examination brought one significant fact to light All the tissues of the diseased branches, even to the smallest twigs, were found to be loaded with starch. Since the main function of the leaves in a plant, as far as nutrition goes, is the formation of starch, it appeared that they were, in this case, doing their work excellently. In healthy branches of small size, however, there was no starch at all. As fast as it is formed this substance is hurried away to be used up in the processes of growth. There was then evidently a sign of stagnation in the diseased plants. For growth, besides the starch formed in the leaves, a plant has need of other substances—salts and water—which are contributed by the roots. In the diseased plants growth had ceased to a large extent, and they were dying with their tissues loaded with undigested food. This fact pointed very distinctly to the roots as the place where trouble might be sought. A certain amount of water and salts is always present in the stem and roots and leaves, and, supposing further supplies of these substances were cut off, this limited quantity would be sufficient to keep things going for a time. This would account for the formation of the leaves in spiked trees, and would also account for their being smaller and smaller until the final death of the tree.

17. Certain other facts may be mentioned in this place as tending to confirm the impression that the roots were diseased. Mr. McCarthy has noted that all the branches of a tree which show "spike" usually do so in the same stage. The disease appears to be one which attacks the plant as a whole, and, although it may not succeed in overcoming the whole tree at once, we do not meet with branches of early and late stages. They

are merely spiked or not; if healthy, then normally so; and if spiked, they are all spiked to the same degree.

18. Another fact of interest is that rootsuckers, or shoots sent up from injured roots, are almost always spiked in trees suffering from the disease. I have, indeed, met with a tree which appeared perfectly healthy, and yet every rootsucker was spiked and formed such a marked contrast to the stem branches that they would have been unhesitatingly assigned to different species of plants had it not been possible to trace the connection between the two.

19 Although I had not the opportunity in the time to make a thorough study of the way in which the disease had spread over the country, the observation of a series of spiked trees, their relative position and the various stages of the disease gave one the impression that the attack was progressive, but whether by contagion or infection could not be determined Taking a set of diseased trees which were selected for careful study, it was found that, while they were all dead or in advanced stages at one end, those at the other were healthy or showed signs of recent attack. Further observations are called for on this point, and an accurate account of the progress of the disease in certain isolated and well marked areas would throw much light on the best way to fight the evil. In the series of specimens referred to above, the direction in which the disease had spread was along the banks of the Kauvery. where countless roots were exposed by the fall of the sandy banks.

20. The examination of the above-ground parts, and the collection of specimens for microscopic work, had taken up so much time that only two days remained for the roots. All the facts noted above were not observed at one time, and it was only the chance discovery of the abundant starch in the tissues of the young shoots which definitely pointed to the roots as the diseased organs. The leaves were doing their work of starch formation; what were the roots about? The collar was examined in several trees, but it showed no disease which might account for the cutting off of supplies. The main roots were living and apparently healthy. It was only after long search that it was discovered that there was something seriously wrong with the root-ends.

21. The root system of the sandalwood is very peculiar and does not seem to have received the amount of attention that it ought to have done. As compared with other trees around, this is the part of the plant which is most characteristic, and attention should therefore have been concentrated upon it in the numerous plantations. It is averred in text-books that the tree, like Thesium and others of its class, is a root parasite, that it attaches its roots to those of other plants and sucks their juices for its own growth. But the pronouncements of the various forest officers

who have written upon the subject are vague in the extreme. Most appear to be doubtful, while some boldly affirm that the sandalwood is not a parasite any longer, having lost the power which it formerly possessed. This is an extremely erroneous statement. The smallest examination proves that the roots of the sandalwood are inextricably united with those of other plants, and that the plant is a greedy and constant parasite. It is moreover to be noted that the development of root-hairs, by which a plant becomes intimately connected with the smallest particles of soil and absorbs water and salts from them, are almost entirely absent in those that I have examined, and it becomes a question as to how far the sandalwood roots are able to act like other roots in the procuring of their food. Upon contact with the root of another plant the sandalwood root forms a small swelling or cushion at the touching point. From the centre of this is produced a sucking organ, and the juices of its host are used for its own purposes I consider it probable, from my own observations, that the sandalwood roots at any rate in Casuarina or Lantana plantations, do very little true root-work on their own account, and are dependent almost altogether on their hosts for their supplies of water and salts.

22. An examination of the roots of spiked trees shows that their sucking organs, or "haustoria" as they are technically termed, are absent or dead. It is a matter of some difficulty to follow the roots to their termination without breaking them. For two whole days my staff were carefully dissecting the earth away and laying bare the root systems of spiked and healthy trees, with the invariable results that all the root ends of the spiked trees wear dead and rotten. That there is a root disease present, then, I have no manner of doubt. As regards the exact cause I have not had the means of judging. It seems to me that this is a suitable piece of work for the Cryptogamic Botanist to the Government of India.

23. Bearing these facts in mind, the following is what appears to happen in spiked trees, although I cannot profess that all the phenomena are explained. An injury occurs to the roots and their ends die: the supplies of salts and water are thus cut off from the plant. This does not take place all at once, for there are a great number of root-ends to be affected, and there is also a certain quantity of salts and water stored up in the stem and main roots: the shortage in the supply of the salts needful for seed-formation accounts for the cessation of flowering: fresh roots are needed and fresh leaves are called upon, at an unseasonable period, to produce the necessary material: the branches continue in their growth, which is not terminated by the formation of a flower, and new leaves are formed in rapid succession: the old leaves are thrown off, and the new ones formed are smaller and smaller; by their active metabolism, the tissues, even to the

smallest twig, are filled with starch which has no chance of getting away: the tree finally cannot stand the strain, and having used up all its supplies of salts and water, finally dies of exhaustion.

24. A number of other facts were observed, and as these may throw light on the study we are engaged in, they are appended. In the few cases where I was able to properly examine the roots of spiked trees, I noted that the Lantana roots near were much diseased, and at first it naturally occurred to me that the supply of poisoned food was quite sufficient to kill the sandal roots parasite on the Lantana And this may, to some extent, be the case. Mr. McCarthy has noted the coincidence of the spike and the Lantana invasion of Coorg. This is a point well worthy of further observation The Lantana has got such a hold of the country around Fraserpet that nothing short of devastating disease can free the country from it. If it is found to be in some way connected with "spike;" then the first thing to be done is to stem the torrent of invasion, and thus to save those portions where the Lantana has not yet arrived. "Spike" is well developed in the Hunsur neighbourhood, and Mr. McCarthy states that it originally came from Mysore into Coorg. I have heard nothing about the presence of the disease in the Hassan District, but little seems to be known about it, and I think it would be well to interest the Mysore Government, so that accurate observations may be made regarding its presence and connection with Lantana.

25. The known healthiness and rapid growth of sandalwood trees in Lantana and Casuarina plantations have been, I believe, usually attributed to the particular kind of shade afforded, and the occurrence of leaf-mould beneath the trees. I do not think that Casuarina is a tree which offers much advantage in the latter respect. On the other hand, the two Casuarina-*cum*-sandal plantations, which I was able, through the kindness of the Dewan, to visit near Bangalore, at once showed that the sandal is as greedy in its attachment to the Casuarina roots as it is to those of Lantana. I would therefore explain the early success of the sandalwood in these plantations as due to the abundant nutriment offered by the surface roots of the nurses rather than to the kind of shade, and especially so since the shade differs so markedly in the two cases. The study of the sandalwood plantations from this point of view—to my mind the most important by far—has been altogether neglected. A thorough biological study of the root system, its likes, its dislikes and its dangers, would be far more productive of useful results than much of the haphazard planting of former years.

26. I would add, as contributions to this interesting study, that the Casuarina roots in the two Bangalore plantations examined, were badly infected with a parasite resembling that of the well known alder root tubercles. The sandal roots frequently

attach their haustoria to their own roots, an operation resulting in curious fusions among the older roots. The poor development of root-hairs in the sandalwood roots suggests a saprophytic as well as parasitic habit. This is in accordance with the experience gained that the seedlings require leaf-mould for their first year. I have found the seedlings firmly attached in all directions to the roots of grasses and other plants, statements to the contrary notwithstanding. While examining the diseased roots of the sandalwood after leaving Coorg, I observed, besides a few hyphæ, not in themselves sufficient to account for the death of the rootlets, certain peculiar bodies in the vessels These upon examination turned out to be thyloses, or protusions of the living cells into the cavities of the empty vessels, due to great pressure. Many of these thyloses were filled with starch, thereby increasing the storage room for this overabundant substance. But their chief function perhaps in the tissues is to stop up cavities through which injurious influences might reach the interior. Here, on the death of a rootlet, the wide vessels afford easy entry to parasitic fungi and bacteria, besides the smaller forms of animal parasites. An attempt is made by the root to stop up the vessels by the formation of thyloses as stoppers. That this view was the correct one received unexpected confirmation from a section through a haustorium which had attached itself to a sandal root At the point where the sucking organ was endeavouring to enter the vessels they were protected by an abundant formation of thyloses which stopped up their cavities

27. A difficulty which occurred to me was, that when a plant is spiked and its root ends are dead, there appears to be no attempt on its part to form fresh adventitious roots from the older parts of the root system. This fresh formation of roots frequently takes place in other plants when they are attacked and destroyed by parasites But it has been mentioned that very young trees do not show "spike," and I would suggest that in these cases the roots are still in a sufficiently plastic condition to form new ones above the point of injury. The roots of the sandal probably quickly pass into the permanent condition as far as root-formation is concerned. The young trees keep up the fight as long as they are able to form fresh roots, but as soon as this plastic condition is passed they too succumb to the disease.

28. In the old plant we have seen that "spike" usually appears suddenly on one isolated branch or part of the tree, so that you see, in the most curious juxtaposition, normal, flowering and fruiting branches and barren spiked ones. Sometimes one-half of a tree is completely spiked, while the other half is healthy. A young plant, on the other hand, frequently goes off into "spike" all over at the same time. This is probably due to the much larger area of the root system in the older tree. As will be seen later, the roots may extend for very considerable

distances. While the whole of the root-system in young plants is very quickly invaded, it takes a very considerable time before this can occur in the case of an old one. It is quite possible also that certain parts of a tree are fed by certain portions of the root system, although there are generally in plants special arrangements for cross connections in case of sudden injuries.

29. In an old plant, such as that reproduced in photograph No. 1, it may be noted that a great many of the spiked branches are such as have been shortly broken off (see photograph No. 3). This at first led me to suspect the entrance of some parasitic fungus at the broken surface. But the examination of the spiked shoots did not show the presence of any fungus, and the tissues were perfectly healthy. It appears, however, that *any* late developing branch on a spiked tree is likely to be spiked. Such are the epicormic branches from various parts of the stems of old trees, and so also are the rootsuckers arising from injuries to the roots. Probably the shoots of the broken off branches are also of this character, being formed late to replace the branches which have been removed. It is worth while also pointing out that all these late formed branches are produced as the result of some injury to the plant.

30. One cannot note the way in which the disease spreads over the country without suspecting the roots as passing on the disease. When the trees are near together, as in a plantation, in a comparatively short time the whole of them are infected. Where they grow along the banks of a river the direction of progress is along the banks. Where finally the trees form isolated clumps in the middle of fields, they are frequently quite healthy, although comparatively near to series of diseased plants. This is a fact that was pointed out to me by McCarthy, and it is quite in keeping with the idea of spread from root to root underground. I may incidentally mention that the roots are far more wide-spreading than might at first be supposed. They probably live long after the trees to which they belong have been removed, and rootsuckers spring up when it is impossible to tell whence they have arisen. In one case I had a root dissected out and it extended to the astonishing length of 100 feet, although I had not reached its end, and this was in a nearly straight line across the field.

31. The conclusion arrived at thus far is that the disease called "spike" in sandalwood is due to the death of the root ends. What causes this has not been determined. An examination of the material brought to head-office has not thrown any light on the subject. The hyphæ present in the dead roots do not seem to me to be present in sufficient quantity to cause this state of things, and to infer a bacterial disease would be obviously a plea of inability to find an adequate cause. The bacterial diseases of plants are few and of doubtful character, and there are none of the lesions and mal-formations in the tissues in the present case

which would be expected to accompany a bacterial disease. A more careful study of the root ends, which was not possible in the time at disposal, and especially of those not yet dead, would perhaps give a clue to this puzzling disease.

32. Meantime, the progress of the disease should be carefully noted. It seems to me most probable that it is spread from plant to plant by means of the roots. There are no appearances of infection in the leaves and young branches If it took place through the broken surface of the stem, what plant could escape ? There is no tree perhaps so much hacked about and so covered with wound-callus-formations as the sandalwood.

33. Some interesting experiments might be conducted. If the phenomena noted in the above-ground parts are merely due to the failure of the roots, then it should be easy to induce them by cutting off root after root of a healthy plant and watching the new shoots forming on the trunk and branches as well as the root-suckers. Branches might be broken off from a tree where the disease has just made its appearance in order to see if the fresh shoots formed will be spiked. Diseased roots may be brought into contact with healthy ones with small difficulty and the evidence obtained as to whether the disease is readily transmitted from tree to tree by this means But it is perhaps early in the enquiry to formulate more of these experiments. There is no doubt that a grave disease has appeared among the sandalwood plantations and forests, and it will rest with those concerned whether they prosecute further the studies thus commenced.

Imperial Institute.

Quarterly Report on enquiries conducted for the Government of India by Professor Wyndham R. Dunstan, M.A. F.R.S., Sec. C.S. Director of the Scientific and Technical Department of the Imperial Institute.

SINCE the date of my Annual Report on the work conducted for India in the Scientific and Technical Department of the Imperial Institute, Flying Seal letters have been received advising the despatch of a large consignment of the pods of *Caesalpinia digyna*, which is required for the purpose of conducting tanning experiments on the large scale. Advice has also been received of the despatch of the promised large instalment of the barks of *Shorea robusta* and *Terminalia tomentosa*, which are being investigated with the view of obviating the purple tint which is communicated to leather tanned with these materials.

2. Advice has been also received of the despatch of samples of *Hyoscyamus muticus* for comparison with the Egyptian plant, which has proved to be an important source of the alkaloid Hyoscyamine. Samples are also being forwarded of *Hyoscyamus niger* from Saharanpur, with the request that these species may be submitted to chemical investigation. There is now a considerable

demand in the English market for different species of Hyoscyamus; so that it is important that the constituents and medicinal value of the Indian species should be precisely determined.

3. The Reporter on Economic Products has also forwarded four samples of tobacco from Assam for chemical examination and an expert opinion on their value. These samples have now been received, but their condition is very unsatisfactory, having apparently undergone deterioration during storage and transit. It is feared that they will be of little value for purposes of commercial valuation.

4. A sample of the fibre of *Agave americana* from Cachar, Assam, has been also received for analysis and valuation. It is at present under investigation.

5. The Reporter on Economic Products has asked for a report on samples of Asbestos from Central India, and has announced his intention of making this product one of the subjects for investigation during the current year. The use of asbestos in this country has considerably extended during recent years, and uses have now been found for inferior grades of the mineral, even when it is composed of short friable threads, and there is no doubt room for the further development of the trade in the Indian material.

6. The Reporter on Economic Products has also requested to be supplied with information as to a fire- and water-proof cement for joining mica. Workers with mica in this country have been asked for their opinion on this subject.

7. I have also to add that since the date of my last report a paper by Dr. Henry and myself on the poisonous constituent of young "Dhurra" or "Juar," the "Great Millet" (*Sorghum vulgare*) has been communicated to the Royal Society, and an abstract has appeared in the Proceedings of the Royal Society for June 1902. I may also mention that at the two soirées at the Royal Society, held in May and June last, specimens of the principal Indian products now under investigation in this Department were exhibited together with the results of their chemical examination, and that these exhibits attracted considerable attention.

8. In February of the present year I read a paper on "The Coal Resources of India" before the Indian Section of the Society of Arts. This paper has now been issued by the India Office, together with a large map of India showing the coalfield and railway communications alluded to in the paper. The paper can be purchased through the Agents for the sale of Indian official publications, and copies have been placed on sale in the Indian Section of the Imperial Institute.

WYNDHAM R. DUNSTAN,
Director, Scientific and Technical Department.

11th July 1902.

IV.-REVIEWS.

Forest Administration Report of the Hyderabad Assigned Districts, 1900-1901.

THE total area of State forests on the 30th June 1901, was 3953 square miles, classified as follows:—

Class A—Timber and Fuel Reserves	...	1675 square miles.
" B—Grass Reserves ...	...	88 " "
" C—Pasture Reserves ...	.	2,190 " "
Total	...	3,953

231 square miles were disforested and made available for free grazing.

122 square miles were transferred from classes B and C to class A, with the object of increasing the area of timber yielding forests and also to enable certain areas of class A to be opened to grazing on rotation, in such a manner as to allow longer closure after felling operations. This is an excellent system, as it provides for large grazing areas and at the same time ensures the safety of the forests.

The complete issue of 1-inch scale forest maps for the whole of Berar is most satisfactory, and will aid systematic forest management very considerably, especially as these maps are also adopted as the Taluq maps for general administration.

Under roads and buildings steady progress has been made. Eight miles of new cart-roads, three miles of new bridle-paths, four new quarters for the controlling staff and 15 for the subordinate staff were constructed. This is an important work, as it is now well recognized that much better protection and supervision of the forests is given where suitable quarters are available for the use of the establishment, and the importance of good communications is well known.

Berar does not appear to be very much troubled with forest offences. There were 757 cases all told, with only 66 cases of illegal grazing. There were no malicious cases of fires, although exporters of forest produce appear to be careless, as they were the cause of eight fires extending over 5847 acres, and in the previous year of 20 fires extending over 11,092 acres. This is a matter which the Department should be able to put a stop to entirely by stricter supervision and imposing heavy penalties for disobedience to comply with rules.

About 38 per cent. of the total area of forests is under fire protection, which probably includes most of class A. The cost of fire protection is Rs.10 per square mile, and only 1·3 per cent of fire protected areas were burnt.

Advantage was taken of the seeding of bamboo in the Wun district, and two tons of seed were collected and sown in all divisions. Other species sown were *Terminalia chebula*, *Dalbergia sissoo*, *Santalum album* and Babul.

The year was unfavourable for lac culture.

The drought of the preceding years caused considerable damage to vegetation. A large number of old pollard teak trees occurring in well-defined belts dried up, which is a serious damage in places where there is insufficient advance growth to replace them. Young vigorous teak does not appear to have suffered, and it is specially noted that *Hardwickia binata* was unaffected by the drought. Owing to the desirability of utilising the dried up teak trees, felling in prescribed coupes were curtailed by 12,202 acres.

Teak has seeded very profusely, and it is hoped that this unusually heavy crop of seed will counterbalance to a certain extent the loss of growth caused by the drought. Bamboo has seeded in the Wun disrtict only, and as the seeding of bamboo is not general over Berar, this is probably normal and not the effect of drought.

The country was restored again to its normal climatic conditions by the break of the monsoon rains in August 1900. Owing to excellent cotton crops there was a large demand for fuel. This, combined with the improved condition of the country after the drought, resulted in a large increase of revenue under all heads, with the exception of grass and grazing. The decrease of revenue under these last heads is due to the mortality amongst cattle caused by the fodder famine. According to the departmental figures, it is estimated that about 539,903 cattle died as a result of the drought, which has reduced the average number grazed in previous years to about one-half.

The total cash sales during the year amounted to Rs. 3,65,357 as follows :—

	Rs.
Timber (chiefly teak)	97,649
Fuel („ babul)	62,788
Bamboos	29,199
Grass	32,840
Grazing	1,20,756
Minor produce	22,125
Total ...	3,65,357

In addition to which forest produce to the value of Rs. 2,16,543 was disposed of as concessions.

The gross revenue was Rs. 3,71,145 or Rs. 94 per square mile.

The total expenditure was Rs. 2,38,031 or Rs. 60 „ „ „

(Rs. 20 Conservancy and Works.)
(Rs. 40 „ Establishment.)

Net revenue Rs. 1,33,114 or Rs. 34 per square mile.

Mr. C. Bagshawe is to be congratulated on the successful manner in which he has guided the forest administration of Berar through the last eight years, and his retirement deprives the Department of a most useful and capable Forest Officer.

Forest Administration in Bengal during 1901-1902.

MR. J. H. LACE, who writes the report this year for the first time, has succeeded in producing an interesting account of the year's work in spite of the maximum limit of 20 pages within which the report had to be confined.

Settlement is still in active progress in Chittagong, where 83 square miles were added to the area of reserved forest, bringing the total area for the Presidency up to 5964 square miles. 160 square miles of protected forest were excluded, mostly in the Sundarbans and Palamau district, making the total forest area borne on the books of the department about 13,500 square miles.

The sum of Rs. 15,464 was spent on demarcation, most of the new work being done in Chittagong, where demarcation seems to be both difficult and expensive, as it was found necessary to incur an expenditure of Rs. 6310 in clearing 184 miles of boundary line 10 feet wide, being equivalent to a rate of Rs. 34-4-8 per mile.

No new working-plans were sanctioned during the year. Plans for 109 square miles were taken in hand, leaving a balance of 2477 square miles of reserved forests for which working-plans have yet to be prepared, somewhat less than half the total area of reserved forests.

Much attention was paid to the matter of communications, Rs. 22,874 being spent on the construction and up-keep of roads and paths, chiefly in Darjeeling and Singhbhum divisions, where nearly 40 miles of road were constructed.

The Setikhola wire rope-way was worked successfully, and 21,880 maunds of fuel passed over it during the year. The rope-way was unfortunately broken after the close of the year by the fall of a large tree, but has been re-erected with a shorter span of 800 feet, which has had the advantage of making it possible to considerably reduce the height of the despatching end of the wire above the cart-road from which all the fuel has to be carried.

The erection of the Mahaldaram rope-way was completed by Mr. C. G. Rogers just before he proceeded on transfer to the Andamans The average gradient of this wire exceeds 15°, which is far too great to admit of free loads travelling down the wire safely and without jumping off. With the experience gained at Setikhola, the impossibility of working a single wire under these conditions should have been manifest from the first, and arrangements are now being made to check the velocity of the loads by the introduction of an endless guide-rope, which it is hoped will have the desired effect.

A decided improvement took place in the protection of forests.

The total number of new cases was 322 less than in the previous year: a decrease occurred under all main heads, that under "Injury by fire" being 29 cases.

The percentage of "undetected cases' was 2 70, the majority of which were, as usual, cases of "Injury by fire." Compared with the previous year, there was a considerable decrease in the total number of cases in the Tista, Buxa and Sundarbans divisions, and an increase in the Darjeeling, Jalpaiguri, and Singhbhum divisions. The decreases occurred chiefly under illicit felling and grazing, and in Buxa the decrease was helped by a marked and satisfactory falling-off in the number of fires. In the Darjeeling and Jalpaiguri divisions the increase was principally under illicit grazing, and may have been in some measure due to the system of liberally rewarding members of the subordinate establishments for bringing offences to light. In Jalpaiguri the number of "Other offences" was double that of the previous year, and for the most part consisted of breaches of the shooting and fishing rules. The increase in the Singbhum Division occurred chiefly under illicit felling and fires.

18. The total number of cases taken into court was 248, and the percentage of convictions obtained in cases decided was 87, as compared with 301 and 86 respectively, in 1900-01.

The area over which special protection from fire was attempted was increased from 2120 to 2205 square miles. Of this area 2125 square miles were successfully protected, the proportion of failure being 3·65 per cent. against 2·02 in the preceding year. The total area burnt was 80 square miles, against 43 square miles in 1900-01. The total expenditure on areas attempted to be protected was Rs.13,273 or Rs.6-0-3 per square mile, the cost per square mile successfully protected being Rs.6-4-0 as compared with Rs. 6-15-0 in 1900-01.

The expenditure on artificial reproduction was Rs. 8849 and the operations comprised the addition of 420 acres to the area under artificial reproduction. The Conservator, however, seems to be of the opinion that but slight reliance must be given to artificial reproduction, and that with judicious treatment natural reproduction will do all we require He says:—

"During the short time the Conservator has been in charge of the Circle, and in the Province, he has been able to inspect a considerable area of the forests in Singhbhum, the Terai, the Duars and the Hills, and he has been much struck by the general adequacy of natural reproduction of the more valuable species, and by the insufficient steps that have been taken to assist that reproduction in the Terai, the Duars, and sal areas situated in the lower hills. The benefit that the forests derive from fire-protection is most marked. The sal is resuming the area it undoubtedly once occupied in the Darjeeling Terai, thanks to fire-protection which, added to the absence of frost, has also enabled a rapid stocking-up of savannahs in a manner that is never attained in forests north of Bengal. In the Buxa Division there are large areas of what must have been once fine forests of *Dalbergia sissoo*, but which owing to constant firing have been reduced to a sea of grass and scattered trees. The manner in which this species is reproducing itself in those portions of the areas over which protection from fire has been successful shows that it only requires fire to be kept out of such areas in order to create forest which would be as valuable as those of sal Much money has been spent in the past on the artificial cultivation of species foreign to the whole or certain portions of the country and with very poor results. With a multitude of indigenous species in the forests producing excellent timber, fuel and even rubber, it will be well for the Department to direct most attention to the encouragement of the valuable native species and to spend money on such work rather than on the cultivation of exotics."

The revenue and expenditure of the year compare as below with those of the preceding year, and the averages of the previous five years:—

	FINANCIAL YEAR			FOREST YEAR.		
	Receipts	Charges.	Surplus.	Receipts	Charges.	Surplus.
	Rs	Rs.	Rs.	Rs.	Rs.	Rs.
1901-1902	12,92,237	6,57,131	6,35,106	13,00,516	6,91,365	6,09,151
1900-1901	12,33,339	5,70,806	6,62,533	12,27,077	5,74,104	6,52,973
Difference in 1901 1902 ...	+58,898	+86,325	−27,427	+73,439	+1,17,261	−43,822
Average for five years ending 1900-1901. ...	11,80,940	5,89,1 9	5,91,778	11,89,421	5,93,090	5,96,331

The net income of the forest year under report was 46·84 per cent. and the expenditure 53 16 per cent. of the gross revenue, as compared with 53·21 per cent. and 46 79 per cent. in the previous year. The figures, however, for 1901-02 do not represent the true results of the working of the year, as the charges include an extraordinary payment of Rs.77,578 to the Raja of Porahat, on account of the profits of the working of the Porahat forests during the five years ending 31st March 1901. The revenue has only once before been exceeded, *viz*, in 1896-97, when it was Rs. 13,45,982, and after making allowance for the disbursement noted above, the true financial results of the year's working show a surplus of Rs. 6,86,729, which is the highest on record.

Ceylon Forest Report for 1901.

ALTHOUGH the Ceylon report this year contains little which calls for special remark, it bears testimony to a year's steady progress in developing the forest resources of the Island and in carrying out the investigations which are a necessary preliminary to placing the forests under systematic management.

There are now 103 reserved forests, having a total area of 713,413 acres. Additional areas amounting to 66,000 acres have been proposed for preservation, so that in time there will be over 1200 square miles of reserved forest containing many valuable species of timber trees, of which the following are some of the more important. Diospyros ebenum, Chloroxylon swietenia, Berrya Ammonilla, Mimusops hexandra, Vitex altissima, Alseodaphne semecarpifolia, Terminalia glabra, Bassia longifolia, Mesua ferrea, Pericopsis Mooniana, Vatica Roxburghiana, Vatica obscura, Michelia nilagirica, Doona zeylanica, Doona Gardnerii, Doona trapezifolia, Calophyllum Walkereii, Dipterocarpus zeylanicus, Vateria acuminata, Azadirachta indica, Palaquium grande, Gardenia zeylanica, Nephelium longana, Homalium zeylamicum, Melia dubia, Eugenia Jambolana, Eugenia assimilis and Garcinia ternaphylla. These areas are gradually being demarcated: during the year the sum of Rs.25,962 were spent on demarcating boundaries and re-clearing lines. Demarcation work would appear to be expensive in Ceylon, as the average cost per mile of clearing 10 feet boundaries was Rs.55½. while a 6 feet boundary cost Rs.21 to clear.

Work in connection with working-plans was still confined to enumeration surveys and sample plots. Enumeration surveys were conducted over an area of 44,774 acres at an average cost of Rs.0·62 per acre. There are now 38 sample areas, varying in size from 15 acres to ¼ an acre, and of these a careful record is kept each year.

The subject of fire protection is dismissed in the report with the remark that a good deal of damage was done. No details are given, nor is any statement of fires to be found. This important matter evidently meets with scant attention in Ceylon.

2863 forest offences were prosecuted and 151 were compounded, but of the cases taken into court, 2609 were reported from one district and consisted mainly of cases of illicit "chena" cultivation; it can therefore be said that there is very little forest crime, or at any rate very little is reported. During the year Rs.6000 was spent on roads and Rs.4600 on buildings, while produce to the value of Rs.1,74,000 was removed departmentally and Rs.1,78,000 by consumers, both amounts being considerably less than were obtained last year.

The receipts for the year amounted to Rs 3,93,053 and the expenditure to Rs.2,86,732, the resulting surplus of Rs.1,06,321 being an improvement on the Rs 84,106 of the previous year.

Forest Administration in H. H. the Nizam's Dominions during 1900-1901.

HIS HIGHNESS the Nizam cannot be congratulated on the progress made in forest administration within his dominions during Fasli 1310. Matters seem to be at a standstill, or rather progress is at a standstill, and forest growth is fast disappearing or at any rate deteriorating. The reason for this appears to be that His Highness and his councillors have not yet fully realised the damage which is being done to State property, and the serious results which must ensue at no distant date if a more decided policy is not adopted and vigorously enforced, even at the cost of some considerable reduction in revenue for the time being. One of the most valuable forest properties in India is being wantonly destroyed with little or no profit to the State.

One reserve of about 185 square miles was sanctioned during the year, bringing the total area of reserves up to 5186 square miles. Proposals have been submitted for the reservation of 4686 square miles, but these have all been returned unsanctioned because the areas had not been surveyed or mapped. The reason is excellent, but the failure of the department to survey and map the areas is due to its being unable to obtain sanction to the employment of either surveyors or draughtsmen.

The condition of the open forest is especially unsatisfactory. They are nominally in charge of the tahsildars, who are allowed no establishment for the protection and working of these forests. Their interest in such areas is consequently limited to obtaining what revenue they can from them.

Little demarcation and survey work was done, and no work whatever was done on communications. Sanction has been obtained to spend the paltry sum of Rs.1000 on roads during the current year. This may be a beginning, but it is a very small one.

In spite of the large amount of illicit removal which admittedly goes on, only 12 new cases were taken into court and only six convictions were obtained throughout the whole year. Most of the forest crime was dealt with departmentally; 4440 cases were compounded for Rs.29,879, which shows that the department is unwilling to take its cases into court. Even though it is not easy to obtain convictions in court, it is probably better to send up the more serious cases to be dealt with by the magistrate, as the ordinary villager much prefers to pay the compounding fee when caught to being taken into court with all the accompanying worry and expense.

Fire protection is attempted on a small scale: 217 square miles were protected out of 225 square miles attempted, the cost being Rs. 7-3-2 per square mile, or about ¼ anna per acre

Much space is devoted in the report to the difficulty experienced in controlling grazing The sum of Rs.34,000 was derived from grazing fees, which averages about 2 annas per head for horned cattle. Of this amount Rs 14,500 was obtained by sanctioning the right to collect grazing fees in certain unreserved lands. A further sum of Rs 11,500 was derived from the sale of the right to collect grazing fees in Pakhal Reserve, so that only Rs.8000 was derived from all the other areas Unless cattle grazed illicitly, the grazing over the other reserves would not appear to be very excessive. It is strongly recommended in the report that cattle should not be grazed free in unreserved lands, but this we believe is the custom more or less throughout India. We also understand it is usual throughout India to permit foreign cattle to graze free in British territory outside reserved areas.

Financially the operations of the year were successful, the gross revenue being Rs.3,45,445 and the expenditure Rs.1.44,368, giving a surplus of Rs.2,01,076—a surplus which has only once been exceeded, but which is still capable of very great extension.

VI.—EXTRACTS, NOTES AND QUERIES.

Athletic Sports at the Imperial Forest School, Dehra Dun.

THE annual athletic sports were held on 15th and 16th October on the old parade ground in the presence of a large assemblage of the residents of Dehra Dun. The proceedings were enlivened by the presence of the band of the 2nd P. W. O. Goorkhas, lent by kind permission of Major Shakespeare and the officers of the 1st Battalion.

In spite of the heaviness of the ground, which was against record breaking, the events were well contested, and both the 100 yards and the hurdle race resulted in the closest of finishes.

The following is a list of the winners of the different events:—

(1)	Throwing the Cricket Ball	Mahomed Hyat, 82½ yards.
(2)	Long Jump	Gupta, 17'-6"
(3)	Putting the Weight	Borges, 22'.
(4)	100 Yards Flat Race	Eagles.
(5)	High Jump	Chit Twe, 5'-1"
(6)	120 Yards Hurdle Race	Porter.
(7)	Three-legged Race	Chengappa and Purushottam Rao.
(8)	Tent-pitching Competition	Littlewood, Eagles, Porter, Simpson.
(9)	Half Mile Flat Race	Sitaram Puri.
(10)	Obstacle Race	Sitaram Puri.
(11)	Servants' Race	Gyan Singh.
(12)	Tug of War	Seniors beat Juniors.
(13)	Tennis Singles	Rama Iyengar.
(14)	Tennis Doubles	Chengappa and Wad.

The Rapid Ageing and Fireproofing of Wood.

THE preservation of wood was formerly accomplished by drying and covering it with coatings designed to prevent the entrance of air and moisture. These have given place to numerous plans for the introduction of antiseptic liquids.

The decomposition of wood occurs soon after it is felled and exposed, whether in logs or pieces, to the air, moisture and variations of the temperature. It is also destroyed by being buried in the ground or immersed in water. Cut up in planks and dried in the open air it warps and cracks, causing considerable loss. At 300 deg. C. all wood, dry or preserved by antiseptics, is carbonized without production of flame, but subjected to a red heat or to the action of a burning body, as in fire, the pieces of wood are completely destroyed, even if they are covered with a coating opposing to the fire a certain resistance. Whence the multitude of processes made use of for more than a century for increasing its durability.

Let us consider in a few words what wood is, the properties of its principal components, and the causes of their rapid change.

Wood is formed essentially of two different substances, one predominating, the ligneous, and the other liquid, the sap.

1. The ligneous is formed of cellulose, that is, with reference to its elements, of carbon, oxygen and hydrogen. This organic tissue constitutes the framework of the plant, in the form of vessels and fibres, which are covered with an agglutinant organic matter (vasculose, cutose, pectose, etc.) The principal cause of change of the ligneous is the great affinity of its carbon

for its oxygen, an affinity favoured by the changes of dryness and moisture, and finally resulting in the disorganization of the fibrous structure. The wood loses its power of resistance, the fibre is disintegrated and falls into a grayish powder.

Pectose and pectic acid, in the state of pectate of lime, form a part of the organic cement which binds together in bundles the cortical fibres of a great number of useful filamentous plants.

Pectose, like cellulose, is insoluble in all neutral solutions, but it has the property of conversion under different influences into soluble gelatinous products. Submitted to the double action of heat and of acids, it is transformed into pectine, a neutral colourless body, soluble in water, then into pectic acid C_{32}, H_{48}, O_{32}, and quite a series of bodies increasing in acidity in proportion as they recede from their origin. These bodies may be presented in the following order: Parapectine, metapectine or parapectinic acid, pectonic acid, pectic acid, parapeptic acid and metapeptic acid.

2. The sap which fills the cellular cavities of the organic tissue is composed of a considerable quantity of water, holding in solution mineral and organic substances (nitrogenized, fatty and sugared). The sap passes by endosemose, and not by capillarity. from the soil into the roots; then circulates through the different parts of the plant, conveying various dissolved mineral substances such as are found in the ashes. This liquid, therefore, is one of the essential causes of the vitality of the wood. After it is cut down, the sap, undergoing the affinity of its carbon for oxygen and of its nitrogen for hydrogen, becomes a favourable medium and an aliment for the nourishment of worms and for the development of cryptogamic germs—additional and powerful causes of the changeableness of wood.

The sappy liquid represents a weight varying from 15 per cent. in the yoke-elm to 50 per cent. in the poplar.

Not only are the chemical and physiological causes of the changes of wood now understood, but a remedy has been found for the evil. It has been known for a long time that a dry wood is much less subject to decomposition than a moist wood still impregnated with sap. This observation has led to submitting the wood before its employment either to natural or to artificial and rapid desiccation.

Until within the last few years the first method, the most simple. that of exposure to the air for a time, afforded good results, but the natural drying, which requires a good deal of time, especially for hard species and for considerable thicknesses, necessitates a very large surface for piling wood and the loss by waste proceeding from splits at the extremities increases the price of dry wood. This explains the numberless methods for obtaining the rapid drying of the wood under the best possible conditions.

To describe all the processes would take us too far from the parts of the subject which we have in view. Paulet describes 173 methods, most of which have been patented, and which may be distributed in the three following groups: —

1. By natural infiltration or displacement applicable to standing wood or that recently cut down.

2. By pressure in the open air, applicable to wood in bark; or by pressure in an inclosure, applicable to dry wood.

3. By superficial application of antiseptic agents (by carbonization, immersion and coating) useful for all kinds.

Before considering the ingenious Nodon and Bretonneau process for the rapid ageing and fireproofing of wood, we will rapidly analyze the principal methods which have afforded material results.

In the first group may be mentioned rafting, which consists in immersing the pieces in water. This allows of drying the wood more rapidly, for the sap having been partially driven out by the water, which has replaced it, this will evaporate more readily than the sap. For instance, oak for flooring, which would require two years of drying in the open air, may be dried in four months after having been subjected to the action of the water.

Wood is immersed in a stream or basin for three or four months. If the circumstances allow of raising the temperature of the water to 30 deg. C., the time of operation may be reduced to fifteen or twenty days.

Steam also afforded good results so far as the drying is concerned, but unfortunately the fibre is in part attacked and the wood is much less tenacious.

In the Leclerc process the operation is conducted by steam, followed by drying in a current of warm air. The wood is arranged in a close chamber of masonry and the steam, strongly distended, is brought in for forty-eight hours by perforated pipes. Under the action of the condensed water a part of the sap comes from the cells of the wood, and the other part is coagulated. Thus the result is not complete.

The wood is afterward dried by causing a current of warm air (30 to 35 deg. C.) to circulate in the same chamber, which requires a fortnight for planks of ordinary thickness. The wood is piled upon the open work floor of the chamber, inclining it sufficiently to cause the sap to flow. Each piece is separated from its neighbours, which allows the air and steam to circulate freely over the whole surface. For drying, the warm air is introduced, at one time from above, at another from below, and alternately at one or the other extremity of the chamber. It is drawn in through the wood and drawn out by a ventilator working at the opposite extremity.

·Boucherie's processes, which belong to the first and second groups, utilize at one time the vital osmatic force of growing trees; at another the infiltration of a liquid, or the displacement of the sap by this liquid, on the tree recently felled. In the first case, one or two saw cuts are made at the base of the trunk or several quite deep holes. An earthen band or a strip of cloth smeared with rubber, is placed around the base and communicates by a tube with a small cask containing any antiseptic solution not too concentrated.

The sap on rising in the tree draws with it the liquid, according to the diameter of the capillary vessels. The tree receives the poison as it receives the nutritive element.

In the second case, if the tree is felled, it is placed in a position slightly inclined, and a leather sack, as impermeable as possible, is attached to the trunk and put in communication with a reservoir 10 or 15 millimeters above. The results are quite noticeable, but the process is incomplete, the penetration being irregular, and the displacement of the sap almost *nil* in the heart of the wood.

In the Renard-Perin infecting process, the piece of wood is sawed off at the two ends perpendicularly to its axis. One of the extremities is covered with a sack of impermeable canvas in which the solution is poured; the other extremity is connected with a metallic receiver, in which a vacuum is produced by the combustion of tow soaked with wood spirit, which completely closes the apparatus.

The aspirator bring sfrom the capillary interstices the natural liquids which they contain. These are replaced with the solution under atmospheric pressure. The operation is repeated two or three times.

In general, the processes by pressure in an inclosure, belonging to the second group, are worked by means of cast-iron cylinders containing the pieces of wood. In many cases a vacuum is produced at the outset in the cylinder containing one or several pieces, then the liquid is introduced under pressure for several hours.

A modification of the Boucherie and the Renard-Perin processes is the new process of G. Lebioda & Co.,—the injection of the wood in mass. The trunk or log is inclosed in a kind of cast-iron autoclave able to support a pressure of 150 atmospheres. The liquid is injected by a pipe under a pressure which is gradually increased for a quarter of an hour in the case of spruce up to 100 atmospheres. The wood is surrounded by the liquid, which is kept at the same pressure as that entering. According to the inventor the fibres of the wood would offer no resistance under this process. The liquid entering would act like steam in the Gifford injector. But, in our opinion, the liquid submitted to so strong a pressure would seek to pass out by the shortest path, and the wood would therefore be penetrated irregularly.

When the object is to dry wood rapidly by this process, the treatment is effected simply with water: the sap, according to the inventors, would be expelled from pieces 10 by 10 centimeters, which would be dried in four days, the temperature of the air of the dryer being gradually raised to 90 deg. C., the temperature at which charring commences on the fibre. As the apparatus used by Lebioda and Co. is more costly than that of the Boucherie and Renard-Perin processes, the results must be similar, the sap contained in the capillary vessels not having time to be completely displaced by the osmose necessary for this exchange of liquids. Under these conditions of rapid treatment, the osmose ceases in the heart of soft woods, and is slight in the whole mass of hard or resinous species.

The superficial carbonization, belonging to the third group, is valuable for hard woods which cannot be impregnated with antiseptic substances. This treatment is of more durable efficacy. The charring is produced by a flaming jet, which in the current of compressed air forms a kind of blow-pipe and causes a strong disengagement of heat. The flame draws out the water contained in the superficial layers, dries the fermentable portions, carbonizing completely the external part, and produces a torrified surface about half a millimeter thick, almost distilled and impregnated with the products of this distillation, which are empyreumatic creosoted substances.

Drying with smoke, which is effected in a chamber of masonry heated by the combustion of moist sawdust, which yields a thick smoke, renders the wood useless for many industries, on account of its disagreeable odour and the slight resistance of its fibres, which have undergone some change.

In fine, of all these processes except that of Nodon and Bretonneau, which we will describe, none resolves in an entirely satisfactory manner the problem of the rapid drying of wood or the complete penetration of antiseptic or fireproofing products. Rapid ageing of wood by electricity of the different processes hitherto employed by Messrs. A. Nodon and A. Bretonneau, preserving only the best principles and inspired by the experiment of Daniel on the displacement of a globule of mercury by the electric current, have succeeded in utilizing electricity for modifying the constituents of the sap. By that physical force which at times produces such unexpected effects, they have introduced on the ligneous tissue a suitable saline solution, which, after rapid drying, secures for the wood resistance to putrifying agents. Daniel, in his interesting experiment, placed in a glass tube bent at its extremities and arranged horizontally, a globule of mercury immersed in acidulated water. He introduced the wire of a battery at one of the extremities of the tube, the other wire in the acidulated liquid at the opposite extremity, and observed the movement of the globule of mercury, which was displaced from the positive to the negative pole.

After several years of study on the modifications of the vital parts of the wood and on the arrangements to be adopted and the choice of the baths for treating the wood, MM. Nodon and Bretonneau have been able, by placing the wood between two electrodes of lead, to finally resolve the difficult problem of the artificial ageing of wood and fibrous substances. The company which operates this important discovery has erected a model factory at Aubervilliers.

The practical working of this process is quite simple. The apparatus serving for the electric treatment of the wood consists of vats of cement or wood rendered tight by a lead lining 1½ millimeters in thickness and isolated from the bottom electrically by porcelain. The dimensions are 6 metres and 12 millimeters in length, 3 millimeters in width and 1 millimeter in depth. A copper coil, placed horizontally at the bottom of the vat, allows of heating the bath by means of steam brought in by a pipe, which is connected on the outside with the coil by joints, easily taken apart in such a way that the temperature of the saline solution can be kept at about 35 deg. C. during the introduction and removal of the wood, and then isolating the coils and consequently the vat from the steam-pipe.

The wood to be placed in the vats is arranged on the outside on movable platforms, a kind of open work frame covered with lead from 1 to 2 millimeters in thickness, forming the first electrode. The logs may be treated before they are cut up, provided they are separated from the bark. The logs or planks are placed in piles on the platforms as nearly uniformly as possible, the different piles being of the same height, 0·70 at the maximum. The quantity, thus prepared, is raised on a turn-table by a windlass, the platforms having a series of books, allowing of their being suspended to an iron frame under the windlass. The wood is then brought over the vat and let down into it The upper face of the wood is covered with the second electrode formed of lead 1 millimeter in thickness, contained in a connected series of small porous vessels or compartments of wood; these are in size from 0·90 metre to 1·25 metres in length, from 0·75 metre to 0·90 metre in width and 0·10 metre in height; closed at the lower part by felt between two pieces of canvas beaten down and fastened on the sides of the frame under wooden lath kept in place by screws. Thus there is a receiver retaining the water that is poured in for assuring the proper contact of the wood and the lead, as well as of the canvas and the felt, which serve as an intermediate vehicle for the different components of the sap expelled from the wood during the operation. The lead of the different porous compartments is united and thus forms a continuous electrode, which is put in communication with one of the poles of the dynamo, the other pole being connected with the lower electrode.

The vat is then filled with the solution employed for the treatment of the wood. This may be antiseptic or formed of salts for rendering the wood uninflammable. That in use at Aubervilliers for the ageing of wood properly so called is a solution of crystallized magnesium sulphate (80 parts water, 20 magnesium sulphate) heated to 35 degs. C. The wood is immersed in this solution, emerging from the surface only a few centimeters (3 to 8 centimeters), the lower face of the upper piece of each of the piles of wood being always moistened by the solution. This bath may be used indefinitely, provided it is regenerated by means of magnesium sulphate according to the density of the liquid or the percentage of the salt. About every month the bath is brought to the boiling point in order to coagulate and readily separate the organic matters proceeding from the wood.

Before the solution of magnesium sulphate was employed, other baths were experimented with, which were abandoned on account of practical objections, such as the deposit of resinous matter on the surface of the wood, which had to be removed by scraping and washing, or on the fibre itself, which too quickly dulled the tools employed in working the wood.

In the treatment with the magnesium sulphate the continuous current employed is 110 volts, but instead of being directed through the wood always in the same direction, a change is made every hour or every two hours, or half the amount of electric horse-power necessary for the operation is passed from the top to the bottom, and then the other half from the bottom to the top.

The duration of the treatment by electricity is proportioned to the electric resistance of the wood, which varies according to its nature, its thickness and its humidity. As in the processes by injection, the operation is the more prompt and complete, whatever the species of wood, provided it has been recently cut down, that is, if the sap has not undergone modification.

The ageing of wood by treatment in vats is completely terminated when six electric horse-power or about 4500 watt-hours have passed per cubic metre of wood. The time may vary from seven to fourteen hours, the intensity of the electric current being generally kept between four and six amperes, which is secured by increasing or diminishing the emergent part of the wood.

Phenomena produced during the Electric Treatment.—According to Daniel's experiment, electricity produces in the cells of the wood movements of contraction and dilatation.

1. A part of the magnesium sulphate of the solution employed penetrates by electro-capillarity into the cells which are more or less free from the sap.

2. Under the influence of the electric current there is an osmotic exchange between the saline substances of the sap and the magnesium sulphate.

3. Electrolytic action on the ferments of decomposition and putrefaction contained in the wood.

4. Finally, and the most important point, the simultaneous electrolysis of the organic salts contained in the sap and incrusting matters of the wood and the magnesium sulphate. The electricity facilitating the contact of the re-agents with the ligneous fibres, the salts and metallic oxide are deposited and united with this fibrous matter, and fabrics are mordanted by alum. The ligneous fibre containing the phosphates which contribute to this precipitation is thus united and protected from the action of the air:—

By the reversal of the direction of the electric current the acids formed coagulate the albumen, the nitrognized matter being always accompanied with sulphur and phosphorus. The metal unites with these metalloids, and the phosphides and sulphides formed render the nitrogenized matter unfit for vegetable and animal life.

There is therefore a formation in the mass of the wood, under the influence of the electrolysis, of new mineral compounds, stable and imputrescible, and this in a way much more complete than by any other process, preventing the ulterior development of the germs which cause the decomposition of the wood.

The action of the electric current in the process of the ageing of wood is therefore very important. Investigation with the microscope and the results of analysis demonstrate the penetration of the elements of this salt in the fibrous matter to the heart of the wood.

The different parts of the wood being of heterogeneous constitution, the proportions of the elements found by analysis vary from one point to another. The results given below are the averages of analysis of samples taken from different parts of the same piece of wood.

Ash obtained by incineration: oak not treated, 0·30 per cent.; oak treated with magnesium sulphate 0·90 per cent.; gray poplar not treated, 0·28 per cent.; gray poplar treated with magnesium sulphate, 0·82 per cent. By analysis of the ash of the gray poplar treated with magnesium sulphate, there are found 0 24 per cent. of sulphuric acid, corresponding to 0·60 of crystallized magnesuim sulphate; 0·55 per cent, of magnesia, of which one part (0·10) corresponds to the 0·60 of the magnesium sulphate above, and the rest 0·45 per cent. is in the free state or combined with the organic acids of the wood.

Drying of the treated wood.—After treatment, if the wood is in logs, it is cut up in timber, according to need. After it is thoroughly soakeo with water, it is left from 8 to 15 days under a shed for drying. For this purpose the pieces are piled on each other separated by two or more spruce laths, according to length, the thickness of the lath varying from 8 to 25 millimeters, according to the thickness of the pieces.

If sufficient space is at disposal, the wood can be left to dry entirely in the open air; still it undergoes the alternations of heat and cold and the irregularity of the action of the air. It seems, therefore, preferable, after a first drying without, to pile the pieces in a chamber, where a current of heated air is kept in constant circulation from two to eight weeks, according to the thickness, at a temperature gradually increased to 35 deg. or 40 deg. C The wood is then thoroughly dried and ready for use.

Principal Advantages of the Artificial Ageing of Wood over the process of natural drying.—If a piece of senilized wood and a piece of the same kind not treated and dried simply in the open air are compared under the microscope, it will be observed that the cells of the former have undergone contraction. The entrance of the air will therefore be rendered more difficult. Then the original albumenoid matters no longer existing, the wood will not be subjected to the influences of the hydrometric state of the air, and may be preserved without change, escaping putrefaction and the attack of insects.

These properties have been proved by tests of the resistance, showing an increase of the tenacity of the fibrous matter. Experiments made by the superintendents of wood paving in the city of Paris have attested conclusively the penetration by this process. Pavements of senilized beech and pavements of beech simply creosoted have been laid in several quarters, particularly at the Porte Saint Martin. When taken up some time afterward, the treated beech showed no sign of the usual putrefaction and exhibited more resistance to wear than the beech not treated.

By ageing the colour of the wood is not modified, and its sonorousness is increased to such an extent that it is now sought for by the makers of instruments of music.

This process not only imparts to the wood the qualities that have been enumerated, but causes an important saving over the methods hitherto employed, especially over that of drying in the open air, in the diminution of the capital represented in the value of the wood and in the land occupied and in the prevention of waste.

It is not only applicable to the rapid drying of wood, but it allows of modifying the conditions of treatment, of increasing any one of the qualities previously cited, according to the kind of wood and the use to which it is to be applied; it is to be observed that for wood of close fibre the phenomenon of endosmose is weaker than for wood of loose texture, while the phenomenon of exosmose still preserves its value.

For instance, in ageing wood in a bath of sodium phosphate and borate, the durability of the wood may be augmented. With the aid of zinc sulphate a quantity of salt may be introduced in the fibre of the wood varying with the strength of the solution and the duration of the treatment. A resisting power will thus be imparted to the wood permitting its employment with success concurrently with creosoting for paving railway ties, draught vehicles, telegraph posts, and other purposes.

Finally, by the electric treatment the uninflammability of wood may be increased by employing, for example, ammoniacal salts.

FIREPROOFING OF WOOD.

Strictly speaking, it is impossible to render wood completely incombustible, but an almost absolute immunity against the attacks of fire can be imparted.

Gay-Lussac was one of the first to lay down the principal conditions indispensable for rendering organic matters in general and wood in particular uninflammable.

1. During the whole duration of the action of the heat the fibres must be kept from contact with the air which would cause combustion. The presence of borates, silicates, etc., imparts this property to organic bodies.

2. Combustible gases, disengaged by the action of the heat, must be mingled in sufficient proportion with other gases difficult of combustion, in such a way that the disorganization of bodies by heat will be reduced to a simple calcination without production of flame. Salts volatile or decomposable by heat and not combustible, like certain ammoniacal salts, afford excellent results.

Numerous processes have been recommended for combating the inflammability of organic tissues, some consisting in external applications, others in injection under a certain pressure of saline solutions.

By simple superficial applications only illusory protection is attained, for these coverings, instead of fireproofing the objects on which they are applied, preserve them only for the moment from a slight flame. Resistance to the fire being of only short duration, these coatings scale off or are rapidly reduced to ashes, and the parts covered are again exposed. It often happens, too, that such coatings have disappeared before the occurrence of the fire, so that the so-called remedy becomes injurious from the false security occasioned.

We will cite some formulas still recommended. They are applied :—

1. By immersion or imbibition.
2. By application of successive coats by means of a brush.

1. For immersion or imbibition the following solution is advised: Ammonium phosphate 100 grammes; boracic acid 10 grammes per litre, or ammonium sulphate 135 grammes; sodium borate 15 grammes, boracic acid 5 grammes per litre. For each of these formulas two coats are necessary.

2. For application with the brush the following compositions are the best.

(a) Apply hot sodium silicate 100 grammes, Spanish white 50 grammes, glue 100 grammes.

(b) Apply successively and hot, for first application, water 100 grammes; aluminium sulphate 20 grammes: second application, water 100 grammes; liquid sodium silicate 50 grammes.

(c) First application, two coats hot: water 100 grammes; sodium silicate 50 grammes: second application, two coatings: boiling water 75 grammes, gelatine white 200 grammes; work up with asbestos 50 grammes, borax 80 grammes and boracic acid 10 grammes.

Oil paints rendered uninflammable by the addition of phosphate of ammonia and borax in the form of impalpable powders incorporated in the mass, mortar of plaster and asbestos and asbestos paint, are still employed for preserving temporarily from limited exposure to a fire.

In England, America and Paris attempts have been made to introduce under strong pressure, preserving solutions into fibrous substances. Even large establishments have been erected in different countries for this purpose. Unfortunately this process by pressure is still attended with the serious evil of introducing fireproofing products only in the outer part of the wood; the solution reaching but a quite a limited depth. The process consists in removing from the wood with the aid of steam under pressure, a part of liquid products which it contains which excites a sort of distillation of the inflammable products, for which solutions are substituted, generally composed of ammonium sulphate or phosphate, boracic acid or alkaline borate.

The best result has been obtained by the electric penetration of the salts. In the Nodon and Bretonneau process fireproofing products have been introduced through the whole mass of the wood, and this in a way much more regular than by injection even under strong pressure. A power of resistance to the attacks of fire truly exceptional has been thus imparted. The quantity of fireproofing products depends on the concentration of the bath and the duration of treatment.

It has been ascertained by experiment that wood is really uninflammable; that is to say, that it resists for quite a long time a very high temperature, if it contains according to its nature, from 15 to 20 per cent. of the salts employed.

FIREPROOFING OF WOOD BY ELECTRICITY.

The successive operations and the apparatus for incorporating the fireproofing salts in the mass of the wood are nearly the same as those for the ageing of wood properly so-called. It is absolutely necessary for the treatment that the wood should be both green and not too hard. The penetration of the salts being effected in great part by osmose, the sap is an important factor; and a hard wood would be difficult for the introduction of a quantity of preserving substances.

The vats employed are on the average 4·50 metres long, 1·50 metres wide, and 0·70 metre deep. They may be of cement or of wood lined with lead, like those used for ageing with magnesium sulphate, but the solution of ammoniacal salts is heated by a worm of hardened lead, instead of copper, in which the steam circulates.

At each of the extremities of the vat is a vertical partition of lead perforated with holes, forming a kind of reservoir, 0·25 metre wide by 1·50 metres long (the width of the vat), in which are poured the fireproofing salts necessary for maintaining the solution at saturation.

The wood is piled upon the lower electrode to a height of 0·15 metre to 0·20 metre at the maximum, and covered with porous vessels containing the second electrode. The fireproofing bath employed is a saturated solution at the temperature of 80 deg. C. of ordinary ammonium sulphate and ammonium borate.

The electromotive force of the electric current utilized ought not to exceed 25 volts. The electricity passes into the wood always in the same direction from below upward.

According to numerous tests which have fixed the constants of the electric treatment, the best results are obtained with an intensity not exceeding 12 to 16 ampères per stere of wood; that is to say, that the electric energy necessary is about half an electric horse-power per stere in treatment.

The total duration of the operation is 48 hours, divided into two equal parts. At the end of the first period, the wood is reversed (turned upside down). The wood thus treated has absorbed from 15 to 20 per cent. of its weight of the salts of the bath. These salts penetrate to the heart of the cells and form a sheath around the fibre. If the wood after drying is submitted to the action of fire, the ammoniacal salts, which encompass the fibres, melt. On increase of the heat, the fibrous matter is carbonized slowly and the gaseous products resulting from the decomposion of the salts prevent the ignition of the combustible products proceeding from the calcination of the fibre. In a word, the fire is limited to the points attacked and is not propagated to the neighbouring fibres.

The official tests conducted at Paris by the fire department are conclusive On the application of the officials the inventors constructed a number of cubic boxes, 0 50 metre in size of spruce and poplar fireproofed planks 26 millimeters in thickness; the bottoms of the boxes were perforated with five holes. One of the boxes was filled with a kilogramme of dry shavings, which, when set on fire, required five minutes for consumption. A large amount of heat was developed. After the combustion it was found that the outside walls of the box had remained cold, and that the inside had not been charred beyond the thickness of 1 millimeter. No point remained on fire and no part of the wood was separated under the influence of the extreme heat.

The second box contained a double weight of shavings which were thirteen minutes in burning. When the combustion was completed it was found that the interior of the box was red with heat, but without flame.

The third experiment took place with a fireproofed box of white wood, in which three kilos of shavings were burned. The test lasted for 30 minutes, the interior was incandescent and the wood charred for five or six millimeters in depth, while the exterior was simply heated.

Another test with a spruce box not fireproofed containing 1 kilogramme of shavings ended in three minutes in a small conflagration, which had to be extinguished with water. These results are conclusive.

A piece of fireproofed wood submitted to the action of the electric spark is simply carbonized at the parts of contact, while wood not treated bursts quickly into flame.

The curious tests on the resistance of certain building materials to fire, conducted before the representatives of foreign fire departments, may also be cited. A square construction of cement was filled with 7 or 8 steres of wood moistened with petroleum. It was furnished on one of its sides with an iron door, on its second side with a door of wood fireproofed by this process, and on the third with a window of protected glass, that is, glass cast on metallic gauze. Wood piled up in this enclosure was set on fire and extinguished after the interior temperature had reached about 1400 deg. The door of wood was consumed only after the lapse of one hour.

The iron door was very quickly put out of shape and allowed such a quantity of heat to pass that ordinary boxes placed at a distance of three metres were consumed.

This method of penetration furnishes complete security in other extreme exposures. The wood designed to receive electric wires may, by being previously fireproofed, avoid the serious accidents which frequently occur.

Wood thus rendered incombustible is imputrescible, its tenacity is the greater, but it can be readily worked. It can be glued perfectly and receive the painting or varnishing desired for preventing the penetration of the moisture of the air and avoiding completely the decomposition of the ammoniacal salts.

This new method of rendering wood incombustible, while materially augmenting its value, does not involve too large an expense. Experience, indeed, has shown that the cost of fireproofing by this process is less than that of other methods in use, and that the wood can be employed for numerous purposes, especially on war vessels, where metal has been hitherto used.—*Translation in the Scientific American Supplement from the Revue de Chémie Industrielle.*

VII.-TIMBER AND PRODUCE TRADE.

Churchill and Sim's Wood Circular.

4th November 1902.

East Indian Teak.—The deliveries in October consist only of 501 loads, against 1,416 loads in October, 1901. For the last ten months they amount to 10,481 loads, against 11,996 loads for the same periods last year. The market has been rather lifeless during the month, and it is difficult to get prices here commensurate with those justified by the lack of supplies at the shipping ports consequent on want of water. Some partial improvement has been experienced in this latter respect according to recent reports. There has been a fair demand for planks at satisfactory rates.

ROSEWOOD, EAST INDIA.—The present small demand is amply covered by existing stock.

SATINWOOD, EAST INDIA.—Plain wood is of slow sale, but for finely-figured logs good prices are obtainable.

EBONY, EAST INDIA—is in steady demand, provided the wood is of fair sizes and in good condition.

PRICE CURRENT.

Indian Teak, logs, per load	...	£10 5s to £18 10s.
„ „ planks „	...	£13 5s. to £20.
Rosewood, per ton ...	...	£7 to £10
Satinwood, per s.ft. ...	...	5d. to 12d.
Ebony, per ton ...	...	£9 to £12

Denny, Mott and Dickson, Limited.

WOOD MARKET REPORT.

London, 4th November 1902.

TEAK.—The landings in the docks in London during October consisted of 1,097 loads of logs and 171 loads of planks and scantlings, or a total of 1,268 loads, as against 1,034 loads for the corresponding month of last year. The deliveries into consumption were 221 loads of logs and 302 loads of planks and scantlings—together 523 loads, as against 1,428 loads in October 1901.

The dock stocks at date analyse as follows:—

	6,183	loads of logs,	as against	7,562	loads at the same date last year.
	3,094	„ planks	„	4,575	„ „ „
	—	„ blocks	„	99	„ „ „
Total	9,277	loads	„	12,236	„ „ „

The falling off in consumption shown by the above figures is a natural result of the enhanced prices to consumers—consequent on the restricted import. Shippers claim that the arrivals from the forests are so short that the supply of European timber must fall short of next year's requirements for Europe. Dull trade is, meantime, strengthening consumers in holding off purchasing; and the substitution in construction of oak and other hardwoods for teak is developing, and serving to check business in planks and converted sizes. A very slow market may, therefore, be expected until time show whether the demand will exceed the quantity which the shippers may find it convenient to supply. Shipments to Europe beyond this convenience can only [illegible] forced by prices sufficiently high to tempt shippers to make [illegible] efforts, and the tendency beforesaid to seek substitutes for [illegible] in construction must play a considerable part in forming a conclusion as to how far the shippers will finally be masters of the position.

October has been a disappointing month to the timber trade; no excuse as to holiday dulness can now serve as a reason for the dragging consumption and much unprofitable trading. There is a disposition to shorten credit, and prepare for difficult times. The high rates demanded by shippers in so many markets naturally limit forward buying: and this feature, though adding to the general dulness of business, is really a healthy one—as tending to restrict unsound finance.

THE

INDIAN FORESTER.

Vol. XXIX.] February, 1903. [No. 2.

The Insect World in an Indian Forest and how to study It.

By E. P. Stebbing, F.L.S., F.E.S.

(*Continued from p. 18.*)

Part V.

The Order *COLEOPTERA.*

These appear to be wingless insects, but have really four pairs of wings. The upper pair, which are called the 'elytra,' are hard and horny and shell like, fitting accurately together over the back, thus protecting it and the lower wings, which are folded beneath them and are membranous. In the mouth mandibles are present, and the lower lip is divided along the middle. The metamorphosis is complete. The larva is grub-like, and changes to a pupa in which all the parts of the perfect insect are distinguishable, but are still white and soft.

Coleoptera are one of the largest and most important of the Orders of Insects as well as being one of the most injurious in the forest. Both larvæ and imagoes bore into timber (and also into the roots) and lessen or destroy its value. They also girdle branches and kill them, feed upon and defoliate the leaves, and burrow into and destroy the seed.

Beetles are chiefly distinguished from other insects by the solidity of their outer covering and by the peculiar nature of their first pair of wings, which are not used as instruments of flight, but merely serve to protect the hinder part of the body. Beetles are not found on the wing as much as other insects, and therefore, notwithstanding their enormous numbers, they are not met with so frequently as ants, bees, flies, etc. The number of species at present known is probably about 150,000, and their habits are so varied that they can be found everywhere when looked for. The general form varies much from flat-spherical to long-linear. The head is well developed, with a biting mouth; compound eyes are present, which are not uncommonly divided. Ocelli (simple eyes) are rare. Antennæ eleven-jointed or with fewer joints. These latter are variable in shape and are of importance in classification. When the elytra are shut up, they cover the greater part of the meso- and meta-thorax, abdomen and the lower wings. At the top there is a triangular portion called the scutellum, which forms the upper part of the meso-thorax. The elytra may leave a few of the lower segments of the body exposed. These elytra are of such importance to the beetle that they are even present in cases where there are no lower wings. When this occurs they are often joined together down the central suture so as to form one piece, though the line representing the junction is always present. When a beetle flies, the elytra open slightly upwards, letting free the lower wings. In the common rose chafer (the green metallic looking flat beetle to be found upon roses), where the elytra are joined together they are merely lifted up; when the elytra are absent, as occurs in some beetles, there are no lower wings present. The nervures or veins in the lower wing are broken up to allow of their being folded up under the wing covers. The number of tarsal joints present varies from 2—5. One may be hidden and is only seen on dissecting. For classification purposes only those visible are counted. Some of the tarsal joints may be bi-lobed; they are set with a spongy felt-work of hair to help the insects to walk up on plants. Only 5—6 segments of the abdomen are visible. There is often a considerable difference in the sexes amongst beetles. There may be either an increase in size of the antennæ in the males or an enlargement of the interior tarsi; occasionally the number of joints of the tarsi vary in the two. The only music produced is chirping or squeaking by rubbing two files together. Phosphoretic organs are present in glow-worms and fire-flies. These consist of masses of cells connected with a fatty body and are freely supplied with air. The light produced is caused by the oxidation of proteid matter. These organs are situated on the abdomen. The larva is grub-like, with a distinct head and jaws; sometimes antennæ and six legs are present. They have no special boring apparatus and the sexes are distinct. They usually feed at night and upon all sorts of substances. They are sometimes parasitic upon other animals, but this is not usual. The pupa is quiescent and usually enclosed in a rough cocoon. The adult may live near the cocoon for some time after emergence without movement, whilst its outer layers of chitin are slowly hardening (this will be found common amongst the bark borers, *Scolytidæ*). The beetle when found in this condition under the bark is yellow or light brown in colour, changing to dark brown or black before it finally emerges from the tree.

Coleoptera are classified according to the number of tarsal joints present, into four great groups, and these groups are again divided into series as follows:—

Pentammera—5 tarsal joints present upon all the legs.	Series. Lamellicornia—Antennæ with the terminal joints broader on one side so as to form a peculiar club, the leaves of which are movable. Series, Adephaga or Caraboidea—Antennæ filiform or nearly so Series Clavicornia—Antennæ usually thickened at the tip or knobbed. Series, Serricornia—Antennæ usually serrate along their inner edge
Heteromera—1st and 2nd pairs of legs have 5 tarsal joints, the third pair have 4 only	The families Tenebrionidæ and Canthandæ only will be considered here.
Tetramera—4 tarsal joints present on all legs.	Series, Phytophaga—Head not forming a definite prolonged beak Series Rhynchophora—Head more or less prolonged in front to form a snout or beak (rostrum)
Trimera—3 tarsal joints present on all legs	The family Coccinellidæ only will be considered here

PENTAMMERA.

5 tarsal joints on all the feet.

LAMELLICORNIA.

Tarsi five-jointed; antennæ with the terminal joints, called *lamellæ*, usually three in number (sometimes more), broader on one side, forming a club, the leaves of which are movable, but in repose look like one piece, as they are held close together. The families *Passalidæ*, *Lucanidæ*; and *Scarabæidæ* are included here; the form of the leaves of the club of the antennæ varies in shape in these three families. The larvæ live in decaying vegetable matter, roots, or dung. They have a horny head, large jaws and three pairs of legs, and are thick clumsy grubs with curved bodies, the last two segments being of larger size than usual and often swollen out in a bag-like manner.

FAMILY PASSALIDÆ.

The upper lip is large and mobile and the mentum is deeply cut out in the middle. The antennæ curl upwards and the plates at the top are thus brought together. These beetles are usually shining black in colour and are abundant in decaying wood in tropical forests. The larvæ appear to have only four legs, the first pair being short processes which are used to produce sounds by scraping over striated surfaces on the next pair. Very little is at present known about these insects in India.

FAMILY LUCANIDÆ (STAG-BEETLES).

The stag beetles are well known owing to the enormous horns present. These horns are only greatly developed mandibles, and are only present in the male beetle. Upper lip is small and the mentum is not cleft. The antennal end consists of a [illegible] cone, which is rigid and does not open and close. The male is usually larger than the female. Five ventral abdominal segments are visible. The larva has the last two segments of its body swollen up in a bag-like manner, and lives in decaying wood and roots, spending several years of its existence in this stage. The pupal stage is a short one, but the perfect insect may remain quiescent some time after leaving the pupa before it becomes active.

In the outer Himalayas the mature beetles are to be found in June and July. It is probable that they issue irregularly during the summer months, as the writer has found fully-developed larvæ just pupating and also mature beetles in July. Some years ago Lucanid larvæ were reported as tunnelling into green living oak trees in Naini Tal. Owing to their queer swollen bag-like extremities it is extremely inprobable that these larvæ are capable of tunnelling into green hard wood. It is probable that if boring was done in hard oak timber, longicorn larvæ were responsible, and the stag-beetles may have taken advantage of the galleries to lay their eggs in the ones whose edges were rotting and thus becoming softer. The writer has found numerous instances of decaying oak, etc., stumps being full of these larvæ but no instance of hard green wood being infested.

Family Scarabæidæ (Chafers).

The leaflets of the antennæ are freely-movable plates, which can be closed together at will by the insect. The number of visible ventral segments is usually six or at the sides seven, never five as in the last two families. The elytra generally leave one or two of the last segments of the body exposed. The beetles of this family are bulky insects, having a powerful prothorax and front legs with flattened spiny tibiæ adapted for digging. Both larvæ and adults feed upon plants and dung. The family is an important one amongst insects. About 13,000 species are already known. At times the males are armed with horns of various shapes growing out of the head and prothorax. Several subfamilies are distinguished.

The *Coprides* or dung beetles live as larvæ chiefly on the dung of the ungulata; they form the dung into balls, which they roll along by means of their hind legs or by pushing with their head until they have reached a suitable place; they then dig a hole and push the ball in and get in themselves and feed upon it. Later on they dig another hole, fill it with dung and lay their eggs in this and close up the aperture. The young larva on hatching out feeds upon the store thus provided. They are thus useful insects, as they act as scavengers.

The *Melolonthides* include the cock-chafers. The larvæ of these beetles feed upon roots, often doing a great deal of damage, whilst the beetles live upon leaves. The larval life extends often over several years, during which time the grub grows in size and feeds voraciously, living underground and only coming to the surface at night. The pupal stage is very short, but the adult may remain a long time in the ground after leaving the pupa before emerging from the soil. The ♂ can be recognised from ♀ by the larger lamellæ on the antennæ In India a species of cock-chafer, *Melolontha vulgaris*, has been reported as doing immense damage in flower gardens, vegetable gardens, and tea gardens, where it is known as the 'white grub' This species does not, however, appear to have been yet reported as causing injury in nurseries. Recently (July 1901) larvæ of a large species of cock-chafer were found by the writer seriously damaging young deodar seedlings, which had been planted in patches in the Bashahr Division in the Punjab. The beds were riddled with holes, out of which portions of young green deodar seedlings were seen protruding. Seedlings bitten off at their bases were also found lying on the bed withering up Three to four inches down in the soil large yellowish-white cock-chafer grubs were found.

The *Dynastides* include the large bulky beetles whose males have enormous projections and horns on there heads and prothoraces, the use of which is not at present understood Members of the family are common in India The large Goliath beetle (*Oryctes rhinoceros*) also called the Rhinoceros beetle, belongs to the *Dynastides*. It lives in cocoanut palms, and injures them by cutting holes in the developing shoots and burrowing downwards This insect has proved excessively destructive in Kanara and the Madras Presidency. Its larvæ are to be found in heaps of rotting vegetable matter. Such heaps should never be allowed to accumulate in the neighbourhood of the cocoanut trees.

The *Cetoniides* include the rose-chafers, the small, brightly-often metallic-coloured beetles which are to be found upon rose bushes.

ADEPHAGA OR CARABOIDEA

Tarsi five-jointed, antennæ filiform or nearly so. Mouth parts highly devoloped with slender projecting mandibles; ventral segments of abdomen visible usually five in number. Active, slim dark-coloured beetles, with long powerful legs, all of whom, including their larvæ, are carnivorous. The larvæ are usually dark-coloured, with a group of ocelli on each side and with well developed legs each with two claws, only one claw is present in all other coleopterous larvæ.

FAMILY CICINDELIDÆ (TIGER BEETLES).

Bright-coloured beetles with large eyes and with the clypeus (lower part of front of the head) extending laterally in front of the insertion of the antennæ, the latter being long and straight. The mandibles are large and are set vertically instead of horizontally. The elytra are often spotted.

This family includes some of the most active and fierce carnivorous of the beetles. They feed upon insects of all kinds. The larvæ live in burrows in the ground, where they lie in wait for their prey. A species named *Cicindela punctata* has been reported as destructive to the rice sapper, *Leptocorisa acuta*, a destructive pest in the rice fields. Investigation will doubtless show that species exist of use in keeping down forest pests.

FAMILY CARABIDÆ (GROUND BEETLES).

These beetles resemble the *Cicindelidæ*, but the mandibles are set horizontally. They are usually blue or black in colour and are carnivorous in their habits. A species named *Calosoma orientale* attacks and preys upon the young of the locust *Acridium peregrinum*, destroying them in large numbers. Several other species are very common in India. The writer noted that a large Carabid beetle with cream coloured blotches on its elytra feeds upon the larvæ of the hawk moth *Pseudosphinx discistriga*, which defoliate the teak in Berar during the rains.

Note.—The water beetles, *Dytiscidæ*, and the whirligigs, *Gyrinidæ*, seen swimming in circles on the surface of pools and streams in the sunshine belong to this series, but are unimportant.

CLAVICORNIA.

Tarsi usually five-jointed. Antennæ thicker at the tip or knobbed. All the parts of the insects in this group may vary, exceptions being numerous.

Some of the insects of this series are kept by ants in their nests.

Many flat clavicorns feed under bark on the sap of the tree. A species feeds in this way under the bark of sal trees and another is to be found amongst bark boring beetles under the bark of the blue pine (*Pinus excelsa*). These beetles should not be confused with the true bark-borers.

FAMILY SILPHIDÆ (CARRION BEETLES.)

Antennæ clavate or at least flattened at the tips. In some forms the elytra cover the whole of the abdomen: in others its tip is left uncovered. These beetles are as a rule carrion-feeders. The genus *Silpha* has slightly clavate antennæ, elytra covering the whole of the abdomen and the body of a flat oval form. The larvæ are broad and flattened and find their own food, that is, it is not stored up for them by the parent beetle Both larvæ and adults feed on dead animals. The burying beetles (*Necrophorus*) have markedly clavate antennæ, elongate bodies and short elytra, usually coloured in red and black bands, leaving the hinder end of the body uncovered. Several generally unite to bury small mammalia, etc., removing the earth below the carcase, in which they lay their eggs. The larvæ are pale and large, possessing legs and eyes; they feed upon the carrion buried by their parents. These beetles may be seen in the forest at work in this way.

FAMILY STAPHYLINIDÆ (ROVE BEETLES).

These beetles are distinguished by the small size of the elytra; the larger portion of the abdomen, which is very movable, is not covered by them, but is covered by a thick layer of chitin on its dorsal surface. The hind wings are folded under the elytra. The body is elongate and antennæ filiform. The adult generally lives upon decaying plant and animal substances. The larvæ are like those of *Carabidæ*, but have only a single claw on each foot. They have two-jointed cerci at the end of their bodies. They feed either like the adults or are predaceous. Numerous mature beetle forms, believed to be predaceous, have recently been found by the writer in the tunnels of bark or wood boring *Scolytidæ* in deodar, spruce, and blue pine, etc., and it is probable that the family will be found to be of considerable forest importance in this respect.

FAMILY HISTERIDÆ.

Compact beetles with hard integument, often shining, and short, bent antennæ ending in a compact club; elytra leave two segments of the body exposed. Abdomen with five visible ventral segments; hind coxæ are widely separated.

These beetles are common in dung, in carcases, decaying fungi, etc., and some live under bark, these being often very flat insects. Some are small cylinders, constructed for entering the burrows of insects boring into wood. It has been for some time believed, and the writer has been able to verify the fact in several instances quoted below, that these insects are predaceous and feed upon the larvæ and adults of boring beetles. Some live in ants' nests, probably devouring the larvæ. A few species live in company with Termites.

From observations made during the last few years the writer is of opinion that members of this family play an important part in keeping down the numbers of wood-boring and bark-boring beetles of the families *Bostrichidæ* and *Scolytidæ*. Species of Histerids (*Teretriosoma*) have been found in the tunnels of the bostrichid wood-borers *Sinoxylon crassum* and *S. anale*, whilst numerous others have been found in the galleries of newly-discovered bark-borers of the genera *Scolytus*, *Polygraphus*, *Hylesinus*, *Tomicus*, etc.*

FAMILY NITIDULIDÆ.

Antennæ have a three-jointed club; all the coxæ are separated, and each has an external prolongation; tarsi five-jointed, the fourth joint being smaller than any of the others; abdomen with five visible segments. The habits of these beetles are very varied; some live under flowers, others in the bark on the sap of trees, others again in carcases. One larva causes much loss by living in the flowers of mustard (rape) and prevents the seed forming. It pupates in the ground. Another one feeds upon turnips. Many Indian forms will doubtless be found feeding upon the sap of trees on newly-cut stumps, etc., and should not be confused with bark and wood borers.

---

* See Departmental Notes on Insects that affect Forestry, Nos. 1 and 2.

FAMILY TROGOSITIDÆ.

These beetles resemble the above family. Some are of fair size. They are predaceous and destroy the larvæ of other insects in large numbers. One species has been found predaceous upon bostrichid beetles which were attacking *Terminalia tomentosa* posts.[*]

FAMILY DERMESTIDÆ.

Small beetles with clavate antennæ and deflexed heads; the surface of the body is covered over with small close-set hairs. The beetles and their larvæ feed upon dead animal substances, such as skins, etc., and are often very injurious to the latter. The larvæ and beetles issuing from a newly-shot skin that has been left untended for a few days are *Dermestidæ* and will not unlikely be the common species *Dermestes vulpinus*. When full fed the larvæ hide themselves away, sometimes burrowing into hard wood. They do damage in museums and to stored hide goods, boots, etc. To protect saddlery, etc., when stored away, from such pests the articles should be placed in tin-lined boxes and plentifully besprinkled with napthaline before the case is sealed up.

SERRICORNIA.

Antennæ usually serrate along their inner edge. Other characters may be variable.

FAMILY BOSTRICHIDÆ (BARK AND WOOD BORERS).

Antennæ straight, often lamellate at the top. Tarsi five-jointed, but the first joint is very short; front coxæ are prominent and contiguous and extend very little transversely; five ventral abdominal segments are visible. The prothorax is often furnished in front with protuberances, and the elytra behind may be truncate and furnished with small spikes. The larvæ are white, have three pairs of legs, and have the posterior part of the body incurved. These beetles attack dry wood in which they lay their eggs, the larvæ on hatching out also feeding upon the wood. The insects are at times present in such numbers that they entirely riddle and destroy the timber they infest. One or two members of the family have already proved to have a wide range in India, such, for instance, as several species of *Sinoxylon* in the wood of broad-leaved trees and of *Dinoderus* in bamboos. *Sinoxylon crassum* and *S. anale*, both of which have a wide distribution in the country, do considerable damage to wood stacks in the Changa Manga plantation, and these beetles will always have to be reckoned with in fuel and wood depôts in India. The life-history of *S. crassum* is as follows:—At Changa Manga this beetle makes its first appearance in the year about the beginning of April and burrows into the Sissu fuel stacks, consisting of the wood cut over between the previous November to March; this wood is collected and stacked upon the adjacent compartment lines to allow the fuel to dry. Eggs are laid by the beetles, which hatch out into small white grubs within a few days. The larvæ feed entirely in the wood and take about six weeks to become full fed. Beetles from these larvæ emerge from the wood in July and at once lay the eggs of another generation in suitable wood, these eggs giving rise to the second generation of the beetles in September-October. These beetles hibernate as such in the wood through the winter. In warmer parts of the country there are probably at least three generations of this pest in the year. *S. anale* will attack drier wood than its companion, and has probably a greater number of life cycles in the year.*

---

[*] *Vide* 'Insect Life in a Terminalia Post' in the *Indian Forester*, Vol. XXVIII, No. 8.

Protection.—Keep the coupes as clean as possible and remove all cut wood before April from the neighbourhood of the forest.

Two species of *Dinoderus*†, *Dinoderus pilifrons* and *D. minutus*, are common bamboo pests. They will not attack the green standing bamboo, but as soon as it is felled, if unprotected, it will be riddled by the *Dinoderus* beetles. These borers act in much the same way as already described above for the *Sinoxylon* and have several generations in the year. They are both widely distributed in the country, *D. minutus* being practically cosmopolitan in tropical regions.

Protection.—As soon as felled, bamboos—and this applies equally to poles—should be either kept under water for a few weeks or smoked so as to dry them quickly.

FAMILY PTINIDÆ.

Tarsi five-jointed, the first joint not reduced in size, often longer than the second; five visible ventral segments. The prothorax is often hood-like and often covered with rasp-like projections, and there are several species the posterior end of the body of which may be truncate. Boring is done in both the grub and beetle stages. Two sub-families, the *Ptinidæ* and the *Anobiidæ*, are included here. The *Ptinidæ* are sometimes destructive to dried animal matter and attack museum specimens. The *Anobiidæ* bore into wood and apparently spend a very short time in the adult stage. Their larvæ resemble those of the last family.

The so-called cheroot 'weevil'* (*Lasioderma testaceum*) and the biscuit weevil [*Anobium (Sitodrepa) paniceum*] belong to this family. The cheroot weevil runs through a large number of generations in the year. To get rid of this destructive insect from a tobacco store, the only plan is to burn all infected stock and thoroughly cleanse out all godowns.

---

* *Vide* Departmental Notes on Insects that affect Forestry, No. 1, pp. 15-18.

† *Vide* [illegible] Indian Forests [illegible] Notes on Insects which affect Forestry, No. [illegible] pp. [illegible]–178.

FAMILY MALACODERMIDÆ.

Beetles with very soft bodies and elytra; the prothorax is generally broad and shield shaped, and the head may be hidden beneath it. The elytra are soft and leathery, and are not rigidly attached to the body. They do not meet in a hard and fast suture in the middle, and often leave several body segments exposed. Eyes are large; seven visible ventral segments of the abdomen are present. The females are often wingless. The family includes the *Lampyrides* or glow-worms and the fire-flies (*Luciola*) The larvæ are supposed to be carnivorous, but little is known about them in India. The phosphorescent apparatus is placed ventrally at the posterior end of the abdomen. In the glow-worms the ♀ is wingless and her light is much more powerful than that of the male and may serve to attract him. In the fire-flies both males and females have wings and the light is more powerful in the male than in the female.

FAMILY CLERIDÆ.

This family contains beetles of varied form and colour. The antennæ are usually more or less club shaped at the tip and not at all serrate. The tarsi are five-jointed, but the basal joint of the hind tarsus is very short and the apices of joints two and four are usually prolonged into membranous flaps. The insects have in some instances a superficial resemblance to small longicorn beetle (*Cerambycidæ*). The *Cleridæ* are exceedingly predaceous and their larvæ are very active, being especially fond of wood and bark boring grubs. Observations have led the writer to form the opinion that members of the family are of the greatest service to the Forester in India owing to their predaceous habits. A species of *clerus*, probably closely allied to the European *Clerus formicarius*, is predaceous, both in its larval and imago stages, upon various wood and bark boring beetles in the coniferous forests of the North-west Himalayas. The following is what is at present known upon the life-history of this insect* :—

The larva is an elongated, flat, pink-coloured grub with a brownish head, well-marked black mandibles, and the last segment of the body terminating in two small black processes or points. The beetle is an active bright-coloured insect with an ant-like black head and prothorax, whilst the elytra are red at their bases and black anteriorly, the black being crossed by two white wavy bands. The abdomen beneath is bright vermilion in colour. The insect is half an inch in length. The beetles are to be found plentifully in June, July, either on the wing or runnning actively about on the bark of coniferous trees (also oaks to a certain extent) such as deodar, spruce, blue pine, etc , searching for bark beetles. As these latter emerge from, or settle upon, the bark of the trees, the Clerids seize and devour them, only the harder portion of the chitinous exterior being rejected. Inside the tree in the galleries made by the bark-boring beetles and their larvæ in the cambium and sapwood are to be found the pink larvæ of this clerid engaged in feeding upon the bark-borer grubs. It is probable that the predaceous beetle lays its eggs in the entrance holes of the boring beetles, and the young grubs on hatching out find their way down the entrance tunnel into the egg and larval galleries of the bark beetle. Larvæ of various sizes have been found in the tunnels between May and October, and it is not improbable that there are several life cycles in the year overlapping each other, and that consequently the beetle is to be found on the wing in the forest during these months. The insect is polygamous and excessively voracious. The writer has observed it to feed upon one or more species of the genera *Scolytus*, *Polygraphus*, *Pityogenes*. *Tomicus*, *Hylastes*, *Rhyncholus*, *Diapus*, and *Platypus*, all bark or wood boring members of the families *Scolytidæ** and *Platypodæ*. All these latter beetles have been recently discovered in the North-west Himalayan forests and are new to science. They will be described shortly later on in this part.

---

* See Departmental Notes on Insects that affect Forestry, No. 2, p. 214.

The importance of the discovery of this Clerid is evident when it is remembered that *C. formicarius* is known to be of the greatest importance in keeping down bark beetles in European continental forests. So great is the value attached to the beetle that in 1892 a specialist was deputed from America to import it into that country in the hopes of bringing down to normal proportions some devastating bark-boring beetle attacks.

FAMILY ELATERIDÆ (CLICK BEETLES).

Small beetles with a much sunk head and a square prothorax which finishes behind in two points. Legs bristly, short, and very rigid. The prothorax is prolonged on the under side into a spine which fits into a pit in the mesothorax. This arrangement is to enable the insect to jump up into the air when on its back and so turn over again. When the prothorax is raised, the spine is supported against the edge of the depression, and on its being allowed suddenly to shoot back into the pit, the insect strikes the ground with considerable force and is thus jerked up into the air. The click they make in this movement gives them their name of click-beetles. The grubs are called 'wire' worms. They are long, thin and hard and consist of twelve segments with a flattened horny head and three pairs of legs. The head is dark brown and the twelve remaining segments yellow to yellowish brown. They can be distinguished from millipedes in possessing only three pairs of legs, whereas the latter have two pairs of legs on each segment.

---

* *Vide* Departmental Notes on Insects which affect Forestry, No. 2.

Some members of this family are quite harmless, since they only devour decaying vegetable matter, either in humus or in the rotting substance of dying trees where they are often to be found. Many elaterid larvæ, however, are destructive as root-feeders, and it is in the forest nursery and in areas sown or planted up in patches where trouble may be expected from these pests. The grubs are very active and destroy much more than thay actually devour, moving from plant to plant and cutting through the roots below the surface of the soil. In this way they may destroy whole lines of young plants in a nursery. The larvæ live for several years in the ground and probably feed during most of the time, growing to full size very quickly and spending the rest of the time as a full-grown grub. Though constituting a serious pest in European forests they have not been reported in this connection in India. Recently, however, the writer has found wire-worms present at the roots of young deodar plants which had been sown in patches and at those of a dying young sweet chestnut which had been imported from England. In both cases, which occurred in the North-west Himalayan forests, an inspection of the roots showed that the dying condition of the young plants was probably due to the elater grubs. This family and the damage they are capable of doing should be borne in mind when seedlings are seen to be dying in the nursery without any visible cause to be seen above ground.

FAMILY BUPRESTIDÆ.

These beetles resemble the *Elateridæ*, but they have not the jumping apparatus, the pro- and meso-thorax being firmly united. The beetles are often very brilliantly coloured with metallic colours. The lower wings are often the same size as the elytra; the antennæ are typically serrate. The larvæ are soft and white with a horny head which is retractile, and an enormous prothoracic segment. They have no legs. The segments of the abdomen are much narrower than the prothorax, and by this these larvæ can be always distinguished from longicorn ones, which they otherwise closely resemble. They usually live upon wood and do damage by attacking newly felled timber, in which they bore large winding flat galleries. Healthy trees are generally safe from these attacks, but the moment a tree becomes sickly and weakened from any cause, buprestid beetles at once lay their eggs in the bark and the larvæ bore into the wood. These insects are numerous in India, but little information has as yet been collected on their life-histories. Most trees will be found to be subject to their attacks. The larvæ of a yet undescribed species are invariably present in deodar bark, which has been attacked by the bark-boring Scolytidæ, and the rule applies to the spruce and blue pine. In each instance the buprestid comes in later than the bark-borer. There is a small buprestid to be found commonly in the branches of the sal, it taking about a year to pass through one life cycle,

Progress in the United States.

How is it that the States have made more moral progress in Forestry as a cause in ten years than India has done, or will do, in a century? There are various reasons, but the fundamental one is that the President, Congress, and an increasing section of the people *mean* Forestry, whereas in India the progress of the Department has been a continual struggle with the people and often with local authorities The other important reason is that the people there are educated enough to conviction.

I have been favoured with copies of *Bulletins* 32, 33, and 34 of the U. S. Department of Agriculture, and they have given me a pleasure which I wish to share with others.

Bulletin No 32 is "Working Plan for Forest Lands near Pine Bluff Arkansas," by F E Olmsted, Field Assistant, Bureau of Forestry, published under the direction of Gifford Pinchot, Forester. Some of us will remember Mr Olmsted's visit to this country, and the interest with which he studied our forestry. The "Working Plan" is illustrated with 19 half-tone blocks from photographs of the forests concerned, and several diagrams It is not at all drawn up on the lines of Indian Plans, for it only occupies 48 pages royal octavo, but it appears to be none the less a sound and practical plan. It is divided into two parts. Part I comprises a general description of the forest, the markets, taxes, transport, lumbering, fires, grazing, etc, with short sylvicultural notes on the more important species These are, shortleaf pine, loblolly pine, cow-oak, white-oak, sweet gum, white ash, shag bark, hickory, holly, and hornbeam. The forest consists of pine ridge, pine flats, and hardwood bottom, the two former covering 85 per cent of the total area, which is about 100,000 acres unsurveyed, belonging to the Sawyer and Austin Lumber Co. The crop is mixed throughout, but in the pine lands the shortleaf pine forms about 35 per cent. The loblolly forms only about 18 or 20 per cent., and is held to be the principal species, the increase of which is one of the objects in view. The shortleaf at present fetches a slightly higher price, since it carries less sapwood, but the loblolly is faster growing, easier to regenerate, forms a denser and purer mass and consequently is a more profitable forest

Part II discusses the question of yield, the effect of fire-protection (which cannot be undertaken all at once), the [illegible] returns, and the rules for management. The method adopted is selection, and the possibility is limited by a diameter of 12 inches at breast height. This is very small, but the forest has to provide steady employment for sawmills able to turn out 40,000,000 board feet per annum. If these mills are to be kept in full work, another 176,000 acres will have to be [illegible], for with the 12 inches limit the yield will only be about [illegible] board feet. Whether the limit be placed at 12 inches or [illegible] inches the crop will be ready for another selection in about 42 years, and the interest on capital varies between 3½ and 9 per cent., according to the size, the prices assumed, and the stumpage value assigned to the cleared land. The refuse is to be burnt in order to give fires less chance of running through.

Bulletin No. 33 is about the Western hemlock (*Tsuga, heterophylla*) by E. T. Allen. This is a tree whose reputation has suffered by confusion with its Eastern namesake. It is found from Alaska, through Oregon, Montana, Washington, etc., to California. It is a large tree up to 8 feet diameter and 250 feet high, and though rejected by lumbermen, is quite fit to replace the various firs, spruces, etc., that are now becoming scarce. It is indeed surreptitiously substituted for these by some few who have realised that the timber is good enough if its real name can be concealed. The *Bulletin* contains 23 excellent half-tones of the tree in its native haunts, its wood, and its diseases. One of its great advantages is that white-ants do not touch it. Comparative tests were made with this object, and one reads with an inward chuckle that in the case of California redwood and Califorina white cedar that the "ants tried, but discontinued after slight effort." It is said that Western hemlock is so distasteful to rodents that they will not attack corn-bins made of it. Casually it may be mentioned here that a solution of quinine is a cheap and effective caution to rats that are given to gnawing boxes, etc. They take one little chunk out, drop it at once, and make tracks.

The bark is a valuable tanning material, and the tree has two distinct kinds of bark in different localities. Above 2000 feet it is rough and often two inches thick, while at lower elevations it is much thinner and smoother. A "peeling crew" consists of three men. The "faller" is a feller. The "fitter" trims off branches, rings the bark at intervals of four feet, and slits each section lengthways. The "spudder" peels the bark with a flattened bar, and spreads it on the ground, with the inner side, or flesh, up. After curing in the sun for five or ten days it is carefully piled, outside up, to season, which takes two or three months in dry weather. If left till winter it becomes covered with snow or ice, curls badly, and loses much of its value. The tanning is 10 per cent for Eastern and 16 per cent for Western hemlock bark, with of course variations. The "long cord" of the East is 2240 lbs. In the West there is also a "short cord" of 2000 lbs. Stems are peeled up to 12 inches diameter. It takes 45 trees 13 inches thick, 11 trees 20 inches thick, three trees 30 inches thick, and one tree 50 inches thick to furnish the long cord. An acre of pure young second-growth hemlock may yield at 50 years two cords, at 80 years nine cords, and at 120 years 11 cords.

Bulletin No. 34 is a very interesting one on the "History of the Lumber Industry in the State of New York." by W. F. Fox.

with 30 more of the excellent half-tone pictures. The earliest settler was the first lumberman, but it is stated that the destruction of the forests is due to the farmers and their fires, rather than to the lumbermen, who do not intentionally burn forests.

In 1614, when the first houses were built, the State of New York was forest throughout, with the exception of a few crops of the indigenous Six Nations, and a few small areas burnt by them for hunting. The principal species was white pine, a species averaging two to four feet diameter and 130 to 160 feet high, but known to reach 255 feet high and seven feet diameter. Other species are the shortleaf (*Pinus echinata*) or Yellow Pine, the Norway pine, hemlock, spruce, balsam, white cedar, etc. In the town of Colchester there is a hemlock which was marked when it was six inches thick, in 1535 probably by an Indian weapon. Two hundred and fifty-three annual rings later, it was blazed by James Cockburn in 1788, and again in 1816 by Christopher Tappen. Sawmills were established over a century before any existed in England. In the old country the early sawmills were destroyed by mobs objecting to labour-saving machinery In 1623, nine years after the first house was built at New Amsterdam, three sawmills were erected there by the Dutch West India Company, who thus became the pioneers of lumbering as an industry. About the same time, perhaps a little earlier, some sawmills were erected at Fort Orange (Albany) and Andries Corstiaensen ran them Thenceforward mills and water-wheels multiplied rapidly. In a letter to the Lords of Trade, England, dated January 2nd, 1701, the Earl of Bellomont says "they have got about 40 sawmills up in this Province (New York) which I hear rids more woods and destroys more timber than all the sawmills in New Hampshire." There is a picture of one of these old mills, with a single upright saw attached directly to the pitman, and kept steady by side pressure from guide blocks. Later the saw frame was invented for keeping the saw under tension. Even at the time of the Revolution there was a lumber trade with England, but even after that event four-fifths of the State was an unbroken wilderness.

In 1626 the *Arms of Amsterdam* carried a consignment of oak and hickory to Holland, and in 1675 *The Castle* carried £400 worth of lumber to England. In 1686 Governor Dongan reported that he could "send over boards of what dimensions you please," adding that "three-inch planks for the batteries cost me 15 shillings the hundred feet." There was no river-driving then. When the lead became too long, the lumbermen simply up sticks and moved the mill. There were timber thieves even in the old days of plenty. Mr. Nathan Ford in 1799 complains that several persons were pretending to settle while really stealing the timber, but Mr. Williams took down their names. They do not seem to have cared much for either Mr. Ford or Mr. Wilkins. "If something is not done about this business, great destruction will arise. An example ought to be made, and this cannot be done without sending an officer from Fort Stanwix. They have got the timber so boldly that they say there is no law that can be executed upon them here" But in 1770 Adolphus Benzel, son of Archbishop Eric Benzel, of Sweden, was appointed Inspector of His Majesty's Woods and Forests at £300 per annum.

As early as 1700, Lord Bellomont recommended that each person who removed a tree should pay for planting four or five young trees, that no tree should be cut that is marked for the use of the navy, and that no trees be cut but when the sap is in the root.

The life was dangerous then as now. The first deaths in a settlement were frequently those of men killed by falling trees, crushed under loads, killed in sawmills, cut off by fires, or drowned while floating logs. "In May 1817 Artemas Shattuck went into the woods to chop. While cutting off a log that had been partly split, his foot caught in the crack, and he hung for a long time suspended by his foot and partly supported by one hand." Despairing of receiving aid, he finally unjointed his ankle with his pocket knife, made a crutch of a crooked stick, and started for the house" Rafting only began about 1788. The rafts in 1865 (when the author of the Bulletin, Mr Fox, was engaged in the trade) consisted of sections 16 feet square called "platforms." Five of these platforms side by side, with three more 5 platform pieces following, formed a raft 48 feet wide and 160 feet long and might contain 180,000 feet of lumber, board measure. The rafts would run 40 or 50 miles a day on ordinary floods and were tied up at night, generally near some town, village or tavern for company and amusement. Then if there were no genuine disputes to settle, there was always the question as to who was the best man to be decided.

In 1872 it appears from the books of the Hudson River Boom Association that 1,069,000 standards, or 218,800,000 feet B. M. were handled. This was the highest point of the trade, and at that time lumbermen were not cutting below 12 inches diameter on the stump, or nothing less than "two-log" trees. The "standard" log is 19 inches diameter at the small end and 13 feet long. Hence the logs then delivered ran about two to the standard, say 2,000,000 logs. In 1890 the business had declined to about a quarter.

"Log-driving," a most perilous business, began about 1800, and required men of superb physique and agility. It is now nearly extinct. "With surprising agility they would leap from log to log while they were running down the rapid, guiding current, and standing upright on a small log, with nothing to aid them but a pike-pole or lever, they would guide their treacherous craft as skilfully as an Indian his canoe. Many a good man met his death in the cold white foaming rapids."

"Log-rules" are contents tables for the sale of logs, and in the State two rules exist. Prior to 1850, E. Doyle published one set and J. M Scribner another. Being practical rather than mathematical, these rules differ materially, on account of the different allowance made for kerf, slabs, waste, defects, etc. The Doyle rule is based on an arbitrary formula which is fairly correct for medium sized logs, but not for others. Starting with the usual 16-foot lengths he arrives at the number of feet board measure in a log of that length and of any diameter by deducting four inches from the diameter and then taking the square of the difference. For instance, for a log 16 feet long and 20 inches diameter the formula is $(20'' - 4'')^2 = 256$ feet. A log 12 feet long and 20 inches diameter would be said to contain $\frac{12}{16}$ of 256 feet and so on. Scribner went to work by plotting circular diagrams showing the number of square-edged boards in a log properly sawn. From these diagrams the amount of lumber was computed for each diameter, after which a fixed percentage was deducted for imperfections. Both rules agree fairly for logs of 24 inches diameter, but for small logs Doyle's figures are much below Scribner's, while for large logs the contrary is the case. As the majority of logs are small, and the sawmills, as purchasers, naturally insist on Doyle's rule, Scribner's is now rarely used, and as a matter of fact, with the usual more or less inferior class of timber, Doyle's is the more practically correct. The "standard" is a log 13 feet long and 19 inches diameter at the small end. The method of comparison for logs of the same length (13 feet) is to divide the square of the diameter of the log at the small end by the square of the diameter of the standard, that is 361. The result, whether decimal or whole number, expresses the size of the log in terms of the "standard" as unit. Five standards are considered equivalent to 1000 feet board measure. The "standard," according to Doyle, contains 183 feet B. M., and according to Scribner, 195 feet. But it is proved by repeated tests that a sound straight standard log carefully sawn will yield 200 feet of straight edged boards, and this is the assumption of the Adirondack lumbermen, who make five standards equal to 1000 feet. The term "market," meaning marketable logs, is often used instead of the term "standard," although it may take 60,000 saleable logs to make up 20,000 "markets." The older modern mills driven by water-power generally use gang-saws, as many as 30 in a frame. The more recent mills driven by steam add a large circular saw and now-a-days band saws.

In a lumber camp the best axe-men fell the large trees. Some of these men are so expert they will set up a stake as a mark, and fell the tree so exactly that in falling it drives the stake into the ground. This avoids much breakage of younger trees. Those who trim off branches are called "guttermen," those driving the teams "skidders." The logs are rolled into huge tiers on the skidways ready to be loaded on sledges when the snow comes. Here the "scaler" and his assistant measure each log inside the bark at both ends, enter it in a book, and stamp both ends with the owner's mark. The contractor who runs the camp and work is called a "jobber," and the laying out of roads is one of the most important things he has to attend to. A "champion" sledge load may contain as much as 5000 or 6000 feet.

Then comes the river driving "At times, in some crooked rocky stream, a jam as formed, and thousands of logs are wedged fast in the channel, held back by some one log firmly braced against an impediment. Then occurs a thrilling scene, as the foreman calls for volunteers to break the jam There is always a prompt response. Two or more daring fellows, impelled by pride in their work, take their lives in their hands, and, with an axe and handspikes make their way over the treacherous logs to the head of the jam. Behind them are thousands of logs filling the angry stream from bank to bank, piled thickly to the bottom in all shapes, tossing, tumbling, and leaping in the air as the dammed up torrent forces them about in wild confusion. Beneath the men is the swaying, rocking, unstable mass, somewhere in the midst of which is the log which forms the key to the position. The balance of the crew of drivers gather on the bank below, where they watch with intense anxiety the men who have volunteered to break the jam. They note every motion of the volunteers as they coolly and undauntedly proceed with their work. The critical moment is close at hand. There is a little more prying with the handspikes, a few more blows with the axe, and then suddenly the huge threatening mass begins to move. Above the sound of the foaming waters a warning shout goes up from the men standing on the bank, and then, leaping from log to log, as the jam breaks, the brave fellows reach the shore in safety amid the applauding cheers of their comrades; or, it may be a cry of horror breaks from the crew, one loses his foothold and disappears beneath the terrible grinding mass, crushed and torn to a mere semblance of humanity."

In felling, the saw is now being largely used instead of the axe, and all trees are cut close to the ground. There are water slides miles in length, and logs are handled by steam jacks and loaders, and planing machines are being added to the equipment of sawmills.

Wood pulp has produced a great and prejudicial change in the conditions of lumbering. About 1867, the first mills were erected for grinding wood to pulp against a grindstone, and for disintegrating the timber by chemicals. There are now 293 mills in the States, of which 1 2 are in New York State. At first poplar was used, and foresters were pleased, for poplar is an otherwise useless weed But soon spruce also was attacked, and pulp unfortunately prefers fine young pole. The result is that, whereas the old lumbermen took out only the finest trees and did great damage, now the new ones take everything, and leave black ruin. To save transport, trees are peeled in the forest, and this is called "rossing" The bark so left causes great danger from fire. In 1898 the total cut in Adirondacks amounted to 644,234,207 feet, of which 529,281,918 feet went into pulp. The lumber industry of New York attained its maximum before 1865. In 1880 the New York mills turned out 1,148,220,000 feet B M., not including laths, shingles and staves The Adirondacks and Catskill ranges are now almost exhausted, and the production is only about 250 millions of feet of sawn stuff and 200 million feet of pulp. Another authority places the total output of New York State at about 900 millions from all sources. Working Plans are now coming in to save what is left of the situation, but the man who in 1799 advertised the half share in a sawmill has long since passed away, and so has his 'inexhaustible quantity of pine wood" Let us look to the beam in our own eye An Administration that thinks all cultivable land ought to be cultivated can certainly not be said to possess the best vision possible.

F. GLEADOW.

II -CORRESPONDENCE.

The Effect of Forest Fires on Insect Pests.

IN the October number of the *Indian Forester* a short article appeared on this subject, which is one, I think, which requires and will bear a great deal of investigation before it will be possible to make any definite statement for or against it. That the matter is of very considerable importance is evidenced by the fact that it is one which often comes up for discussion amongst Forest Officers, and the views at present held by many are of a diametrically opposite nature The letter in question clearly proves this to be the case, since the views of the author as expressed therein are in obvious opposition to the opinion of the writer of the article on "Fire Protection in the Forests of Lower Burma," which appeared in the August number of this magazine.

The question of the effect of fire protection, in increasing or decreasing insect attacks is, one which, when given careful and mature consideration, is seen to be beset with considerable difficulties, since before any opinion of sufficient weight to carry conviction can be laid down, the holder thereof must know fully the exact life-history of the pest [illegible] say that [illegible] fires [illegible] time is unknown. Were it in the pupal stage amongst the dead leaves on the ground it would naturally suffer more severely than if in the egg stage in the case of an insect which lay its eggs on the twigs just beneath the buds high up on large trees, or of another which passes its pupal stage in an earthen cocoon some inches down in the soil.

The "stage of its metamorphosis," therefore, which an insect may be in at any period is a very important point to bear in mind when a sickly tree or trees are being examined with a view to finding out the cause of disease, and I may here perhaps be allowed a short digression under this head.

It is a common thing in India—a very common thing—to attribute to drought or poor soil any sudden falling off in the quality of a forest, or the sickly appearance or death of trees, either singly or in patches. In the colder parts of the country frost is also brought in as a reason. It need hardly be said that fires are also a strong *raison d'être* on such occasions. That such are often the resultant causes of the death of trees I would be the last to deny, but that such arguments can be invariably advanced as the reason *per se* without further investigation and closer observations than are usually made is open to considerable doubt. That insects often play a very important part on such occasions numerous instances might be advanced. I will give two.

Aphidæ (plant lice) and *Coccidæ* (scale insects) swarm over a tree at times in large numbers, feeding upon its sap by suction for several months together during the best part of the growing season, and multiplying at an incredible rate The enormous amount of sap lost by the trees results, more especially in the case of conifers, in a considerable thinning of the foliage * If such a tree be examined in the late summer or autumn, it will be seen to be in a sickly and moribund condition. An examination, however, shows no easily recognisable external evidence as to the reason for the sickliness or dying condition of the tree, since all the insects will have died off by then, and possibly only minute winter eggs, which will easily escape detection, will remain. It will perhaps be remembered that the past spring and summer has been a particularly hot and dry one and the cause of the sickliness of the trees will be attributed to drought. And yet this same hot dry weather in the earlier part of the year was particularly favourable to the increase of the aphids or coccids, etc., enabling them to increase rapidly and undermine the health of the tree. The insect and not the drought is the primary cause of the condition of the tree.

Fires, we know, do serious injury in a forest, but it is important to look further afield than the mere actual damage done to the crop at the time. In the fire returns this is shown as an estimated lump sum. This, however, is very often far from representing the real injury done to the forest. Many trees in the area have their vitality reduced for a time owing to the bad scorching they have undergone. If left alone they will probably recover, and the loss incurred will only be represented by the loss of increment sustained during the period the trees were recovering from the scorching. What, however, very often happens, and it is probably the rule and not the exception in coniferous forests, is that bark-boring insects make their appearance, settle on the tree in swarms, and burrow into the bast layer and oviposit. The larvæ hatching out from the eggs laid carry on the tunnelling operations in the bast, and the trees, which would probably otherwise have recovered from the effects of the fire, succumb, the direct cause of death being the bark beetles, the primary cause the fire.* My readers may perhaps be wondering what the above digression has to do with the question at issue in this letter, but I venture to think that it points a moral and one of some importance. Not until we know fully the life histories of the more important of our forest insects, not until we know the chief and most serious insect enemies to which our most valuable timber trees are subject, will it be possible for us to definitely say with any reliable certainty, except in the cases where absolute and uncontrovertible proof is forthcoming, which is not usually the case, that such and such trees have died from drought, poor soil, or fires, etc. The tendency to take the easier way out of the difficulty and to put on record statements, without full and exhaustive investigations into all sides of the question, is hardly consonant with a scientific training, and is, I think, to be deprecated.

---

* A marked instance of this kind was noticed by Mr. Oliver and myself in May and June 1901. The blue pine (*Pinus excelsa*) in the Jaunsar and Simla Hill Forests was badly attacked by a black aphid during these months. The effect on the trees was to cause over 50 per cent., and in some cases probably as much as 70 per cent, of the needles to wither and drop.

The writer of the article under reply states that in his experience in Burma "the visible insect life in a forest is much greater after the annual fires have taken place than before." Not much importance can, I think, be attributed to this circumstance, since the fire season closes with the burst of the monsoon, and at that period of the year insect life appears in far greater numbers than at any other.

The writer continues: "Most insects adapt themselves to their surroundings and manage to be in a place of safety during the season of fires." This would not be a comfortable form of doctrine for the Forester could much real faith be placed in it. A dry cold weather followed by an early hot one generally results in a bad fire season. The same weather will also certainly favour insect life and be productive of a large increase in numbers, since fewer individuals are killed off by the damp and cold. Let us consider for a moment the effect of a fire respectively on a defoliating caterpillar and on the trees in a broad-leaved forest in such a year. In the absence of a fire the insect will swarm in large numbers on the trees, since the dry cold weather has been particularly favourable to it. Natural checks, such as attacks of parasitic insects, etc., do not really begin to produce any sensible reduction in a pest until it has reached a fairly advanced stage in its growth, by which time a larger amount of damage to the leaf crop will have been done. On the other hand, should a severe fire run over the area, the chances are in favour of its completely, or almost completely, freeing the area over which it spreads of the caterpillars, whilst at the same time it will burn a portion at least of the leaf flush upon which they were feeding. Thus for the moment, provided the fire has not done more than scorch the trees, the damage done to the forest is the same as would have been effected by the caterpillars. The gain to the forest comes with the new flush of leaves. Had the insect developed unhindered with only its natural checks to cope with, a certain percentage would have reached the pupal and imago stages, eggs would have been laid, and a second generation of the insect would have appeared and eaten off the new flush. The fire by clearing off all the caterpillars has prevented this, and probably saved the forest from further attack from this particular pest for some years to come.

---

* I noticed a good illustration of this in a piece of old spruce (*Picea morinda*) forest on the northern slope of the Huttoo Mountain situated not far from Narkanda, on the Simla-Tibet Road. A serious fire had overrun a portion of this area some years before. The fire had been followed by a serious infestation of the Blue Pine Tomicus beetle, *Tomicus* sp., with the result that many of the fine large-girthed old trees had succumbed to the attack.

Fires therefore on occasions undoubtedly do good in a forest by killing off insect pests.

Again, with reference to the adaptability of insects to their surroundings, it would not be possible, I think, for an insect, with perhaps three generations or life cycles between February or March and August to so modify its metamorphoses as to be always in the safest stage of its existence when a fire occurred, when it is considered that the latter might take place at any time between March and June, and that the whole of a life cycle of the insect will be passed through within 6 to 7 weeks. That insects, like other animals and plants, adapt themselves to their surroundings is of course well understood, but these surroundings are 'natural' ones, amongst which they have gradually acquired their present forms and habits through innumerable generations of slight modifications. That such insects could have adapted themselves to anything so comparatively recent and fitful as the fire season in a forest in India is out of the range of probability.

In support of the theory that fires are not inimical to insect pests various insects are alluded to. The first mentioned are the well known teak defoliators *Hyblæa puera* and *Pyrausta machæralis*. The second number of Departmental Notes details what is known at present about the life-histories of these moths. From Burma we have not sufficient data at present on these life-histories to be able to make any definite statements upon the

---

Note.—In most Indian forests fires usually occur at a time when the trees are practically leafless and when there are no feeding insects to wipe out.—HON. ED.

subject. I am unable form any opinion about the 'flies' alluded to, as the species are not mentioned and the "milaung-hmet" is unknown to me under that name. The life-histories, however, of many flies (*i.e.* *Diptera*) are known to be so complex that it would not, I think, be possible to say what effect, if any, fires had upon them. It is possible that the larval stages of many are not passed in the forest at all. Little also is at present known about our Indian Cicadas (also alluded to by the writer) but some species of this family lay their eggs in incisions on the soft bark of twigs of trees, the young feeding upon the sap after emergence from the egg. Such a mode of life passed high up in the tree would not be particularly harmed by forest fires below, unless they were of such magnitude as to kill the tree. In the case of the Noctuid moth, whose larva is mentioned as defoliating the sal tree in the rains in the Dun forests, it is not improbable that the insect is in its pupal stage in an earthen cocoon in the ground or in the egg stage on the young twigs of the tree during the fire season, in which case the insect would not be much affected save by very severe conflagrations. In this respect it is probable that many Noctuids are safer from vicissitudes of this nature than are many other forms of insect life.

Summary.--Summing up, I would say, therefore, that in the present state of our knowledge of the life-histories of insect pests in the forests of India, it is not possible to put forward with any certainty statements as to whether fires are or are not beneficial in minimizing attacks of insects. At the same time it is a fact that can hardly be disputed that at times a great deal of good is done in a forest by an opportune fire in wiping completely out a serious attack of a pest, and in such cases it probably takes the insect some time to repopulate an area so denuded of its individuals.

On the other hand, it is equally an undoubted fact that bad fires are often followed by severe attacks of bark-boring and wood-boring insects, which are ever on the look-out for trees reduced in vitality. This evil is perhaps greatest in coniferous forests, in which bad fires cannot be looked upon otherwise than as a most serious calamity. For example, whereas a fire might do the greatest good in a sal forest by clearing off a bad caterpillar defoliating attack, without reducing the vitality of the trees to such an extent as to attract and invite a bark-borer attack, in the case of the coniferous forest matters are very different. Here, although the fire might put an end to the defoliating attack, the scorching of the trees and the stoppage of growth would so lower their vitality as to make a bark boring beetle infestation an almost certainty. The above arguments will, I think, show the impossibility of estimating the value of a forest fire, whether good or bad, on insect attacks, until we have studied and found out—

(1) The more serious of the insect pests attacking our most valuable trees,

(2) The complete life-histories of such.

It may be that at some future day, with the above knowledge to guide us, it may not be considered a heresy to suggest that in the case of severe insect attacks in certain classes of forests the best remedy is *a forest fire.*

E. P. STEBBING.

Grass for Paper Manufacture.

MR. GAMBLE in a list of trees and shrubs in the Ganjam and Vizagapatam districts, written some years ago, mentions a species of grass which he calls *Andropogon involutus* and which he mentions as being equal to the "Esparto" grass as a material for paper manufacture. I have lately identified a grass in the Vizagapatam district with the bhabar grass of the Central and United Provinces. It bears the characteristic woolly base of the *Ischæmum angustifolium*, and is locally put to the same uses as the bhabar grass is by the natives of the United Provinces, *viz.*, twisted into twine and rope for charpoys. One more use it is put to on the sea coast is the seaming of fishing boats and the making of the large fishing nets used in the sea. What I should like to know is if *Andropogon involutus* is synonymous with *Ischæmum angustifolium* or is it a separate species of grass altogether?

The local name of the grass I refer to is "Kopiri," or more correctly "Kamkku kopiri," because there is another called also "Kopiri" and more correctly "Nunna kopiri," which is probably *Eriophorum comosum*; and in a recent working-plan for a forest in the Godavery district, the W. P. O. referred to "Kopiri" grass there—which is evidently identical with the "Kopiri" of this (Vizagapatam) district—as *Andropogon involutus.* I therefore feel rather doubtful about the identity of my grass and should like to have my doubts cleared.

The Central Provinces seems to make a large revenue by its "Bhabar" grass. There is a possibility of the Northern Circars districts of the Madras Presidency possessing great potentialities of revenue in regard to their "Kopiri" grass. I request therefore that some of my brother officers in the Central Provinces will kindly give information in the *Indian Forester* that will help their brethren in this Presidency in their endeavours to work up the "Kopiri" grass for the Calcutta paper-mills. Information is solicited on the following points:—

(1) Method and time of year of collection.
(2) Cost of collection per maund (82 lbs).
(3) Method and means of transport and cost per maund, by road and rail separately, for a given distance.
(4) How is the grass packed and transported? Is it compressed to reduce bulk?

This and any further information which may appear helpful and necessary shall be most thankfully received. And as its publication in the *Indian Forester* is likely to benefit many more than myself, I request you will kindly undertake to publish the same in the *Indian Forester*. One more point I should like to notice is, if both the *Eriophorum comosum* and *Ischæmum angustifolium* are sent to any paper-mills, and if the cost in each case be different, these different rates may be separately quoted.

NURSAPATAM;   GEO. W. THOMPSON.
30th November 1902.

IV.-REVIEWS.

Forest Administration in British India during 1900-01.

THE review issued this year by Mr. Wroughton, Officiating Inspector-General of Forests, is compiled on the same lines as in previous years, and is an eloquent witness to the growing importance of forest work in India and to the rapidly increasing value of the property which India possesses in her State forests.

The area of reserved forests increased by 1170 square miles, of which the largest additions were made in Madras and Burma, the total area of reserved forests at the close of the year being 88,140 square miles. Of this area 18,800 square miles are situated in the Central Provinces, 17,800 in Burma, 16,500 in Madras, and 13,707 in Bombay.

Burma by adding 10,145 square miles to the area of unclassed forests in the Southern Circle, is mainly responsible for the total increase of 10,909 square miles in the area of forest lands under the management of the department The Forest Department is now in charge of 208,369 square miles or 21·97 per cent. of the whole area of India.

4007 square miles were finally reserved during the year and at the settlement 1338 square miles were taken in hand. Good progress was made in the Punjab, Burma and Madras, while in the N.-W. P. and Bombay little now remains to be done.

Under demarcation 5221 miles of boundary were newly cleared during the year, mainly in Madras, Bombay aud Burma, and 40,539 miles of boundary were re-cleared. The total cost of new work amounted to Rs.60,921, varying from Rs.59·1 per mile in the N.-W. P. to Rs.1·3 per mile in the Central Provinces. Repairs cost Rs.50,131 as compared with Rs.65,776 in the preceding year.

The outturn under surveys was 4935 square miles at a cost of Rs. 4,48,803. The surveys were made chiefly on the 4-inch scale and the outturn surpassed that of the previous year by about 300 square miles, although the total expenditure incurred was considerably less. It is probable that the cost of these forest surveys has now reached the lowest figure compatible with good work. It is now proposed to place the whole of the forest surveys in India under one administrative officer, when it is hoped that the ten-year programme, sanctioned by the Government of India in 1898, will be completed earlier than was anticipated.

The following statement compares the position of each Province with regard to the progress made up to the end of the year in the preparation of working plans :—

Province.		Areas for which working-plans have been completed and sanctioned		Areas for which working-plans are being compiled		Areas for which working-plans have still to be taken in hand.	Total forest area.
		At commencement of the year.	During the year.	At commencement of the year.	Taken in hand during the year		
		Sq. ms.	Sq. ms.	Sq. ms.	Sq. ms.	Sq. ms.	Sq. ms.
Bengal	... ...	4,460	...	841	...	8,269	13,5 0
North-Western Provinces and Oudh.	Central Circle...	1,551	4	...	...	374	1.9.9
	Oudh " ...	1,107	...	197	...	8	1,312
	School " ...	792	...	77	...	13	882
Punjab	... ...	2,644	76	1,329	...	5,705	9,754
Burma (Lower)	Pegu Circle ..	1,023	...	...	...	15 507	16,53
	Tenasserim Circle	738	...	449	...	33,029	34, 16
Burma (Upper)	Northern Circle...	37	...	...	...	19,744	19.781
	Southern "	79	208	275	242	28,070	28,872
Central Provinces	Northern Circle...	1,306	521	5,994	...	1 678	9,498
	Southern "	5,976	585	1.001	...	1 959	9 521
Assam ...	... ...	533	...	...	...	20,315	20,844
Berar ...	... ...	725	...	...	...	3,228	3 953
Coorg ...	... ...	178	...	22	...	700	901
Baluchistan	... ..	...	...	...	...	303	203
Andamans	... ...	.	...	...	...	1,9 1	1,951
Ajmer ...	... ...	139	...	. .	...	10	149
Total Bengal Presidency 1900-01		21,288	1,391	10,185	242	140,764	173,870
" " 1899-1900		20,163	1,338	10,847	856	129 6.2	16 ,806
Madras Presidency	Northern Circle .	72	158	1,022	385	5 179	6,816
	Central "	117	252	608	518	5,716	7.271
	Southern "	109	244	66	158	4,813	5,454
Total	1900-01 ...	358	658	1,756	1,061	15,708	19,541
	1899 1900 ..	139	219	1,410	768	17,113	19,649
Bombay Presidency.	Northern Circle ...	638	...	...	631	1,058	2,327
	Southern "	681	59	521	112	3,926	5,298
	Central "	...	404	3,856	..	2,080	6,260
	Sindh "	...	...	613	150	310	1,073
TOTAL	1900 01 ..	1,319	463	4,989	893	7,294	14,958
	1899 1900 ...	1,318	16	5,146	892	7,574	14 946

Most progress was made in the Central Provinces and Madras, while most remains to be done in Burma, Assam, Madras and the Central Provinces. In Bombay all working plans have to be submitted to the Local Government through the Senior Conservator in order to secure uniformity—a measure which with advantage might be adopted in Madras.

The total expenditure on roads amounted to Rs.1,60,000, being an increase of Rs.10,000 on the preceding year. The outturn of work was highest in the North-Western Provinces, Madras and Bengal, while Burma, the North-Western Provinces and Madras mainly contributed to the expenditure of Rs.2,71,000 on buildings. The following table shows the expenditure incurred under this head on each of the Provinces :—

Province.	NEW WORK.		REPAIRS.		Other works	TOTAL.
	Buildings.	Roads	Buildings	Roads.		
	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.
Bengal	17,336	11,901	12,46	7,584	1,543	50.826
North-Western Provinces and Oudh.	31,186	12,084	16,135	33,600	6,246	99,251
Punjab	14,447	6,353	5,617	3,613	5,646	35 681
Burma	54,001	14,950	15,769	4,685	6,166	95,571
Central Provinces ...	8,672	287	7,876	2,912	1,355	21,082
Assam	8,493	1,370	9,467	4,995	1,345	25,670
Coorg	528	510	727	1,242	814	3,821
Ajmer	1,214	...	63	53	150	1,480
Baluchistan	...	...	104	...	1	105
Andamans	1,165	1,824	456	1,051	...	4,496
Berar	4,684	675	5,643	5,499	811	17,312
TOTAL BENGAL PRESIDENCY.	1,41,726	49,939	74,319	65,234	24,077	8,55 295
" MADRAS " ...	21,357	13,616	21,020	18,867	6,960	81,820
" BOMBAY " ...	6,111	6 510	6,552	5,898	2,173	27,244
GRAND TOTAL 1900-01 ...	1,69,194	70,065	1,01,891	89,999	33,210	4,64,359
GRAND TOTAL 1899-1900 ...	1,98,367	69,465	93,868	80,600	47,498	4,89,798

The statement given below shows the amount of crime which occurred in each province. Altogether 52,341 offences occurred, of which Madras alone is responsible for 22,130, and Bombay for 13,184, leaving only 17,027 for the rest of India and Burma. There was an increase both in the number of cases taken into court and in those compounded, while the percentage of convictions obtained rose from 85 per cent. to 86·7 per cent., the percentage being satisfactory in all provinces except Coorg, where it was as low as 67 per cent.

PROVINCE.	CASES TAKEN INTO COURT.				COMPOUNDED CASES.				CASES IN WHICH THE OFFENDERS REMAINED UNDETECTED.				TOTAL OF EACH CLASS OF OFFENCE.				
	Injury to fire-protected forests by fire.	Unauthorised felling or appropriation of wood and minor forest produce.	Grazing without permission in tracts in which grazing is prohibited.	Other offences.	Injury to fire-protected forests by fire.	Unauthorized felling or appropriation of wood and minor forest produce.	Grazing without permission in tracts in which grazing is prohibited.	Other offences.	Injury to fire-protected forests by fire.	Unauthorized felling or appropriation of wood and minor forest produce.	Grazing without permission in tracts in which grazing is prohibited.	Other offences.	Injury to fire-protected forests by fire.	Unauthorized felling or appropriation of wood and minor forest produce.	Grazing without permission in tracts in which grazing is prohibited.	Other offences.	GRAND TOTAL OF CASES.
Bengal	38	147	28	88	1	1,620	683	179	75	14	...	1	114	1,781	711	268	2 874
North-Western Provinces and Oudh	22	65	30	18	17	269	152	35	79	18	2	1	118	352	184	54	708
Punjab	34	704	505	166	11	1,351	1,837	18	83	13	7	...	128	2 068	2 349	84	4,729
Burma	14	677	8	62	1	1,268	17	445	79	60	...	1	94	2 005	25	508	2,632
Central Provinces ...	39	116	28	17	140	2,437	757	76	301	234	..	1	480	2,787	785	94	4,146
Assam	11	86	2	19	5	189	1	39	14	...	...	...	30	275	3	58	366
Coorg	...	6	...	5	...	40	23	13	...	..	..	...	...	46	23	18	87
Ajmer	2	289	17	7	1	223	2	1	3	30	2	...	6	542	21	8	577
Baluchistan	...	46	2	2	1	14	76	1	1	6	...	...	2	66	78	3	149
Andamans	...	2	...	...	...	..	...	...	..	.	...	...	...	2	...	...	2
Berar	12	72	11	21	31	494	53	27	15	19	2	.	58	585	66	48	757
Total Bengal Presidency ...	172	2,210	631	405	208	7,905	3,601	834	650	394	13	4	1 030	10,509	4 245	1 248	17,027
" Madras " ...	36	3 821	2 623	477	21	7,067	6,307	703	197	511	295	72	254	11,399	9,225	1,252	22,180
" Bombay " ...	147	846	393	219	65	4,077	2,872	474	1,814	1 918	318	41	2,026	6,841	3,583	734	13,184
GRAND TOTAL { 1900-01...	355	6,877	3,647	1,101	294	19,049	12,780	2 011	2 661	2 823	626	117	3,310	28,749	17,053	3,229	52,341
GRAND TOTAL { 1899-1900	453	6,786	3 252	1,090	334	19,798	1,624	2,345	2,849	3,088	1 357	123	3 686	29,672	16,233	3,585	53,149

The total area fire-protected rose from 32,737 to 33,906 square miles, owing to a considerable extension of fire-protection in Burma. Details are given in the following table:—

PROVINCE.	AREA IN SQUARE MILES. Attempted 1900-01.	AREA IN SQUARE MILES. Attempted 1899-1900.	AREA IN SQUARE MILES. Protected. 1900-01.	AREA IN SQUARE MILES. Protected. 1899-1900.	Proportion of failures to area attempted. 1900-01.	Proportion of failures to area attempted. 1899-1900.	COST. Per square mile protected. 1900-01.	COST. Per square mile protected. 1899-1900.	COST. Per acre protected. 1900-01.	COST. Per acre protected. 1899-1900.	Proportion of area under fire-protection to total area of all forests. (*Leased* forests included.) 1900-01.	Proportion of area under fire-protection to total area of all forests. (*Leased* forests included.) 1899-1900.
					Per cent.	Per cent.	Rs.	Rs.	Pies.	Pies.	Per cent.	Per cent.
Bengal	2,120	2,114	2,077	1,920	2	9	7	7	2	2	16	16
North-Western Provinces and Oudh	3,923	3,222	3,169	3,159	2	2	19	21	6	6	78	78
Punjab	908	806	905	788	0·5	2	6	8	2	2	9	9
Burma	5,163	3,810	4,562	3,473	12	9	34	80	10	9	5	4
Central Provinces	4,796	4,757	4,733	4,591	1	4	9	10	2½	3	25	25
Assam	1,190	1,189	1,088	1,165	9	2	9	10	2	3	6	6
Coorg	204	204	202	151	0·9	26	26½	36	8	11	23	23
Ajmer	149	149	149	149	...	...	2½	¼	0·3	...	100	100
Total ...	17,753	16,261	16,578	15,388	5	5	17	17	5	5	10	10
Berar	1,483	1,473	1,464	1,454	1	1	9	9	3	3	37	35
Total Bengal Presidency ...	19,236	17,724	18,342	16,842	5	[illegible]	17	16	5	5	11	10
" Madras " ...	5,218	5,136	5,182	4,855	2	5	7	7	2	2	26	26
" Bombay " ...	9,452	9,877	8,810	8,904	7	10	4½	4	1	1	63	60
GRAND TOTAL ...	33,906	32,737	32,334	30,601	5	7	12	10	3½	3	16	6

95 per cent. of the area was successfully protected, the results being least satisfactory in Burma, where also the cost of protection was greatest. The cost per square mile was Rs.34 in Burma as compared with Rs.4¼ in Bombay, the average throughout India being Rs.12.

The total grazing revenue was Rs.12,06,713 or Rs.1,54,257 less than last year. Madras contributed no less than Rs 4.79,045, Central Provinces Rs.2,46,614 and Bombay, Rs.1,92,283. The area closed to all animals was 35,166 square miles and to browsers only 33.016 square miles. The closed areas were located principally in Burma and Bengal, where 14,000 and 7,000 square miles respectively were closed. The percentages of closed areas for the different presidencies were—Bengal 18 per cent., Bombay 15 per cent., and Madras 8 per cent.

The amount of forest produce removed by Government agency, contrasted with the amounts removed by purchasers, were as follows:—

PROVINCE.	TIMBER.		FUEL.		BAMBOOS.		MINOR PRODUCE (INCLUDING GRASS AND GRAZING).	
	Removed by Government.	Removed by purchasers.	Removed by Government.	Removed by purchasers.	Removed by Government.	Removed by purchasers.	Removed by Government.	Removed by purchasers.
	C. ft.	C. ft.	C. ft.	C. ft.	No.	No.	Rs.	Rs
Bengal	165,351	6,818,608	163,280	19,256,196	561,338	18,233,419	3,861	2,35,711
North-Western Provinces and Oudh...	656,113	2,811,467	1,935,008	2,982,367	298,949	10,181,019	33,919	1,59,710
Punjab	1,021,339	1,222,220	3,794,709	1,099,731	439,597	19,021	28,929	1,70,710
Burma	2,733,080	23,276,993	6,714	15,069,274	59,000	58,314,000	2,649	1,79,592
Central Provinces	283,055	1,855,939	1,125,623	7,841,482	1,365,203	14,638,478	47,822	3,73,180
Assam	50,742	3,078,902	4,651	2,727,895	12,065	25,095,857	12,888	79,981
Coorg	59,401	272,448	9,200	85,929	...	173,210	172	15,074
Ajmer	163	1,683	39	214,979	...	1,770	4,462	1,099
Baluchistan	407	8,626	26,286	358,836	...	...	5	1,005
Andamans	252,724	30,511	1,238,387	3,340	44,095	34,000	3,702	309
Berar	...	442,209	...	1,507,329	...	2,013,378	...	1,75,721
Total Bengal Presidency... ...	5,223,375	39,189,606	8,303,897	51,147,358	2,780,247	128,704,152	1,38,409	13,92,092
" Madras " ...	568,039	2,510,201	3,052,275	11,085,484	318,782	29,386,376	43,142	10,04,973
" Bombay " ...	1,225,399	2,185,978	5,886,151	20,729,592	63,689	3,990,532	41,299	3,41,471
GRAND TOTAL ...	7,015,813	44,515,785	17,242,323	82,962,434	3,162,718	162,081,060	2,22,850	27,38,536

The total amount of timber removed was 2,523,726 cubic feet less than in the preceding year, the deficiency occurring mainly in Assam. The outturn of fuel remained the same as last year, but 8¼ lakhs more bamboos were removed, the increase taking place chiefly in Bengal, Burma and the Central Provinces. Burma, the Central Provinces and Bombay are responsible for the decrease of Rs. 6,67,000 in the value of minor produce extracted.

The financial results are summarised in the following table :—

PROVINCE.	REVENUE.		SURPLUS.		DEFICIT.		Proportion of surplus to gross revenue.	Net revenue per square mile of land under control of Forest Department.
	1900-01.	Average for preceding five years.	1900-01.	Average for preceding five years.	1900-01.	Average for preceding five years.		
	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Per cent.	Rs.
Imperial	2,463	9,910	...	...	81,115	75,226	...	...
Bengal	12,33,339	11,18,012	6,62,533	5,49,796	...	...	53·7	49
North Western Provinces and Oudh	15,65,403	15,23,122	6,02,024	5,86,830	...	...	38·4	146
Punjab	13,50,842	12,13,178	4,63,499	3,65,070	...	...	34·3	47
Burma	80,54,444	70,90,596	53,99,727	48,65,064	...	...	67·04	58
Central Provinces	9,63,062	9,72,934	32,299	...	...	74,574	3·4	2
Assam	5,49,521	4,42,514	2,01,549	1,38,618	...	...	36·8	10
Coorg	1,37,596	1,35,328	66,691	55,566	...	...	48·5	74
Ajmer	10,646	13,649	...	...	6,136	3,164	...	...
Baluchistan	16,956	15,482	...	...	12,298	15,580	...	...
Andamans	2,77,886	2,83,652	1,37,749	94,592	...	...	49·6	70
Forest School	3,697	3,124	...	...	67,541	63,510	...	...
Forest Surveys (Imperial) ...	327	368	..	...	33,664	32,396	...	...
TOTAL ...	1,41,66,242	1,27,21,868	73,65,317	66,55,536	...	..	51·9	43
Berar	3,02,552	4,66,116	67,419	2,25,340	...	...	22·3	17
Total Bengal Presidency ...	1,44,68,794	1,31,87,984	74,32,766	68,80,876	...	...	51·4	43
„ Madras	23,40,170	21,92,640	6,24,739	6,32,448	...	...	26·7	32
„ Bombay	29,61,529	27,79,278	5,52,948	9,85,594	...	...	18·7	37
GRAND TOTAL IN { 1900-01 ...	1,97,70,493	1,81,59,962	86,10,453	84,98,918	...	...	43·5	41
GRAND TOTAL IN { 1899-1900 ...	1,90,09,610	1,77,15,796	79,84,930	79,19,596	...	...	42·0	40

Burma still continues to contribute over 50 per cent. of the surplus, followed by Bengal, Madras, the North-West Provinces and Bombay, each of which contributes about 6 lakhs.

The following table is very instructive in showing the increase in forest revenue and expenditure during the last quarter century :—

Quinquennial periods	Gross Revenue	Expenditure	Proportion of Expenditure to Gross Revenue.
	Rs.	Rs	Per cent.
1873 74 to 1877 78	67,23 191	44,76,303	66
1878 79 to 1882 83	79 15,956	52,09,538	66
1883 84 to 1887 88 .	1,10 59,434	71,42 382	64
1888-89 to 1892 93	1,51 86,115	8 ' 61,176	55
1893 94 to 1897-98	1,74,50,655	96 97,496	55
1898 99	1 9 ,38,520	1,00,33,920	53
1899 1900	1,90 09 610	1,10,24,680	58
1900 01	1 97,70,493	1,11 60,040	56

VI -EXTRACTS, NOTES AND QUERIES.

The Institution of Civil Engineers on Forestry.

THE enclosed cutting from the *Standard* of the 5th November 1902, may interest your readers. It is a hopeful sign for forestry when the President of the Institution of Civil Engineers insists on the importance of the subject in his inaugural address, and gives his opinion that, in spite of the extended use of iron and steel in construction and for railway sleepers, Engineers have cause to be uneasy about the supplies of timber and pit-props.

PORT SAID, 20*th November* 1902. **F. B. MANSON.**

The eighty-fourth session of this Institution was opened last night when the President (Mr. J. C Hawkshaw) delivered his inaugural address. There was a large attendance of members and their friends. The President, who was cordially received, said the century which had just closed would always be memorable for the birth and growth to maturity, and, as some might say, to an honourable old age, of traction by steam power on railways. Far-reaching as the results of this growth had been throughout the world, this country could not have reaped so rich a harvest from it without a corresponding growth of our dock system, which had also made its mark on the Nineteenth Century. That we required deeper docks with deeper entrances to them was because iron had taken the place of timber in shipbuilding, so that the use of iron had not only revolutionised shipbuilding, but had necessitated the rebuilding of our docks and harbours. The progress of the last century had been mainly due to the use which had been made of the metal, iron. In their enthusiasm for the great results achieved by this new material they might overlook what they had owed in the past and what they still would require in the future from an "old-world material," timber. Engineers here could not do without timber, nor, indeed, without much timber. For the last 30 years they had heard it said in that room that steel would shortly be adopted in place of wood for sleepers; but although we could make our own steel, but had to import our timber sleepers, this had not come to pass France had experience for years in iron and steel sleepers; but few were laid in France, which, in spite of her well managed forests, had to import sleepers. More metal sleepers are used in Germany, also a timber-importing country; but Germany used much wood still for sleepers. Metal sleepers were used in South Africa, and together with native timber, in Australia, India, and South America. In Argentina some of the iron sleepers had recently been replaced by native wood sleepers. The United States and Canada use wood only, and use wood more for sleepers in proportion to their railway mileage than any other country, 2500 to 3150 being laid to a mile in the former, and 2600 to a mile in the latter as compared with 1760 to 2145 a mile in this country. The consumption of timber for sleepers increased yearly, and more are now laid to a mile than formerly, especially in the United States and Canada, but there is a tendency to slightly reduce the number in the United States and to increase it in this country. The increase in the use of creosote prolonged the life, and so somewhat reduced consumption. In this country we had less area under forest in proportion to our size than any other country in Europe except Portugal, and our timber imports were, in weight, more than half the total timber imports of the timber-importing countries of Europe. In Europe there were only five countries which exported timber—Russia, Sweden, Austria-Hungary, Norway and Roumania—and the amount exported by these five countries was nearly 2¾ million tons short of the total amount required in Europe. Germany with 26 per cent. of its area under forest, and that admirably managed on scientific principles, against our 4 per cent., imported nearly half as much as we do. France, too, with 18 per cent. of its area under forest, and that scientifically managed as in Germany, import 1½ million tons of timber a year. Belgium, with 17 per cent. under forest, imported still more largely in value, though somewhat less in weight. Denmark, Italy, Spain, Holland, all import. Of the timber imported into this country in 1899, more than nine-tenths in weight and nearly four-fifths in value was coniferous wood, which was grown in the temperate countries of the northern hemisphere, and this was the timber which was most largely consumed in engineering work. As Europe could not supply its own wants, our only other source was Canada, on which the United States was making increasing demands for timber, and Canada itself, with its enormous resources in water-power, would soon be a large consumer of its own forest produce. In this country forestry was neglected. Germany and France had long applied science to the growing of timber, and to them we had to go to learn. Belgium had done likewise. Even Spain, which had suffered more than any country in Europe from the destruction of forests, had a Government Forest Department. Russia, Sweden, and Austria-Hungary looked after their forests. Denmark did much, Norway something, but not enough. As recently as 1890 the Chief of the Forestry Division of the United States Agricultural Department said that the United States was the most backward of all civilised nations in recognising the necessity of action with regard to forest resources. Happily a change had taken place in the last ten years in the United States, and Great Britain might now be regarded as the most backward of all civilised nations "in recognising the necessity of action with regard to forest resources." It was to be hoped that the labours of the Committee now sitting, which was appointed by the Board of Agriculture this year to inquire into and report upon the present position and future prospects of forestry and the planting and management of woodlands in Great Britain, would result in steps being taken to remove this reproach. Dear timber would mean higher rents and higher wages to meet them. Why should we import nearly 100 million cubic feet of timber in pit-props each year which we could grow ourselves? Prop-wood did not take three or four generations to grow, like sawyers' wood. The Railway Companies were partly to blame. They did little to help the buyers of home-grown timber, who had already begun to carry what they buy by steam traction on roads in consequence. The Railway Companies took thousands of tons of unpaying dead weight from all parts of the country back to the collieries each year in the shape of empty coal wagons, many of which might go back loaded with home-grown pit-props if the Companies would seek to encourage such traffic.

VII.—TIMBER AND PRODUCE TRADE.

Churchill and Sim's Circular.

December 3rd, 1902.

East Indian Teak.—The deliveries have improved during November, amounting to 1279 loads, against 1051 loads for November 1901. For the eleven months the comparison shows 11,760 loads this year against 13,047 loads last. Prices are also a point better than in October both for logs and planks, and business generally more active, consumers recognising that there is no sign at present of relief from high prices and tiring of their recent waiting policy. The improved supply of water in the shipping rivers seems to be maintained, but the process of getting down and shipping supplies of fresh timber appears to be lengthy.

ROSEWOOD, EAST INDIA.—Stocks are quite sufficient to meet the current demand, which is small.

SATINWOOD, EAST INDIA.—Finely figured logs sell well, but plain wood is very quiet; stocks are, however, very moderate.

EBONY, EAST INDIA.—Sizeable, good logs would realise fair prices.

PRICE CURRENT.

Indian Teak, logs, per load	...	£10 10s to £18 10s.
" " planks "	...	£13 10s. to £20.
Rosewood, per ton ...	...	£7 to £10
Satinwood, per s.ft. ...	...	*5d.* to *12d.*
Ebony, per ton ...	...	£9 to £10

Denny, Mott and Dickson, Limited.

WOOD MARKET REPORT.

London, 2nd December 1902.

TEAK.—The landings in the docks in London during November consisted of 108 loads of logs and 285 loads of planks and scantlings, or a total of 393 loads, as against 806 loads for the corresponding month of last year. The deliveries into consumption were 656 loads of logs and 492 loads of planks and scantlings—together 1148 loads—as against 978 loads in November, 1901.

The dock stocks at date analyse as follows:—

	5635	loads of logs,	as against	7606	loads at the same date last year.
	2887	" planks	"	4369	" " "
	—	" blocks	"	88	" " "
Total	8522	loads	"	12,063	" " "

The above figures go to strengthen the hands of shippers, who continue to be very reluctant to pledge themselves to shipments of any extent—even against offers for next year's arrival, both for logs and planks, of some 25 to 30 per cent. increase on the prices ruling in the early part of the year. Business is difficult under these conditions, and there will be the tendency to a shrinkage in demand under the pressure of high prices.

Business during November showed a somewhat better tone than characterised the Autumn months, but shippers' views generally continue to restrict forward business.

THE

INDIAN FORESTER.

Vol XXIX.] March, 1903. [No. 3.

Forest Fires.*

DAMAGE THROUGH LOSS OF THE SOIL-COVERING.

So far as I remember, the only occasion on which the daily press has done the *Indian Forester* the honour of quoting anything was in the case of an article of a somewhat pernicious nature in which the author advocated forest fires He did not specify the precise localities, conditions, and limitations under which a forest fire may be supposed to be more or less beneficial. .The article was only *quoted* as bearing on the breeding of mosquitos, but the Revenue Officer and the public may *seize on it* as a warrant for disputing the need of anything so oppressive as *fire protection in general*. Hence I call it somewhat pernicious. The following translation of an article by M. Jacquot in the *Revue des Eaux et Forêts* for 1st June 1902 may be of use towards a study of the question. In any case it is worth preserving. This and the final paragraphs alone are mine.

DEAD LEAVES.

M. Berthelot, and more fully MM. Gauthier and Drouin, have proved that a fire, if sufficiently intense to decompose the humus and humic acid, thereby destroys the faculty they possessed of developing those most essential and scarce substances which contain nitrogen. Even if the fire does not destroy woody tissues it burns up the covering of dead leaves. M. Détrie suspected what M. Coudon and especially M. E Grandeau have proved, *viz.*, that these dead leaves possess the precious faculty of *absorbing nitrogen from the air*. Since MM. Schlœsing and Müntz in 1877 discovered the nitromonad, the first bacterium whose powerful action on the chemical changes in the soil was proved, attention has been concentrated rather on its agricultural than on its forest utility. The researches of M. Henry therefore mark an important step in science. By his experiments in 1897 the learned professor of the Ecole Forestiere proved that dead leaves may even double their original richness.

---

* Brief translation of an article by M. Jacquot in the *Revue des Eaux et Forêts* for 1st June 1902, with remarks by F. Gleadow.

The quantity of leaves produced annually on 1 hectare (2½ acres) varies with the soil, climate, species, age, treatment, and density of the crop and the luxuriance of the crowns. It may reach 12,000 kilogrammes (of 2¼lbs.) of the living substance. The Bavarian stations have supplied some valuable figures, but these, as M. Henry remarks, are minima. "They relate indeed to forests afflicted with rights to fodder. The impoverishment resulting from this detestable practice reacts fatally on the vegetation." Other countries supply similar proofs. Jaeger and Buro, working under the same conditions, arrived at the same results as Professor Ebermayer. But Dr. Krutsch, examining soils that were not so impoverished, found weights one-fourth greater for spruce and one-seventh greater for Scotch pine The latter would have given figures as good as the spruce if the crop had been thinned so as to bring it under better conditions of light and air. "On trees which are prospering in sufficient light and liberty the leaves are not only more numerous but larger than on trees growing on poor soil or in bad condition." M. Huffel's work "Les Arbres et les Peuplements Forestiers" gives an account of the density of the German pine forests and shows the enormous increase of production which is obtained when these forests are treated by early and frequent thinnings. In Bavaria itself, under good cultural conditions, the dead covering has given figures considerably superior to those obtained when sweepings took place at six years' intervals (weight of all organic débris fallen during six years and not yet decomposed).

AVERAGE WEIGHT OF THE COVERING.

Forests.	GATHERED OFF SOIL SUBJECT TO SWEEPINGS.		Gathered off soil not thus impoverished.
	Annual	Sexennial	
	Kilos.	*Kilos.*	*Kilos.*
Beech ...	4107	8460	10,417
Spruce ...	3538	9390	13,857
Scotch pine ...	3706	13 729	18,279

The researches of M. Henry in the high forests and stored copices of France confirm the above. Thus, in Lorraine, though it is one of the coldest and foggiest provinces, a full-grown beech forest furnished in one year twice the weight gathered in Bavaria, that is to say, over 5000 kilograms of leaves dried at 100°C. and over 8000 kilos of total dead covering. A table can thus be prepared on the model of those used by the Director of the Bavarian stations. Experiments have not been made with all species at all altitudes and in all climates. Hence a mean has to be struck which is liable to slight variations in special cases. But a dictum of M. Ebermayer limits the probable error. "The differences in the quantity of leaves produced by the several species at the same age cannot be very great." The figures have been derived from crops growing under ordinary conditions. Consequently they are greater than those obtained from crops impoverished by sweepings, and less than the maxima for either France or Germany. They vary but little from truth, and experts are free to adapt or modify them for special cases.

WEIGHT OF THE DEAD COVERING, FULLY AIR-DRIED, PRODUCED ANNUALLY PER HECTARE OF HIGH FOREST.

Crop.	Leaves.	Debris excluding phanerogamic living axile organs	Total.	REMARKS.
	Quintaux.	Quintaux.	Quintaux.	
Beech aged 10 years ...	19	12	31	If regeneration has not been satisfactory, the figures must be reduced.
" " 20 " ..	30	13	43	
" " 30 " ...	39	20	59	
" " 40 to 60 years,	47	29	76	
" " 60 to 90 "	46	28	74	Weight diminishes with age.
" " over 90 "	45	28	73	
Oak " 10 years ...	14	10	24	For oak the figures are approximations. Experiments insufficient.
" " 20 " ...	23	11	34	
" " 30 " ...	29	18	47	
" " 40 to 60 years	37	25	62	
" " 60 to 90 "	36	24	60	
" " over 90 "	35	25	60	
Hornbeam 10 years ...	9	12	31	
" " 20 " ..	30	13	43	
" " 30 " ..	37	20	57	
" " 40 to 60 years	42	27	69	For hornbeam do. do.
" " 60 to 90 "	40	24	66	
" " over 90 "	36	28	64	
Scotch pine 25 to 50 "	34	22	56	Weight increases with age.
" " 50 to 75 "	35	23	58	
" " 75 to 100 "	40	30	70	

The metric *quintal* is very near 2 cwt.

In the stored coppices studied by M. Henry "the weight of the dead covering rises steadily to the age of 10 years, from which period to the felling it oscillates round 5500 kilos of dry substance for forests and soils such as those of the Forêt de Haye." In this quantity of total débris the share of the leaves varies from one-third to three-fourths. The following table gives the weights found at ages of 1, 20 and 30 years; those for 6 and 10 years are interpolated from the known inclusive totals of leaves and twigs, etc., combined.

WEIGHT OF THE DEAD COVERING PRODUCED ANNUALLY PER HECTARE BY A STORED COPPICE OF OAK, BEECH, AND HORNBEAM.

Age.	Dry soil (Oolite).			Clay soil.		
	Leaves.	Debris excluding living phanerogams.	Total.	Leaves.	Debris.	Total.
	Kilos	Kilos.	Kilos.	Kilos.	Kilos.	Kilos.
1	600	1500	2100	...	...	...
6	2000	2400	4400	...	...	...
10	3400	2300	5700	..	...	...
20	3900	1300	5200	2800	1800	4600
30	3100	2400	5500	...	...	...

M. Henry augments the force of his demonstration by assuming the least favourable case, and neglecting the soluble compounds of ammonia, starches and nitrates, which may have been formed and washed out by rain. According to his weighings, at the end of one year a weight of 100 kilos of oak and hornbeam leaves produces a gain of at least 666 kilo of nitrogen. The leaves have by that time lost their colour, but not their form, and are far from being reduced to humus. Their action as gas-absorbers is slowed down, but only ends with their complete decomposition. This takes three years for certain common species such as beech, and nearly twice as long for pine needles. It is thus a very moderate estimate to say that, after allowing for all losses of gas returned to the atmosphere during the process of decomposition, there still remains ·850 kilo of nitrogen absorbed and fixed from the air by each 100 kilos of dead leaves. This quantity is pure profit, the increment of the leaves from the moment they fall to the ground. But at the time of falling they contain a certain quantity. The analyses of MM. Fliche, Grandeau and Henry, which are wider than those of Wolff, give the following figures :—

Species.	Albuminoids in dead leaves (November).	Corresponding weight of nitrogen per 100 kilos of dead leaves.
	per cent.	Kilos.
Beech	7·81	1 250
Oak	6·62	1 060
Scotch Pine	11·81	1·890
Birch	3·00	0·480
Chestnut	3·75	0 600
Larch	5·50	0 880
Spruce	8·43	1·350

The percentage of nitrogen is over 1 per cent. for the principal species. It may be considered as the minimum for oak, beech and hornbeam. The total loss of nitrogen resulting from the burning of the leaves is therefore 1·850 kilos per 100 kilos of dry leaves of these three species. Probably it is at least 2 500 kilos for pine, but for safety it may be taken as 2 kilos.

DEBRIS.

The dead twigs, etc., etc., which reach the ground are also nitrogenous compounds. "They decompose more or less slowly, but always end by conversion into substances useful to plants (such as starches, nitrates, ammoniacal salts). A fire, even a slight one, destroys these small organs and dissipates the nitrogen, which exceeds ·7 per cent.

Under normal conditions the nitrogen derived from the two above-mentioned sources would have contributed to the formation of ulmic compounds and humus incorporated in the vegetable soil. A fire dissipates it in pure loss. The damage corresponds to the price of a *manure containing the same proportion of the gas.* This will vary, according to localities and manures available, from 1fr. 50c. to 1fr 85c. (15 to 18½ pence) per kilogram for mineral manures; farmyard manure would cost 2fr. 50c. per kilo of nitrogen contained. Tables could thus be drawn up, according to the nature and price of various manures, showing the money value of the dead covering exclusive of ashes. On a clay soil for instance nitrate of soda may work wonders, as seen in the nurseries of MM. Huberty and Guffroy. If the nitrogen contents is 15 per cent. and the price 24fr. 75c. per quintal, the kilo of nitrogen works out to 1fr 65c In the case of a hectare of high beech, aged 100 years, the loss of the soil covering would amount to 169fr. 70c. (over £2 16s. or Rs. 42 per acre), since the 4500 kilos of leaves and the 2800 kilos of débris represent respectively 83·250 kilos and 19·600 kilos of nitrogen. Similarly, in the case of a 40-year old pine forest the loss will be 137fr. 60c.; and in the case of a 6-year old stored coppice, the loss will be 88fr 75c. per hectare. The cost of transport and labour would be additional.

The artificial product applied to restore the loss contains, it is true, some other substances of a fertilising nature, but these cannot be considered as replacing any of the nitrogen due. Mineral foods cannot be substituted even for each other. Forest crops, though less exhausting than field crops, nevertheless make equally imperious demands for certain substances and suffer equally severely as soon as any one of the necessary elements becomes insufficient. Field manures are intended for field crops, and do not produce the same effects in forests. What the latter want is nitrogen, and nothing else can make good the loss of the soil covering. The author of a forest fire should be compelled to make good the loss under strict analytical tests to within 1 per cent, and he should furnish that manure which is most appropriate to the soil and the season; nitrate of soda for clays and compact soils, since it soon disappears in permeable ones; sulphate of ammonia (20 per cent. nitrogen) for calcareous or less compact soils; organic manures, such as dung (4 per cent. nitrogen), dried blood (11 per cent.), oil-cake (4 to 5 per cent.), ground horns, hair (14 to 15 per cent.), etc., for light and strong soils. In spring and summer when roots are active, a quicker manure may be used. In winter one of more durable nature.

M. Jacquot proceeds to consider the time of year at which the fire takes place, and the effect of a second fire following the first at one or two years' interval The former question is entirely negligeable. The second he does not develop fully, and in fact if the fire recurs before the next set of leaves are decomposed, the matter becomes complicated The idea of a forest incendiary having to make good the damage, in addition to his punishment, will be a startling novelty in India. Nevertheless it is unassailable, and even admissible under the Forest Act.

F. Gleadow.

The Insect World in an Indian Forest and how to study it.

BY E. P. STEBBING, F.L.S., F.E.S.

(*Continued from p. 68.*)

PART V—(*continued*).

ORDER.—*COLEOPTERA*—(*continued*).

HETEROMERA.

THE first and second pair of legs have five-jointed tarsi, the third pair having four only.

FAMILY TENEBRIONIDÆ.

Very common beetles in India. Owing to their dark colouring and shape they have a general resemblance to the *Carabidæ*, from which they can of course be distinguished by the tarsal joints. The larvæ are elongate and cylindrical and are hard and have six legs, being not unlike Elaterid grubs. Their food is mostly vegetable matter, including grain and flour. Some years ago a species was reported as tunnelling into sandalwood in Mysore, but the specimens were in bad condition and could not be identified. Recently the writer was able to breed an as yet undetermined species of Tenebrionid beetle from larvæ taken from the wood of dead spruce and blue pine trees in the Jaunsar Division in the N.-W. Himalayas; the timber tunnelled into was in several cases still sound, though in others rotting.

FAMILY CANTHARIDÆ (BLISTER BEETLES, OIL BEETLES).

Head with an abrupt neck; no hind wings present, elytra short and do not fit well together, but overlap; each claw of the feet has a long appendage beneath it. The beetles have a very soft integument and they secrete irritating secretions which raise blisters on the skin. Some of the insects are wingless. The *Cantharidæ* feed upon flowers and leaves and frequently do a little damage in this way. A common one in India, *Mylabris*, has the elytra banded with yellow and black stripes. Several others are equally typically marked.

TETRAMERA.

Four tarsal joints are present on all feet. Several of the families of this group contain serious pests both to forests and agriculture.

PHYTOPHAGA.

The head does not form a definite prolonged beak or rostrum; the three basal joints of the tarsus are densely covered with pubescence beneath, the third joint being divided into two lobes so as to allow of the fourth joint being inserted near its base.

FAMILY BRUCHIDÆ.

These are small unattractive beetles, having the hind femora more or less thickened. The front of the head is produced into a short rostrum and the antennæ are bead-like and straight, thus distinguishing them from the *Curculionidæ* where the antennæ are elbowed. The larvæ are little white, fat maggots, without legs, and live in and feed upon the seeds of plants, more especially the *Leguminosæ*. In India leguminous plants of all kinds are attacked by members of this family, and it is probable that the seed of leguminous forest trees suffers heavily from these pests. A species of *Caryoborus*, *C. gonagra*[*] attacks the seeds of the tamarind (*Tamarindus indica*), its life-history being as follows:—The eggs are probably laid on the pods before they reach maturity. The larvæ on hatching out make their way through the pod and tunnel directly into the seed. It has been found that none of the seeds contain more than one grub. When full fed the grub leaves the seed and spins a close-matted cocoon inside the pod and passes the pupal stage within this. The beetle, which is brown in colour and about the size of a pea, after emerging from the pupal skin, rests for sometime before cutting its way out of the cocoon and pod. Since there is only one set of pods per year, the life cycle probably takes a year to pass through.

FAMILY CHRYSOMELIDÆ (LEAF BEETLES).

Antennæ moderately long, eyes round and do not at all surround the insertion of the antennæ. The insects are small, bright-coloured, and thick set. The head is usually partially sunk into the prothorax, and the insects differ in appearance from other tetramerous beetles. Both the adults and larvæ feed upon leaves, and several do much damage in India by defoliating crop plants. A species, *Melasoma* sp., has been reported as defoliating a willow in the N.-W. Himalayas[†]; whilst a member of the group *Halticides* was found by Mr. Wroughton and the writer feeding upon the leaves of *Boswellia serrata* near Poona[‡]; at present, however, but little is known as to their action in the Indian Forest. The larvæ are small and active and are sometimes covered with spines, on which they carry their cast-off skins as a kind of shelter. The pupæ may be found either on the leaves or in the ground, and several generations may be gone through in the year—a fact which intensifies the insects' capabilities of inflicting damage.

FAMILY CERAMBYCIDÆ (LONGICORN BEETLES).

A large family of beetles containing from 12,000 to 13,000 known species. In form they are usually long, with well-marked "shoulders" to the elytra and a vertical head. The antennæ are very long, consisting of long cylindrical joints, often tumid at the nodes. They are held over the back in the position of rest. The eyes are hollowed out round the insertion of the antennæ. The latter are longer in the male than in the female. The first three joints of the tarsus are always large, spongy, bi-lobed and covered

---

[*] *Vide* Injurious Insects of Indian Forests, pp. 49-50. [†] *Id.*, p. 50.

[‡] *Vide* Departmental Notes on Insects that affect Forestry, No. 2, p. 179.

with hairs. The beetles are of all sorts of colours (but rarely metallic as in the case of the *Buprestidæ*), being often covered with hair or having hair in tufts on them. The thorax is square in outline and cylindrical and in most cases spined. The ♀ has a long strong ovipositor for laying eggs in crevices. The legs are long and strong The larvæ are almost entirely wood-feeders and so are white and soft. They have a broad head, powerful jaws, and long body, but have not the enormously developed prothorax of the buprestid larva which they otherwise greatly resemble; in the longicorn larva the abdominal segments are nearly as broad as the prothorax, it is practically legless, and has four-jointed antennæ. The grubs often spend their lives burrowing up and down in the wood of trees, making galleries which have usually a larger diameter than those of buprestids, and when they change into the pupal state, they do so either in the outer layer of the wood or in the bark, and the beetle is thus enabled to bore its way out.

Three sub-families of this family are distinguished as follows:—

Prionides—The front coxæ large and transverse; prothorax has distinct side margins.

Cerambycides—Front coxæ not greatly extended transversely, thorax not margined; the head is sloped in front obliquely, palpi have the terminal joint truncate, the inner side of the tibia has no groove; small legs are just visible in the larva.

Lamiides—Front coxæ usually round and deeply embedded; head is vertical and the terminal joint of the palpus is pointed and the inner side of the tibia has a groove; legs invisible in the larva.

The *Prionides* are on the average considerably larger in size than the members of the other divisions, and they include some of the largest of insects. Some have a great development of the mandibles in the male sex, analogous to those of the stag-beetle of the *Lucanidæ*. The larvæ in various parts of the world appear to have been a favourite article of food with native tribes. In consequence of the great destruction of forests that has taken place so largely in many countries of late years, these gigantic cerambycids have become much rarer.

The modes of life of the larvæ of the sub-families *Cerambycides* and *Lamiides* are various. Some bore up or down in the hard wood of trees and live for a portion of a year or for several years in this condition before changing to the beetle state. The female beetle in others girdles twigs of trees and then lays her eggs in the branch above the girdle. An example of one of these insects is the sal girdler, *Coelosterma scabrata*, whose life-history is as follows:—The female lays her eggs towards the end of the rains in notches in the bark of the shoot, somewhere near the upper end, either of a leading shoot or side branch. The beetle then girdles the shoot below the point she has laid her eggs in. The shoot dies above the girdle and the larvæ on hatching out feed upon the dying wood thus provided by the female. They change to the pupal state within this dead portion, which will probably by then have been blown or got knocked off the tree. The beetle emerges during the rains, laying its eggs towards the end of this season.

A common cerambyx wood-borer in India is *Plocederus obesus.* The eggs of this beetle are laid in crevices in the bark of the tree about March or April and the young larvæ on emerging first feed upon the bark and cambium layer and outer sapwood. As it becomes stronger it goes right down into the heartwood of the tree, boring large galleries in it When pupating the larva forms a peculiar solid calcareous cocoon in the outer layers of the wood. The insect pupates in August and September, becoming a perfect beetle in November. The beetle remains in the cocoon until March or April of the succeeding year to enable its outer parts to slowly harden, and then cuts its way out of this and of the wood. Recent observations tend to show that the larva only lives about six months in this stage of its existence in the Siwalik forests, where it is very common in *Odina wodier* and other trees. [*]

Another beetle, *Hoplocerambyx spinicornis* (the Singhbhum sal borer) lays its eggs in the sal. The larvæ when full-fed, instead of forming the calcareous cocoon of *Plocederus*, cover over the outer portion of the tunnel with a white calcareous covering resembling the end of a Brazil nut. This insect is common in the sal forests of Chota Nagpur, its larvæ probably spending more than one year in the tree, where they bore right down to the heartwood. [†]

A similar or closely allied species attacks the sal in the Siwaliks, and its galleries are to be found in considerable numbers in the sal posts (tors). As far as present observations go the genus would appear to contain the most aggressive of the sal wood borers.

RHYNCHOPHORA.

The head forms a more or less elongated beak or snout. The third tarsal joint at least is usually broad and densely pubescent beneath.

FAMILY CURCULIONIDÆ (WEEVILS).

The head is prolonged into a well-marked beak called the 'rostrum,' which bears a pair of elbowed clavate antennæ on it and carries the mouth parts at its tip. The palpi are small and the labium absent. The elytra bend down over the edge of the abdomen.

---

[*] In the 2nd edition of Gamble's *Manual of Indian Timbers* this insect is alluded to as probably the chief insect enemy of the sal tree. Present observations, however, by no means shows this to be the case.

[†] Vide *Injurious Insects*, p. 71, Plates IV, IX, c. (larva).

The *Curculionidæ* are an enormous family of beetles, containing about 25,000 known species, which do damage to the wood, leaves, shoots, fruits, and seeds of trees and crops They have been reported in this connection from many parts of India. The larvæ are white legless grubs, which tunnel into vegetable matter of all kinds. The Palm weevil (*Rhynchophorus ferrugineus*,*) is a typical example of this family. The female lays its eggs at the base of the leaf stalks on some spot where the stems have been injured, or in the holes drilled by the rhinoceros beetle (*Oryctes rhinoceros*). The larvæ tunnel their way through the heart of the trunk and often kill the tree outright. The pupa is formed in a cocoon of palm fibre in the burrow. The beetles fly at night, being often found in the day in the holes of the rhinoceros beetle. The palms in the Saharanpur Botanical Gardens were badly attacked in this way some years ago, several being entirely killed, whilst others were so riddled that they had to be cut down. This beetle is a common and serious pest in parts of Madras and other places in India.

Remedy.—There can be no doubt that in valuable plantations the best treatment is to at once cut out and burn entirely all infected trees. Of course to secure permanent good this must be done throughout the whole of the plantations of a district or series of districts and not only in one or two, as these latter will soon become reinfected from the neighbouring untended areas.

Mahogany, *Pinus khasya*, and dhak have been reported as tunnelled into by weevils. In the case of the former two, the grubs feed in the bast, gnawing out large winding galleries in it. When full-fed they eat out a chamber in the sapwood and pupate in it.

The shoots of the hill bamboo (*Dendrocalamus*) are bored into by the weevil *Cyrtotrachelus dux* and tops so attacked die off.

In the Chittagong Hill Tracts a large weevil named *Cyrtotrachelus longipes* attacks young muli bamboos (*Melocanna bambusoides*) when they are 1—2 feet above the ground. The female, a large brown beetle with a long rostrum, fairly long elbowed antennæ and enormously developed front legs, lays two eggs on the side of the shoot towards the end of June. Only one of these eggs appears to develop as only one larva is subsequently found in the shoot. On hatching out the young larva tunnels directly into the heart of the shoot and then burrows down the centre of it till it reaches the ground level. It then moves back to near the top and cuts the shoot through all round below it; the top containing the grub thus falls to the ground and gets pressed or dragged into the rain-sodden soil. The larva then pupates within the shoot about the end of July, and the insect remains in the pupal state all through the heavy rains and winter months, the mature beetles emerging the following June. This insect is capable of doing a very considerable amount of damage to the bamboo which grows socially over large areas in the Chittagong Hill Tracts and areas to the east. A severe cyclone swept up into this region in October 1897 and cleared for some distance a path through the forest in the hills. The succeeding year the muli bamboo came up in dense masses in this cleared area, and this abundance of their food plant probably caused the severe attack experienced from this insect in 1899 and 1900. I have no information as to the abundance of the insects since this latter year.*

---

* *Vide* Injurious Insects of Indian Forests, pp. 52—55.

Another genus of small weevils named *Apoderus* defoliates trees by laying an egg in the apex of the leaf and then rolling it up into a roll or ball. Species of this genus have been observed defoliating the sissu, *Quercus incana*, *Q. dilatata*, *Prunus padus*, hazel, *Anogeissus latifolia*, &c., the species collected being found in places as far apart and under as varying conditions as obtain in the Jaunsar Hills and the Sutlej Valley in the N.-W. Himalayas on the one hand and the forests of the Satpura Range in the Central Provinces and the Coimbatore Hills in Madras on the other. In ovipositing the female deposits one egg apparently usually, if not invariably, at the apex of the upper side of the leaf and to the right of the mid-rib It then cuts the leaf across about the middle or near the base, either on both sides of the mid-rib, leaving the latter intact, or else right across from one edge to the other, leaving a small portion at one side uncut. The cutting is done first and the egg laid at the apex afterwards. The cut portion of the leaf is then folded inwards down the mid-rib and the leaf is rolled up from apex downwards into a little roll, the edges being neatly tucked in on either side. The roll hangs to the untouched part of the leaf till it dries and then drops to the ground. The larva, on hatching out, feeds upon the store of food thus provided for it and probably pupates in the ground. †

The seed of both oak and sal is attacked by weevils and ruined.

An as yet undetermined species of weevil was recently found by Mr. B. O. Coventry attacking the oak, *Quercus incana*, about 80 per cent of the seed crop of the trees round Mussoorie being destroyed in 1902. ‡ In this case the eggs would probably have been laid near or in the flowers, since the grubs were found riddling the acorns and immature and mature beetles were cut out of these in June. Mr. Coventry says that he was led to this observation owing to his noticing the general absence of natural regeneration of this oak. He collected a large number of acorns to test how many were sound. The reason for the unsoundness soon became obvious. If others will follow this lead we shall know more about the reasons for the absence of natural regeneration in our forests.

---

* *Vide* Departmental Notes on Insects that affect Forestry, No. 2, p. 193.

† *Vide* Departmental Notes on Insects that affect Forestry, Nos. 1 and 2.

‡ *Vide* Indian Forester, Vol. XXVIII, No 10.

The mango weevil, *Cryptorrhynchus mangiferæ*, lays its egg in this way in the flowers of this tree and the young grubs get enclosed in the young fruit, in which they burrow about and feed and finally change to pupæ. The beetle on maturing bores its way out. *

FAMILY SCOLYTIDÆ (BARK-BORERS).

Small beetles, often very minute. Cylindrical in shape and generally dark brown or black in colour. The head is only prolonged into a very short beak and often not at all; antennæ are short, with a broad club which is elbowed and inserted close in front of the eye, which is often hollowed out to allow of the insertion of the antennæ. The antennæ do not fold back into grooves. They may be considered to consist of three main divisions—1st, the portion joining on to the head, which is the lower part of the elbow and consists of only one long joint called the *scape;* 2nd, the *funiculus* consisting of as many as seven joints or fewer; 3rd, the *club*, which may be solid or divided by transverse divisions, and varies greatly in shape. The antennæ are of importance since they are used in the classification of the family. These elbowed antennæ and four-jointed tarsus distinguish these beetles from *Bostrichidæ* which they greatly resemble. Prothorax is generally very long, often forming half the total length of the insect. Elytra cover the whole abdomen. The tibiæ are flattened laterally and in the majority the front tibiæ are set with spines on their outer edges; the third tarsal joint may or may not be bi-lobed. The larvæ are small white curved grubs resembling bostrichid grubs but differ in being legless. These insects feed as a rule in woody plants either in the bast layer and sapwood or tunnel right into the heart of the tree. The female burrows through the bark to lay her eggs, and does not usually lay them in crevices outside, as is the case with buprestids and longicorns. The beetles only appear for a short time for egg laying, but during this period they are often present in large numbers. The bark forms (*i.e.*, those which lay eggs in the bast layer) of this family may be either monogamous or polygamous.

In the monogamous forms the female usually pairs outside the tree and then bores through the bark and proceeds to make a gallery in the bast and sapwood in some definite direction, which is always the same for the same species. The beetle may take some days over this. As she bores she makes a series of small depressions, in each of which she lays an egg as she goes along. The grubs on hatching out make a gallery at an angle from the mother boring. When full fed they enlarge the end of their galleries into a pupal chamber, which may be either in the bast or may be bored into the sapwood. The larval galleries may differ in length and also in direction. The female beetle usually starts the gallery, then attracts the male near the entrance hole, pairs, and then finishes the egg gallery.

---

* Vide *Injurious Insects*, pp. 55 57, Plate III, fig. 1, a, b, c, d.

In the polygamous forms the male beetle tunnels through the bark till it reaches the sapwood, in which it bores a small depression, which is the pairing chamber, and there remains. The females come to him, are fertilized, and then bore galleries leading off from the pairing chamber. On either side of these galleries they bite out small depressions, laying an egg in each. There is usually only one entrance hole by which the beetles enter. If the egg gallery made by the female is a long one, she bores ventilation holes horizontally through the bark here and there to the outside. The shape and length of these galleries is, in the cases of the Indian forms at present studied by the writer,* always the same for the same species of beetle. The dead body of the female is often to be found at the end of the egg gallery, as she dies as soon as she has finished this work. The egg gallery may or may not be blocked up with wood dust by the beetle.

This family contains numerous species which are destructive to trees, and research is showing that they probably play a very important part in the Indian forest, attacking both broad-leaved and coniferous trees. It may be mentioned here that this Family is almost entirely unknown both economically and scientifically. Since he has held the post of Forest Entomologist the writer has become acquainted with over 50 species, mostly new, and from what he has been at present able to study of their habits, the economic importance of thoroughly studying this important family of pests cannot be too strongly urged. The damage is done by the beetles, and the larvæ resulting from the eggs laid by them, boring beneath the bark in the bast layer, thus destroying this latter and leaving an indelible impression of their former presence either in the bark, or in the sapwood, or both, of the tree. When severe attacks have been experienced, if the bark be removed, both it and the sapwood will be seen to be completely covered, sometimes from the top to the base of the tree, with the galleries of the beetles. Now, as in making each of these galleries a certain amount of cambium has had to be destroyed, it follows that the strength of the tree has been lessened thereby, and when the attacks are on the scale described the tree will die. The insects do not usually attack healthy trees, but choose either newly felled or sickly ones in which the flow of sap is less strong. When the beetles are however very numerous, and no sickly trees or newly felled ones are available, they will attack healthy ones. Numbers are drowned in their burrows by the flow of sap put out by the tree in answer to the attack, but the flow becomes gradually weaker and weaker and the beetles finally kill the tree.

---

* *Vide* Departmental Notes on Insects that affect Forestry, No. 2, in which a number of new forms are described.

The family may be divided into three main sub-families: the *Scolytini*, *Hylesini* and *Tomicini*.

The *Scolytini* can be distinguished by having the end of the abdomen flexed upwards and the tibiæ are entire on their outer edges and end in a hook. The genus *Scolytus* has been found to attack the deodar in India. The following is the life-history of one of the species, *Scolytus major*, MS.* The beetle is a monogamous one, the female pairing with the male outside the tree. The eggs are laid in the bast and sapwood, and to do this the beetle bores horizontally through the bark, the entrance hole being generally beneath a branch or flake of bark, until she reaches the cambium layer. The female then turns and bores her egg-gallery in an upward direction, grooving both bark and sapwood. This egg gallery consists of a number of small continuous zig-zag curves taken vertically up the tree. On either side of the groove indentations are cut and an egg is laid in each, from 60 – 70 being laid. The larvæ, on hatching out, bore away from the mother gallery at various angles, so that the figures impressed on the wood and bark consist of a number of radiating larval galleries, longer than the female gallery, which give off from the central mother tunnel. This plan of gallery is very characteristic of the genus *Scolytus*. The beetles oviposit towards the end of May, the larvæ are full grown in a month, and the mature insects issue during June and July and at once pair and lay eggs, which produce a second generation of the pest the same year, *i.e.*, fresh beetles mature about October. A closely related species, *Scolytus minor* MS., smaller than the last, is usually found in company with it and lives in exactly the same manner. Its galleries are smaller and fewer eggs are laid.

The *Hylesini* may be distinguished from the *Scolytini* by having the abdomen flat beneath instead of flexed upwards, whilst the tibiæ are toothed on their outer edges. This division contains both monogamous and polygamous forms. Species of the former have been found by the writer,—to give but two instances,—attacking sal trees in the Siwaliks and *Anogeissus latifolia* in the Coimbatore forests (in Madras) in a very similar manner. The female beetle after pairing bores through the bark down to the cambium layer and then mines out in this and the sapwood a short straight egg gallery parallel to the long axis of the tree. Eggs are laid in notches on either side of this gallery. The larvæ on hatching out bore away at an angle to the egg gallery and the pattern produced is not unlike that made by a *Scolytus*. The sal beetle here described has three if not four generations in the year. A monogamous species of *Hylastes* has been discovered in the N.-W. Himalayan forests. *Hylastes* sp. bores into the dying and dead wood of blue pine and spruce trees. The beetles pair inside the wood and the female then continues the tunnel and lays eggs in small offsets eaten out at right angles from it.

---

* This beetle is allied to *Scolytus destructor* of Europe, and is probably new to science. For further information on its life-history, *vide* Departmental Notes on Insects that affect Forestry, Nos. 1 and 2.

Amongst the Indian polygamous forest *Hylesini* as yet known there are species of *Polygraphus* and *Pityogenes*, etc.* Three species of *Polygraphus* are to be found attacking the blue pine, two of which also attack the deodar and spruce. The largest one, *Polygraphus major*, MS., confines itself to the tops and branches There is a central pairing chamber from which usually three egg galleries are bored. The larvæ feed wholly in the bast layer but pupate in the sapwood, boring a depression or hole in it. There are at least three generations of the insect in the year.

The life-history of *Polygraphus minor*, MS., is very similar save that it practically confines itself to the main stem of the tree, where it is almost invariably the companion of the blue pine *Tomicus* (see below).

Pityogenes coniferæ. MS., is a minute beetle which has usually 5—6 egg galleries radiating from the central pairing chamber. It often pupates in the sapwood, and is to be found in the blue pine and deodar—at times in enormous numbers. It has at least three, and probably more generations in the year.

The *Tomicini* are distinguished by having the ends of their elytra truncate, the head is spherical and hidden beneath the prothorax, which is often covered with projections and asperities; the third tarsal joint is simple. Several species of this division of the *Scolytidæ*, both monogamous and polygamous forms, are also already known in India* Amongst the former may be mentioned members of the genus *Cryphalus*. These beetles are very minute and are generally to be found in the smaller branches or right at the tops of saplings. They lay their eggs in the bast layer and the larvæ, on hatching out, feed there. It is not improbable that it will be found that most forest trees in the country have a member of this genus present in the bast layer of their branches. Species have already been found infesting the following trees:—Teak, *Boswellia serrata*, spruce, *Pinus longifolia*, and deodar.

An example of a polygamous beetle of this division is the Blue Pine Tomicus, *Tomicus* sp., which is at times very abundant in blue pine and spruce trees and is a source of very considerable injury to them. The beetles commence laying the first batch of eggs of the year at the end of April or in the first week of May. The male bores into the bast layer and makes a pairing chamber in the sapwood; the females enter, and after pairing with the male mine away from the pairing chamber, their egg galleries running more or less in the long axis of the tree; from three to five such galleries are made, eggs being laid in notches at their sides. The larvæ, on hatching out, feed in the bast layer and sapwood. They pupate in the bast. Three if not four generations of these beetles are produced in the year, and at times they swarm so plentifully that the inner surface of the bast and the sapwood appear to be almost black with beetles.

---

* *Vide* Departmental Notes on Insects that affect Forestry, No. 2.

FAMILY PLATYPODÆ (PLATYPIDES SOME AUTHORS).

These insects are the most aberrant of all *Rhynchophora*, the head being very short, flat in front, with the mouth placed on the under side of the head, there being no trace of a rostrum; the tarsi are elongate and slender, the third joint not at all lobed, whilst the true fourth joint is visible. The beetles are of a narrow elongate form, and from the above description it will be seen that they have not the appearance of *Rhynchophora*. Some authors treat them as a sub-family of the *Scolytidæ*. From my own observations of several new species found in India I incline to the side of those scientists who consider that these beetles should be placed in a separate family. The larvæ are white with a straight almost cylindrical body which terminates in an oblique truncation.

These beetles bore into the wood of trees and stumps, and may not unlikely prove to be somewhat numerous in the country. A species *Diapus impressus* was reported some years ago as attacking oak stumps in the North-West Himalayas The writer has since found this insect in considerable numbers in felled *Quercus incana* trees in the same locality. The beetles drill cylindrical holes right down into the heartwood of the tree and then lay their eggs at the bottom. The larvæ on hatching out feed upon the solid wood. Other species of this family new to science have been found in the same locality in dead spruce wood and drilling holes down to the heart of large newly-felled deodar trees. Another species has been found tunnelling into newly-felled *Shorea talura* trees in the Coimbatore forests of Madras, whilst a fourth bores into *sundri* wood (*Heritiera littoralis*) in the Sundarbans.

FAMILY BRENTHIDÆ.

Elongate beetles. The rostrum is straight, not bent over at an angle as in weevils, and often very thick. The antennæ are not elbowed. This is a tropical family of beetles about which very little is at present known in India. Some are stated to be wood feeders, whilst other forms are predaceous, their larvæ entering the burrows of wood-eating beetles to search and feed upon their larvæ. The rostrum is often used for boring holes in wood or bark, an egg being subsequently laid in the hole so made. The males of these insects often differ entirely in appearance from the females.

TRIMERA.

The tarsi are apparently three-jointed. Other characters are variable.

FAMILY COCCINELLIDÆ (LADY-BIRD BEETLES).

Small, often somewhat brightly-coloured beetles with the elytra spotted; first two joints of the tarsi are pubescent beneath. Head is concealed by the thorax. Antennæ are slightly clubbed

The larvæ vary in shape and markings, some being small coloured grubs covered with spines; they are often very conspicuous. When changing to the pupal state they often attach themselves to a leaf of a plant. One small division of the family are plant feeders, but the greater bulk prey upon other insects and are exceedingly carnivorous. They destroy wholesale plant lice, scale insects, etc., which are injurious to cultivated plants. In this way they do immense service to man. A study of this family in India is likely to prove of the very greatest use, since it is probable that it contains a number of members which are most valuable allies both to the forester and the agriculturist. One instance of this kind, recently discovered, will be given here, the life-history being that of a lady-bird beetle *Coccinella* sp., predaceous upon a *Monophlebus* scale insect, *Monophlebus Stebbingi*, which during recent years has appeared in enormous numbers and committed serious injury in the Siwalik and adjacent sal forests in the United Provinces and Punjab. The life-history of this predaceous beetle is very simple. The female monophlebus scale (whose life-history will be described in a subsequent part) first appears upon the leaves in the cold weather months, December and January. By the middle of March it is half-grown, having by then descended from the leaves to the twigs. The small active black or grey coloured larvæ of the lady-bird beetle are then to be found running over the trees or feeding upon the scales. They suck the soft fat scales quite dry leaving only a shrivelled skin. When feeding upon the coccid they attach themselves to the branch by means of a small sucker-pad arrangement they have at the end of their bodies. This attachment is so powerful that the scale, which is several times larger than the coccinellid larva, is quite unable to drag the grub off and thus escape. Towards the end of March and on into April the larvæ begin to change into small crimson pupæ. In doing this they first attach themselves to a leaf or branch by the sucker-pad and remain projecting out at an angle from it. After 24 hours the skin splits down, shrivels back, and discloses the crimson pupa sessile on the leaf or branch. After 7 to 8 days the skin of the pupa splits down in front and the small red beetle crawls out. It is first covered with a white down, but soon loses this, darkens to a dark red with six black spots upon the elytra. The beetle also feeds upon the scale. It pairs about the end of April and then lays eggs. The life-history for the rest of the year has not yet been studied.

USEFUL COLEOPTERA.

Amongst the *Adephaga* the *Cicindelidæ* and *Carabidæ* are useful predaceous families containing many carnivorous forms. In the *Clavicornia* the *Silphidæ* include the useful carrion and burying beetles and the *Staphylinidæ*, *Histeridæ*, *Nitidulidæ*, and *Trogositidæ* containing numerous forms predaceous upon bark-boring and wood-boring pests. Under the *Serricornia* the larvæ of the *Malacodermidæ* are supposed to be predaceous, whilst the family *Cleridæ* are likely to furnish the Forester with several useful allies, the *Clerus* sp. beetle described as feeding upon several scolytid pests being of inestimable value in the forest. Some of the *Elateridæ* larvæ may prove to be useful in this connection. The metallic-coloured elytra of the *Buprestidæ* are used to some extent in Southern India for ornamentation purposes and also as caste marks, whilst the *Cantharidæ* contains beetles such as the oil and blister beetles, which are used in medicine. Little is at present known about the *Brenthidæ* in India, but the family is known to include predaceous forms. The *Coccinellidæ* are likely to prove of very great value, as the family contains many excessively predaceous insects.

The Harcourt Working Plan. *

In the Department of the Eure, at Harcourt, the National Society of Agriculture possesses an estate of over 400 hectares; 100 hectares surround the chateau; 350 acres of forest form two outlying blocks. The soil, a clay with more or less sand, is covered in places by mud brought down from the plateaux, and is by no means flat. The management is perfect, cultivation is restricted to the alluvial deposits, the sandy clay is covered with splendid oak and beech forest, and a portion recently cleared displays a fine young crop of Scotch pine. The present management was explained to the Society by M. Bouquet de la Grye as follows:—

"The working-plan of M. Gurnaud was applied from 1890 to 1901, twelve years, the full rotation adopted by him. The results seem to be favourable, but this is not a proved fact, because certain special fellings of Scotch pine made during the first period render it impossible to compare the past stock with the present. It has, moreover, appeared to us that the necessity of undertaking a full enumeration of a forest of over 400 hectares at the close of each period was a very large order, and that the sale in small lots of coppice material that has become almost valueless through the heavy fall in the price of wood fuel was no longer advantageous. These considerations induced us to ask the Society to sanction some modifications in the plan without changing its essential features. As the treatment proposed by us is very simple and applicable to the stored coppices of many private owners who may desire to transform them into high forest, or at least into standards over coppice, we have thought that an explanation may be of interest.

---

* Translated from the *Revue des Eaux et Forêts* for 1st August 1902, by F. Gleadow, in the hope that it may be found both new and interesting. It suggests ideas outside the usual grooves, and is not without its bearing on the treatment of high forest in general. The name of M. Bouquet de la Grye commands esteem throughout the world.

"M. Gurnaud's division into three series is retained. Each of these series is divided into coupes laid out on the ground. The first series has 12 coupes, the second has 15, and the third has 12. The first series according to M. Gurnaud had 20 coupes, but as eight of these coupes have been clean felled and are useless for the present, they are set apart as a reserve for the future. The order of working for all three series being the same, it will suffice to describe that of one only.

"First we enumerate all trees over 60 centimetres (24 inches) girth at breast-height. This is the high forest. From tests made, we assume that the annual increment of the high forest share is two per cent. or for 12 years 24 per cent. At the felling, the possibility (or possible yield) is 24 per cent. of the stock, calculated in cubic metres. The inventory is made by means of a table based on the (inexact) assumption that trees of the same girth at breast-height contain the same quantity of timber. As this table is only used for subsequent comparisons, its accuracy is sufficient. It is not used for sales. For these the usual commercial methods are employed. In making the felling, 24 per cent. of the stock is chosen from the dominated, defective, and inferior trees. These are then valued on commercial principles, either standing or felled, according as the felling is done by the purchaser or by the owner.

"The coppice portion, consisting of shoots and standards below 24 inches girth, undergoes a strong thinning or clearing with the object of freeing all the stems which are suitable to grow up into the high forest stage. This thinning is a most important operation, and must therefore be done by the owner, or at least by workmen under his pay and supervision. The undergrowth, shrubs, and other elements of soil-protection must be carefully preserved, and this requires the eye of a forester.

"Twelve years later, when the second felling comes round, the same stock-taking is repeated. If the stock, valued in the same manner, amounts to a nearly similar quantity as at first, there is proof that the increment has been truly estimated. If the new stock is greater, the increment has been more than the two per cent. per annum, and the owner may either increase his felling or devote the gain to the enrichment of the high forest portion. If the new stock is less, the increment has been over-estimated, and the owner must reduce future fellings so as not to impoverish the forest.

"It is thus clear that each coupe is treated as an independent unit; instead of a general enumeration, the coupe of the year only is valued. The high forest portion can be felled either by owner or purchaser. The underwood should only be felled by the owner. This method of treatment, under which the yield is checked by the periodical verification of the increment, dispenses with many hypothetical calculations that are at present adopted in order to fix the exploitable age and the possible yield."

II.—CORRESPONDENCE.

Treatment of the Sandal Tree.

WITH reference to Sir D. Brandis's article on this subject in the January 1903 number of the *Indian Forester*, I beg to inform you that the sandal tree grows very abundantly in North Coimbatore Division, but that there are absolutely no casuarina trees, and practically no lantana bushes in the area in which it is found.

At Osahatti—a place referred to by Mr. P. M. Lushington in the same number of the *Forester*—it grows most luxuriantly amongst dense clumps of *Scutia indica*; but it was found that even large trees, supposed to be quite mature, to a very large per cent. (over 40 per cent.) gave no heartwood. The places in which it was found to give the greatest amount of heartwood were those in which it was associated with *Premna*, *Erythroxylon*, *Polyalthia*, *Acacia Sundra*, *Suma* and *Leucophlœa*, *Vitex altissima* and *Negundo*, *Gmelina arborea*, *Tectona grandis* (sparse), *Albizzia odoratissima*, *Capparis sepiaria*, *Phyllanthus reticulatus*, *Limonia acidissima*, *Toddalia aculeata*, *Murraya Konigii*, a few *Alseodaphne umbelliflora*, etc.; and a circumstance that struck my notice was that such a large number of species containing aromatic oils were to be found with this aromatic oil-giving species. Whether the sandal derives its oil from those species, or from similar sources, or whether it is a mere coincidence, I cannot say.

At Hossanur a small nursery was started some years ago, and a few plants (some 50 or 60) were left there. I took the trouble to have several of these dug up, and I found them to be *parasitic on one another*.

Another thing that may be of interest is an experiment made in planting sandal seeds in bamboo tubes. The difficulty of transplanting sandal, and therefore of obtaining natural reproduction, has often been put forward. About 3000 bamboo tubes were filled with earth and one or two seeds put in each, and hung up under shade in the forest near Bailur. Owing to the illness and changes of officers, these were not as well looked after as they might have been; but Mr. R. D. Richmond, Assistant Conservator, took charge of the range in September, some nine months after the operation was started, and found that in about 1000 of these tubes the young seedlings were doing excellently, and he had them planted out, tubes and all. This latter operation was entrusted to a Forester, and he again did not attend to it properly, but about 75 per cent. of those planted out were reported to be doing very well, and all that I saw personally were certainly thriving. The experiment is to be tried again with greater attention (it is hoped) paid to it; for if it is successful it will solve the difficulty about artificial reproduction.

Mr. Barber's note about parasitism came out just at the time when Mr Richmond was carrying out these operations, and he made a careful inspection of the roots of the seedlings at Bailur, and found no traces of "haustoria" whatever. In the plants that I examined at Hossanur there were "haustoria," but only very few; the plants being some six or seven years old. At Hossanur (and I believe also at Bailur) there were certainly small hair-like ramifications of the roots as referred to by Sir D. Brandis.

Mr. P. M. Lushington found that it was a most disastrous thing to clear away the undergrowth around sandal; it is quite possible that by doing so the hosts, on which the sandal thrives, were being cleared out.

A. W. LUSHINGTON.

12th January 1903.

The Application of Section 67 of the Forest Act.

If my old friend A. G. Hobart-Hampden had had the advantage (not to say pleasure) of serving in Bombay, he would have been severely taught his position by this time, and been aware that it is an illegal and oppressive act to "*demand*" anything from an offender, or even to suggest an amount as being acceptable. The offender's speculative instinct is supposed to suggest the smallest amount likely to get him off, and the Forest Officer has but to take it or leave it. One great beauty of this fine distinction is its careful imitation of the "bribe," in which also the amount is left more or less to the liberality of the donor. Another is the complete absence of pretension or authority. I hope A. G. H.-H will practise the words *huzoor ki khushi* with the proper deprecatory attitudes. The law indeed allows the *acceptance* of any amount up to Rs 50, but executive orders are above the law, and here in Sind Rs 5 is the limit. In the Presidency the limit is, or was, the value of the produce stolen, so that nobody could accuse the Department of taking the bread out of the mouths of the luckless offenders who got caught, say, once in ten journeys. The law again requires "reasonable suspicion," while executive orders require "proof that would ensure a conviction." It has been ingeniously contended that these two are really one and the same thing. The ordinary man will form his own opinion as to whether this is legal humour or what. The first thing to do is thus to ascertain not so much the law as the executive orders.

As regards the mere law of the particular question asked, I may say, in the light of the above, that we can *not* "demand compensation" from either owner or herdsman, but if either of them *asks* to compound and offers a sum, it would be idle to boggle over the detail of ownership. This view is supported by the common law principle (as well known to A. G. H.-H. as to myself) that an employer is responsible civilly, but not criminally for the acts of his servants, *i.e.*, he must pay damages, but not go to prison. The "compensation," even though it is "for the offence," as distinct from "damages," is here a civil penalty, as the Forest Officer cannot himself enforce it criminally. A court, if well advised, would certainly fine an owner, and send him to prison if the money was not forthcoming. The same principle shows that it is an owner's duty to employ reliable servants, and that an owner's grievance is against his servant, and not against the State, if his cattle get him into trouble.

There have been, however, rulings of courts on the point, not perhaps as to compounding, but as to its alternative, prosecution. The misplaced ingenuity of native magistrates cannot be better exemplified than in the case of Imperatrix *v.* Kalappa Ishwar and Ganu Martand. Defendants were charged with (1) trespass, (2) resistance. They were convicted of the trespass, but acquitted of the resistance, on the ground that "trespass" must be *accidental*, whereas these cattle, having been *wilfully* driven into the forest, *could not be impounded*, though the "owners" might be prosecuted. This intelligent judgment was quashed by JJ. Jardine and Telang.

The Madras High Court has decided the very point, but fortunately Madras is peculiar, and there are hopes for Northern India At p. 167, Vol. X, Indian Law Reports for April 1892, may be found the following:—"To sustain a conviction ..... there must be some evidence either that defendant pastured the cattle, or permitted them to trespass in the reserved forest. In the present case all that the prosecution proved was, that defendant's cattle were found in a reserve. Such cattle may be impounded but the owner cannot be held liable unless some overt act of his be proved."

In Bombay I do not know of any other case than the one above quoted of Justices Jardine and Telang. But it has been held by a District Magistrate that "if a man's cattle are found trespassing in a Reserved Forest, there is a *primâ facie* presumption that he is guilty of 'permitting cattle to trespass' unless he can rebut the presumption by evidence. The second clause of section 25 (*d*) seems expressly to meet cases where the owner or herdsman is not present with the cattle. If he is actually present the first part would be applicable." This is very sound as far as it goes, but it seems to leave the owner an opening for hard swearing, and to introduce the question of *intention*, which I think the section itself excludes.

An important omission occurs in section 25 (*d*), *viz.*, that of the words "knowingly and wilfully." As the criminal law generally inserts such words whenever the *intention* is to be considered, the omission of them in the case of trespass may very properly be held to imply that a man who turns his cattle abroad *does* thereby "permit" them to trespass within the meaning of the Act. This is also common sense, since a man who turns out his cattle unguarded must know that the first place the cattle will make for will be his neightbour's garden, or the nearest closed block where good feeding can be found. Another principle of law is, that "no man is bound to fence against his neighbour's cattle" It is the owner who is expected to keep them under control. There are generally "Grazing Rules under the Act" in some or most provinces, and these should specify clearly that the owner is liable under all circumstances. Then there is no excuse for ingenious magistrates.

F. GLEADOW.

V.—SHIKAR AND TRAVEL.

The Indian Pheasants and their Allies.

BY. F. FINN, B A., F.Z.S.

CHAPTER V.

KALIJES—(*continued from Vol. XXVIII, p.* 446).

THE height of perplexity has, I believe, been exemplified by a blind man looking in a dark room for a black hat that is not there! Somewhat similar is the state of mind induced by the study of the Kalij pheasants of this Empire. Once we get away from the three species I dealt with in the last chapter, I doubt very much if the birds themselves know to what species they belong; at any rate, if they do, they are singularly free from any restrictive rules about inter-marriage, and the result is a collection of mongrel hybrids exceedingly interesting to the philosophic naturalist, but maddening to the casual observer who wants to name what he shoots.

On the principle of proceeding from the known to the unknown, I shall first describe the first species about which no doubt exists, and then proceed to the consideration of those concerning which authors are not agreed. I may, however, first of all recall to mind that the males of all the kalijes now to be dealt with differ markedly from those previously described, in having the breast-feathers of the ordinary rounded shape, not narrow and pointed. Moreover the breast is always mostly black, generally completely so.

THE BLACK-BREASTED OR PURPLE KALIJ.

Gennaeus horsfieldi, Blanford, Faun. British India, Birds, Vol. IV, p. 92.

Native names:—*Mathúra*, Chittagong and Sylhet; *Dúrúg*, *Dirrik*, Garo Hills; *Dorik*, at Dibrugarh. The last name seems commonly used by Europeans.

This is a bird of similar type to the light-breasted kalijes hitherto dealt with, with a narrow projecting crest, and rather short hen-like tail. The cock is altogether of a glossy purple black, except for the white barring on the rump which he has in common with two of his allies above mentioned.

The hen is just like the hens of the previous kalijes—brown, with each feather tipped with a lighter shade, and with the tail feathers black, except the top or central pair.

The bill is horn-colour, face red, and legs drab or grey.

The dimensions are also as in the previous species, the cock being about two feet long and the hen about twenty inches. This bird's range extends from the lower hills of East Bhootan and the Daphla country, north of the Assam valley, throughout the ranges to the southward to Chittagong, North Arrakan, South Manipur and Bhamo. Its eggs, which resemble those of the preceding kalijes, have been found in Sylhet towards the end of March. If has been tried as a game-bird in English preserves, but though it throve well, was killed off again as a nuisance, being very pugnacious to the true pheasants, hard to put up, and flying dangerously low for shooting when it could be made to rise.

THE LINEATED KALIJ OR BURMESE SILVER PHEASANT.

Gennaeus lineatus, Blanford, Faun. Brit. Ind., Birds, Vol. IV, p. 92.

Native names:—*Yit*, *Kayit*, Burmese; *Rak*, Arrakanese; *Synklovk*, Talain; *Phuqyp*, Karen.

This is a slightly larger bird than the last, but of the same type as regards the narrow stiffish crest and rather short tail; its colouration is, however, of a quite different character.

The male is blue-black only on the crest and on the under parts from throat to beak; the flanks are also black, with white streaks in the centres of the feathers, which streaking may extend over all of the breast also. But the upper plumage, wings, and tail, are of a grizzly grey or pepper-and-salt colour, produced by fine zig-zag black and white pencillings, which get stronger and coarser on the quills of the wing and tail. The topmost or centre tail feathers, however, are pure white on their inner webs and tips, contrasting well with the rest of the plumage.

The hen is brown, with the head, neck, upper back, and breast distinctly streaked with white, the white marks being

V-shaped on the back of the neck and shoulders. Her centre tail feathers have the inner webs and the tips buff, corresponding to the white of the same pair in the cock; and the outer pairs are black, marked with brown, and pencilled with wavy white lines. She is thus easily distinguishable from the hens of the previous species.

The face is red, as usual, in this species, and the bill greenish horn-colour; the eyes, however, vary from red-brown to white, and the legs from drab to flesh colour.

This is the kalij of Burma, and it extends to south-western Siam. It frequents hilly ground, and keeps to cover, being an inveterate runner and skulker. It breeds in March and April, the nest being merely a hollow lined with a few dead leaves, and containing seven eggs of a pale buff colour.

In order to understand the kalijes of this group, it will be necessary to describe a species which is not Indian, but which with the extension of our Empire or of its own ranges may come to be a British subject, and is at all events better known generally than any other kalij.

This is the *Silver Pheasant* (*Gennaeus nycthemerus*) of China now rare in a wild state in that country, but very widely known as an aviary bird, as it thrives better than any other pheasant in captivity. In this bird, which is larger than any of our species, the male has a long full drooping crest and a very long tail, reaching two feet, and gracefully arched and tapered; but the feathers composing the tail are flat and lie vertically and back to back as in other kalijes. The crest, under-parts, and flanks in the cock are blue black, and the upper plumage, wings and tail pure white, with fine hair-like black pencilling, which becomes strong and bold on the wings and side tail feathers. The centre tail feathers are plain, and at a little distance the whole upper plumage looks white.

The hen has a very short crest and a moderately long, closely-folded tail. She is of a plain uniform brown, with the side tail feathers boldly pencilled with black and white.

Both sexes have bright red legs, pale green bills, and red faces, the male's face having a beautiful velvety appearance. He is, altogether, a most lovely bird, unequalled in the whole family for grace of form, while his colouring, though so chaste and simple, is particularly striking. He is no better than other kalijes as a sporting bird, but there is more meat on him, and as he is unequalled among game birds as a landscape ornament, I should strongly advise his introduction in India, where kalijes of any sort can live, as one may as well have a very beautiful bird about as an ordinary looking one.

CRAWFURD'S OR ANDERSON'S SILVER PHEASANT.

Gennaeus andersoni, Blanford, Faun. Brit. Ind., Birds, Vol. IV, p. 94.

This species, which is rather doubtful and has been described under several names, is intermediate between the two last. The tail of the male, although not so long as that of the Silver Pheasant of China, is nevertheless considerably longer than the wing, and curved; the crest is full and drooping. This crest, with the under-parts and flanks, is black with a blue gloss, as usual; the upper parts appear grey at a little distance, but close at hand are seen to be boldly and clearly marked with concentric lines of black and white, equal in breadth and resembling a curved V or a Gothic arch in shape. The accuracy of the pattern is something remarkable, and has a very beautiful effect. On the quills of the wing and tail the marking becomes a rather irregular pencilling, and on the inner webs and tips of the middle tail feathers the black pencilling dies away altogether.

The hen is plain brown almost throughout, including the side tail-feathers, but is marked on the breast with V-shaped white streaks.

The cock is two-and-a half to three feet long, of which more than half is tail. The wing measures about ten inches.

This is one of the doubtful species to which I alluded above, as are also those which follow. Only a few specimens have been obtained, and these appear to differ considerably. The type of the species, however, obtained by the late Dr. Anderson in the Kachin Hills, closely agrees with birds from the Ruby Mines in Burma and with others obtained by French naturalists from Annam. I was able to observe the last in Paris some years ago, and there saw the hen. Dr. Anderson's bird, which is still in the Indian Museum, had flesh-coloured legs, but the others I have seen had red ones like the Chinese Silver Pheasant. Several skins collected by Captain W. G. Nisbett in the Kachin Hills, north of Bhamo and east of Myitkyina, show the most remarkable gradations between this species and the Purple or Black-breasted Kalij (*Gennaeus horsfieldi*), and the two species evidently interbreed there, the Purple Kalij strain predominating on the lower ground and the Silver Pheasant on the higher. One such hybrid, with the white pencilling on the upper surface less strong than in the true *andersoni* and showing white rump bars, has been called *Gennaeus davisoni*. Mr. Oates considers this form the true *andersoni*, and calls the Ruby Mines birds *Gennaeus rufipes*. All I can say is, however, that what I have above described as *G. andersoni* corresponds with the typical specimen in Calcutta and with the figures which have been published to accompany accounts of that species, so that there should be no doubt about it.

Dr. Blanford, in the *Fauna of British India*, suggests that *G. andersoni* may after all only be a cross between the Lineated Kalij and the Chinese Silver Pheasant; and certainly there is a stuffed specimen of this cross in the Paris Museum which nobody could call anything else but an Anderson's Silver Pleasant if they did not know its origin. On the other hand, the uniformity of the type in several specimens might be used as an argument for its distinctness. Many hybrids, however, are known to be very uniform in type, especially those between the Golden and Amherst Pheasants, and the goldfinch and bullfinch. Moreover, intermediate forms appear to occur between Anderson's and the Lineated Pheasant, and also between the former and the true Chinese Silver Pheasant, so that on our eastern frontiers there seems to be a great deal of confusion among these birds which has not yet been cleared up. Experimental breeding in confinement ought to settle the matter, and with birds so easily kept and studied as are the kalijes the problem might be solved in a few years.

I have dwelt on this point at such length because the same remarks apply to the other doubtful forms I shall now describe, though none of these are so interesting as the Anderson's Silver Pheasant, which is really a very beautiful bird in its own way and quite unlike anything else, so that if it really is a hybrid it is a very remarkable product.

CUVIER'S KALIJE.

Gennaeus cuvieri, Blanford, Faun. Brit. Ind, Birds, Vol. IV, p. 93.

In this bird, which exactly resembles the Purple Kalij in shape, the plumage is also much like that of that bird, being mostly purple black with white bars on the rump; but the upper parts, wings, and tail are all regularly but finely pencilled with white lines. The marking, in fact, is that of the Chinese Silver Pheasant reversed. All the tail feathers are pencilled in this way, from the centre pair to the outside, whereas in most of these pencilled pheasants the marking differs on the different feathers of the tail.

The hen is brown with lighter edges to the feathers, like that of the Purple Kalij, but her outer tail feathers, instead of being plain black as in the hen of that species, are pencilled with fine white lines like the plumage of her own mate.

This species, which resembles the Purple Kalij in size, seems to be found in the most typical form in the Chin Hills; at any rate some specimens I have examined from there agree remarkably in their plumage. The figure given by Temminck, who first described *Gennaeus cuvieri*, also agrees closely with the Chin Hills birds; but Temminck could give no locality for his specimen.

At the same time, these Chin Hills kalijes with fine white pencilling on black may be merely hybrids between the Purple and the Lineated Kalij, as Dr. Blanford thinks. They certainly are just what one might expect from such a cross.

OATES'S KALIJ.

Gennaeus oatesi, Blanford, Faun. Brit. Ind., Birds, Vol. IV, p. 94.

This is still more like the Purple Kalij, not only resembling it in shape and size, but being almost completely blue black with white rump-bars. But there is on the upper plumage a scanty and broken pencilling, or rather peppering, of white, giving it a frosted appearance; and the inner webs of the middle tail feathers are nearly white, as in the Lineated Kalij.

The hen is like that of the Purple Kalij, but has the black outer tail feathers mottled with black and chestnut, and the inner webs of the centre tail feathers pale buff or green colour.

This seems to be the kalij of the Arrakan Hills, two of Blyth's old specimens, in the Asiatic Society's collection deposited in the Indian Museum agreeing with the above description. The description which Dr. Blanford gives of *G. cuvieri* in the place above cited, also agrees better in some respects with this bird than with Temminck's. But he considers this form also a hybrid, as did Blyth, who identified it with Temminck's *G. cuvieri*. And two other specimens of Blyth's from Arrakan are most obviously hybrids between the Purple and Lineated Kalijes.

Several other pencilled kalijes have been described, but I have contented myself with noting the forms I have been able to make out personally, as, except the Purple, Silver, and Lineated birds, all the species with which we are here concerned are very doubtful. Sportsmen should preserve, however roughly, the skin of any pencilled kalij they may shoot in out-of-the-way places, or at least take photographs of such, the black and white markings lending themselves admirably to photographic reproduction. The dimensions and locality should of course be noted. By the collection of such evidence we may at length find out how many species there really are, but I fancy experimental breeding would determine the point a good deal sooner.

THE FIRE-BACKED PHEASANT.

Lophura rufa, Blanford, Faun. Brit. Ind., Birds, Vol. IV, p. 87.

After such a terribly mixed up lot as the pencilled kalijes, it is a relief to come across a bird which is very distinct from everything else, as is the present one. In its general appearance the Fireback resembles the shorter tailed kalijes, but the male has a different style of crest, this being erect and brushlike, and composed of feathers which are bare-shafted at the base. There does not, indeed, seem much reason for separating the few species of

Firebacks from the kalij genus. In the male of our only species, the general colour of the plumage is metallic purple; the lower back is fiery copper red, and the two centre pairs of tail feathers and part of the next pair are white. There are also some white streaks on the sides of the body.

The hen is chestnut-coloured with white edges to the feathers of the neck in front; below this the feathers are black, still with white edges, and the pattern extends along the flanks; the centre of the belly is plain white.

The bare skin of the face is bright blue and the eyes red; the bill all white in the male, but brown below in the female. The legs and feet are bright red.

The cock is a large bird, measuring twenty-eight inches in length, of which less than a foot goes to the tail; the wing is almost a foot long, and the shank nearly five inches. The hen is less than two feet long, with a ten-inch wing and tail of only eight inches.

This pheasant only just comes within our area, inhabiting Sumatra and the Malay Peninsula, whence it extends into the most southern part of Tenasserim. It inhabits evergreen forests, and is found in small parties of about half-a-dozen, though the males are sometimes solitary. They buzz with their wings like the kalijes. Like them also, they are vicious birds, a very fine specimen shown me recently by a native gentleman in Calcutta, which had been kept for more than twelve years, was confined in a cage for attacking one of the servants—whose wrist it had ripped open with its spur—when allowed to run at large. Another of the species, now in Mr. Rutledge's possession and also allowed liberty was, when I last saw it, walking round and round an old native in a manner which boded an attack. It was interesting to see that the bird's fighting attitude was exactly like what would be the show position before a hen The blue face skin was expanded, and the slanting pose assumed, so as to keep the copper back always in full view of the spectator on whom the bird was intent.

Little seems to be known of the Fireback altogether; our information about its breeding has been furnished by a captive hen, which laid, in July, a buff egg a little over two inches long. All the Firebacks seem rather scarce in captivity, so that specimens would be acceptable to any zoological garden

(To be continued).

VI.—EXTRACTS, NOTES AND QUERIES.

Experiments on the Latex and Rubber from Castilloa Elastica.

THERE are many important problems in connection with the extraction of the latex from rubber trees and its conversion into rubber which require careful investigation by scientific observers, and considerable interest, therefore, attaches to a series of articles contributed by Dr. C. O. Weber, a well-known rubber expert, to *The Indiarubber and Gutta-percha Trades Journal* (Vol. XXIV, Nos 6, 7, 8), giving an account of some experiments which he conducted while on a visit to the rubber plantation of the Las Cascadas Plantations Company on the Isthmus of Panama.

The plantation is situated in the hilly district near the town of Panama, where the land rises very gradually to a height of 1200 feet or more, and, at the lower altitudes, is eminently suited for the cultivation of rubber, cacao and coffee. The Central American rubber tree, a variety of *Castilloa*, is the one cultivated, and, at the present time, the plantation contains 70,000 of these trees, of which 15,000 are from eleven to twelve years old. An exact botanical identification of the tree was difficult, since at the time of the visit neither flowers nor fruit were present, but from a close study of the morpholcgical characters, Dr. Weber concludes that it is almost certainly the true *Castilloa elastica*. Very discrepant accounts are given by different observers as to the quantity of rubber which can be obtained from a Castilloa tree, figures ranging from 2 to 49 lb, or even more, being quoted as the yield from trees growing in Central America, while, on the other hand, experiments conducted by Dr. Trimen in Ceylon upon a large number of trees gave a maximum yield of only 4·3oz. The yield of rubber from the trees at Las Cascadas was as follows :—

Age of tree.	Yield of latex.	Percentage of rubber in latex.	Yield of rubber.
6 years	1 lb. 13 oz.	26	7 5 oz.
7 ,	2 lb. 5 oz.	26	9·6 oz.
8 ,,	3 lb. 1 oz	20	14·2 oz.
11 ,,	5 lb. 3 oz.	31	25 7 oz.

The yields from the trees of eight and eleven years of age present the means of a number of experiments, while the figures for the younger trees are the means of two trials; the results were considered to be rather below than above the average. The trees can be tapped with perfect safety twice a year, so that the annual yield of rubber would be twice that given in the above table. There is little doubt that the amount of rubber yielded by the same tree in different districts is liable to considerable variation, and the need for careful experiments before the cultivation of any particular variety is undertaken upon a large scale cannot be too strongly emphasised.

The yield of rubber is, of course, intimately associated with the amount of latex furnished by the tree, and many experiments have been made from time to time to determine the best method of making the incisions in order to secure the maximum quantity of the latter. The point to be aimed at in the tapping process is to obtain as large a supply of latex as possible without in any way injuring the vigour and growth of the tree. It is clear that the best method of making the incisions will depend largely upon the distribution and arrangement of the laticiferous tissue, and as the latter may vary widely, it is impossible to lay down any universal rule; the method of tapping must be adapted to suit the particular conditions. The laticiferous vessels in rubber trees are usually stated to lie in the layers of bast immediately beneath the bark, without extending into the wood, but Dr. Weber found that in Castilloa, although the bulk of the vessels were thus situated, there were also a number of large ducts distributed through the wood, and a considerable number surrounding the pith in the centre. Whether these inner vessels communicate at all with the outer ones was not investigated at the moment, since, in any case, only the external vessels lying in the bast can be opened without risk of seriously injuring the tree. In the bast the vessels were found to run longitudinally, and there was surprisingly little evidence of any lateral intercommunication between them. This observation at once explained the fact that longitudinal incisions in the bark gave either an extremely small flow of latex, or, in many cases, none at all, and suggested that horizontal cuts would yield the best result. In the case of Castilloa, however, a horizontal cut is not very satisfactory for the collection of the exuding latex, and, in addition, a large number of such cuts require to be made in order to extract the whole of the available latex, so that it was found preferable to employ a continuous spiral cut which can be made to drain practically the whole of the trunk. A spiral incision of this kind, made at an angle of not more than 45 degrees, gives an excellent result as far as the flow of latex is concerned, and is much better than the system of making a series of V-shaped cuts connected by a single vertical one.

The method of making the incisions is of some importance, since if they are carried too deep, there is danger of inflicting permanent injury upon the tree, though Dr. Weber, as the result of his observations, expresses the opinion that cuts penetrating to the wood are not necessarily injurious to the tree, but may retard the healing process. With a view to preventing the attacks of insects on the exposed surfaces, the wounds were treated with an antiseptic paint, and it was found that this materially assisted the healing, as in these cases the cuts began to close up a week after the tapping. A new kind of tool, enabling a clean and continuous cut to be made, was also introduced with very satisfactory results, and particulars of this are promised in a later communication.

The latex obtained from *Castilloa elastica* at Las Cascadas does not flow like milk, but issues from the cuts in the form of a thick cream containing a very high percentage of rubber. This point again illustrates the variation shown by the same tree growing in different districts, for while a similar latex is yielded by *Castilloa elastica* in some parts of Guatemala and Venezuela, yet in general it gives a fairly thin milk. The variation in this respect cannot be due to a difference of species, differences of altitude, or range of temperature, but may possibly be connected with the condition of the soil and the annual rainfall. At the moment of issuing from the cuts the latex forms an almost pure white creamy mass, which, however, almost immediately begins to discolour, and in a very short time becomes brownish-black, changes due to the presence of an oxidising ferment in the latex. It is intensely bitter in taste, due, it is thought, to the presence of a glucoside, and contains a large percentage of albuminous matter, which may reach as much as 11 per cent. This latter fact is thought by Dr. Weber to account for the ease with which Castilloa latex can be coagulated, rather than the large size of the rubber globules to which it is generally attributed.

The methods adopted by the native collectors for coagulating Castilloa latex vary considerably, and are usually of a very crude nature. The following are the most important :—

1. The latex is washed with water, but just as often this is neglected, and is treated with a decoction of the crushed stem of the moon-plant, *Calonycton speciosum*, which is strongly acid in reaction. This is the process employed in British Honduras.

2. The latex is treated with the juice expressed from *Ipomœa bonâ nox*, which is stated to be strongly alkaline, though this latter point is open to considerable doubt.

3. The latex is collected in shallow holes dug in the ground and is mixed with a boiling solution of soap in water. This method is extensively used in the Isthmus of Panama.

4. The latex is treated with a solution of alum.

5. The latex is coagulated by boiling in earthen vessels. This process is said to be employed in Mexico.

These methods need not be referred to in further detail, since they are all more or less unsatisfactory, but it may be noted that the fresh latex obtained at Las Cascadas, after being slightly diluted with water, was not coagulated even by prolonged boiling, but if allowed to stand until it had assumed a very dark colour. it was rapidly and completely coagulated by the application of heat. The serum of the latex, which contains a large amount of albuminous matter, also showed a similar behaviour. In all the above methods the separation of the rubber appears to be brought about indirectly, the added substance really coagulating the albuminous matter present, and this coagulum carries with it the rubber globules previously suspended in the latex. The rubber thus obtained is, therefore, always contaminated with albuminous matter, often containing from 9 to 13 per cent. of the latter, and it is the presence of this which makes Castilloa rubber, as usually prepared, so prone to putrid fermentation. The value of the rubber would be greatly increased if these albuminous substances could be eliminated, either by removing them from the liquid before coagulation, or by bringing the latter about in a manner which does not also involve the coagulation of the albumen. Methods have been already suggested for accomplishing this in special cases, and a very simple process, applicable to Castilloa, is now given by Dr. Weber. It has been observed that if Castilloa latex be diluted with water and allowed to stand, it "creams," *i. e.*, the rubber globules rise to the surface but do not unite to form a coherent mass. Dr. Weber finds, however, that if formaldehyde be added to the diluted latex, the rubber globules, which separate, do coalesce to form a cake, while all the albuminous matter remains in the liquid. In carrying out the process the crude latex was first diluted with at least five times its volume of water, and in dealing with the thick latex obtained at Las Cascadas, it was found advantageous to dilute with boiling water, but this plan would not be applicable in all cases. The diluted latex was then strained through cotton gauze into well-washed petroleum barrels, to each full barrel 8oz. of formaldehyde was added, the whole was well stirred and allowed to stand for 24 hours. The formaldehyde prevented any coagulation of the albumen in the hot solution, and also caused the rubber to separate as a white mass of such strength and toughness that it could be lifted entire from the barrel. This mass of rubber is rather porous and contains a quantity of the liquid enclosed in its cavities, so that it is at once cut into strips which are thoroughly washed with water until quite free from albuminous matter, and then dried. The rubber thus obtained is of exceptional purity, it does not undergo any change on keeping, and could be used for many industrial purposes without further treatment. The dry strips are extremely light in colour, semi-transparent, and, when dissolved in the usual rubber solvents, form almost glass-clear solutions; the characteristic rubber smell is almost entirely wanting, the strength is said to be superior to that of washed and dried strips of Para rubber, and the behaviour in the vulcanizing process and the character of the vulcanized product are at present under investigation. An analysis of one of the strips showed that it contained only 2·6 per cent. of resinous matter, 0·44 per cent. of ash, and no albuminous or insoluble constituents.

Some interesting observations were also made regarding the amount of resin present in the rubber obtained from different parts of the same tree and from trees of different age. It was found that in an individual tree the resin increased in amount from the root upwards, and that the rubber from the younger trees always contained a far larger portion of resin than that from the older ones. The following table gives the differences observed:—

	Percentage of resin present.
Rubber drawn from trunk	2·61
" " " largest branches ...	3·77
" " " medium " ...	4·88
" " " young " ...	5·86
" " " leaves	7·50
Rubber from tree 2 years old	42·33
" " " 3 " "	35·02
" " " 4 " "	26·47
" " " 5 " "	18·18
" " " 7 " "	11·59
" " " 8 " "	7·21

Similar differences have been recorded in a few other cases, and the amount of resin present in a sample of rubber would therefore appear to depend not only on the particular variety of tree from which it was obtained, but also on the age and to a less degree on the part from which the latex was drawn. The above figures indicate that in the case of Castilloa it would not be advisable to tap the trees until they are at least 8 years old, not only in the interest of the life and development of the tree, but also in the amount of resin which may be safely admitted in rubber of high quality.

In conclusion, Dr. Weber gives some particulars concerning the prospects of rubber-planting in Central America, and one point mentioned is of interest to all intending planters of *Castilloa elastica.* It is stated that there are three varieties of the tree, viz., *alba*, *negra* and *rubra*, distinguishable only by the colour of the bark, but of very different value as rubber producers. The *alba* has a white bark of a distinct yellowish or pinkish cast; it is the hardiest of the three varieties, suffering little from the tapping process; it produces a thick, creamy latex, and yields the largest quantity of rubber. The *negra* has a very rough, dark bark; it readily yields a thin milk, producing a good rubber, but the tree may be easily bled to death in tapping. The third variety, the *rubra*, has a reddish bark which is very smooth, thin and brittle, and does not show the longitudinal furrows noticeable in the other two; it yields a very small quantity of latex, but the quality of the rubber is good. The *rubra* is very common all over Central America, and it is possible that it has been planted in a number of instances instead of the *alba*; indeed, Koschny is inclined to think that it was the *rubra* variety which gave such discouraging results in Ceylon and Java. In planting Castilloa, therefore, great care would appear to be necessary in order to make quite sure that the seeds or seedlings employed are really those of the best variety.—*Imperial Institute Journal.*

Professor Bailey on the want of a State Forest.

COLONEL BAILEY, in opening the Forestry Class, said the present was the twelfth occasion on which he had addressed an introductory lecture to the students of that class. In France, Germany, and other foreign countries, he went on to say, they had fully equipped special schools with woods in which practical instruction was given, and the students' whole time, for three or more years, was at the disposal of the professors. At Cooper's Hill candidates for the engineer, telegraph, and forest department of India received their training, and the course for forestry students extended over three years, one year of which was spent in practical work in German and French forests. In Edinburgh they were limited to a course of one hundred meetings, and the students of the class were for the most part engaged in other university work, so that the practical work was unavoidably limited to excursions on Saturdays to woods in the neighbourhood, which had not been managed on correct principles for a sufficiently long time to render them suitable object-lessons to the class. The want of a State demonstration forest was very badly felt. Woods privately owned could never answer the purpose satisfactorily. In consequence of representations made by the Arboricultural Society, a Departmental Committee had been appointed by the Board of Agriculture, and it might be hoped that one result of that committee would be the provision, within a convenient distance of Edinburgh, of a State area in which practical instruction could be given to this class. Visits to Continental forests would, however, be desirable for some years to come, until well developed middle-age and older crops could be shown here. The prospects now offered to foresters in this country were not encouraging. That was largely because their woods had not, generally speaking, been managed on business principles, with the sole object of making them pay a profit from the sale of their produce. For that and other reasons they had not, in the past, yielded the returns they would have rendered under different management That result, however, had not been attributed to its true cause, but had been falsely ascribed to defects in their soil and climate, the non-existence of which might be concluded from the splendid specimens of isolated trees which adorned their parks and policies. Their woodlands had great potential value, which had not yet been generally recognised by their owners and the public. But the old views on many points connected with British forestry were rapidly losing ground; and as soon as a fair proportion of their landowners began to realise the possible value of their woods, and to recognise forestry as a science, they would begin to pay adequate salaries to trained men. The certain falling off in their supplies from abroad would enhance the market value of home-grown timber, and that again would add to the value of their woods, and render their owners more desirous of placing their management on a sound basis.—*The Timber Trades Journal.*

Forest Destruction by Insects in Norway.

CHRISTIANA, *December 20th* 1902.

OUR big forests in Osterdalen and Solor have met with a fearful plague, and are in great danger of being destroyed.

A larva "furuspinner" (firspinner) appears in masses, and has already totally destroyed 6000 "maal" (one maal equals 1000 metres). It appears, besides, in abundance over an area of 60,000 to 70,000 maal, setting aside the areas where it does not appear so numerous. The hitherto caused damage can scarcely be estimated less than 300,000 kroner, to which comes the value of the infected and threatened areas. The value of these latter is estimated at 1,200,000 kroner. Under these facts—and in consideration of the rapid spreading the larva has had, and paying attention to—that we still only are in the beginning of its devastation—the forest societies are letting their daily work rest for getting time to fight the great danger only.

How rapid the larva has spread the following facts will show: In 1901 10 to 20 maal were destroyed; up to August 12th, 1902, 1000 maal; to September 26th, 1902, 2000 maal; October 8th, 1902, 3500 to 4000 maal; and to October 22nd, 1902 6,000 maal.

A petition has recently been handed to the Agricultural Department with a request, as soon as possible, to grant and pay 25,000 kroner, to the "Hedemarken Forest Society," who are willing to conduct the fight against the pest. This temporarily, 25,000 kroner, will be used for preliminary ~~enquiries~~ how the larvæ can best be destroyed.

The forest owners themselves are now preparing to protect their forests against the destroyers when they, in the spring, awake from their sleep in the bog. For instance, by glue-rings around the trunks, where the larvæ will then stick to when crawling up; or by digging trenches, with small deepenings, with food in, is an easier way to be able to destroy them. Isolation lines of glued laths will also be used.

The larva is very big, quite 2½ inches long, and about a little-finger thick. It eats a fir leaf in five minutes, and 1000 fir leaves before changing into a butterfly. It was hoped that they would perish during the winter; but the fact is that they easily stand 10 to 15 degrees. They are lying together in balls under the bog during the winter, and awake in April, when they at once go to their destroying work. It is pitiful to look at an area where the larva has stayed for some time. All is eaten—not a fir leaf left—only brown, brown, brown.

It is believed nature only destroys them by parasites (mushrooms), but only after a three years period; but as they, during three years, can waste big areas, of course, something must be done, and as fast as possible. To cultivate parasites will be tried, and spread them out over the infected forest. The last four dry years have caused this plague.

Perhaps the worst of all is that nothing will grow on the places where the larva has wasted.

The last time these pests appeared in such numbers was in 1812 to 1816, when big forests were destroyed.—*The Timber Trades Journal.*

VII.—TIMBER AND PRODUCE TRADE.

Churchill and Sim's Wood Circular.

London, January 12th, 1903.

EAST INDIA TEAK.—The importation of timber and planks has been:—

	1896.		1897.		1898.
	23 312 Loads	...	20,428 Loads	...	18,063 Loads
And the deliveries	21,941 „	...	18,410 „	...	18,526 „

	1899.	1900.	1901.	1902.
	12,835 Loads...	15,024 Loads...	12,860 Loads...	8,764 Loads
Deliveries.	17,017 „ ...	11,053 „ ...	13,807 „ ..	12,598 „

A comparison of the figures of importation, delivery and stock given in our tables reveals the fact that the London market for teak has been badly starved for supplies during 1902. An abnormal shortage of rainfall in Burma and Siam has resulted in a block of logs up country, which there has been no water in the rivers to bring down for manufacture to the shipping ports, and occasional heavy storms, causing sudden temporary floods, seem to have done more harm than good, by washing logs away altogether. A more normal state of things is thought now to have supervened, but the process of getting into working order again will be very slow, and in the meantime, stocks in the importing markets all over the world are being reduced to a minimum. Prices have risen slowly and with a good deal of hesitation throughout the year, and at its close are certainly not so high as might well have been expected under the circumstances—partly, perhaps, from sheer lack of anything to feed upon, for it is difficult to raise prices without any wood to sell. In London the consumption remains at about the average of the two previous years, but is greatly below the figures of the years before that, when supplies were so much larger. Logs and planks have about maintained their relative position, the demand for the latter not having made any notable further advance during the year. The supplies from Java have been more ample, and, partly aided, no doubt, by the scarcity from the older sources, have advanced greatly in favour, and been saleable at fairly remunerative values. The demand for teak grows and spreads steadily, and although less is probably used in an individual warship than was formerly the case, many more warships are now built and planned, and the general use of the wood increases yearly.

ROSEWOOD—EAST INDIA.—There was a considerable increase in the imports last year, and the demand, although still small, was rather better. The bulk of the import was taken into consumption, but sufficient stock remains on hand to supply current inquiry, which is mostly for large prime logs of good colour. Prices kept fairly steady, and are now firmer at from £8 to £11 per ton.

SATINWOOD—EAST INDIA.—The heavy stock brought forward was increased by fresh arrivals in the early part of the year, and for several months sales were slow and difficult, only figury logs attracting attention. Later on, supplies being less and the demand better, considerable sales were made, and although stocks are now quite moderate, there is sufficient ordinary wood, but finely-figured logs are rather scarce, and continue to bring good prices. Quotations are from 6*d*. to 1*s*. per foot.

EBONY—CEYLON.—There was a considerable increase in the imports last year, but the demand remained inactive. Prime large logs were scarce, and the small lots sent brought full prices, but the bulk of the supply consisted of ordinary or poor wood, for which buyers could only be found occasionally, even at low prices, and the unsold stock is now rather heavy. Quotations are from £8 to £15 per ton.

EAST INDIA.—The imports were in excess of the previous year, but were still very moderate. The demand was steady, and prices kept firm for good wood, but lower qualities were weaker towards the end of the year. Quotations for average sizes are from £9 to £12 per ton.

PADOUK—EAST INDIA.—The import, although slightly larger than that of the previous year, was still very small, and sold readily at good prices. Supplies are now much wanted, as there is an active demand and scarcely any stock. For African there was more enquiry, but only one small parcel was sent here; this sold well, and the demand is increasing. Quotations for East India wood are from 5*s*. to 6*s*., and for African from 4*s*. to 5*s*. per foot cube.

Denny, Mott and Dickson, Limited.

WOOD MARKET REPORT.

London, 1st *January* 1903.

TEAK.—The course of this market during the past year has been consistently upwards, and the year closed with an advance of some 25 per cent. on the prices ruling at its commencement. This winter's abnormally short supplies from the forests in Burmah and Siam, owing to a short rainfall, point to a very restricted supply to Europe during next year; and, although the consequent increase on f.o b. prices may already have been largely discounted, it seems clear that there will be a still further rise in values. Irrespective of the difficulty always created by unusually high prices, merchants and dealers here are already embarrassed by finding it impracticable to fill the usual specifications of consumers, who have become accustomed to have their needs more or less specially cut against in the Indian mills, which now find this class of business almost impossible—owing to the short supplies of suitable log timber for conversion. Planks and special conversions have, therefore, become so costly under the stress of increased demand and decreased supplies of raw material to the mills that it is to be feared the widening use of teak during recent years for architectural and domestic purposes will be seriously checked, seeing that teak is rather a luxury than a necessity for this class of work. It must, however, be recognised that teak logs are a necessity for naval and high-class passenger ship construction, and also cannot be lightly displaced for rolling-stock construction, so that the inevitably small supply to Europe during next year threatens to seriously inconvenience important industries, and put teak consumers out of humour with both shipper and merchant. It is, however, to be hoped that the next season's supplies, which should commence to reach the Indian shipping ports next autumn, will be sufficiently ample to remove any great apprehension of the enforced high prices for this year's arrivals bringing about a seriously permanent displacement of this increasingly appreciated wood, where high-class construction is the main object. The import of teak last year has been some 53,000 loads against a consumption of some 65,000 loads; and the total landed stocks in Europe are only about 17,000 loads, which is a record minimum and about 42 per cent. under the working stock in Europe of 1902, which, in its turn, was a record, as the average landed stocks for the previous 10 years were some 47,000 loads. Whilst the shortfall in stocks here of some 30,000 loads and the inevitably restricted importation for next year have to be faced up to, it must not be forgotten that the dull condition of trade will probably tend to lessen the demand for shipbuilding and rolling-stock construction, although the demand for South Africa should be a special exception—owing to the prospective railway developments, and the re-equipment of the existing railways necessitated by the events of the recent war.

In respect to London *per se*, the imports into and deliveries from the London Docks during the twelve months ending 31st December 1902, shew as follows:—

Logs	5,420	loads imported, against	7,834	loads delivered	into consumption.
Plank and conversions	2,814	"	" 4,283	"	"	"
Total .	8,284	"	" 12,117	"	"	"

NOTE.—The above figures deal only with *landed* stocks, and are exclusive of the overside deliveries, which, although very important in quantity, are not noted by the Dock companies.

The Dock stocks at date analyse as follows:—

	5,394	loads of logs,	as against	7,779	loads at the same time	last	year.
	2706	" planks	"	4,115	"	"	"
	—	" blocks	"	12	"	"	"
Total	8,100	loads	"	11,936	loads.		

The past year has been characterised by a dead level of dullness throughout all departments of the timber trade, the demand having been of a monotonous hand-to-mouth character, with few forward contracts of any importance. On the other hand, the cost of most hardwoods, of which teak and mahogany are the leading examples, has steadily risen; and American and Canadian woods have also advanced all round. With the possible exception of pitch pine the increased cost in all these woods has not been due to any artificial manipulation, but the legitimate result of light supplies and increased cost of forestry operations owing to the appreciation in value of land, the giving out of the old forests near the main streams, and, in the case of teak, increased royalties and Government restrictions on the depletion of forests. As populations grow in the countries supplying timber to Europe, there is a greater demand for the home needs of such countries, and the trend is to increase the cost to Europe for the decreased quantities to be shipped; and although countries near home, like Russia, Norway and Sweden, may force down values by prematurely forcing on Europe more than it is in need of, time will surely, if slowly, bring about a permanently higher level of value, seeing that it is a generally accepted fact that nature is not replacing trees at the same rate as they are being cut down. Financially, the timber trade has continued to be sound, as the great dullness in trade has served to emphasise caution, rather than, as is sometimes the case, caused rash speculation in order to galvanize trade with the spurious activity which ends in financial trouble.

Market Rates for Products.

TROPICAL AGRICULTURIST.

January 1st 1903.

Cardamoms	...	... per lb.	1s. 9*d* to 2s.
Croton seeds	...	... „ cwt.	15s. to 25s.
Cutch	...	... „ „	25s. to 30s.
Gum Arabic, Madras		... „ „	18s. to 25s.
Do. Kino	...	... „ lb	4½*d*. to 7*d*.
India-rubber, Assam		... „ „	2s. to 2s. 6*d*.
Do. Burma		... „ „	2s. to 2s. 4*d*.
Myrobalans, Madras		... „ cwt.	5s to 6s.
Do. Bombay		... „ „	4s. to 7s.
Do. Jubbulpore		... „ „	4s. 6*d*. to 6s.
Do. Bengal		... „ „	3s. 6*d*. to 5s.
Nux Vomica	...	... „ „	7s. to 10s.
Oil, Lemon-grass	...	... „ lb.	5*d*.
Sandalwood, logs	...	... „ ton	£15 to £30.
Do. chips	...	... „ „	£5 to £5 10s
Sapanwood	...	... „ „	£4 10s. to £5 10s.
Seedlac	..	... „ cwt.	117s. 6*d*. to 120s.
Tamarinds, Calcutta		... „ „	8s. to 10s.
Do. Madras		... „ „	4s. 6*d*. to 6s.

Errata "Indian Forester," January. 1903.

Page	3,	line	7,	from below,	read	" first "	instead of	" firts "
"		"	2	"	"	" Graf "	"	" graf "
"	18	"	7	"	,	" more "	"	" non-"

THE

INDIAN FORESTER.

Vol. XXIX.] April, 1903. [No. 4.

The Unity of Sylviculture.*

SYLVICULTURE is one. Professor Mayr of Munich, who emits this aphorism in the pages of the *Allgemeine Forest und Jagdzeitung*, means thereby to emphasise the unity of the principles of the art in all countries, however deeply they may have to be modified in order to meet human interest and local conditions. The author has travelled much. He has studied forests under the most various climates, and has deduced from his studies a series of general principles. A discussion of each of these would lead us too far, but a selection is here offered to the reader, who may make his own comments thereon.

1. When the mean temperature of the four months of most active growth falls to 10°C. the forest disappears or is represented by a poor stunted growth. This holds equally for Europe, Asia, and America in both hemispheres. Under the equator the limit of woody growth is at about 3500 metres† yet at this elevation it seldom freezes! (*Query.*—During the four months at 11,400ft. on the equator.—TRANSL.) The temperature of 10° is there nearly constant; the *annual* mean is that of the regions where in Europe the wine and tobacco prosper, yet wood will not grow. It follows that the 10° of the winter season do not count, and that the total temperature cannot serve to characterise the vegetable life.

2. In the northern hemisphere, when the mean temperature of May, June, July and August is between 12° and 15°, forest vegetation exists, and resembles that which is found in Germany

---

* Translated from M. A. Schaëffer in the *Revue des Eaux et Forêts* for 1st August 1902.

† Say 11,400 ft., but the translator has seen firs and bushes at between 12,000 and 13,000 in the Himalayas.

under similar climatic conditions. It is the zone of the fir and spruce in Europe, Asia and America. If, during the same months the mean temperature is between 15° and 18°, the locality is that of the beech, while the oak, maple, *tsuga* and *chamæcyparis* can also be grown. A knowledge of the summer mean is therefore fundamental when introducing exotics. Conversely, if a region produces naturally spruces, beeches, chestnuts or what not, a close idea can be formed of the mean summer temperature. This is a very useful piece of knowledge in countries where the meteorological stations are few and far between, such as Asia and America.

The constitution of climatic zones should not be based on herbaceous plants, even perennials, but on trees, and among trees those which have a limited *habitat*, for instance, spruce, beech, chestnut, lime. The Scotch pine, whose *habitat* extends from that of the chestnut south of the Alps to the Polar Circle, is useless as a character. (It would be interesting to compare the opinion of M. Mayr with the learned theories propounded by M. Flahaut in the *Revue* of 1901.)

3. Forest species may be grown in places far from their original *habitat*, provided that the local climate of the new region is analagous. If the exotic comes from a warmer climate, it should be placed on south slopes with plenty of sun; if it comes from a colder climate, it should be placed in moist soils and cool aspects. Climate opposes an insurmountable barrier to natural reproduction. There is no such thing as acclimatisation. If certain species like walnut and robinia have been naturalised for centuries, it is simply because the climate of naturalisation was essentially like that of origin. There is no adaptation to a new and different climate.*

4. Trees of cold climates do not possess in themselves any special power of resistance to frost, and the immunity which seems to be sometimes possessed is an individual and non-transmissible quality. It is thus useless to import seed from colder climates in the hope of obtaining greater hardiness.

5. Trees growing in hot localities or in open crops are less exacting in the matter of soil. They are more exacting in cold moist localities or in the crowded state. The conditions of heat and light are similarly related. All species bear shade better when brought to a warmer climate, and require more light when brought to a cooler one. Trees which bear a certain amount of cover in their optimum climate (ash, maple, elm, Weymouth pine) become shade bearers in hotter climates and cannot endure shade in colder ones.

---

* But trees brought, for instance, from the southern to the northern hemisphere will accommodate themselves so far as to flower say in June in India when their natural season may have been December in Australia.—TRANSL.

6. In level countries where the heights do not exceed 100 or 200 metres above sea-level, the *habitats* depend on latitude, modified very considerably by winds from the sea; thus in the west of Northern and Central Europe they follow rather longitudes than latitudes. In high mountain regions, altitude may produce effects similar to those of latitude. The climate of the northern plains is found in the south at some elevation above sea-level, so that a species has often two *habitats*, a northern and a southern. It is therefore a mistake to label one species as a mountain species and another as a plains species. The spruce in Europe, the Douglas pine in America are mountain species in the south and plains species in the north.*

7. The climatic needs of a species are better characterised by its *habitat* than by the latitude or altitude at which it grows. Latitude and altitude combined furnish a more reliable but still insufficient basis. If you tell a forester that the European larch grows at 1500 metres altitude on the 46th parallel of north latitude, or that the Japanese larch flourishes at 2000 metres on the 38th parallel, he gets no clear idea. But if told that both larches prosper in the region of the fir and spruce he grasps it at once. Perhaps a certain reserve is here necessary; few foresters will agree that the larch has the same *habitat* as the fir and spruce.

8. If, in a given climatic zone, there are found two neighbouring species of the same genus, such for instance as *Quercus pedunculata* and *sessiliflora*, it may be predicated that these two species were not originally amalgamated, but each had its distinct *habitat*, and that the mixture is generally due to the action of man. In Japan and America, where the flora is much richer, the applications of this law are far more striking. In practice, too, little attention is paid to these divergent exigences of climate, for though slight they are of great importance.

9. In primitive forests the species which harmonise best are those which differ most botanically, though requiring the same climate. (Beech and fir, oak and pine, maple, ash and lime.)

10. When two species are so alike as to be considered almost varieties, but have nevertheless different climatic needs, they are in reality true and distinct species. It is an error to consider morphological differences as a result of climate, and to say, for instance, that the Russian spruce (*Picea obovata*) is only a form of the German spruce modified by severity of its locality. If this were so the Russian spruce would be found on the tops of the mountains, but we know that there is nothing of the sort.

---

* True for many species, but is not barometric pressure a condition affecting plants?—TRANSL.

M. Mayr will perhaps permit a note of interrogation here. It appears from certain studies made in France, notably by MM. Brenot and Mathey, that *P. obovata* exists both in the Alps and in the Jura.

11. Frost-injury is always due to the death of the plasma killed by the direct action of cold. The plasma is most sensitive during the time of cell-formation and active growth. When the functions of life appear dormant the chlorophyll is more sensitive than the colourless plasma. This explains the disease called "*le rouge*," which is due to sun and cold combined killing the chlorophyll. Plasma in the inert stage, as in seeds, is insensible to the intensest cold.

12. All species become more hardy as they grow older, but this is not a phenomenon of adaptability. The fact is simply due to the trees rising above the cold layers of temperature near the ground, and to the greater thickness and mass of the trunk.

13. The degree of moisture in the air is a great factor in forest vegetation. Experiments made in North America convinced M. Mayr that the forest ceases to exist in regions where the tension of water vapour averages less than 0 50 during the four months of growth: here is the domain of the steppe. Oaks and 2—3-leaved pines are the pioneers of the steppe; it is they which least fear the neighbourhood of the dry zone. As this zone is left further behind, the number of species increases, but it is only on approaching a moist zone that the firs, spruces, cypresses, and 5-leaved pines appear. Hence the broad-leaved trees and 2—3-leaved pines are the only suitable species where the air is very dry, or where its moisture is subject to sudden variations.

14. The association of trees as a crop has the effect of raising to some extent (10 per cent. at most) the degree of atmospheric moisture. This emphasises the need for maintaining forests in regions where the water-vapour tension varies round 0·50 per cent. The partial destruction of a forest may entrain the death of the remainder, and render *reboisement* impossible except adjoining existing forests. Inside a forest the greater humidity of the air has an action as beneficent as that of the moist ocean winds, and is exempt from their violence.

15. It is in moist cool localities (mountain and northern) that climatic variations are least extreme during the growing season. It is there that the annual rings are all equal and the grain fine and regular. It is there that wood attains its maximum of industrial utility (resonance to sounds).

16. The moister the climate, the easier becomes forest culture; regeneration fellings, thinnings, etc., all are simplified.

Air-moisture seems to exercise a favourable influence on the straightness of stems in all trees, and especially in Scotch pine. It would be interesting to verify the fact in France.

17. It is known that a failure of rain for several days may be fatal to young plants The faculty of persistence increases with age, and the grown tree can endure fairly prolonged periods of drought without much harm. But if the phenomenon recurs so that the mean rainfall of the four months growing season falls below 50 millimetres (two inches) the true forest disappears even if the air-moisture remains always above 50 per cent. Exception must be made in cases where the winter rains are very heavy and in the neighbourhoods of lakes and rivers with their sub soil percolation.

18. A fairly moist soil is the best for all species when in their true climate. In hotter places, the locality must be more damp, while in colder ones it may be dry without hindering growth.

19. Snow protects those parts of a plant which it covers, but it increases the danger of frost in the parts just above, for there the cold becomes excessive. Snowy winters are, therefore, useful to low plants, but harmful to trees.

20. As regards winds, the most dangerous are those which follow the direction of barometric minima, in Europe from the west, in Eastern America from the east,—in Eastern Asia from the south. Those coming from the opposite direction are less dangerous, but still more so than those coming from other points. Every elevation, mountain or hill, determines a deflection of the current, a vertical whirlwind as high as the obstacle, and a return in one of the opposite directions. In localities called sheltered the most dangerous wind for Europe is thus from the east, and consequently the rules for laying out coupes may require some modification. On the east slopes of a plateau, the regeneration fellings should be laid out north-east and south-west.

21. In their youth trees are almost indifferent to the quality of the soil, but with age their exigences become manifest. This explains the arrested development of many very promising plantations (larch on sand for instance).

22. In their most suitable situation all species are so to speak polyphagous, that is to say, they succeed on soil of any mineral formation; but as the locality becomes less favourable their exigences increase, so that certain exotics will only grow in parks or even in pots. This point is contestable, and it is doubtful if the chestnut would prosper on limestone in the best possible locality on the south side of the Alps.

23 The light that most favours the activity of the chlorophyll, and consequently the growth of trees, is not that of a blazing sun in a cloudless sky, neither is it the diffused light coming through rain or fog; but that reflected by brilliant white clouds. This shows what differences there may be in the effect of shade. Cover is favourable when it filters the rays of a too burning sun; unfavourable when it cuts off too much of the necessary light. Under a Continental climate cloudless days are more numerous than near the coast, light and heat are more intense; the influence of cover, of lateral shelter, and the effect of thinnings will thus differ with the Continental position. Forest operations need to be conducted not alone with regard to the soil and species, but also in accordance with the climate, aspect, and degree of sunlight. Here, again, sylviculture does not rest on arbitrary rules, but on the laws of nature. Under a more or less foggy maritime climate, young trees do not require cover; the mist and clouds suffice; the underwood is also unnecessary. The maritime climate is not limited to the sea coast; it is found also in certain mountain regions and notably round great lakes.

24. A knowledge of the laws of nature is especially necessary in the regeneration of forest crops. Those which are approaching their exploitable age in their most suitable climate are the easiest. If the climate is warmer, seed will indeed be more abundant, and the young plants will endure cover better, but the moisture of the air and soil may be wanting, and the necessity of maintaining a denser cover over them may intercept too much of the needful rainfall. If the climate is colder, the moisture of the air indeed increases, but the production of seed and the persistence under cover both diminish

25. In mixed crops artificial regeneration is more difficult than natural regeneration. The clean felling induces a capricious complication of laws and phenomena whose contrary actions are not easily understood. Certain mixtures, such as spruce and larch, beech and larch, oak and beech, seem to require a mixed method, natural regeneration aided by artificial.

. . . . . .

The principles of M. Mayr are open to discussion, but few in France will controvert his conclusion, which is this:

"Natural regeneration, a mixture of species suitable to each locality, a crop resembling as closely as possible the primitive state, such are the conditions which the forester should seek to realise, not only for the avoidance of dangers, but also for the greatest possible yield of the most valuable produce." And he adds:

"The more one seeks to build up sylviculture on rational bases, the more one becomes convinced that there is no method of treatment which harmonises better with the laws of nature than the method of *jardinage* (selection method). Not the primitive *jardinage*, which was merely a harvesting of the ripe trees, but that regulated *jardinage* which, in a forest containing the greatest possible variety of species and age classes, removes no single tree without aiming definitely towards either the regeneration or the improvement of the crop. Irregular *jardinage* is the most ancient, the easiest, and the roughest mode of treatment. Regular *jardinage*, with the view of placing each tree in the conditions most favourable to its development, is the most perfect and the most difficult of treatments. It is an ideal not always easy to realise."

For our part, we can only endorse this conclusion, which seems to be the coming idea. Standards over coppice and selection forest have many points of contact, and there are already many foresters who hesitate to destroy a crop on pretext of regenerating it. Is it not possible to conceive a treatment which, given a duly constituted forest, should maintain it always and for all time in the same condition? Why should not the XXth Century realise this "*Unity of Sylviculture*"?

The Insect World in an Indian Forest and how to study It.

BY E. P. STEBBING, F.L.S., F.E.S.

(*Continued from p. 111.*)

PART VI.

THE ORDER *LEPIDOPTERA*.

THIS order comprises the butterflies and moths, both of which are very numerous in India. They are provided usually with four wings, all of which, together with the body, are covered with coloured scales, those on the body looking more or less like hair. The mouth parts in the perfect insect are formed for sucking, and are in the form of a coiled tube or proboscis. This proboscis is the characteristic feature of the mouth of a lepidopterous insect, and owing to the possession of such a mouth the destructive powers of the adult are very limited. The head is small, with two large eyes, and ocelli may be present. The antennæ are simple and knobbed or pectinate. The prothorax is small, flat and scale-like, and is attached to the other portions of the thorax. The wings are various in shape, and the hind wing is sometimes prolonged into a tail. The wing is divided for purposes of description into the following regions: inner angle, costa, outer angle, hind margin, anal angle and inner margin. The wings are always fringed with hairs. The legs are unusually long, slender and weak, the tibiæ being furnished with spines. In most moths the upper and lower wing is joined by a hook-and-loop arrangement, the loop being on the upper and the hook on the lower wing. This is never present in butterflies. Tarsi are five-jointed. The abdomen is cylindrical and sometimes flattened on each side. The males differ from the females in being smaller, more brightly-coloured, with a thinner body, more highly developed antennæ, and by having the body sometimes terminated in a clasping arrangement for catching hold of the female. The eggs are various in shape and are often very elaborately marked. Practically the only damage done by this Order is committed in the larval state. The larva has a cylindrical worm-like appearance. It consists of a well-marked head followed by twelve segments. The first three segments bear legs which are jointed and horny, and are called thoracic legs; next there are two small segments with no legs, and then four segments bearing each a pair of sucker-like legs provided with small hooks for clinging to leaves, etc. These legs are called the abdominal legs. Following these there are two more legless segments, and the last segment bears a pair of clasping legs. Never more than eight pairs of legs are present in *Lepidoptera*, though the number may be fewer, and in this way caterpillars can always be distinguished from saw-fly larvæ (*Tenthredinidæ*), which greatly resemble them, the latter having always more than five pairs of clasping legs. In some caterpillars only the thoracic legs and the last pair of abdominal and clasping legs (also called pro-legs) are present. In a few cases the pair of clasping legs is absent. The head is provided with a few ocelli placed just above the mouth. The antennæ are short and three-jointed. The larva is sometimes provide with silk, and there are then two small glands at the sides of the body, the silk coming from these as two separate threads, which become glued together by a cement that hardens in the air; the larvæ suspend themselves by this thread. There are nine pairs of spiracles (breathing openings) present, situated at the sides of the 2nd, 5th, 6th, 7th, 8th, 9th, 10th and 11th segments. The anus is covered by a triangular flap. The larva is covered with hairs which may be few and small or long and numerous; these spring from tubercles situated on the grub. Whilst developing the caterpillar passes through a series of moults, 2—5 in number, but usually four, during which it may change considerably both in form and colour.

The larva pupates either by burying itself in the ground, hanging itself up by its tail, making a silken cocoon (external covering) and changing to a chrysalis within this, rolling up the edge of a leaf and pupating inside, etc. The pupa is covered by a continuous skin, which only shows the outline of the limbs of the future insect and the division of the abdomen below; projections indicating eyes and proboscis are also visible. The proboscis may project a long way in some cases, as in the Hawk Moths. When the insect is mature it bursts the skin and crawls out. The wings at this stage are very small and soft and crumpled up. After leaving the pupal skin the perfect insect hangs itself up, head uppermost, and pumps fluids from its body into the wings so as to expand them This process never takes more than two hours, by the end of which period the wings are fully expanded and hardened and are ready to be used for flight.

The length of the whole life-history of Insects of this Order may vary from two weeks or less to over four years. In the latter case the greater part of the time is passed in the larval or destructive period of their life. Little is at present known about the wood-boring members of the Order in India, and their study is becoming an important matter. Mimicry and protective resemblance is very marked amongst the *Lepidoptera*, and cases are numerous where a harmless insect assumes the colouration and markings of a noxious one to escape the attacks of its bird and insect foes. For instance members of the genus *Papilio* often mimic the colouration of the noxious *Danaids*.

The *Lepidoptera* are divided into the two series, *Rhopalocera* or butterflies and *Heterocera* or moths

Series Rhopalocera or Butterflies.—Antennæ knobbed at the tip or thickened a little before the tip, without pectinations or projecting processes. Hind wings without a frenulum (the one or more stiff bristles projecting forwards and outwards from the inner upper angle of the hind wing are called the frenulum) but with the costal nervure strongly curved. The insects are diurnal in habits. Larva has always 16 legs.

Series Heterocera or Moths—Antennæ vary in form, generally pectinate, only rarely knobbed at tips, and then a frenulum is present, and the costal nervure is either not arched at the base or there is a large margin between it and the front margin.

RHOPALOCERA—(Butterflies)

Are of little importance in forestry as far as is at present known. They may be divided into the following four groups:—

I—Includes the majority of butterflies. The first pair of legs are strikingly modified, they being generally smaller than the others and not used for walking; the tarsus often does not consist of a succession of simple joints, as is usually the case with insects. There is no pad on the front tibia. The chrysalis is naked and suspended by its tail to the food plant, or is girt round the centre with a silken cord. The families included in this group are the *Nymphalidæ* [to which the leaf-butterfly (*Kallima*) belongs], *Erycinidæ*, and *Lycænidæ* (to which the Blues and Coppers belong).

II.—The front legs are similar in form to the others; their tibiæ have no pads; the claws of all the feet are bifid. The pupa is attached to the food plant by a silken cord girt round about its centre. The group includes the *Pieridæ*, containing the Whites, Brimstones, Clouded Yellows, etc.

III.—The front legs are like the other pairs; their tibiæ, however, possess pads; the claws are large and not bifid. The pupa is naked and tied to the food plant by means of a silken cord round it. The family *Papilionidæ*, consisting of the swallow-tail butterflies, comes here.

IV.—The front legs are like the other pairs, their tibiæ possess pads; the claws are small, toothed at the base, and there is a hook at the end of the club of the antennæ. The chrysalis is rolled up in a leaf or other covering. The family *Hesperidæ* or skippers are included here. Mr P. Mackinnon, a well-known Indian authority on the *Rhopalocera*, has informed me that he has bred these insects from various fruits in India, and it is now, I think, becoming more than probable that the family will be found to contain many species harmful to orchards, to crops and vegetables, and perhaps to trees in the forest as well. Mr. Mackinnon has promised to continue his interesting and important economic investigations into the habits of these pests.

HETEROCERA—(Moths).

The series *Heterocera* or Moths is a most important one in forestry. Next perhaps to the great Order *Coleoptera*, the moths contain some of the most dangerous pests the forester has to deal with. Both as defoliators, wood-borers, shoot miners and seed destroyers these insects are to be found at work in the forest, and the destruction caused is sometimes on a very large scale. For our purpose we shall consider the series as comprising fourteen families, and these will be dealt with below in such detail as seems to be required.

FAMILY BOMBYCIDÆ (TRUE SILK-WORM MOTHS).

Largish moths with stout woolly bodies, with no proboscis and no frenulum to the wings. Antennæ are short and are feathered in the male. The larvæ are hairy and are gregarious. The pupa is formed within a silken cocoon, the silk of which has often a commercial value.

There are several important species in the family. The domesticated mulberry and *eri* silk-worms and the semi-domesticated *tusser* and *muga* silk-worms are worthy of note. In addition there are a number of wild silk-worms in India whose silk is very good and would be extremely valuable were it forthcoming in larger quantities.* Several varieties of the mulberry silk-worm, *Bombyx*

---

*In 1895 and again in the following year the writer, whilst holding charge of the Tista division, offered a prize at the annual Kalimpong *mela* (held towards the end of the year at Kalimpong in British Sikkim in the eastern Himalayas) for the best exhibit of silk from some of the wild silk-worms from that part of the world. The conditions were that all stages of the life-history of the insect were to be shown, together with specimens of the reeled silk, the apparatus used to reel it and specimens of materials made from it. Some exceedingly interesting exhibits were sent in, especially in the second year, and the writer has little doubt that could a good cross be obtained with some of these Sikkim silk moths a most valuable silk would result.

mori are cultivated in the plains of Bengal upon mulberry leaves, and a large amount of valuable silk is obtained from them annually.

The insect suffers considerably from Tachnid fly and other parasites. The *Eri* silk-worm, *Attacus ricini*, is reared in Assam on castor oil leaves. It has several generations in the year (as also has *B. mori* in India), and the silk produced is the well-known coarse Assam silk. In the forest the most important silk-worms are the *Tusser* and *Muga*.

The larva of the *Tusser* (*Antheræa mylitta* and *A. paphia*) is a brilliant green adorned with numerous tubercles. The moth is a large yellow or buff coloured insect, which can be recognised by its shape, size, and the curious transparent glass window-like patches in its wings. The cocoon is large, hard, and is attached to the food plant by a silken stalk of great strength. This insect is reared in the forests of the Central Provinces, Chota Nagpur, and elsewhere throughout the central and southern parts of India. The caterpillars feed upon the leaves of *Terminalia tomentosa*, sal, *Zizyphus Jujuba*, etc. The insect hibernates through the winter in the cocoon. The moths of the first generation emerge in the beginning of the rains (June) and lay eggs from which cocoons are obtained about the middle of the wet season. Moths are obtained from these and lay eggs immediately. From the eggs so laid cocoons are formed about the beginning of the cold weather (October, November). Fresh cocoons for breeding are generally collected each March in the forest when the foliage is thin and they can be easily discerned. These are tied on to the trees, the latter being pollarded.

The *Muga* (*Antheraea assama*) is reared in Assam in much the same way as the Tusser in Chota Nagpur as above described. The cocoon has no stalk, and the silk has a beautiful golden sheen. The insect is reared upon *Machilus odoratissima*, *Tetranthera monopetala*, etc.

Forest revenue is obtained in various parts of India from these insects, and it is not at all improbable that, if the experiment were carefully conducted, their introduction might be possible into poor areas of forest growth in parts of the country where they are are not at present found.

FAMILY EUPTEROTIDÆ

The wings in this family possess a frenulum, the larvæ are hairy and these hairs often produce great irritation to the skin. The caterpillars are sometimes social in their habits, and live together in dense webs on trees and plants or march about in processions, when they are called 'processionary caterpillars.' Those living in dense webs on the other hand are called 'tent caterpillars.' Processionary caterpillars are not uncommon in India. Two instances of the annoyance they cause may be mentioned. In 1891 a plague of hairy caterpillars appeared in

Shwebo, Burma, and covered the country, eating all herbage and swarming on roads and in buildings in enormous numbers; their hairs produced irritation and even sores on the skin. In September 1901, another of these processional caterpillars swarmed in the station of Seoni in the Central Provinces, appearing in millions and invading gardens and houses, stables, cook-houses, choking up drains, etc.

It follows that the members of this family are dangerous not only owing to the actual defoliation damage they are capable of doing, but also to the fact that when they swarm, they become a veritable plague to man, bad sores resulting from the irritating properties of the hairs Their dead bodies choke up drains, etc., giving rise to noxious effluvias, which are liable to produce pestilence, and in this way they resemble that scourge the North-West locust.

FAMILY SPHINGIDÆ (HAWK MOTHS).

Moths of large or moderate size, with frequently a very long proboscis, and provided with a frenulum on the long narrow wings; bodies stout and often torpedo-shaped. Antennæ are short and stiff, ending in a hook at the tip. The larva is large and fleshy and generally remarkably coloured and is provided with a horn on the dorsal surface of the eleventh segment, and has sixteen legs. The caterpillars do not spin cocoons, but bury themselves in the earth. In the pupa the proboscis sometimes projects on the breast like the handle of a pitcher. The larvæ feed upon vegetation. A species named *Pseudosphinx discistriga* defoliates the teak in the Melghat forest in Berar. It is bright green in colour, changing to dark yellow-green on maturing. In July, 1901, it was in considerable numbers on the trees, and a fairly large amount of defoliation had been occasioned by it. The same larva was also found in the Central Nursery at Poona, and it may prove to be general throughout the Bombay and Central India teak forests. The moth issues about the beginning of August, and the pupal stage is probably a short one.* The rest of the life-history has not yet been worked out, but the case is an interesting one, since hawk moth larvæ are not usually to be found feeding gregariously together.

FAMILY SESSIIDÆ OR ÆGERIIDÆ (CLEAR-WINGS).

A comparatively small family of moths, whose wings are without scales; the tip of the body is tufted, and the insects resemble wasps to a great extent. The larva is nearly naked and colourless, and thus resembles a longicorn grub. It can be distinguished, however, by the fact of its having 16 legs. The larvæ feed in wood and do damage to trees in this way. They invariably feed concealed in stems, branches, etc. The pupa is

---

* For further information on this insect *vide* Departmental Notes on Insects that affect Forestry. No. I., p. 52, Pl. II, fig. 1.

furnished with a row of spines on the segments of the abdomen. The Baluchistan poplar borer, *Trochilium omnatiæforme* is a larva belonging to this family. The eggs are probably laid in the bark of the tree attacked during October and November, the larvæ hatching out either immediately or more probably in the ensuing spring. As soon as hatched they bore through the bark. In April, when about half-grown, they may be found between the bark and the wood. From this time they commence boring straight into the heartwood and remain tunnelling in this until September. The larva changes into a pupa inside a cocoon formed of wood chips placed near the entrance of its burrow * The adult insect appears in October It greatly resembles in appearance the small Indian wasp, *Vespa cincta.* In 1890, the poplar trees (? *Populus euphratica*) suffered severely in Baluchistan from this insect. The trees were grown from cuttings, and when about two years old they were attacked by the larvæ. The eggs must have been laid on the bark near the ground, and the caterpillars on hatching out bored through the trunk and riddled the wood in all directions, the stems being generally killed off before they reached the age of five years. The roots were not attacked, and therefrom fresh shoots came up in the majority of cases, the loss experienced being the putting back of the plantation by several years.

FAMILY PSYCHIDÆ (BAGWORMS).

Small or moderate-sized moths, with imperfect scales and dusky in colour. The sexes are very different, the female being wingless and sometimes quite maggot-like; the male often has bipectinate antennæ, the branches of which are sometimes very long and flexible. The larva soon after hatching forms for itself a case of pieces of stick, leaves, etc., in which it lives, carrying it about on its back, like a snail its shell. This case is always present, and the wingless female moth never leaves it. The larvæ do damage as defoliators.

A species of this family, *Clania variegata*, has been reported as defoliating the sal tree in the Duars in Bengal. The female lays her eggs about the beginning of March, within the pupal shell inside the case. After laying these. eggs, her abdomen becomes much reduced in size and she drops out of the case and dies. The eggs are smooth yellow ovals, from which larvæ hatch out at the beginning of April. This is the first brood of the year, and several others follow it through the hot weather and rains. Three to four days after hatching out the young larvæ begin to construct their cases with pieces of moss and bark of sal trees, etc., and they feed upon the young new sal leaves. The mouth of the case is made flexible so that the larva can draw in its head for protective purposes. As it grows older the larva feeds upon the older leaves of the tree. When about to change to the pupal state the case is fastened to a twig or to the bark and the mouth of the case is then closed. The larva then proceeds to cover the inside of the case with a fine loose silk, and turning round hangs head downwards inside and changes to a pupa In emerging the male cuts its way out of the cocoon by means of its sharp edged beak, a portion of the empty pupal skin being often seen projecting from the case. It has highly pectinated antennæ, and is about two and-a-half inches across the wings. The female has some means of attracting the male to her, and pairing takes place by the male inserting the end of his abdomen down into the case, which the female, being as mentioned above practically wingless, never leaves.

---

* For a further account *vide Injurious Insects*, pp. 95-98. Figs. 62, 63, 64.

The larvæ of another member of the family, *Clania cramери.* feed upon the needles of the *Pinus longifolia* in the N.-W. Himalayas. The caterpillars hatch* out in July and at once commence to feed upon the needles of the pine, from which, together with twigs, they construct their cases. They remain feeding upon the trees until November. The winter is passed either in the larval or semi-pupal state. Perfect pupæ are to be found within the cases in April of the year succeeding that in which the defoliation took place. The moth appears in June.† This insect occasionally does a great deal of damage (markedly so in 1898) to the P. *longifolia* by entirely stripping the trees of all their needles, in which state it is not improbable that the trees will be attacked by the *Polygraphus longifolia*. MS., and *Cryphalus*‡ bark-borers which infest this tree (*vide p.* 108 *ante*).

As the larvæ of this family usually form their cases of dried twigs, moss, grass, straw, leaves, etc., they are generally very difficult to see when amidst their natural surroundings, and it is probably due to this that at present so few species have been reported as doing damage in the forest. Many species are known to feed entirely upon the leaves of woody growths (trees or shrubs), and the cases constructed are remarkable for their ingenuity and variety. A study of the family should well repay those who take it up.

Navigability of the Garonne.

MANY readers of the *Indian Forester* may be unaware that the most important river of the south of France. the Garonne, used to be navigable for considerable ships, and no longer is so. In addition, the river has become a standing menace to life and property, and a sink-hole that swallows gold like water, all through the enjoyment of forest rights by the mountain population, and for no other reason whatever. There is an important society, calling itself "La Garonne Navigable," the object of which is expressed in its name, *viz.*, to work for the navigability of the Garonne. Before this society two important papers were recently read by MM. Favre and Buffault, the gist of which I have boiled down from the *Revue des Eaux et Forêts* for 15th July 1902.

---

* *Vide Injurious Insects*, pp. 98 – 101 and Fig 65

† *Vide* Departmental Notes on Insects that affect Forestry, No. 1, pp. 56-57 and Plate II, Fig. 2, a b,c.

‡ *Vide* Departmental Notes on Insects that affect Forestry. No. 2. pp. 255--257, 267 -273.

M. Favre commences by pointing out that the forest is nature's own chosen weapon in both struggles, *viz.*, the struggle *for* water, and the fight *against* water. In the absence of forest there is still the perennial vegetation on the soil which can be turned to good account. "The forest is the sovereign governor of the water supply "—(E. Risler). The " torrential " characters now acquired by the Garonne are costing many human lives, and in addition about eight million francs annually, including three millions for dredging alone. The hydrographers say that the silting-up is frightful. None of the forest works in the upper valleys take any note of navigation. Their object is purely local, being the protection of the threatened localities in the Pyrenean mountains. No law touches the primary cause of erosion of the " 'torrential " character of the mud-transport, namely *the surface flow.* Its origin is not always confined to the actual sources of the rivers themselves, but extends to other parts of their basin. The question is not a purely geological one, but is greatly affected by the action of the great Pyrenean screen which condenses rain from the ocean winds.

Agricultural irrigation has greatly increased, and now greatly affects the Pyrenean river supply, with the result that the low-water flow is diminished to the great injury of manufacturers and sailors, whilst the floods are worse than ever. The destruction of the turf, and especially of the woods, is visibly increasing; its progress is evident from the statistics of the dangerous zones of the basin.

The cause is to be found in the difficulties surrounding the application of forest regulations and in the unrestrained enjoyment of common rights in the mountains. The proposed measures of defence are the following :—

(1) An understanding with a view to joint action over the whole of the forest and pastoral regions round the sources of the Garonne and Loire.

(2) The appointment of a technical commission to elaborate a programme for the localisation of the evil, and for its treatment through the agency of the Forest Department.

(3) The application, to the forests, of measures calculated to preserve the wooded condition; and to the pasture, of steps to restrain the enjoyment thereof so far as may be needful to preserve pastoral conditions.

M. Buffault's paper had reference to the insufficiency of forest legislation for the purpose, and the difference between French and Indian laws renders it useless to go into details, but he, too, laid stress on the great progress of denudation, and on the need for subjecting all communal lands to strict management by the Forest Department. He showed how the common-holders formed so called syndicates, and used them as an agency of destruction. After some remarks in support by M. de la Bruyere, Councillor of the Rhone, the society adopted the conclusions.

To apply this lesson to India is a somewhat delicate task, which each forester may do for himself. In France the forest administration is autonomous. There is a Minister of Agriculture, a professed politician, but generally sympathetic and keen. After him comes the Director-General of Forests (and Waters) a trained forester, to whom alone the conservators, etc., are responsible. In France the enemies of forests are mostly interested right-holders, and that only in certain regions. In India we have right-holders and endless privilege-holders, who are as bad, together with others, who ought to know better but do not. The latter have sometimes done their best to fix for all time the most harmful practices, and have even crushed the professional staff under repressive and penal legislation. The question of autonomy stands in the way. It is a necessity, and it is perfectly feasible, but stands little chance of adoption at present. The State forest domain is of equal importance with the State public works, though the current revenue will not bear comparison. Yet the latter have great secretariats in each branch, while the former is muddled by the local caprice of all kinds of uninstructed, prejudiced, incompetent persons, down to the tehsildar. Even if a bad forest policy is a temporary necessity, it could be run by a Forest Secretariat better than at present, and the reins would be much nearer to the hand of Government.

F. G.

IV.—REVIEWS.

A Manual of Indian Timbers.*

We cordially welcome the appearance of this work which supplies a much-felt want the original small edition published in 1881 having long since been exhausted. The origin of the book is explained in the introduction to the first edition. A representative collection of timbers was required for the Paris Exhibition of 1878. The nucleus of this collection was a set of 320 correctly named specimens contributed by Sir Dietrich Brandis and 194 similar specimens from the collections of Mr. Gamble and the late Mr. S. Kurz, and to these were added specimens of some 400 other species specially collected from different parts of India. These woods were examined and described by a committee composed of Sir Dietrich Brandis, Mr. Gamble and Mr. Smythies, the descriptions being generally dictated by Sir Dietrich Brandis after the specimens had been examined and discussed by the whole committee. This formed the basis of the original Manual, the publication of which was entrusted to Mr. Gamble.

---

* *A Manual of Indian Timbers: an account of the growth, distribution and uses of the trees and shrubs of India and Ceylon, with descriptions of their wood-structure*, by J. S. Gamble, M.A., C.I.E., F.R.S., F.L.S., late of the Indian Forest Department. New and revised edition. Pp. xxvi + 868. (London: Sampson Low, Marston & Co., 1902). Price 18s. net.

A duplicate set of the specimens prepared for exhibition was subsequently deposited in the Forest School Museum, which since that time has been enriched by large numbers of specimens collected by Mr. Gamble himself or contributed by Forest Officers from various parts of India, so that in the new edition Mr. Gamble has been able to describe no less than 1450 different species, which include representatives of nearly all the most important genera. As, however, the Indian forests are estimated to contain some 2500 species of trees, not counting shrubs and climbers, there must still be a large number the wood-structure of which has yet to be examined, more especially from the remoter parts of Burma and Assam. We trust therefore that Forest Officers and others interested in the work will continue to collect specimens and send them to the Forest School Museum. Any specimens received will then be prepared and forwarded to Mr. Gamble, who will be glad to publish the descriptions in *The Indian Forester*. We would here, however, emphasise Mr. Gamble's warning as to the danger of relying on native names for the identification of species. A vernacular name is often a useful help in tracing the scientific name of a plant met with, but it sometimes happens that entirely different trees are known under one and the same name in localities not very far apart, and it is not safe to trust to native names without further proof of identity. Disregard of this in the past has been a fruitful source of error.

The new edition follows generally the lines of the older work, the geographical regions adopted by the committee in the first instance having been adhered to as well as the former standards of comparison. The geographical regions are indicated by letters, but no separate letter has been given for Ceylon, the timbers of which have been included at the special request of the Ceylon Forest Officers.

The descriptions of the woods are given under the following heads:—

1. Size and appearance of tree, and whether evergreen or deciduous, mode of branching.

2. Description of bark.

3. Description of wood, both sapwood and heartwood, with its colour, hardness, grain, scent, the characters of the annual rings, pores and medullary rays, etc.

The descriptions given in the older work have been revised wherever necessary, and the information in regard to *habitat* has been brought up to date. Additional notes have been added in regard to the uses to which the woods are put or for which they are suitable, their liability to deterioration, including damage by insects, and the sylvicultural requirements of the more important species.

No attempt has been made to form a general key to the woods, as this was not thought feasible, but the keys of Sir Dietrich Brandis, Messrs Nordlinger, Mathien and Marshall-Ward have been reprinted in order that Forest Officers may utilize them in preparing local keys to the woods of any particular area.

The book is illustrated by photographs of trees and numerous enlarged reproductions of wood-sections. It has been printed on thin paper and bound in limp boards, so as to avoid the necessity of having two volumes, which is always inconvenient in a work of this kind. It is a matter for regret however that red cloth, which is particularly disagreeable to handle in a hot climate, should have been chosen for the binding It is hardly necessary to say that this Manual is indispensable to Forest Officers, and should be in the hands of every engineer who has to deal with timber construction work.

VI.—EXTRACTS, NOTES AND QUERIES.

Large Trees in Kashmir.

I HAVE been measuring the girths of some of the big trees of Kashmir, and send you a list with names of places where the trees stand :—

Chinar (*Platanus orientalis*), Drogmula 50′; Jahama, 43′, hollow, 92′ at ground. Walnut, Salkut, 20′ 10″; Sogam, 20′ 2″. *Elm*, Diur 43′; Arhama. 3 ′ 5″. *Poplar*, Nedibal, 17 3″. *Mulberry*, Dregmula, 22′4″. *Ash*, Boniar, 14′2″. *Alder*, 15′.

In Jammu, at the village of Manapur, are two huge *arjan* (*Terminalia arjuna*) trees of 32′ and 26,′ the home of thousands of flying-foxes ; the girth of these was taken by me at 5′ above ground. At the remarkable Saruinsar Lake near Jammu is a *jaman* 20′6″ in girth. All the measurements were taken well above the ground at breast height.

J. C. M. D.

Lac in Guzerat and the Konkan.

GUZERAT.

WHEN on famine duty in the Panch Mahals district in 1899 I collected, during my wanderings, the following information about lac produced in the forests and waste lands of the district and in the congeries of Native States bordering on it, which form what is known, I believe, as the Rewa Kanta, and it seems to me that it may be interesting to have this information recorded rather than permit it to be buried in oblivion. It is observed that in the recent valuable note in the *Agricultural Ledger* drawn up by Sir George Watt, Reporter on Economic Products, information about lac in Guzerat is confined mainly to a description of the lac industry in the Panch Mahals, which may render the present brief data about quantity, etc., of lac available all the more necessary.

It is estimated by merchants that the following quantities of lac are annually collected and exported from the places named below to other parts of India:—

Panch Mahals District.

	Mds. (of 80 lbs.)
British Territory	300 to 500
Lonewada State	1000
Deogud Baria State	4000
Chota Udepur "	4000
Ali Rajpoor State	not known

In order to verify these figures information on the subject was sought from the Political Agent, Rewa Kanta, Mr. Carmichael, I.C.S., and he has very courteously supplied me with details about the export of lac from the different Native States surrounding the Panch, Mahals, as follows:—

Deogud Baria State.—621 maunds of 40 seers average amount exported annually during past seven years.

Chota Udepur State.—Average of five years 1168 maunds of 40 seers.

Lonewada State.—Nil.

All these Native States permit their subjects to collect lac from the forests and waste lands free of charge, levying merely a duty on the amount exported.

The vast discrepancy between the figures supplied by contractors and those of the Political Agent seems to need explanation, which I am not in a position to give.

It is proverbial how much the native is addicted to exaggeration, and the figures supplied by merchants on the spot may in consequence be very inaccurate; but room for suspicion seems to exist that the native administrations are not obtaining all the revenue they are legitimately entitled to from their exports of lac.

The Political Agent states that during the past five years, up to 1900-1901, the export duty on lac from Chota Udepur amounted to Rs. 2533 or about Rs. 506 per annum, and from the Deogud Baria State to Rs. 310 per annum for the past seven years.

No other State appears to derive any revenue at all from lac.

The produce is gathered in the forests chiefly from the following trees:—

Kakra.—*Butea frondosa*, abundantly.
Bhor.—*Zizyphus Jujuba*, also abundantly.
Ghat Bhor.—*Zizyphus nummularia*.
Pipul.—*Ficus bengalensis*.
Sadar *or* Ain.—*Terminalia tomentosa*.
Pasi.—*Dalbergia paniculata*.
Kala Sirus.—*Albizzia odoratissima*.
Koshimb.—*Schleichera trijuga*.

There are two crops: one gathered in May-June and the other in November; the former being considered the better on account of the larger number of insects.

Naikdas and Bhils mainly are engaged in collecting them. An adult gathers about four to five seers of lac per diem, and the price paid for the produce by petty contractors is one anna per seer. As the trees on which the lac is found are not gregarious, collection is somewhat troublesome. In private areas the produce is sold from two annas to four annas per tree to contractors.

In the Godhra taluka of the Panch Mahals district, centres or depôts exist where lac is brought by the wild tribes to petty contractors from the neighbouring Native States as follows:—Shera, Nadurho, Ratanpur and Mora; at the two latter places the collections are comparatively large, as they are situated close to the borders of the Native States. A certain quantity of lac is also collected from the Panch Mahals forests, but the quantity apparently is not large enough to be noticeable. The petty contractors remove their produce to Godhra, where it is purchased by large wholesale lac merchants, who export it to various parts of India.

One contractor stated that the price of lac in Godhra in a favourable year is Rs.16 to Rs 18 per maund of 80lbs; that the price in 1899, during the famine, fell to Rs.4 per maund, and that in 1897-1898 it was Rs.7.

These figures correspond mainly with those given in the Panch Mahals *Gazetteer*.

In the latter work it is shown that quite a large industry exists among the Bhils in the eastern parts of the district in the manufacture of bangles and other ornaments made from lac.

Konkan.[*]

With the exception of the lac found by Dr. Carter inside the grounds of the old Bombay Mint in 1860, no record exists apparently of it having been discovered elsewhere in the Konkan. In 1899 I noticed pipul trees (*Ficus religiosa*) on the maidan in Thana and khair trees in some of the forests in the Bassein taluka of the same district bearing lac; but the incrustation on the trees was sparse. Close to Bassein, which is on the sea-coast, roadside trees of *Pongamia glabra* have also been found bearing lac.

The rainfall, it may be mentioned, in the Thana district averages about 90 inches, and the soil is laterite, *i.e.*, decomposition of trap. The thermometer in the hot weather rises above 110.

In the Panch Mahals and surrounding Native States the rainfall varies between 25 and 40 inches.

THANA DISTRICT:
14th January 1903. G. M. RYAN.

British Forestry.

THE report of the Departmental Committee appointed last February (see *Journal*, vol.I., p. 428) to inquire into the present position and future prospects of forestry has been published as a Parliamentary paper. The present Departmental Committee endorse the conclusions of the Select Committee of 1885-87 as regards the neglected condition of forestry in Great Britain, the possibility of improvement, and the necessity for the provision of better means of education. As regards the question of the extension of the forest area, the committee point out that there is on the highest authority in these islands an area of waste, heather, and rough pasture, or land out of cultivation, amounting to 21,000,000 acres, on a large proportion of which afforestation could be profitably undertaken. The committee believe that the importance of afforestation in such a district as the Highlands of Scotland will be readily grasped. The area of waste land which might be afforested becomes a matter of grave national concern, when it is remembered that according to exports, the world is rapidly approaching a shortage of, if not actual dearth in, its supply of coniferous timber, which constitutes between 80 and 90 per cent. of the total British timber exports. The committee do not feel justified in urging the Government to embark forthwith upon any general scheme of State forests under present circumstances, but believe that the question of planting suitable waste lands under the control of the Crown, or over which the Crown exercises manorial rights, is worth the attention of the

---

[*] The Konkan is a tract of country below the Western Ghats, including mainly the districts of Thana, Kolaba and Ratnagiri.

Commissioners of Woods and Forests. Dealing with the question of education, the committee state that even where access may be had for purposes of instruction to private woods, it is exceedingly desirable that collegiate instruction in forestry should be illustrated by means of example plots, a total area of 100 to 200 acres at each educational centre being necessary and sufficient for this purpose.

The recommendations of the committee are:—

"(a) That two areas for practical demonstration be acquired, the one in England and the other in Scotland, of not less than 2000 acres, if possible, nor over 10,000 acres in each case. We suggest that the Alice Holt Woods in Hampshire be made available as soon as possible to serve as a demonstration area in England; and that a suitable estate be purchased in Scotland, as convenient as possible to Edinburgh, for the same purpose. These recommendations would have to be carried out by arrangement between the Commissioners of Woods and Forests and the Board of Agriculture; and assistance should be looked for from local authorities, societies, and individuals interested in forestry and technical education.

"(b) That additional facilities for instruction be afforded, by the appointment of a lecturer on forestry in connection with each of the Universities of Cambridge and Oxford, and that example plots be provided in connection with each of these centres and with Edinburgh.

"(c) That a good grounding in forestry form an integral part of the curriculum of the colleges providing instruction in agriculture in Great Britain; and that short courses of instruction suitable for the requirements of young foresters be provided there. Instructors should also be available for giving practical advice in connection with the management of woods, the owners of which desire an expert's opinion.

"(d) That provision be made for the education of foresters and woodmen by employing students to work in both the demonstration forests; and that suitable buildings be erected on the ground for the instruction, and, where necessary, for the accommodation of these student-foresters.

"(e) That lectures be given, under the auspices of the county councils, in neighbourhoods where there is a considerable area underwood: and that scholarships be offered in such counties to enable working foresters to attend courses of lectures.

"(f) That the inequality shown to exist in the levy of the state duty on timber be redressed.

"(g) That the Government be urged to secure the early enactment of a Bill to protect owners of woods against loss by fire caused by sparks from locomotives.

"*h*) That the inquiry conducted in 1895, concerning the area of woodlands, be repeated by the Board of Agriculture, and that details concerning the character of the timber crop grown upon them be ascertained.

"(*i*) That the attention of corporations and municipalities be drawn to the desirability of planting with trees the catchment areas of their water supply."—*Journal of the Society of Arts.*

VII.—TIMBER AND PRODUCE TRADE.

Churchill and Sim's Wood Circular.

February 4th, 1903.

EAST INDIAN TEAK.—The stock of timber in London continues to shrink and prices remain quite steady at the high level attained in December. There is no better prospect yet of fuller supplies, and it seems fairly certain that they must again be very restricted throughout the year. The deliveries in January were 567 loads, against 1053 loads in January 1902.

ROSEWOOD, EAST INDIA.—There has been enquiry for large good logs, small lots of which would realise fair prices, but of other descriptions the stock is ample.

SATINWOOD, EAST INDIA.—There is now a fair stock on hand, the chief demand being for figury logs.

EBONY, EAST INDIA.—Sizeable logs, if really good, would sell well, but for lower qualities there is less demand.

PRICE CURRENT.

Indian Teak, logs, per load	...	£10 10s. to £18 10s.
" " planks "	...	£13 10s. to £20.
Rosewood per ton ...	...	£8 to £11
Satinwood, per s.ft. ...	...	6*d.* to 12*d.*
Ebony, per ton ...	...	£9 to £12

Denny, Mott and Dickson, Limited.

WOOD MARKET REPORT.

London, 3rd *February* 1903.

TEAK.—The landings in the docks in London during January consisted of 60 loads of logs and 275 loads of planks and scantlings, or a total of 335 loads, as against 890 loads for the corresponding month of last year. The deliveries into consumption were 289 loads of logs and 270 loads of planks and scantlings—together 559 loads, as against 1072 loads in January, 1902.

The Dock stocks at-date analyse as follows: —

	5165	loads of logs,	as against	7763	loads at the same date last year.
	2711	„ planks	„	3979	„ „ „
	—	„ blocks	„	—	„ „ „
Total	7876	loads	„	11,742	loads „ „

The above figures shew that the restricted supply of teak is being met by a diminishing demand, although dull trade is probably a graver factor in such falling away in consumption than any check caused by the increased cost of this wood. Rolling stock continues to be urgently needed for South Africa, and this will no doubt benefit our home railway carriage and wagon industry, as the Cape does not yet manufacture to any extent for itself. On the other hand, shipbuilding prospects continue gloomy, although the "tramp" class of ship, which is chiefly depressed by the over-supply of tonnage, does not greatly affect the building of the high-class boats for which teak is specified.

Business during January was lacking in volume, but prices were well maintained in all descriptions of goods owing to the impracticability of replacing stocks at present landed cost. The financial position is still sufficiently sound to cause no appreciable apprehension of large parcels of goods being forced into consumption.

Market Rates for Products.

TROPICAL AGRICULTURIST.

February 2nd, 1903.

Cardamoms ...	... per	lb.	1s. 8*d*. to 1s. 10*d*.
Croton seeds ...	... „	cwt.	15s. to 25s.
Cutch ...	... „	„	25s. to 30s.
Gum Arabic, ...	... „	„	18s. to 25s.
Do. Kino ...	... „	„	4s. to 6s.
India-rubber, Assam	... „	lb.	2s. to 3s.
Do. Burma	... „	„	2s. to 3s.
Myrobalans, Madras	... „	cwt.	5s. to 6s.
Do. Bombay	... „	„	4s. to 7s.
Do. Jubbulpore	... „	„	4s 6*d*. to 6s.
Do. Bengal	... „	„	3s. 6*d*. to 5s.
Nux Vomica, Madras	... „	„	7s. to 10s.
Oil. Lemon-grass ...	... „	lb.	5½*d*.
Orchellaweed ...	... „	cwt.	10s. to 12s 6*d*.
Sandalwood, logs ...	... „	ton	£15 to £30.
Do. Chips ...	... „	„	£4 to £8.
Sapanwood ...	... „	„	£5 to £5 10s.
Seedlac ...	... „	cwt.	117s. 6*d*. to 120s.
Tamarinds, Calcutta	... „	„	8s. to 10s.
Do. Madras ...	... „	„	4s. 6*d*. to 6s.

NOTICE TO SUBSCRIBERS.

Mr. J. W. OLIVER, who has for so many years devoted much time and labour to the editing of the *Indian Forester*, having now proceeded on furlough, the question of the appointment of an Editor to replace him was considered at a meeting of Forest Officers at Dehra Dun in March last. The meeting appeared to be in favour of placing the future management of the *Indian Forester* with a Committee formed of three Forest Officers, of whom one should be on the staff of the Forest School in order that the valuable collections at that institution might be at the disposal of the Committee, while the other two should be in a position to represent the presidencies of Madras and Bombay as well as Bengal. The formation of the Committee will, after all details have been arranged, be duly notified to subscribers. Meanwhile the Departmental Magazine will continue to issue from Dehra Dun under the Editorship of the Director of the Forest School.

A. G. HOBART-HAMPDEN.

Contributions should, therefore, be sent to the Honorary Editor, A. G. HOBART-HAMPDEN, Dehra Dun, and *not* to E. P. Stebbing, as printed by mistake in this month's issue.

THE

INDIAN FORESTER

Vol. XXIX.] May, 1903. [No. 5.

Notes on a Tour through the Kheri Division, Oudh.

OWING to the presence of plague at Changa Manga, the senior classes of the Imperial Forest School were obliged this year to forego the usual tour to the Punjab, and were therefore able to spend a rather longer time in Kheri.

The following is compiled from notes made by the students of the School on a variety of subjects to which their attention was directed during the three weeks in January, 1903, spent in this interesting and instructive Division.

KISHANPUR FORESTS.

The first forests visited were in the Kishanpur Working Circle, Bhira Range, which are being worked under a provisional treatment of light improvement fellings on an eight year rotation, until the crop becomes sufficiently regular to allow of its being treated by the Selection method.

The present stock being very poor and consisting largely of small unsound trees, which, even when mature, can never yield good timber, it might perhaps have been better to work the forest under coppice-with-standards until it was fully stocked with sound well-grown trees.

The first cycle of fellings has just been completed, as the working-plan came into force eight years ago.

Although this forest has been protected from fire and grazing for 18 years, the crop still consists chiefly of old coppice shoots and of small badly-grown trees.

Even in Coupe I, felled over eight years ago, where there is a good amount of young growth, the crop is still so open that it

THE
INDIAN FORESTER

Vol. XXIX.] May, 1903. [No. 5.

Notes on a Tour through the Kheri Division, Oudh.

Owing to the presence of plague at Changa Manga, the senior classes of the Imperial Forest School were obliged this year to forego the usual tour to the Punjab, and were therefore able to spend a rather longer time in Kheri.

The following is compiled from notes made by the students of the School on a variety of subjects to which their attention was directed during the three weeks in January, 1903, spent in this interesting and instructive Division.

Kishanpur Forests.

The first forests visited were in the Kishanpur Working Circle, Bhira Range, which are being worked under a provisional treatment of light improvement fellings on an eight year rotation, until the crop becomes sufficiently regular to allow of its being treated by the Selection method.

The present stock being very poor and consisting largely of small unsound trees, which, even when mature, can never yield good timber, it might perhaps have been better to work the forest under coppice-with-standards until it was fully stocked with sound well-grown trees.

The first cycle of fellings has just been completed, as the working-plan came into force eight years ago.

Although this forest has been protected from fire and grazing for 18 years, the crop still consists chiefly of old coppice shoots and of small badly-grown trees.

Even in Coupe I, felled over eight years ago, where there is a good amount of young growth, the crop is still so open that it will not be expedient to continue the prescribed fellings for the next eight years, so it is proposed that this part of the forest be simply protected and left alone.

The young shoots of eight years old measured about one foot in girth and 25 feet in height.

Each coupe consists of about one thousand stocked acres.

calculation of the possibility in the working-plan is based on an eye estimate of the stock, which has proved to be unreliable. It prescribes the removal of 107 sal stems of all size classes per acre; no lower limit of size is stated to define what is meant by a Vth class tree, of which about 22 stems are to be removed and 66 retained per acre at each operation.

This method of calculating the yield is unusual, but is only intended as a rough guide to prevent overcutting The fellings should be made on purely cultural considerations without any number of trees being fixed.

In the actual working the fellings are made—as improvement fellings should be-strictly in accordance with sylvicultural requirements alone. In the coupe visited a complete enumeration of the stock left after the felling made over 157 acres, omitting all trees of less than three inches diameter, showed 52 II, III and IV class trees left per acre, instead of 41, as the estimate in the working-plan gives, and 56 Vth class trees, instead of 66.

The total of stems left per acre is therefore 108 (omitting trees of under 3" diameter), which is practically the same as the number prescribed by the working-plan. There is hardly any miscellaneous species in this part of the forest, though the working-plan gives 55 as the number of stems of these species which are to be retained per acre in addition to the 107 sal trees.

The present workings produce principally fuel, and are sold at an average price of about nine rupees per acre. The selling price varies according to the distance of the coupe from the railway: at five miles distance the wood barely pays for the cost of extraction; at eight miles distance it has no market value. The railway rates for poles are so heavy that very few are exported by rail.

Firewood is stacked 5′ by 6′ by 20,′ or 600 cubic feet per stack; this corresponds to 300 cubic feet solid when the wood is half dry; and four stacked cubic feet go to the maund.

The forests of the Bhira Range are largely intersected by extensive grassy plains, which occupy more than one-fifth of the total forest area. These grassy plains are either *chandas*, which probably originated in old clearings made for cultivation, and are now often covered with a low growth of sal coppice shoots, which are killed back perennially by frost, or else *phantas*, which are blanks, often low-lying, filled with coarse grass without any tree growth.

This present season has been a very dry one; the rainfall has been only 55 per cent. of the normal amount, and the frosts have been proportionately severe. The result is that not only have the ordinary yearling shoots been killed back, but also all taller shoots, which had succeeded during the last two or three years in raising themselves above the ordinary frost level.

These grassy blanks are gradually filling up, but the process is exceedingly slow and the area is vast. Signs are nearly everywhere apparent of a tendency of the surrounding forest to encroach on to these blanks.

Terminalia tomentosa generally advances into the *phantas*, and the sal follows as the ground becomes more drained and protected. There are some very encouraging islands of young sal reproduction around old sal trees on the edges of these blanks, and occasionally round isolated seed-bearing trees standing in the grass.

The improvement of these *chandas* is a very difficult matter. Frost and fire together have waged an unequal war against the sal, and in course of time it seems inevitable that the old stools must die and natural re-stocking become impossible.

Meanwhile perennial shoots are thrown up every summer from the old stumps, which are often shaped like hollow bowls with shoots growing up in a ring all round the edge, which shoots are year by year killed back by the frost.

The cost of artificially protecting these shoots from the frost by means of grass matting, etc., is prohibitive. Artificial standards have been tried of such species as *Odina*, *Spondias*, *Garuga*, but a nurse to be of any practical utility must be one of a hardy, light-loving and frost-resisting species, which retains its leaves late through the dry season. *Eugenia operculata* would be an excellent tree for this purpose: it is a hardy evergreen tree, with a broad, spreading crown through which sal saplings can easily push their way.

The second excursion from Mailani was to visit Coupe V of the Marha Coppice Working Circle. These forests are treated under the method of coppice-with-standards for the production of fuel; the standards being reserved to protect the underwood from frost as well as for the production of timber.

The difference of the effects of the frost inside and outside is very noticeable. In the open *chandas* every shoot is killed, but under the protection of the forest a few yards away not a leaf is withered, and in the allocation of coupes there is no necessity to take the danger of frost in consideration.

The railway takes nothing but sal wood as fuel, in billets of nine inches diameter and under.

The rotation of the coppice has accordingly been fixed at 24 years with a view to producing wood of this size.

About 55 standards are reserved per acre, and it has been hitherto the intention to keep them for three rotations only, till 72 years of age, as it was thought they would probably not remain sound long after acquiring 3½ feet in girth. It seems not improbable, however, that with improving conditions of growth, the sal would grow sound up to six feet girth and supply good timber. This part of the forest, Coupe V of the Marha Working Circle, is not as good as some parts of the trans-Sarda forests, Dudwa for example, but the growth is very good; the standards are rather close together, but the trees have small crowns, and the young growth is thick and very vigorous. The height of the leaf-canopy is about 70 feet.

The crop being practically composed of pure sal, with a varying admixture of *Terminalia tomentosa*, this forest might very well be selected for an experimental working circle, to be treated under the regular method with successive regeneration fellings.

The best parts of the forest are on the highest ground, and there is nothing to fear inside the forest from frost. Even this year, when the frosts have been exceptionally severe, not a leaf is touched in the forest, though everything in the open *chandas*, which intersect the forest, is killed. A protective belt of forest 50 feet broad is left round the *chandas*, and nothing is cut in it. The soil is a loamy sand. Measurements of sal coppice shoots of 4—5 years old showed an average of seven inches girth and 15 feet in height.

The working-plan originally prescribed that with a view to supplying data regarding the rate of growth every standard should be measured in every coupe.

It is an important part of every working-plan to prescribe the systematic observation and record of everything connected with the growth of the trees of the principal species, so that as time goes on, each working-plans officer may have more full and detailed data to go upon than his predecessor. It would be, however, neither necessary nor desirable to keep a record of the rate of growth of every standard reserved in the whole forest, so it has now been ordered instead, that a sample plot of one acre in extent shall be selected in every fourth coupe, and that all standards in it shall be measured every five years.

The students accordingly measured a new sample plot in Coupe V, containing 70 standards. Both girth and height of all trees were carefully measured.

Each tree bears a ring of white paint at a height of 4 feet 6 inches from the ground: it is, however, preferable to have the ring at a point where the stem is cylindrical and free from all irregularities of growth, rather than always to have it exactly to an inch at the proper height from the ground: in the case of trees with sloping stems too, the ring must be perpendicular to the axis of the tree, and not horizontal. The measuring tape must be held along the top edge of the paint mark.

Each annual coupe is divided into a number of plots, four or more, which are auctioned at a rate per acre to the contractors.

The work, however, is limited by the means of export, and as the railway has often been unable to supply a sufficient number of waggons, some parts of the annual workings have not been felled in the prescribed year, and the fellings have consequently fallen into arrears.

Each coupe is about a thousand acres in extent, and the yield is about 3000 cubic feet per acre. The fuel is disposed of by contractors at about Rs 17 per stack of 600 cubic feet, a large proportion being bought by the railway. The price paid by the contractors varies between Rs.5 and Rs. 25 per acre according to the distance of the coupe from the railway, and it has been lowered in past years by the contractor knowing that though he buys the entire plot, he will probably have to leave a part of it unworked. These parts of the coupes which remain uncut are resold a second, and sometimes a third, time.

This Coupe V, which the students visited, was not all worked in one year as it should properly have been, but was worked in parts during three consecutive years. A map is kept on a large scale showing each year the areas actually worked over.

The work in this working circle is now (1902-1903) just one coupe in arrears, but with an improved supply of railway waggons it is hoped this year to work two coupes and so get straight again.

A revenue of Rs 6000 per annum is made in this Bhira Range from the sale of Bhabar grass, *Ischæmum angustifolium*. It sells at Re.1-5-0 per maund delivered on the railway. It is said to be best when cut in the rains; the fibre is then strongest, and it retains a pale green colour. It is cut, dried, shaken out, and then twisted into hanks, which are exported for the manufacture of ropes, matting, paper, etc. In other places this grass is always harvested in February and March, because in the rains it is mixed with young sappy blades and the last year's grass has lost some of its strength.

CHARCOAL KILNS.

At Marha the students saw a camp of twenty charcoal kilns of an unfamiliar kind, which appears to give good results in places where a large supply of wood renders the labour employed in burning the charcoal of more importance financially than the cost of the wood burnt.

These kilns are used several times.

The first time, the wood is stacked in the ordinary way into a small hemispherical mound, and covered over with a thick coat of mud overlying a first cover of leaves.

This kiln is burnt without any chimney, and the shell of mud is not beaten down as the wood subsides, but is cooked into a hard crust forming a sort of permanent oven Each kiln, which is paraboloid in shape, is 6½ feet high and 13½ feet in diameter. The crust is about six inches thick, and the floor is the natural level ground.

The wood, which is green, and includes some huge old hollow pieces of sal of three or four feet girth, is stacked on end vertically with other pieces laid on the top. The billets are about two feet in length.

The kiln thus contains 75 maunds of wood or 150 cubic feet solid.

The burning takes ten days, and after leaving it two days to cool, the kiln is opened by breaking a hole through one side of the baked crust, and about 27 maunds of charcaol is obtained.

The first burning yields a poor outturn both in quantity and quality.

Next time, the kiln is restocked by the door broken in one side, and billets of wood are again stacked inside : the doorway is then built up again and smeared over thickly with wet mud.

The kiln is fired from a hole at the bottom on the side from which the wind is blowing. The fire passes upwards to the top of the stack, and there spreads into the wood all round and thence burns downwards. There are holes left in the crust of the kiln, a few rather large holes on two levels, which are gradually closed from above downwards as the fire spreads to the lower part of the kiln. There are also holes left on the ground, which are the last to be closed. After the first burning, the mud crust is burnt dry, and is absolutely air-tight. Any cracks are filled up with mud, and the whole kiln is kept luted over.

Only waste wood—wood too big or not fit for sale as firewood—is carbonised. The interstices between the billets in stacking are not filled in : the labour is the only real expense, and a little waste of wood is of little consequence.

The wood practically costs the contractor nothing, as it is only waste pieces.

The cost of cutting the wood for burning one kiln is Rs.2, and the cost of burning the kiln is Rs.2.

The yield is 27 maunds of charcoal, which after paying one anna per maund for cartage to Mailani, sells there at Rs.50 for 180 maunds.

The total cost is therefore about Rs 5-11-0. and the receipts Rs.7-8-0, or the profit on each burning Rs.1-13-0.

COPPICE WORKING.

Until a short time ago, almost the entire produce of the Marha coppice working was exported as fuel, as it was thought unwise to allow the contractors to sell timber to outsiders inside the coupe on account of the temptation to fell standards.

A system has therefore been lately applied by which every tree of three inches or more in diameter, which is possibly fit for use or sale as timber, felled in the coupe, is marked with a hammer, and the standards reserved are marked with black paint only.

With this safeguard against abuse of the permission to sell timber locally, a considerable trade has arisen, and the contractors now recover the greater part of the money that they have paid to Government for the coupe from traders, who come with carts from distant places to buy small timber.

There is no longer any waste therefore in cutting up into fuel wood capable of being used for small timber.

The contractor saws up into metre-gauge sleepers the thickest sal logs, but they are seldom free from sapwood, and only sell for Rs.1-1-0. The price of first class sleepers is Rs.1-12-0, and of the second class Rs.1-6-0. These sleepers are passed and marked by the Ranger before they are moved away from the stump, so that no standards can possibly be felled for this purpose

The principal produce of this forest however is fuel, chiefly for the railway. In executing the felling, all trees, including the smallest seedlings, are cut for the sake of uniformity in the new crop. The railway only takes sal fuel; wood of miscellaneous kinds is all exported to Bareilly, Lucknow and other large cities.

The coupe now being felled sold for ten rupees per acre, and the outturn is about 3000 cubic feet per acre.

The coupe is divided by lines into four plots. Temporary wells are sunk by contractors wherever required, as the water level is only 8 or 9 feet below the surface. The felling is mostly done by hillmen. One contractor, however, imported Bareilly men, as they are better workmen and use very heavy axes (7lbs.).

One Bareilly man can cut a quarter of a stack of fuel per diem, and thereby earns one rupee: this work would take two local woodmen, or four Paharis, to do.

SYSTEMATIC MARKING OF STANDARDS.

The working-plan does not go into much detail on the subject of the reservation of standards. It merely lays down a minimum of 50 trees per acre, or 75, if Vth class trees have to be reserved. A tree of three rotations' age is reckoned for the present to be exploitable.

On an average about 55 trees have been reserved per acre.

If the plan is to realise 20 standards of 72 years old per acre at each felling, it would have been the right thing to reserve about 30 trees of two rotations' age, and 40 of the age of the coppice; total 90 trees.

This would have allowed for casualties; and several trees are always broken in the working; it would also have given further opportunity for continuing the selection of those trees which are considered to be worth reserving for a third rotation.

Formerly the marking of standards was always done by eye, and the result was that the number reserved per acre was very variable, according to the personal idiosnycracies of the marking officer. As a rule the tendency was to reserve too may standards, in which case the coppice suffered proportionately.

In the Kheri Division now every square chain of the coppice coupe is measured out, and six trees selected therein to allow for trees which may afterwards be accidentally broken. This may sound rather unpractical, but in reality it takes no time at all.

The whole coupe is gone over in strips parallel to one side; four boys hold cords of a chain's length along the sides of the strip, while a cooly marks the outside of the line by cutting branches along it; there are also two other cords of a chain's length going cross-wise across the strip, so that as the marking officer goes down the strip, it is all divided up successively into plots of one square chain, in each of which he selects six standards.

One marking officer can do 15 acres a day. By this means the standards are perfectly uniformly distributed over the whole area, and are more or less equidistant one from another: another practical advantage is that the contractor knows exactly how, and in what number, the marking of the standards has been done, and he will therefore have more confidence in bidding high at the sale.

The standards are supposed to be of two sizes (24 and 48 years old), but practically they are reserved of almost any size.

In grassy places there may be practically no choice, as there may not be more than six trees altogether growing on the square chain, in which case nothing can be cut.

This systematic selection of standards may sometimes result too in the reservation of trees unworthy from a timber-producing point of view, but selected purely on account of their position.

No statement regarding the size or species of the standards marked is kept: in last year's coupe the crop looked rather open on account of the small size of the majority of the trees reserved, and there might possibly be a little danger of frost penetrating.

On the whole there is no doubt that this systematic method of marking standards is an admirable one in every way. The difference in the appearance of two coupes, one marked by eye and the other by this system, is very noticeable, and shows the advantage of the new method.

SAMPLE PLOT.

The students laid out a sample plot in this year's coppice area at Marha in accordance with the orders abovementioned.

A typical piece of forest was selected and laid out in rectangular form, five chains in length, parallel to the road, from which it is separated by a protective screen 40 feet wide, and two chains in breadth. It was found to contain 57 standards. The plot was laid out by chain measurement, and a narrow trench dug all round to mark the perimeter. It was also divided across into four equal quarters.

The trees were first numbered with white paint on a scraped surface of bark. They were then ringed with white paint at 4 feet 6 inches from the ground, avoiding all bumps and irregularities of shape, and always ringed at right angles to the axis of the tree. This is done by scraping the tree clear of projecting roughnesses and tying a string tight round the place chosen, and then painting a band up to the level of the string.

The position of each tree on the ground is then measured by co-ordinates from the four corners of the plot, and thus recorded :—



The four quarters of the plot are called A, B, C and D.

The list is as follows:—

1.	A	9	13
2.	A	10	15
3.	A	8	17
etc.			
17.	B	2	5
18	B	6	12
19.	B	7	17
etc.			

The first number shows the distance of the tree measured from its corner along the longer side of the rectangle, that is, from A or B in the direction of D or C, and *vice versâ.*

The second number gives the offset at right angles to the longer side of the rectangle, that is, the distance of the tree from the perimeter of the plot measured parallel to the shorter side.

Tree No. 1 is therefore in A quarter at a point 9 feet distant from the base A B, and 13 feet distant from the side A D.

Tree No 19 is in B quarter, and is found by measuring 7 feet along B C, and then taking an offset of 17 feet at right angles.

The girths and heights of all the trees are then carefully measured and recorded.

PONTOON BRIDGE OVER THE SARDA RIVER.

The railway extension from Mailani to Sonaripur, 32 miles, which is soon to be carried on to Katarnian Ghat, is at present practically a forest line merely, which is closed for half the year in the rains.

The Sarda is a river which shifts its channel from time to time, and there is therefore no permanent bridge over it.

The river crosses it at present on a temporary bridge, which is dismantled every year at the beginning of the rains; it is built on piles for the shallower half of the river bed, and continued on pontoons across the deeper part. The piles are made from II class sal trees specially selected from the forest and supplied to the railway at the rate of fourteen annas per cubic foot. The pontoons are seven in number. They are of iron, and are 50 feet in length and 20 feet in breadth. They are anchored in line across the stream 50 feet apart. Each pontoon carries a section of the bridge of 50 or 20 feet alternately in length, fixed on a vertical shaft, in the centre of the pontoon. These sections of the bridge, iron girders, are then swung round into line, and connected by horizontal steel pins, from which they swing. As the train passes over the bridge, each pontoon is depressed about a foot into the water by the weight of the engine and train, and the rail can thus undulate to a slight extent without any harm resulting.

NEW WORKING-PLAN OF TRANS-SARDA FORESTS.

The old working-plan of these forests prescribed fellings up to the end of the season 1901-1902, and its place is now taken by a new plan, which will come into force on 1st July 1903.

This forest is divided into two working circles, east and west, both worked under the Selection method, with a 30 years' felling cycle and annual coupes in each of about 1500 acres.

The sal forest is exclusively on the high alluvium. The low alluvium, the later deposit, contains nothing but grass, with shisham, khair and scrub jungle.

		Sq. miles.
High alluvium ...	Sal forest	143
	Grass	56
Low alluvium ...	Shisham and khair	20
	Various	20
	Grass	34
		267

The high alluvium or sal area is again divided into high level and low level.

There is not very much difference between these two types, but on the high level the forest is better stocked and the soil is more clayey. On the low level, the soil is more sandy, there is more grass, and frost and fire have done more harm: the forests, however, being less good than those on the high level, have been less worked.

The whole country is flat, with a gentle slope of three feet per mile to the south-east. The average cold weather water-level is 33 feet below the surface on the high level areas, and about 15 feet down on low level areas.

High alluvium sal area.	Stocked.	Fire lines.	Grass.	TOTAL.
High level...	29,203	272	70	29,545
Low level	61,233	759	35,600	97,592
	Total acres ...		127,137	

Sal forms nearly three-fourths of the stock, and *Terminalia tomentosa* nearly one-fourth. The latter tree occurs principally on low ground; the timber is of less value than that of sal, and is nearly all exported to Meerut, where, it is said, white ants do not eat it. It is very good in quality, but the general state of reproduction at present is poor.

The annual yield is fixed at a maximum of 12,000 sal trees: this is probably less than the possibility, but the forest is not fully stocked, and it is intended to raise the exploitable size from 6 feet to 7 feet 6 inches girth.

For the first half-period of 15 years, the exploitable size is taken as 6 feet corresponding to 120 years of age, but it is intended then to raise it to 6 feet 9 inches.

This raising of the exploitable size would seem to be rather premature in the absence of any reliable data as to the size to which under existing conditions sal trees can grow without beginning to become unsound.

The trees are marked for felling a year in advance, and an estimate is then made of the expected outturn of sawn timber from the coupe. This estimate is based on figures obtained from past workings, which roughly give 30 cubic feet and 5 cubic feet respectively for each sound and unsound I class tree: sal, sain and haldu are sold separately. If necessary the coupe is allowed to be kept open for export during the year after the felling, and in the following season,--two years, that is, after the felling—subsidiary fellings are made for the removal of old worthless trees and of trees of inferior species suppressing young sal growth, while badly grown or damaged young trees are cut back flush with the ground, and climbers are cut.

These subsidiary fellings are very important, as can be well seen at Dudwa, for if only the marketable trees are extracted and a large quantity of old unsound trees left to cumber the ground, these latter can only be afterwards removed at the cost of incalculable damage to the young growth around them.

WORKING OF THE FORESTS.

The principal produce of the forests is sal metre gauge sleepers (6′ × 8″ × 4½″ = 1½ cubic ft.), of which seventy thousand were exported last year.

Until recently the railway worked the forests by their contractors, and paid twelve annas per cubic foot on all sleepers extracted. The railway paid their Delhi sawyers seven annas for first class sleepers, and two and one anna respectively for second and third class sleepers.

— - The normal price for sawing sleepers being four to five annas, the workmen naturally tried to confine their work to the conversion of first class sleepers, and consequently a large amount of unsound and unconverted timber was left in the forest.

Each coupe therefore had to be resold afterwards a second, and often a third, time, to be again worked for the extraction of the refuse timber it contained. There are many obvious disadvantages connected with this mode of working, in addition to the fact that all felled timber barked and left lying in the forest is at once attacked by large longicorn beetles.

This has been all changed now by the introduction of what is known as the monopoly system, which was started last year with outside contractors, though the railway continued working for one season under the old arrangement of paying twelve annas per cubic foot on all timber exported. The forests are now worked entirely under this admirable system.

As soon as the coupe has been marked, an estimate, as stated above, is made of its probable yield There is a regular sanctioned scale of export rates detailed for every variety of converted timber; this royalty is debited against the purchaser's account as each cartload of sleepers, beams or scantlings passes the forest chowki on its way out of the forest.

The intending contractor or purchaser, being familiar with this scale of export rates, is able to calculate, on seeing the coupe and the estimate of its produce, how much in addition he is able to bid to buy the exclusive right to work the plot or group of plots which are offered for sale.

The monopoly price at present works out to about two annas per cubic foot on the outturn, or about one quarter of the whole price, as the greater part of the sawn timber extracted comes under the category for which six annas per cubic foot is due.

Instead therefore of taking out only the best timber at a comparatively high rate of royalty, and leaving everything else lying in the forest, the contractor under the new system, having paid down a considerable lump sum for the monopoly of his plot, which sum he has to pay whether he works the plot or not, has every incentive for working out as much timber as possible from it, and in practice nothing but wood worth less than three annas per cubic foot—fuel that is—is left in the forest to waste.

The monopoly price too allows for differences of distance from the railway and of productiveness of the locality, which cannot so conveniently be allowed for in the printed scale of rates for export duty.

Five Range Forms are kept up, showing details regarding the working of the year Form I is simply a list of all trees felled, showing a serial number for each tree and its girth.

Form III is a form for conversion, and shows either logs in the round with their girth, or scantlings of various dimensions. The number of pieces yielded by each tree is thus separately shown, and the progress made day by day in the work in the forest is shown as it goes on.

The annual compilation of these returns gives very reliable yield tables for the forests of this locality.

Form V is an export form, and shows the number of pieces of all sizes removed from the forest by each contractor The clerk at the forest chowki examines each cart as it passes, puts the *sold* mark on the timber, notes the name of the cartman, and the number of pieces it contains. The royalties on each class of scantling are entered and totalled, and the amount subtracted from the contractor's deposit, and his balance stated. Each contractor has a separate book of Form V.

Form II gives the monthly totals of Form V, and must always give smaller returns than Form III.

Form IV gives the monthly totals of Form I.

In addition to the hamner-marks which the forest gang clerks—who keep Forms I and III and are under the Ranger's orders, though paid for by the contractors—put on the sleepers and pieces at each stage, there is also a serial number put on every stump in the forest in red paint, and the same number is painted on all sleepers and scantlings made from the tree. These paint marks are only for use in the forest for checking Form III, before the timber is removed from the ground where the tree was felled, to show which tree yielded any particular pieces of timber. They are of no use when once the timber has been removed from its original spot.

EXECUTION OF THE FELLINGS.

The work in these forests lasts for seven months in the year, from the 1st December to 30th June; sawing is allowed only to the end of March, but carting is allowed to end of June. The sawing is largely done by Delhi men, who work very well: two men can saw up five or six metre gauge sleepers a day out of green sal logs.

The felling is done by saw and axe combined.

A ring of bark about a foot wide is first taken off the tree at the level where it is going to be felled.

Then a notch—not a very large one—is cut with the axe out of the side towards which the tree is leaning, or out of the side towards which direction it is desired that the tree should fall if it is standing straight and pretty evenly balanced.

An oblique sawcut is then made on the other side sloping downwards towards the centre of the tree.

No wedges are used, as the weight of the tree aided by the notch cut out of the other side keeps the sawcut open, so that the saw works quite freely.



The saw used is not the broad curved Delhi saw, but a less curved, narrower and more flexible saw of only about three inches in width at the widest end.

A sound sal tree of ten feet girth was felled in 23 minutes by two men.

For purposes of conversion, the advantage of the Delhi shape of saw is best seen when it is being used in a vertical plane.

Instead of having to dig a hole in the ground for the men holding the lower end of the saw to work in, as the Gorakhpuris do who use frame saws, the Delhi man simply sits on the ground, and works his back, legs, and arms just like a man sculling.

Although the saw is curved, it produces an oblique cut in a straight line through the wood.

The Delhi saw costs Rs 3-8: it is said to be made out of old railway rails hammered out. The teeth are filed and set two or three times a day. The setting is not done by a key, but by two small hammers; every fourth tooth is set alternately right and left.

Large hollow sal trees are used for boat hulls; they only cost about Rs. 75 each to make and export, and they sell at Bahram Ghat for nearly double.

These logs are often about twelve feet in girth, and cube nearly two tons.

They are hollowed out, and then stretched open by firing the under surface, in the same way as teak hulls are made in Burma.

In measuring the girth of a standing I class sal tree seven inches is allowed for the bark.

In the conversion of kurries of *Terminalia tomentosa*, it is to be noticed that the sapwood of this species being considered by the natives to have greater transverse strength than the heartwood, which may sometimes be rather brittle, they always try to keep some of the sapwood on their beams.

FIRE-PROTECTION.

The Kheri forests are intersected by a very well developed network of fire lines.

These are cleared in November and burnt at the end of December and January. By the end of January the young grass springs up, and the fire lines are green.

The vast extent of grass areas which intersect the whole forest, would constitute a great source of danger from fire if they were not burnt every year in self-defence. They are accordingly all fired in January, but a belt of 200 feet of grass is left all round the edge of the forest to encourage tree growth therein. The sal trees round the *phantas* are not likely to produce seedlings at any distance greater than this.

WELLS.

The water level being at a uniform distance below the surface of the ground, and never deeper than 40 feet down, even on the high level, permanent wells can be easily sunk throughout the forest wherever they are required. The average cost is about Rs. 100 for every ten feet of depth; thus an ordinary well with the water at 30 feet below the surface and 20 feet of water in it, costs Rs. 500. The well is first dug out until the water-level is reached, and then the well-curb, made of pieces of *Eugenia jambolana* wood, with a section as here shown, is laid down, and ten feet of brick cylinder is built up on it. This cylinder is then sunk down to water level by digging out the earth from the bottom under the curb, whose sloping under-surface presses the earth into the middle of the well.



The brick cylinder is then built up another ten feet in height, and the whole is again sunk down to water level, so that there is always twenty feet of water to start with.

SYLVICULTURAL NOTES.

It is probably safe to say that almost without exception every sal tree in these forests is sprung from a coppice shoot.

If any young seedling, or what appears to be a young seedling, be dug up, it is found to be growing on a thick bulbous stool, possibly thirty or even forty years old.

If it is, as appears at first sight, an inevitable part of the plan of nature that all young sal growth should thus be always thrown back, say, even 20 years, this fact is obviously of the greatest importance in designing a systematic treatment to be applied to a forest, especially if the cultural mode of treatment were the regular method, with successive regeneration fellings and single-aged crops. The possible causes of this untoward habit are therefore worth considering.

Suppression from want of sufficient direct sunlight naturally suggests itself in this connection.

The sal is reputed a shade-bearing species, and it certainly can exist without much light, but to grow it requires direct sunlight. Perhaps the more vigorous growth of the sal in Kheri renders it more light-demanding than it is in the Dun.

The thick sappy carrotty stems that shoot up when, after a long lapse of years, the swollen underground stem throws up a strong vigorous shoot that now at last will survive and continue to grow, seldom, if ever, are seen (at any rate in Kheri), under cover of surrounding growth, but only under direct sunlight. The result of improvement fellings too is most striking, and the removal of worthless and unsound trees with spreading crowns has everywhere resulted in a splendid growth of young sal, which was only waiting for more light. Even the clearing away of bushes of *Mallotus philippinensis*, under which suppressed sal seedlings are often found, has been found to assist in raising a crop of young sal.

It is incontestable therefore that the young sal plant requires light for its growth, but the action of overhead cover alone will not satisfactorily account in every case for the periodic (it is not necessarily annual) dying back of all young sal plants, since the phenomenon is equally common and noticeable in open grassy places, and round the edges of blanks where there is absolutely no shade at all.

The failure to tap the permanent water-supply has also been suggested as a possible reason for this waste of production, and would in many respects fit the case.

What more natural than that the young plant should be withered and scorched up by the dry winds of the hot season, so long as its roots are only yet working their way through a great depth of loose sandy soil and have not yet reached the water-level?

It is to be remembered, on the other hand, that the best grown sal is on the high level area, where the water-level is about three times as far below the surface as it is on the low level. On water-logged soil sal will not grow at all, and in places where the water-level is not far below the surface it is natural to suppose that the length of the taproot and the length of the trunk are in a direct proportion, and it is certain that if the water-level is near the surface, the sal tree is stunted.

Moreover, the most active period of the sal's vegetation is just in the driest time of the year, and at the end of March the striking phenomenon is seen of a tuft of green leaves appearing a short way below the terminal shoot, before any other part of the young tree has put forth its new leaves. Whether the habit which the sal has in the pole stage of periodically replacing its leading shoot, which dries up, by an extra vigorous side shoot, is to be attributed to the same cause which results in the periodic dying back of the young shoot which springs from the ground for many years in succession, is a point to be decided by careful observation.

If drought caused this repeated dying back for the first 20 or 30 years of the life of the young sal, it is difficult to understand how the subterranean part of the plant continues to grow in vigour and succulence all the time, and this same objection holds with reference to suppression from want of direct sunlight.

Other possible causes for this habit are frost, fire, grazing and injuries from men and animals, and lastly insect attacks. Frost would readily account for this natural coppicing of the seedling if all parts of the forest were exposed to frost, but as large areas of sal forest are never touched by frost, but still suffer everywhere from the periodic and continual dying back of sal, it is evident that frost alone will not account for it. A similar argument disposes of fire, grazing and external injuries from men and animals, because, although any of these reasons might readily produce this result, yet the same thing is frequently observed in places which have been successfully protected from fire for many years, and which have not been exposed to any direct injuries from cattle grazing or working in the forest: besides, we see the same thing happening when the tree is well advanced in the pole stage, and the leading shoot often dries up and is replaced by a strong sappy side shoot.

Lastly, we have to consider insect attacks. The scale insect swarms in the sal forest at certain times of the year, but so far no connection has been proved between its ravages and this habit of the sal tree. Common as it is, it is hardly credible that this insect should be so universal that no part of the forest should ever be left undamaged by it.

A significant point to observe too, both in connection with the *monoflebus* and some of the other suggested causes of this habit, is that the buds which are going to supply the side shoot on its drying up, are already well developed and clearly visible long *before* the leading shôot has begun to lose its leaves, or to show any symptoms of the fate which is awaiting it.

Possibly a combination of some or all of the above-mentioned causes may account for this unfortunate habit; it is conceivable for example that an insufficient water-supply might, to begin with, diminish the seedling's vigour of growth, and then that accidental fires, or deer browsing, or insufficient overhead light might eventually result in its dying back.

The habit however is so universal that the cause would seem to be something more far-reaching than any external injuries can be, and the only way to satisfactorily settle the question is to sow a nursery bed and to carefully watch the development of the young trees as they grow up.

Meanwhile, this habit of the sal of continually dying back, and thereby losing perhaps 20 years of growth in its earliest stage, is quite sufficient to upset any working-plan that ignores this fact.

RESULTS OF IMPROVED METHODS OF WORKING.

The increase of revenue in the Kheri Division last year resulting from the introduction of the monopoly system in the trans-Sarda forests, from increased export of timber by contractors in the Bhira forests, instead of cutting up everything into fuel, and from the rise in the value of the coppice coupes, consequent on the introduction of the systematic method of marking standards, is nearly Rs. 87,000.

In the Bhira Range, while the average annual revenue was formerly Rs. 15,000, the present revenue is nearly Rs. 45,000, and will probably next year be Rs. 60,000.

In the Kairigarh Range, however, the outturn will be only one-third of the estimated annual outturn, which is two lakhs of cubic feet, or one and a half lakhs of metre gauge sleepers, owing to the large proportion of old unsound trees in this year's coupe. However this decrease will be counter-balanced by the improved revenue in Bhira Range. Until recently the second and third year's fellings over each coupe were necessary, because the railway only extracted the best timber, which it paid them to work out at twelve annas a cubic foot, and left everything else lying in the forest, and also because the coupes were so large.

The best thanks of the School are due to Mr. P. H. Clutterbuck, the Divisional Officer, to whose kindness and good management the tour in Kheri was both extremely enjoyable and instructive.

All information regarding the forests and their working was freely given, and the matter contained in these notes is almost entirely derived from his explanations.

H. J.

The Insect World in an Indian Forest and how to Study It.

By E. P. Stebbing, F.L.S., F.E.S.

Continued from p. 148.

Part VI—*(continued)*.

ORDER.—*LEPIDOPTERA*—*(continued)*.

SUB-ORDER HETEROCERA (Moths)—*(continued)*.

Family Cossidæ (Carpenter Worms).

The Cossids are moths of large size having no proboscis. They have frequently a dense covering of matted, imperfect scales on their wings, the pattern being vague. The larvæ are often large, are nearly bare of hairs, and have no bright markings. They bore into trees, often making large ramifying burrows and boring holes to the exterior, from which the sap exudes and runs down the bark outside, serving as an indication of their presence. These larvæ often attain a length of several inches and may live for several years in this condition, mining up and down in the wood of the tree. The pupa is formed within a slight cocoon of silk mixed with gnawed wood. It is furnished with spines along the dorsal surface of the abdomen, by means of which it can move to a certain extent up the tunnel.

This family requires serious study in Indian forests. One or two pests are already known, and it will not improbably be found that others are a serious menace to young saplings, attacking and riddling them before they have grown to a size sufficient to escape damage from the pest.

A species of this family named *Cossus cadambe* has been reported as attacking lopped teak trees in Travancore. The tree is found on considerable areas both in the low country and on the hills up to 3000 feet elevation. The teak over this area is largely lopped for fodder, and in the rotten wood which forms by decay at these wounds, the moth lays her eggs about April. The larva is smooth, without hairs, and red in colour; it probably spends over a year boring inside the wood. The tunnel formed is a winding one. The pupa is apparently not enclosed in a cocoon. It is spiny, the spines being made use of to enable it to work up the tunnel to the opening to the outside, thus enabling the moth to creep out of the hole originally bored to the outside by the larva for this purpose.* When trees are badly attacked they are said to die down, only the base of the stem remaining, which throws out suckers.

The well-known coffee-borer of Southern India, *Zeuzera coffeæ*, belongs to this family, the larva feeding in the coffee branches and stems and, it is said, in the roots, and killing them off It is also said to attack the stems and roots of the sandal-wood, young saplings of this tree being either killed outright or so weakened that they were thrown down by the first storm.

---

* *Vide* Injurious Insects of Indian Forests, p. 102, fig

The writer has had an opportunity of examining both coffee and sandal-wood in the Madras Presidency, both young saplings and older trees, and his investigations, although they have not been carried far enough at present, lead him to suspect the real pest of these trees and the one which causes the most serious injury is a longicorn grub (*Cerambycidæ*) which attacks the trees in their sapling stage, and, usually starting in a branch, works its way down to the heart of the stem, perhaps hibernating in the cold weather in the roots. Whilst the coffee boring caterpiller undoubtedly does damage to both coffee and sandal-wood, investigations will not unlikely show that this damage is by no means so severe as that done by its beetle grub companion. Since on the one hand coffee bushes are killed off or are so riddled as to be useless by the grubs, whilst on the other the tunnels in the heart of the sandal sapling whilst perhaps not killing the plant reduce the value of the wood for sale purposes when the tree is finally cut over, it becomes obvious that it is imperative that the habits of these borers should be thoroughly understood.*

FAMILY HEPIALIDÆ (GHOST AND SWIFT MOTHS).

Moths of varying size, some being gigantic. The wings do not fit well together at their bases; no proboscis is present and no frenulum; the scales on the wings are imperfect. The larvæ are nearly bare of hairs, and they live either in the earth, feeding upon the roots of plants, or they burrow in the wood of trees and shrubs. The chrysalis is generally elongate and cylindrical in form and very agile, having a considerable number of spines on its dorsal aspect; by the aid of these the pupa is able, by wriggling, to move a considerable distance in the tunnel in the wood.

Very little is at present known about the operations of these moths in Indian forests, but grubs thought to be Hepialid have been reported as boring into teak wood at the Nilumbur plantations and into young teak saplings in plantations in the Prome division. These reports require careful observation and confirmation.

The eggs in this family as well as in the families *Ægeriidæ* and *Cossidæ* above alluded to are usually laid upon the bark. The caterpillar tunnels into the wood. The tunnels so made are kept open by the larva and it occasionally comes out and feeds upon the bark. If often builds for itself a covered gallery of silk and excrement, this gallery being very conspicuous on tree trunks. When it feeds in this way the tree attacked will be often found to have a juicy, soft succulent bark.

---

* *Vide Injurious Insects of Indian Forests*, p. 104, fig. 65.

Family Lasiocampidæ (Eggers, Lappet Moths).

These moths are usually large, are densely covered with scales, and have no frenulum. The costal area of the hind wing is largely developed Antennæ in the male are highly pectinate. These characters render it easy to distinguish a Lasiocampid moth. There is at times a great difference in size between the male and female, the latter having three times as great an expanse of wing as the male The eggs are smooth and sometimes spotted in an irregular manner like birds' eggs. They are often covered with hair by the female The larvæ are clothed with a soft woolly hair as well as with short stiffer hairs. These hairs are not arranged in definite tufts and pencils, nor are they as highly coloured as in the case of the larvæ of the next family to be considered, the *Lymantriidæ*, and thus they can be distinguished from these latter. This hair has sometimes very irritating properties. The caterpillar spins a cocoon in which the hairs of the body are often mixed. In some species the walls of the cocoon have a firm appearance, looking very like egg-shells, and this has probably given rise to the name of 'eggers.' The caterpillars feed upon leaves and probably do some damage in this way.

An example of one of these Lasiocampid defoliators is an insect by name *Suana concolor*, whose larvæ feed upon the leaves of the sal tree in the Siwalik Forests in the United Provinces.

The larvæ caterpillars of this insect are large, over three inches in length when full grown in October, and grey in colour, with irregularly arranged tufts of soft hair. They pupate in November, spinning a strong hairy silken cocoon on to the bark or a branch of the tree. The winter is spent in the pupal stage, the moth appearing about the end of March. The rest of the life-history has yet to be worked out, but the female probably lays its eggs on or near the sal twigs, and the young caterpillars hatching out feed upon the new flush of leaves which appears in April. The moth is grey in colour and answer the above description of a Lasiocampid moth.*

Family Lymantriidæ or Liparidæ.

Mostly small or moderately-sized moths, without brilliant colouring, whites, greys, browns and blacks being the predominant tints in the family; the male has the antennæ highly pectinated. The larva is very hairy and usually bears tufts or brushes of shorter hairs together with others much longer and softer, these being sometimes amalgamated to form pencils, the tufts and pencils having a definite arrangement on the insect. The colouration of the larva is often very conspicuous, the tufts and pencils of hair being of vivid and contrasted colours This arrangement and colouration of the hairs distinguishes these larvæ from Lasiocampid caterpillars Any one who has been in tropical or semi-tropical forest at the commencement of the monsoon, must have noted the great variety and brilliant colouration of the caterpillars of this family. The writer was particularly struck with the gorgeousness of what may be termed the 'grub world' at this season in both the Perai and Coimbatore (Madras) forests, whilst he was visiting them at this period of the year

---

* *Vide* Departmental Notes on Insects that affect Forestry, No. 1, p. 58, Pt. V, fig. 1 a, b, c, d, for a description of the life-history of this insect.

The larvæ form a cocoon in which much hair is mixed up. The pupæ are very remarkable, as they are sometimes also hairy, which is very unusual amongst Lepidoptera.

This is an important family of moths, as it contains species which occasionally increase in enormous numbers and commit great ravages One of the first allusions to such an event having taken place in an Indian forest is contained in a description, by Mr W R Fisher, * late Conservator of Forests, of a severe attack, in which the trees were completely stripped by one of these insects which took place in the sal forests in Assam in 1878 The egg is laid by the female moth on the young leaves of the tree The caterpillar on hatching out at once commences to defoliate the trees, and in the attack in question an area of over 200 square miles of sal forests was completely stripped of all leaves, the trees being rendered perfectly bare and the ground being strewn with their debris, and with the caterpillars' droppings In 1897 Mr Campbell† reported an attack to have spread over 800 square miles in Assam. all the trees associated with the sal, such as *Bombax malabaricum*, *Careya arborea* and *Dillenia pentagyna*, etc, being also defoliated , at the same time he noted that pure sal forest had suffered more than mixed. In this attack the larvæ first appeared in August, a second generation appearing in November, a third about the end of January and a fourth towards the end of March. The chief insect responsible was a species of *Dasychira*. This insect was accompanied by *Leucoma diaphana* in August, by *Trabala Vishnu* in May and by *Lymantria grandis* in all the attacks ‡ In 1899 all the sal trees in the Duars in Bengal were defoliated in a similar manner, four different species of *Lymantria* moths sent to the writer by Sir H. A. Farrington, the Officer in Charge of the forests, and identified by Sir George Hampson, being concerned in the attack § It is not certain how many species or what moth was responsible for the Assam defoliation, as confusion appears to have arisen in the identifications of the insects sent.

---

* *Vide* Indian Forester, Vol.

† *Ibid*, Vol. XXIV, No. 9, (1898)

‡ *Vide* Departmental Notes on Insects that affect Forestry, No. 1, p. 62.

§ *Ibid*, pp 67—77.

From what has been written it will thus be seen that species of this family, when they swarm in large numbers, are a source of serious danger to the forest.

FAMILY GEOMETRIDÆ (GEOMETERS).

An extensive family of fragile moths having a large wing area, the antennæ being frequently highly developed in the males. The larvæ are elongate and slender, having in addition to the three pairs of thoracic legs, only one pair of abdominal pro-legs placed on the ninth segment and an anal pair. They progress by moving these two pair of feet up to the thoracic legs, so that the body is thrown into a large loop, and then moving forward the thoracic legs. From this habit of progression they are called 'loopers' or Geometers. The number of these larval legs and the resultant mode of walking is one of the most constant characters of the group. The larvæ assume various attitudes in repose, either clinging to the stem with their pro-legs, holding the rest of their body straight out at an angle from the twig, being attached to it anteriorly however by a strand of silk projecting from the mouth; or they prop themselves up between two twigs more or less at right angles to each other. They often vary in colour, the same species being either green or brown, and this colouration and the markings upon them often gives them a great resemblance to their food-plant, but in many cases they appear to make no or little use of this for protective purposes, as one would expect to find them doing.

These larvæ are defoliators, but little is known about their operations in Indian forests at present. The following is a portion of the life-history of a typical member of the family by name *Boarmia selenaria*:—

In the sal forests of the Siwaliks (on the Dun side of the range) a plague of caterpillars appeared about the middle of April 1901 and in parts entirely stripped the trees of all the new year's shoots, leaves and flowers. Young saplings suffered very severely, and the writer noted that towards the end of September they had no green shoots upon them, many bearing numerous dead branches. The growth of the year in the portions of the forest most heavily attacked was *nil*. Sal of all ages were attacked. The pupal stage was a short one, and moths were bred out in May. There is probably more than one generation of the pest in the year, but observations on this head have to be yet made.[*]

NOCTUIDÆ (NOCTUIDS).

A very large family of moths, generally of sombre colours, the insects being, with some exceptions, very rarely seen in the daytime. Both proboscis and frenulum are present, and the antennæ are not highly pectinated in the male. About 8000 species are known, and owing to their great resemblance their classification is difficult. The larvæ are, as a rule, destitute of large tufts of hair and are not brilliantly coloured; they are fond of concealing themselves during the day and coming out to feed at night, and thus when defoliating trees they are very apt to be overlooked, as when searched for during the daytime they are not to be found upon the leaves and twigs. Many of the caterpillars of the family pass most of their time at or beneath the surface of the ground, finding nourishment in roots or the lower part of the stems of plants. This is especially the case in the genus *Agrotis*, perhaps the most widely distributed of all the genera of moths. In some forms the abdominal pro-legs are reduced to two in number, and we then get larvæ resembling the loopers of the last family, the caterpillars being then known as 'semiloopers.'

---

[*] *Vide* Departmental Notes on Insects that affect Forestry, No. 1, p. 100, Pt. II, figures 5, *a*, *b*, *c*, for a further note upon the habits of this insect.

Noctuid larvæ either defoliate trees and plants, or they may have a limited wood-boring capacity. Others feed in the seeds of plants or live upon the roots, either feeding upon the smaller ones or tunnelling into the larger ones. The larvæ living upon leaves are usually hairy to a certain extent, and spin a cocoon before changing into the pupal state; those living in wood form a rough cocoon of hairs and chips of wood, whilst those pupating in the ground usually build an earthen cell to change in. In Indian forests we have representatives typical of each of these methods of feeding and pupating.

Hyblæa puera is the well-known teak leaf defoliator. The eggs are laid upon the leaves or twigs of the tree, and the larvæ commence their defoliating operations some time in April (the period of course varies in different parts of India, being later in the drier tracts) and the insect passes through several generations—the number being at times as many as seven—in the year The defoliation is easily recognisable, as the caterpillar in feeding upon the leaf leaves intact the main rib and the side veins, eating all the green leaf tissue between these. They pupate either in rolled-up portions of the leaf itself or on dead leaves upon the ground. The moth is small and dusky in colour, with reddish patches on the hind wings. It is apparently to be found all over India wherever the teak exists, and the larvæ at times entirely strip the teak of their leaves at least twice in the same year.*

The silk cotton-pod caterpillar, *Mudaria cornifrons*, destroys the pods of the silk cotton tree (*Bombax malabaricum*). The eggs are laid in the flower or immature pods of the tree in February-March, according to when the tree flowers; the larva on hatching out tunnels into the pod and remains feeding in it until the pod falls to the ground. When full-fed the caterpillar bores its way out and burrows into the ground, and constructs the earthen cell typical of the hairless Noctuid larvæ. The grub then changes into the pupal state and passes the rest of the year—hot weather, rains and cold weather—until the succeeding February in this cell. The moth on coming out lays her eggs in the flower or immature fruits of next year's crop.*

---

* *Vide* Departmental Notes on Insects that affect Forestry, No. 2 p. 267, for a fuller description. Also Plate XVIII fig 1; Pl. XIX fig. 1, a,b,c,d; *Injurious Insects*, fig. 71.

The genus *Agrotis* includes the typical earth-living noctuid larvæ, who spend the whole of their larval life in the earth, feeding upon roots, etc. A widely-spread Indian species is *Agrotis ypsilon*, the caterpillars, which are known as "cut worms," occasionally committing great havoc amongst crops. Up to recently it had not been reported as dangerous in the forest, but in 1900 Mr. B. O. Coventry found it eating young deodar seedlings in the Gora Gali nursery near Rawalpindi, and the writer discovered it committing the same damage in some nurseries in the Simla Hills the following year. This larva feeds upon the roots and also comes above ground at nights and in dull, cloudy weather and cuts off young seedlings† close to the soil surface, and either leaves them to die *in situ* or drags some to its hole to feed upon, thus acting much in the same way as the cricket *Brachytrupes achatinus* and the cockchafer grub already described. We at present know very little about the wood-boring noctuids.

FAMILY PYRALIDÆ.

This division must be considered rather as a group of families than as a single one. It includes a very large number of small or moderate-sized moths of fragile structure frequently having long legs; the antennæ are simple, being only in a few cases pectinate. The larvæ are usually nearly bare, with only short scattered hairs and little colouration; they have most varied habits, are fond of concealment, and are very lively and abrupt in their movements, wriggling backwards and forwards when disturbed. They form a cocoon before changing to the pupal state. Species of the family have proved exceedingly destructive to deodar and other cones such as those of the spruce, silver fir, and blue pine. Mr. Ribbentrop, at the time Inspector-General of Forests, noticed that nearly the whole of the crop of deodar cones on trees round Simla were destroyed in 1898 by a larva which proved to be a Pyralid. Recent observations have shown the writer that not only deodar cones but those of the silver fir, spruce and blue pine are infested by one or other or both of two species of the family named *Euzophera cedrella* and *Phycita abietella*, which have apparently much the same life-histories.

---

* *Vide* Injurious Insects of Indian Forests, p. 118, fig. 70.

† *Id* p 113, Plate VIII and Departmental Notes 1, p. 81.

The eggs are laid by the moths some time in autumn either on the flower buds or near them. The exact period at which the larvæ hatch out has not been observed, but they are to be found burrowing in the cones towards the end of May, and continue to do so until about the beginning of August, when they become full fed. The cone by now has become rotten and falls to the ground, and the larvæ will either pupate within it or leave it and burrow into the soil. The moths issue in September and October.

One of the widest known defoliators of the family in India is *Pyrausta machæralis*, which in its larval stage strips the teak of its leaves all over the country, working often in company with *Hyblæa puera*. This insect has as many as seven generations in the year. It spends the winter as a larva in the ground in the Central Provinces, appearing as a moth in May and laying the eggs of the first generation of the year upon the leaves of the tree. As these moths do not all appear exactly at the same time, the egg-laying is spread over several days, and as the eggs laid first hatch out first we have a series of uninterrupted and overlapping generations provided up to November or even December, and one or more of them may produce an enormous number of individuals, the caterpillars stripping the entire crop of leaves from the trees. In feeding these latter do not touch any of the veins of the leaf, but only eat the parenchyma, thus skeletonising it.* Mr. R. S. Hole gives the following as the period approximately spent in passing through a generation :—

From appearance of moth to hatching out of young larvæ laid by it	7 days.
Larval stage	16 ,,
Pupal stage	7 ,,

Or 30 days for a complete generation.

Two other species of Pyralid, *Macalla moncusalis* and *Tetridia caletoralis* have been reported as defoliating sal trees in Ganjam, Madras. The grass moths, small insects which fold their wings tightly round the body and have a head pointed in front, belong here.

FAMILY TORTRICIDÆ.

Moths of small size with a rather large wing area, the wing fringes being never as long as the wings are wide; the hind wings without any pattern in them. The larvæ inhabit their food plant, which may be rolled-up or twisted leaves, or the interior of fruits and herbs, or galls, or even roots. The larvæ have all sixteen legs present. The name *Tortricidæ* refers to the habit the larvæ have of rolling up leaves, or twisting and distorting shoots and buds. Little is known about this family in India.

---

* For a fuller description see Departmental Notes, No. 2, p. 301. Plate XVIII, fig. 2; Pl. XIX, fig. 2 (larva).

FAMILY TINEIDÆ.

Small moths with the labial palpi more flexible and mobile than in other moths; usually separated and pointed. Hind wings frequently with very long fringes, the wing being reduced in size and pointed at the top. Larvæ are very different in shape and nearly always conceal themselves They feed upon a variety of substances, such as clothes, furs, hair, horns, and seeds, and probably defoliate to a certain extent. They also mine into leaves of trees. Little is known at present about the family, although it probably contains numerous forest pests. The spruce bud binder, *Eucosma* sp. is one of them. The moth lays its egg upon the terminal bud of the spruce branches, probably some time in the summer. The egg remains here until the following spring, and hatches out before the young opening needles of the bud have pushed off the outer cap or covering. The young larva at once spins the tips of the needles together, thus preventing their opening and parting asunder, and thus forms a shelter in which it lives feeding upon the inner and more succulent of the needles. Some weeks are spent in this stage, and the grub then changes to a pupa within the hollowed out bud, and after about 10 days passed in this stage the moth emerges, the external needles of the shelter having by then dried and parted asunder. The writer has seen trees with as many as 70 per cent. to 80 per cent. of the terminal buds treated in this way.

USEFUL LEPIDOPTERA.

Although Lepidoptera are the most exclusively vegetarian of all the Orders of insects, a certain number of their larvæ prey upon insects which are themselves filled with vegetable juices (such as Coccidæ or scale insects, Aphidæ or plant lice, etc.), and a very small number, such as Tinea, etc., eat animal matter.

In the winged state Lepidoptera may be said to be useful as a whole, since many feed largely upon honey, which they collect from flowers, and in doing this they thus become important agents in the distribution of pollen from flower to flower, as it adheres to their scales and hairs whilst obtaining the honey from the flower.

The Heterocera or moths include several insects which may be said to be of considerable use to man. Amongst them are the silkworm moths of the family Bombycidæ. The mulberry silkworm, *Bombyx mori*, is the cultivated variety in the plains of Bengal, whilst in the forest there are the important Tusser (*Antheræa mylitta*) silkworm of Chota Nagpur and Central and parts of Southern India, the Muga worm (*Antheræa assama*) of Assam and the eri worm (*Antheræa ricini*).

The Noctuidæ contain the genus *Erastria*, the larva of a species of which is predaceous upon a Lecanium scale insect which infests the peach in Southern Europe. It may be found that the forester in India has allies of this nature in the family.

II.-CORRESPONDENCE.

Teak in Evergreen Forest.

MR. BRUCE's account of patches of teak in moist evergreen forest in the Ruby Mines District and Mr. Oliver's remarks thereon I have read with great interest.

On a tour through the Attaran forests, which I made in July and August 1858, I came across several instances of Teak growing in the midst of dense evergreen forest, and on page 55 of my report (Selections from the Records of the Government of India, Foreign Department, No. XXXII, Calcutta, 1861,) I said: "Teak has been found only in a few instances in the dense evergreen forest, and wherever this is the case there is every reason to believe that the locality was originally covered with forest of a different character. The Teak trees in the evergreen forest attain a gigantic height, being obliged to draw themselves up toward the light between their fast-growing companions. But seedlings are wanting; the dense shade does not favour the springing up of young Teak."

The largest of these patches was in the upper Mittigate or Kyauktag forest, and it is fully described on pages 70,71 and 189—191. On 0·135 square miles (86 acres) were counted 43 trees above 5 cubits in girth and 211 dead (*nathal*). trees, all giants. The total area of the patch was estimated at 0·675 square miles (430 acres) with 215 living and 1055 dead trees. Smaller trees and seedlings were almost entirely absent. The entry made at the time in my Forest Day Book (Report, page 189), slightly condensed, was as follows: "The whole of the Teak is dying out fast. It is an interesting instance of a Teak forest, which at one time may have been vigorously thriving here, being affected and at last stopped in its development by the rise of a vegetation of different trees on the same spot. When Teak first sprang up here, perhaps two centuries ago, the forest must have been altogether of a different character. The cessation of jungle fires for a few years, either caused by rainfall during the dry season, or because there were no travellers or others to set fire to the jungles, may have permitted the accumulation of vegetable mould and favoured the springing up of a new class of trees among the Teak. Let these trees of the dense evergreen forest once take possession of the ground, so as to keep off jungle fires, and the progress of their growth is irresistible. Their first effect on the Teak is beneficial; the Teak is obliged to clear itself of its side branches, and it is gradually drawn up to that stately height which is the character of the evergreen forest. But here the beneficial influence ends. The springing up of Teak seedlings in the dense shade is out of the question, and the Teak dies of old age without any chance of propagation."

Two other patches of smaller size in the Attaran forests are mentioned on pages 163 and 177 of the Report, and a similar patch in the middle Thaungyin forest is mentioned on page 25 of my Report on the Tennasserim and Martaban forests for 1858-59 and 59-60. The subject is also discussed on page 356 of my *Forest Flora of the North West and Central Provinces.*

The most interesting point in Mr. Bruce's communication is, that he found patches (*waiks*) of Teak surrounded, if I understand him right, by evergreen forest, containing hundreds of thousands of saplings. These waiks were near villages, where all the old Teak trees had been cut out. The remarkable fact is, that the evergreen forest did not encroach upon these patches of young Teak. Unless Teak seed was sown by hand in these patches, which is not likely, the plants must have grown up in thick masses under very favourable circumstances. Perhaps a few Teak trees had been left standing, which seeded profusely in a season favourable for the growth of the young plants, or, a circumstance which I have often noticed in Pegu, a flood of the chaung brought down masses of seed.

What Mr. Bruce says regarding these patches of young Teak in the evergreen forest, reminds me of the Thinganneennaung Teak plantation, which was established in the midst of the evergreen forest in the Attaran district by Mr. Gemmer, my predecessor in Tenasserim. A nursery of 4½ acres was prepared by rooting up the stumps and trenching the ground 12 inches deep, and the seed was sown thick in March and April 1856. The seed germinated well, but unfortunately only a very small portion of the seedlings raised were transplanted into the adjoining forest. On taking charge of the Tenasserim forests, I visited the spot in July 1858, and found 57,200 plants on the 4½ acres, of which 5600 had a girth from 9 to 13 inches and a height from 27 to 32 feet. These were the dominant trees, but the thicket of young Teak was so dense that the trees of the evergreen forest had not encroached upon it.

Some of the readers of this paper may perhaps remember the Oak areas of the Spessart in the midst of the Beech forest. Suitable areas with good soil are cleared and acorns are dibbled in thick. My first visit to the Spessart was in 1865, when the then head of the Forest Administration in Bavaria, the late Herr von Mantel, asked me to join him on a tour of inspection through Spessart and Steiger Wald. At that time natural regeneration of Oak was mainly relied upon, but the difficulty was, that on the sandstone of that mountain range the Beech usually got the upper hand of the Oak, and this led to the establishment of the Oak areas. When 20 years later I paid my second visit to the Spessart, the Oak areas often reminded me of the Thinganneennaung Teak plantation, with this exception, that Teak in its youth grows much faster than the Oak.

On the soil overlying the Keuper formation in the Steiger Wald, also in Bavaria and not far distant from the Spessart, the

Oak grows with greater vigour and is not readily overtopped by the Beech; there are large areas here of even-aged Oak and Beech from 100 to 120 years old, a feature wanting on the sandstone of the Spessart. Very likely the waiks of young Teak described by Mr. Bruce have soil which is particularly favourable to the growth of Teak, thus protecting it against the encroachment of the evergreen forest.

The account given by Mr. Bruce of the high ground on both sides of the valley, stocked with Eng forest (*Dipterocarpus tuberculatus*) reminds me of Captain Latter's report on the Thaungyin forests of May 1848, a portion of which is printed in an appendix to Dr. Falconer's report on the Teak forests of the Tenasserim Provinces (Selections from the Records of the Bengal Government, No IX, Calcutta, 1852). On pages 153—155 of that volume Captain Latter gives a description, illustrated by coloured diagrams on the map, of alternating stretches of high ground stocked with *Dipterocarpus tuberculatus* and *Pinus Merkusii*, and low ground along the streams with Teak-producing forest on alluvial soil. On the high ground Latter says the sandstone is on the surface. I have, on my repeated visits to the Thaungyin in old days, found stretches of high ground between the streams composed of laterite, and stocked with Eng and Pine, alternating with stretches of low ground, stocked with Teak-producing forest

KEW D. BRANDIS.
12th February 1903.

Grass for Paper Manufacture.

REFERRING to G. W. Thompson's letter at p. 80 of your February Number, there was for some time a good deal of uncertainty about the identification of the 'Bhabar' *grass*, and it was very frequently confused with the *sedge* (*Eriophorum comosum*) which is found in similar localities, often mixed with it, and of apparently equal value as a fibre material. The name given by me in my Circar list, *Andropogon involutus*, Stendal, was, if I remember rightly, ascertained at Kew from specimens named by the late General Munro, C.B, the principal authority on grasses of his day. In 1884, 'Bhabar' or 'Bhaib' grass was the subject of a note by Sir W. Thiselton-Dyer, published in Vol. XX, p. 40[illegible], of the *Journal* of the Linnæan Society, where the name given it *Pollinia eriopoda*, Hance. In 1888 a figure of the grass was published as Plate 1773 of Hooker's *Icones Plantarum*, the plate being accompanied by a note by Prof. D. Oliver explaining that in the monograph of the Andropogoneæ by Herr E. Hackel, which was about to issue, the name finally adopted would be *Ischæmum angustifolium*, Hackel. The same plate and an account of the grass was also published that year in the *Kew Bulletin*; and later on, in 1893, a full account of it by Mr. E

Thurston was published in the appendix series of the *Indian Forester*, Vol. XIX. Finally, the full synonymy of the plant is given in Vol. VII, p. 129, of the *Flora of British India*, by Sir Joseph Hooker.

It is only when the plants are not in flower that there is any possibility of confusion between the grass and the sedge, unless the observer is totally ignorant of botanical characters; for their flowers are utterly unlike each other The *Eriophorum* may be gathered in flower at almost any time, especially in the early cold season, but the *Ischæmum* only flowers, so far as my own observation goes, in the hot season. I believe the leaves, which are the part used for fibre, are of equal value, and I feel sure I have seen two grass-cutters of the Siwaliks cutting these of either species indiscriminately.

The grass and sedge are largely used in paper-making in Northern India, and I will leave the reply to Mr. Thompson's enquiries on the subject of the trade to the many Forest Officers whose information is likely to be more up to date than mine would be.

J. S. GAMBLE.

Sweet Chestnuts in India.

THE sweet chestnut, *Castanea sativa*, grows well at Dehra Dun and on the slopes of the Himalayas above 2000 feet. This tree is calciphobous and will not grow in a soil containing more than 4 per cent. of lime. Its fruit is sold in the Dehra Dun bazaar, and forms an excellent article of food, from which cakes and puddings are made. But the fruit produced in India is small, being only that of the forest tree and not of the varieties improved by cultivation, which are grown in the South of France, Spain, Italy and other Mediterranean countries. There would therefore be much advantage to India if the better varieties of sweet chestnut were imported and grown in suitable localities. In these varieties the large size of the fruit is said by Sir W. Thiselton-Dyer to depend on selection, only one or two ovules being developed in each involucre in the better varieties, the rest being suppressed. Such varieties as the *Marion de Lyons* and the *Gros Merle* are grown in Kew Gardens and produce fruit, and some years ago a sack of good chestnuts were sent to Covent Garden from Gloucestershire and fetched £3, the fruit coming in earlier than imported fruit. Mathieu, in *Flore Forestière*, says that most of the large fruited chestnuts in France are grown by grafting on the common stock. In Corsica, meal is ground from the dried fruit and forms *pollenta*, an important article of food used by the peasants. These large fruited varieties are very liable to injury from late frosts, and when they were introduced into Alsace, where much chestnut coppice is grown for vine-props, the large fruited varieties were frozen down annually to the stool. They are very subject to this injury at Kew, but could easily be grown in warm places in the west of England and in Ireland. Certainly in warm situations, on soil which does not contain too much lime, above 2000 feet altitude, in the Himalayas, the climate is sufficiently like that of the South of France, for the large fruited chestnuts to thrive and form a great addition to the food of India. Sir W. Thiselton-Dyer has also informed me that there is a difficulty about keeping the fruit, and that in India it will not keep for more than a few weeks, but it is kiln-dried in Italy and will then keep indefinitely. Kew would certainly arrange to supply the Indian Government with plants if application was made.

W. R. FISHER.

[1] In December 1900, 375 seedling and 50 grafted dwarf chestnut plants, ordered by the Secretary of State were received from Messrs James Veitch and Sons Ld., and planted out in the Chakrata Forest Garden and in the Malon nursery near Kathian, where most of them are doing well. A similar consignment, it is believed, was sent to Kulu.—HON. ED.

Forest Destruction by Insects in Norway.

THE extract under this heading from *The Timber Trades Journal*, which appeared in the March number of this magazine, should be widely read by, and receive the serious consideration of, all interested in the up-keep and well-being of the forests of, India; and its application need not be limited to coniferous forests only.

In the extract in question we read that the great forests in Osterdalen and Solar in Norway are suffering from a fearful plague of caterpillars, which are stripping the pine trees bare, and that already the estimated damage has reached the figure of 300,000 kroner (over £15,000), whilst the value of the threatened areas is estimated at 1,200,000 kroner (over £60,000). The attack is considered to be as yet only in its initial stages!

But the pest—and this is where the lesson should strike home to us in India—is well known, its annual life-history has been well studied and is understood by the most illiterate of the forest hands; the previous severe attacks experienced from it are all on record, and consequently the districts affected are up in arms as a whole and are banding together and devising means whereby the young larvæ are to be attacked simultaneously in the spring, when they reappear after their winter hibernation and endeavour to mount the pine trees to continue their depredations. The details of the life-history being common knowledge, it is known where the caterpillars are hibernating and when and how they will re-appear. The Agricultural Department have been asked for a grant of 26,000 kroner (nearly £1700), which is being employed in preliminary enquiries as to how the pest can be best destroyed.

I would ask—What would our position be in this country in face of a misfortune of this nature? Such an attack would probably occur on a scale so colossal, owing to the greater vastness of our forest charges, as to make the gravity of the Norway infestation, serious as it is, appear insignificant beside it. Even were the attack to last several years (it is considered this Norway one will last three unless the caterpillars can be killed off) it would be too late for us to do much more than watch it and thus to learn by bitter experience the life-history of the pest and perhaps how to do better next time. Knowing nothing of the life-history, we should have to start at the commencement and study this whilst the destruction in the forests was perhaps running into lakhs and crores of rupees. In all probability we should not be able to say where the pest would hibernate, or when and how it would reappear in the following year, nor how many life cycles we had to expect, to fight in the year. Further, it is more than probable that we should know nothing about any of its parasitic or predaceous enemies. We should have to learn all this whilst the damage was being done. These are not the mere illusory or fanciful statements of the alarmist. The world has furnished numerous instances of such inflictions. This Norway attack but adds one more to the lengthening list.

In India our forests were natural virgin ones when the Department started work, and as such consisted of trees of all ages and, in many instances, of very different species. In such Nature holds the scales and keeps even the balance of power between the trees and the insects which prey upon them. When the forester appears he alters all this He wishes his forests to contain valuable species of trees packed as close together on the ground as possible. He accordingly takes the virgin forest in hand, cuts out all dead timber and badly formed and mature trees, and encourages the growth of more valuable species. Thus large tracts of forest soon approximate to a more nearly even age and the growth assumes a more similar character, the valuable species being encouraged to grow together, where possible, in large masses. Further, he forms plantations in which large blocks of the trees are naturally of the same age and ofttimes of the same species; he clear cuts other areas and gets up even-aged coppice, or sows seed wholesale over the tract felled and produces an even-aged young forest consisting of often but one or two species of tree.

In all such operations the forester is helping the insect pest against the tree by affording it every facility in its growing stage of life of (1) finding a large amount of its favourite food material ready to hand; (2) enabling it to move easily and quickly about over this, since the tree next to the one upon which it is feeding is of the same species. The insect has not, therefore, to undertake perilous journeys, during which it is at the mercy of birds and predaceous insect foes, to search for a fresh host. Given one or two dry seasons, which will be favourable to the insect, and enormous plagues of it appear, following an ordinary law of Nature. That the Department in India will in the future have to meet such plagues and fight them is as absolutely certain as the fact that there are such laws to be obeyed, and I ask again—

What shall we be capable of doing? It will be of little use going to Europe or America for parallel cases. The life-histories of our pests in India, or what is known of some, show that they differ from those of closely-allied European or American confrères, and what therefore may be a good remedy there will probably be useless in India and may even do much harm.

To the thoughtful there can be little doubt that the present is the time to work out the life-histories of our forest insects, any and every one met with, for we know not which is to prove the pest of the future. This work should move hand in hand with the amelioration of the forests—amelioration, that is, from the forester's and commercial point of view, and which has become essential owing to the necessities of the growing population of the world, which demands and will have a high outturn per acre of the crop growing upon it. It is therefore necessary that we should be in a position to fight the insects which dispute with us the possession of our crop In Europe every Forest Officer has an acquaintance with the insect pests he may have to fight. The knowledge is as essential to him as his sylvicultural knowledge, for large sums of money may depend upon his possessing it and being able to apply it promptly.

I do not mean by this that all European Forest Officers are Entomologists. They are not so any more than they are wood-cutters because they know how to fell a tree, clerks because they understand how to keep accounts, or learned pleaders because they may have to conduct cases in court. But they have a working knowledge of the chief insect pests whose attacks are to be feared.

Unfortunately in this country such knowledge is not at present available for general information, for it has yet to be culled from Nature's handbook, but I would point out that in such a vast continent as India every Forest Officer should help in these observations and endeavour to learn something about the insect life of his own forests We shall thus arrive more quickly at the knowledge of which are and which are not the insects most to be feared in particular forests. That the day will surely come to some, whether in charge of a circle, a division, a range, or a beat, when such knowledge may be the means of saving, by their being able to take immediate action (this means everything in such attacks), large areas of the valuable forests entrusted to their charge, is only too probable. Our endeavour in India should therefore be to get ready by studying the life-histories of the insects we meet. This is the first step. It is useless talking about the possibility of remedial measures until we know what our enemies' tactics are and where they are to be found at the different seasons.

INDIAN MUSEUM,
March 11th, 1903.

E. P. STEBBING.

The Harcourt Working-plan.

ALL readers of the *Indian Forester* who are interested in the intricate problems presented by the treatment of high forest in this country, must be grateful to Mr. Gleadow for occasionally letting in gleams of French sunlight on the darkness which surrounds us. On a former occasion we benefited by a highly interesting, though somewhat barren, discussion on "Proportionate Fellings," and in the March number of this year Mr. Gleadow presents to us another method of ascertaining the possibility in high forest. However, the chief interest of the article entitled "The Harcourt Working-plan" lies in Mr. Gleadow's footnote rather than in the article itself. The note is rich with suggestion, yet commits the translator to nothing, and the question at once arises—Which part of the working-plan does he consider to be "not without its bearing on the treatment of high forest in general?" Presuming that we are dealing with a forest which is already high forest, it would appear that the method of calculating the possibility and executing the fellings in the high forest, is alone of interest The latter bears a strong resemblance to the prescriptions for the improvement fellings which are being carried out in many sal forests, while the former is remarkable for being the very opposite of the method formerly advocated by Mr. Gleadow under the title of "Proportionate Fellings" One of the advantages of that method was that it obviated all necessity for any "clawings and scratchings," but now we are invited to measure every tree over 24 inches girth before felling This is certainly a new idea as regards the treatment of Indian forests, and it is likely to remain so; but intrinsically it seems a notion of great antiquity, for it must have been obvious to the first man who ever proposed to make fellings which should keep the volume of timber on the ground a constant quantity, that the best way to do it is to ascertain accurately what you have got to start with. The difficulty as usual is to do it, except over a very small area.

BAHRAICH, 7*th March* 1903. F. F. R. CHANNER.

Manual of Indian Timbers.

THE long expected revised edition of Mr. Gamble's *Manual of Indian Timbers*, available for sale is valued 18s. per volume. It means Rs.13-8-0, exclusive of postage, etc.

It is hardly necessary to point out that every native forest officer will wish to possess such a valuable book, but the price is prohibitive considering the emoluments of the native forest officers of the Madras Presidency.

I would respectfully suggest that Government will be pleased to arrange to have it sold at a reduced rate to forest officers whose salary is Rs. 200 per mensem or less, as was done in the case of some publications, such as Board's Standing Orders, Treatise on Family Medicine, etc.

SOUTH CANARA, 3*rd January* 1903. S. KUBHUSWAMY CHETTIER.

IV.-REVIEWS.

Forest Administration Report of the Punjab, 1901-02.

THE total area of all forests at the close of the year was 6,131,702 acres, of which 1,555,657 acres are reserves. The gradual assimilation of the plains forests, locally known as *rakhs*, by the Civil Department for cultivation steadily continues as irrigation schemes are extended, and the Punjab Government review states that "it is only a question of time before all the chief fuel preserves of the Forest Department in the Punjab plains will have been surrendered for colonisation." From the Lahore Division 16,971 acres were handed over for cultivation, and in the Shahpur Division 225,335 acres of reserves were disforested with a similar object in view, although for the present they are still shown as unclassed forests. Again, in the Montgomery Division a working-plan had been prepared and submitted to Government for sanction, but had to be abandoned, as orders were subsequently received that some of the forests included in the plan would be required for cultivation

There can be little doubt that the policy of converting these arid *rakh* lands into flourishing cultivations under irrigation is a sound one, but at the same time it is probable that it would be beneficial to the cultivator and country generally if a certain proportion of the areas were converted into irrigated plantations on the same lines as the Changa Manga Plantation. That the *rakh* lands support little timber may be seen from the figures given below with reference to the fuel fellings, which show that the outturn per acre varies from 10 cubic feet to about 350 cubic feet per acre. In comparison with this it may be mentioned that the Changa Manga Plantation, which was previously, before irrigation, a *rakh* of the Lahore type, yields under coppice-with-standards about 2500 cubic feet per acre.

Considerable progress has been made with working-plans, and there is little new work which now remains to be done. The only new plan of any great importance to be made is probably one for the Kangra forests, dealing with an area of 992 square miles, and a considerable amount of work on this plan has already been carried out. The work of the future will mainly consist in revising old plans as their time expires.

Under "Communications and Buildings" Rs 5959 and Rs. 16,168 respectively were spent on new work. The former figure represents the expenditure incurred on the construction of 73 miles of bridle-paths and 23 miles of inspection-paths, the work being confined to four divisions only, namely, Rawalpindi, Kangra, Kulu and Bashahr. The Chamba and Simla Hill Tracts Divisions together show an expenditure of Rs 10 only on new communications. In consideration of the favourable financial results of the Province, it would appear that more work could be done with advantage in this direction, as there must be considerable scope for the construction of good communications and buildings in the hill Divisions. It is to be regretted that the tramway at Changa Manga was not brought up to an efficient state of working, for the report states that the length of line does not extend to the compartments now being worked and many of the waggons are worn out.

The total number of forest offences was 4086, of which 1213 were prosecuted in the courts, 2688 were compounded and 185 were undetected. The greatest number of offences occurred in the Rawalpindi and Kangra Divisions, each having over a thousand cases. The punishments inflicted were usually fines or short imprisonments, but in the Rawalpindi Division one offender was fined Rs 50 and sentenced to 18 months' hard labour for assault on a forest guard and forcible rescue of cattle.

The forests were comparatively free from fires, the number of outbreaks being 246, burning an area of 12,291 acres, of which about half were specially protected. The expenditure incurred on fire-protection was Rs.5377 for an area of 553,846 acres, or about Rs.6 per square mile.

The year was unfavourable for cultural operations, owing to the failure of winter rains and the absence of snow on the hills. There was practically no deodar seed produced, and the deodar plantations suffered severely. In Chamba 45 acres, in Bashahr 41 acres and in Kulu 53 acres were planted up with deodar.

The cultivation of the Spanish chestnut is still fairly successful in Kulu and Bashahr. The object of experimenting with this species is to try and encourage villagers to take up its cultivation as a source of food-supply, and during the year 152 good graft plants were sent out from Europe and planted in Kulu, out of which 103 have survived.

The following statement gives a summary of all produce removed from the Government forests during the year :—

Agency by which removed.	Timber.	Fuel.	Bamboos.	Grass and grazing.	Minor produce.
	C ft. solid.	C. ft. solid.	Number	Value Rs.	Value Rs.
Government ...	1,180,640	4,222,705	944,754	144	27,760
Purchasers ...	919,784	1,054 522	30 065	147 064	14,788
Free-grants ...	15,950	112,096	...	1,278	..
Right-holders ...	1,322,925	33,223,011	120	293,704	47,026
Total ...	3,439,299	38,612,334	974,939	442,190	89,574

With regard to timber it may be noted that 942,119 cubic feet represents the amount of deodar removed, the balance being pine, fir and miscellaneous timber. The principal departmental fellings were in the Chamba, Kulu and Bashahr Divisions, where 2793, 2642 and 2234 deodar trees were felled respectively, under the Selection method.

The quantity of timber actually launched into the Chenab, Ravi, Beas and Sutlej rivers and the quantity caught and landed in the depôts is as follows :—

	Launched. c. ft.		Landed in depôts. c. ft.	
	Deodar.	Pine & others.	Deodar.	Pine & others.
Logs	327,434	87,260	132,252	78,567
Sleepers and scantlings ...	563,441	29,234	633,216	41,372
Ballies	2,256	...	11 969	2,850
Pieces	...	..	35,224	342
Total ...	893,131	116,494	811,661	126,131
	1 009,625		937,792.	

From these figures it will be seen that the quantity of timber landed in the depôts does not agree with the quantity launched, but this is not to be expected, as the timber often takes several years to reach the depôts. As an interesting example of the loss which occurs during transit by the rivers, the followings figures give the quantity of timber launched from the Chamba and Bashahr forests and the quantity received in the depôts for a period extending over 10 and 20 years respectively.

Deodar.

	CHAMBA, 1893—1902.				BASHAHR, 1883—1902.			
	Logs.		Scantlings.		Logs.		Scantlings.	
	No.	C. ft.	No.	. ft.	No.	C. ft.	No.	C. ft.
Launched ...	21,249	545,999	64,933	229,129	152,812	3,964,190	324,214	1,073,509
Received in depots ...	8,097	388,947	47,754	135,094	143,210	3,129,397	300,595	876,794
Loss in transit ...	3,152	157,052	17,179	94,035	9,602	834,793	23,619	196,715
Do. per annum ...	315	15,705	1,718	9,403	480	41,739	1,181	9,835
Do. per cent. ...		29°/o	...	59°/o	...	21°/o	...	18°/o

This shows an average loss from the Chamba forests of 315 logs and 1718 scantlings, or 25,109 cubic feet per annum, and from the Bashahr forests a loss of 480 logs and 1181 scantlings, or 51,574 cubic feet per annum. It is stated that this loss is not by any means all due to theft or accident, but is largely due to a shrinkage in volume during transport by water. Observations taken in Chamba by measurements of identified logs show that between the forests and the sale depôts a shrinkage in volume of 13 per cent takes place, while similar observations made in Bashahr show a shrinkage of 19 per cent. From the mean of these two figures we obtain the result that deodar logs during transit by water from the Chamba and Bashahr forests to the sale depôts lose on the average 15 per cent of their volume by shrinkage.

The loss in transit from all causes is shown by the figures in the above table to be 28 per cent for logs from both Chamba and Bashahr, and 59 per cent for scantlings from Chamba and 18 per cent. for scantlings from Bashahr.

The loss in converting deodar logs into scantlings in both the Chamba and Bashahr forests is 45 per cent.

The principal fuel operations are represented in the following table, which gives the outturn from the principal coppice fellings :—

Division.	Name of forest.	Area in acres.	Total outturn in. c. ft stacked.	Out-turn per acre in. c. ft. stacked.	
			ft.	ft.	
Montgomery	Rakha	4125	1,385,215	335	
Multan	Do.	3295	1,226,191	372	
Lahore	Changa Manga ...	...	1,948,620	...	
Do.	Shahdera ...	...	341,005	...	
			120,358		
Chenab	Kalachitta R. ...	950	669,528	127	
Rawalpindi ..	Phillour Plant. ...	27	60,400	2240	
Bashahr	Ludhiana ,, ...	17	49,200	2894	Felled with a view of giving up the land for cultivation.
Lahore	Rakha	44,490	423,390	10	

The report does not state the area felled at Changa Manga or in the Shahdera plantation. The difference in outturn from the natural *rakh* lands and the plantations is very marked.

1,974,000 cubic feet stacked of fuel were extracted from the Changa Manga Plantation and carried to the sale depôt, mostly by tramway, at a cost of annas 6-8 per 100 cubic feet stacked.

The manufacture of turpentine and colophony from the resin of *Pinus longifolia* in the Kangra Division continues a success and shows good financial results. During the season of 1901, 63,188 blazes yielded 6047 maunds of crude resin, or an average of 4 seers per blaze, the cost of harvesting and delivering being Rs.1-14-0 per maund. During the season of 1902 only 25,260 blazes were being worked, as there is a large balance of resin and colophony in stock. The work of the year is shown in the following statement :—

Kind.	Balance on the 1st July 1901.	Receipt during the year.	Total.	DISPOSALS DURING THE YEAR.				Balance on 30th June 1902.
				Distilled	Lost by all causes.	Sold.	Total.	
Crude resin (mds.) ..	3322	5581	8903	4505	87	343	4985	3918 mds.
Colophony (,,) ..	2189	3132	5321	...	247	2867	3114	2207 ,,
Turpentine (gals.) ...	1398	7081	8479	...	193	7677	7870	609 gals.

The total revenue realised during the year was Rs.28,559 and the working expenses Rs.16,159, giving a surplus of Rs.12,400. The following table is interesting, as it shows the financial results of the resin manufacture from the commencement of the undertaking up to 1st July 1902 :—

Financial year.	Capital expenditure.	Working expenses.	Revenue realised.	Surplus	Deficit	Total sum on which interest is chargeable.	Amount of interest at 4 per cent.	Value of stock on 1st July 1902.	
									Rs.
1899-1900 ...	8939	6835	3109	...	3726	12,665	506·60	Value of buildings and machinery...	9119
1900- 901 ...	6496	18,87	10,594	...	8279	27,440	1097·60		
1901-1902 and up to 1st July 19 2.	173	19,759	40,557	20,798	...	27,613	1104 52	Value of turpentine, resin, &c., on hand	23,435
Total ...	15,608	45,467	54,260	20,798	12,005	...	2708·72		32,554

This shows the actual profit up to date, minus interest charges, to be Rs.6084, whilst a sum of Rs.15,608 exists against the undertaking, which is, however, counterbalanced by the value of stock on hand, namely, Rs.32,554. It must be borne in mind however that the latter figure includes the value of turpentine, resin, etc., which has remained unsold.

Large quantities of timber are imported into the Punjab from foreign territory by river, chiefly from Kashmir, the States in the Simla neighbourhood, and from the country north of

Peshawar *viâ* the Kabul River, as will be seen from the following figures :—

	IMPORTS.		
	Deodar.	Pine and others.	Bamboo.
	C. ft. solid.	C. ft. solid.	Number.
Logs	545,359	139,984	
Sleepers	769,220	190 116	
Scantlings	886,194	474,621	
Miscellaneous	...	39,356	241,100
Total ...	2,200,773	844,077	241,100
	31,044,850		

By comparing these figures with those given in the summary of produce removed from the Government forests, it will be seen that the total imports are about equal to the total outturn from the Government forests, being 3,044,850 cubic feet and 3,439,299 cubic feet respectively, but it must be borne in mind that the latter figure includes a large quantity of timber removed by right holders and as free-grants, which is utilised more or less on the spot by villagers and can hardly be considered as competing in the open market. The timber which is really brought into the open market from Government forests is that removed by Government agency and by purchasers, which amounts to 2,100,424 cubic feet, which is considerably less than the timber brought into the open market from foreign territory. If deodar timber alone be considered, it will be seen that the outturn from Government forests is only 942,119 cubic feet as compared with 2,200,773 cubic feet imported, or considerably less than half. These figures are interesting as showing the keen competition with which the Government produce has to contend.

The financial results of the year are very favourable, showing a surplus of Rs. 5,71,677, which is more than a lakh in excess of the surplus of the previous year. The gross revenue realised was Rs. 15,05,952 and the expenditure Rs.9,34,275. The different heads under which the revenue was realised are as follows :—

	Rs.
Timber	7,56,914
Fuel	4,52,977
Bamboos	23,501
Minor produce	43,518
Grazing	1,49,172
Miscellaneous	79,870
Total ...	15,05,952

The Hazara Division was transferred to the North-West Frontier Province on the 8th November 1901.

Mr. C. T. Elliott, Conservator of the Punjab, retired under the 55-year rule on the 2nd March, 1902, and was succeeded by Mr. F. B. Bryant, the present Conservator of the Punjab, both of whom are to be congratulated on a successful year's work.

Forest Administration in the N.-W. Frontier Province during 1901-02.

THE forests of the Frontier Province are comprised in the former Hazara Division of the Punjab, and the Administration Report for the year contains little which calls for especial notice in these columns. Mr. A. V. Monro, Deputy Conservator of Forests, is in charge of the forests, and the exact procedure in connection with the forest administration of the Province has not yet been settled. There are roughly 234 square miles of reserved forest and 131 square miles of protected forest in charge of the Department, no alterations of any importance having taken place during the year.

Arrangements have been made to commence a detailed survey of the forests on the 4-inch scale in place of the mere boundary survey originally proposed, and this is undoubtedly a wise step, which will be of great value in connection with the future working of the forests.

No progress is being made at present with the preparation of working-plans, owing mainly to the fact that at present the supply of forest produce greatly exceeds the demand. A working-plan does exist for the Upper Kagan forests, and with regard to various other forests enumeration surveys have been made and statistics compiled in preparation for the time when, owing to increase in the demand, it will become advisable to place the other areas under a systematic plan.

Forest offences were fairly frequent: thirty cases were prosecuted and 455 compounded during the year; the most common offence was illicit grazing, which would appear to require to be more severely dealt with in future years.

Fire overran only 3538 acres of fire-protected forest, while 42,295 acres were successfully protected, the cost of the protective measures amounting to Rs.763, all of which was spent on the employment of fire guards.

Measures for the improvement of forest growth consisted mainly of sowing, transplanting and tending of seedlings. Much attention was given to felling and girdling pines over deodar, 15,000 acres of forest being systematically gone over for this purpose. It is still a matter of opinion whether this really does much good, and whether deodar if left alone will not succeed in struggling up through the not very dense cover given by blue pine.

Most of the major produce was removed by Selection fellings, but an attempt was made in the Khanpur forest to introduce the system of coppicing instead of restricting the removals to dry wood.

The financial results of the year's working are not very satisfactory. A deficit of Rs 8325 on a total expenditure of Rs.46,000 calls for rigid economy in the management of the forests, until an increased demand justifies the incurring of a larger expenditure on works of improvement.

Forest Administration Report of Burma for the year 1901-02.

IN their modern form Forest Administration Reports, which are cut down to bare statements of progress in matters of routine, do not offer such interesting material for reading as formerly.

The report on forest administration in Burma during the past year shows, however, that in spite of (from a revenue point of view) an exceptionally bad year, steady and strenuous advances were made in this young and promising province, which already contributes more than half of the surplus forest revenue of the whole of India, although customarily spoken of as hopelessly backward and slack compared with some of the "model" provinces of Northern India.

The constitution of the natural wealth of the country into permanent forest estates is a work which will not be completed for a long time, owing to the vast areas to deal with, and the necessarily gradual development of the country. During the year under report nearly a thousand square miles of forest were added to the reserved forests, making a total of 18,606 square miles altogether.

The hitches which occurred in the settlement of some of the new reserves may very well be accounted for, we think, by the fatally frequent transfers of Divisional Officers. No Forest Officer who has spent three or four years continuously in one division, and has pushed forward the preliminary work connected with the selection of new tracts for reservation and for their settlement, can be so devoid of any personal interest in the matter as to occasion the miscarriage of the settlement.

Demarcation and survey operations were carried out conformably with the extension of the areas under reservation and the practical requirements of the working of the forests. In the older part of the province new detailed surveys of nearly 100 square miles of reserves were made, and in Upper Burma the Forest Survey Department mapped about 875 square miles of reserved forest.

As regards working-plans, very little progress was made, except in the Pyinmana and Shwegyin divisions. The insufficiency of the number of qualified officers, and the constant changes that consequently take place, have seriously interfered with this work. Provided that a sufficient staff of officers is available, the Government has now drawn up a five years' programme, providing for eight working-plans parties, two in each circle. Good results should follow from this plan so long as the undermanning of the staff does not render it impracticable.

The results of fire-protection showed some improvement, though there is still a good deal to be desired in this respect.

In Burma the difficulties and hardships connected with fire-protection are considerably greater than in other provinces, but the results, even when every allowance has been made for this condition of things, cannot be considered as satisfactory.

We believe that Sir Frederick Fryer has hit the right nail on the head in attributing the backwardness of Burma in the matter of fire conservancy to want of sufficient personal supervision by superior officers.

In this connection a paragraph in the Annual Report of the Southern Circle, Upper Burma, is significant. It is there stated that a Deputy Conservator of considerable experience openly declares that fire-protection in teak forests is a mistake, and proposes to periodically fire his forests for several years in succession ! The observations on which this revolutionary doctrine is based are true enough, but it is hardly possible to believe that the temporary retardation of natural reproduction, which often results from fire-protection, is not more than compensated for by the advantages obtained by the exclusion of fire from the forests, not only for the soil and vegetation generally, but also for the young teak growth itself.

Under the heading of natural reproduction some interesting information is given with regard to experiments which are being carried out in parts of Bhamo and Katha, where natural reproduction offers serious difficulties.

In Bhamo the simple expedients of fire-protection and cutting back, and in Katha the equally simple operation of raising the cover and clearing the ground under old teak seed-bearers, have been resorted to.

In Pyinmana the Conservator reports that the Divisional Officer absolutely refuses to extend teak plantations in spite of all orders and working-plans which prescribe them.

The planting of teak *taungyas* requires to be done with discretion, and only in places suitable for it, but for the last thirty years the greatest success has attended the extension of teak *taungyas* in Burma, and the Lieutenant-Governor's regret that the present generation of Forest Officers in parts of the province are disinclined to make any advance in this important work is easily understood.

A single paragraph in the report disposes of the forest garden and plantations at Maymyo. Further details of this interesting work would be worth recording, and it is hoped that now that the ground is to be systematically planted, more information will in future be given with regard to the measures taken for stocking the plantations and the success that they obtain.

The year under report was a bad one for floating, and the quantity of timber extracted was comparatively small in consequence.

Over three million cubic feet of teak were extracted departmentally, and over 5¼ million feet by lessees and purchasers.

Including free grants, the outturn of the year was 8½ million cubic feet, and fourteen million cubic feet of other kinds of timber. The average price realized at Government sales of teak during the year was Rs.61 per ton, and the average price per ton of teak timber exported from the country was nearly Rs.86.

Under the heading of minor produce it is stated that the forests of *Ficus elastica* in unadministered tracts in the extreme north of the province are being rapidly devastated, and that no effective measures can be taken to protect them. The revenue from rubber is 83 per cent less than it was last year, and that again was 60 per cent. less than that of the year before.

The financial results of the year's working show Rs.59,51,334 and Rs.28,20,311 as the receipts and charges respectively.

The surplus is therefore Rs.31,31,023, or 53 per cent. of the gross revenue.

The surplus for the previous year was over 50½ lakhs, and the decrease in revenue is explained by an abnormally bad floating season, resulting in a decrease of over 5 lakhs to the revenue derived from departmental workings, and of nearly 11 lakhs to revenue paid by lessees.

We are glad to notice in conclusion that the constant trouble caused by the collection of botanical specimens and economic products has been officially recognised, and that it is proposed to detail a special officer for this work. This is certainly a step in the right direction.

V.—SHIKAR AND TRAVEL.

The Indian Pheasants and their Allies.

BY F. FINN, B.A., F.Z.S.

(Continued from page 122.)

CHAPTER VI.

PARTRIDGES.

WITH the fire-back discussed in the last chapter the series of pheasants comes to an end, and we enter on the consideration of the various partridges. These are, as was said in the Introduction, short-tailed birds, usually much smaller than pheasants. They fall into several very natural generic groups, some containing only one Indian species each. There is some difficulty for the beginner in making them out, for the males are generally plain and much like the females, and do not present those striking characteristics which make the various cock pheasants referable to their proper genera at once. But with a little trouble partridges are not more difficult to correctly identify than are hen pheasants.

Taking as partridges all the short-tailed game birds with a wing over five inches long — under that size they rank as quails — we find that they may again be subdivided, as were the pheasants, by the length of tail. All partridges have rather short tails, but in some the tail is *very* short and not a very noticeable feature.

Among the longer-tailed partridges, in which the tail is more than half the length of the closed wing, we find the Ramchukors or Snow-cocks, the Snow-partridge, the Bamboo-partridge, the Spur-fowls, the Chukor, the Tibetan partridge, and the Francolins. Of these:—

The *Ramchukors* (two species) are easily distinguished by their great size, being a foot-and-a-half long, and bulkier than an ordinary fowl. No other partridge exceeds fifteen inches.

The *Snow-partridge* is at once recognisable by having the front of the shanks feathered half-way down, the only other Indian game bird with this peculiarity being the very easily distinguishable Monauls.

The *Bamboo-partridge* has a particularly long tail, only about an inch shorter than the wing. [By some slip or other I said in the Introduction that this partridge's tail was *longer* than the wing; but this is of course not the case.]

The *Spur-fowls* (three species) have equally long tails, but their eyes are surrounded by a bare skin, unlike those of the Bamboo-partridges.

The *Chukor* is easily recognisable by its plain drab upper surface.

The *Tibetan partridge* by the black patch in the middle of its breast.

The *Francolins* (five species) include all the other medium-tailed partridges. They may be known by having no striking points, so to speak; no particular length of tail, no bare skin round the eye or feathering on the shanks; their backs are never plain drab, nor have they a conspicuous black patch on the breast.

To the section of partridges with *very* short tails belong the hill partridges, the Green-legged partridge, the Red Wood-partridge, the Crested partridge and the Seesee, distinguished as follows:—

The *Hill partridges* (six species) by their remarkably long nails.

The *Green-legged partridge* by a peculiar patch of white downy feathers under the wing, just behind the armpit.

The *Red Wood-partridge* by being mostly of a chestnut colour.

The *Crested partridge* by the male being dark blue and the female green.

The *Seesee* by its sandy colour and pale yellow legs.

In the present chapter I propose to deal briefly with the Alpine Ramchukors and Snow-partridge, the Chukor, and the desert-haunting Seesee. These rarely go into cover, and so do not really concern Forest Officers in the ordinary way. But for the sake of completeness it is as well to include them; besides, some of my readers may go shooting in their treeless haunts when on leave, and then make their acquaintance.

The Ramchukors or Snow-cocks are very large grey birds, living on the mountains above the forest-level, and feeding on grass chiefly—there is not much else to eat where they are found. Two species are found with us. The cocks and hens are alike in plumage, but the former alone are spurred.

THE HIMALAYAN RAMCHUKOR.

Tetraogallus himalayensis, Blanford, Faun. Brit. Ind., Birds, Vol. IV, p. 143.

Native names:—*Kullu*, *Lupu*, *Baera*, in Western Nepaul; *Huinwal* in Kumaun; *Jermonal*, in the hills north of Mussoorie; *Leepin*, Kulu; *Galound* in Chamba; *Gourkagu* or *Kubuk*, in Kashmir; *Kabk-i-dara* in Afghanistan. The name *Ramchukor* is, I believe, used in Gilgit. It is certainly the best one for these birds, which are really gigantic relatives of the Chukor. The European names of Snow-cock and Snow-pheasant are unmeaning, as the bird is obviously a big partridge, not a pheasant or jungle-fowl.

The general colour of this bird is grizzled grey with some chestnut markings; the throat is white with a chestnut border and the breast white with some black bars, the pinion quills are white with broad black tips. The bill is horn colour, the feet orange, and the eyes dark, with a patch of bare yellow skin behind them. The hen is easily distinguishable from the cock by her much smaller size; she is about two inches under two feet long, while he exceeds that length by about two inches. Young birds show some brown mottling on the forehead which is not present in old ones.

This noble partridge is found from Afghanistan and Central Asia all along the Himalayas as far Kumaon. According to season it is found at from 18,000 to 7000 feet elevation, keeping usually in flocks, which frequent open rocky ground. It breeds high up, from May to July, usually laying five eggs, drab with reddish brown spots, and reaching nearly three inches in length. The golden eagle appears to spend a good deal of its time in trying to catch these birds, without very much success; for they are very wideawake, and the human hunter finds a rifle the best weapon with which to come to terms with them. And then when they are brought to bag they are not good eating according to European tastes, although natives are glad enough to get them. The call of this bird is a whistle, which it keeps uttering all the while it flies.

THE TIBETAN RAMCHUKOR.

Tetraogallus tibetanus, Blanford, Faun. Brit. Ind., Birds, Vol. IV, page 144.

Native names:— *Hrak-pa*, Bhutias in Sikkim.

This bird bears a general resemblance to the last, but is considerably smaller; it has no chestnut about the neck, and the breast is devoid of black markings, but crossed by a broad grey band. The most striking differences, however, are that the underparts are streaked with black and white instead of being grey, and that the pinion quills are brown with white tips. The cock and hen do not differ much in size in this species, and even the former is smaller than the hen of the Himalayan bird. The cock's bill and legs are red, and there is a red skin round the dark eyes. The hen's bill, however, is of a greenish colour, though she appears not to differ otherwise in colour. Young birds, however, have only the throat white, the breast being grizzled with dark-grey and buff.

This species is properly a Tibetan bird, but in our territory it has been found in Ladak, Spiti, Kumaun and Sikkim, always at a very high elevation, being an even more alpine bird than the last. All that is known about its breeding is that its egg is like that of the Himalayan species, but smaller. It appears to be a much better bird for the table.

THE SNOW-PARTRIDGE.

Lerwa nivicola, Blanford, Faun. Brit. Ind , Birds, Vol. IV, page 145.

Native names:—*Lerwa*, Bhutia; *Janguria*, Kumaun; *Quoirmonal*, Garhwal; *Golabi*, *Bhair*, *Ter Titar*, Bashaur, etc.; *Barf ka Titar*, Kulu; *Biju* Chamba.

This is a much smaller bird than the Ramchukors, and in appearance and habits much recalls a Ptarmigan. The cock and hen are alike in plumage, but the former is distinguished by possessing spurs.

The head, neck and upper plumage generally are closely barred with black and white, the latter colour running into buff in places; the under parts are mostly of a dark chestnut. This rich plumage is well set off by the red beak and legs. The eyes are dark. Young birds are less distinctly barred and are mottled with black below. The length is about fifteen inches, with a wing of nearly eight, tail four-and-a-half, bill nearly one, and shank half an inch longer.

The Snow-partridge inhabits the Himalayas from Kashmir to Sikkim, and extends to Moupin and Western China. It is locally distributed with us, and is usually found at very high elevations, close up to the snow, among stones and stunted herbage. Its usual elevation is about 11,000 feet, though in winter it may come down as low as 7000. It goes in pairs in the breeding season, and its chicks have been found late in June. Later on it is found in coveys, and affords excellent sport; it is also remarkably good to eat. But as it is commonly found on the same ground as Burrhel and Tahr, it is usually neglected by sportsmen for the nobler game.

THE TIBETAN PARTRIDGE.

Perdix hodgsoniœ, Blanford, Faun. Brit Ind., Birds, Vol. IV, page 142.

Native names :—*Sakpha*, Tibetan.

This partridge bears a strong resemblance to the common partridge at home, and is indeed nearly related to it: the cock and hen are alike, and neither of them possesses spurs. The plumage is an intricate mixture of buff, black and chestnut, with the throat white and neck chestnut; the underparts are barred with black, which colour forms a patch in the centre, and there is a black patch on each cheek; the bill and legs are of a dirty green, and there is some reddish skin round the eye.

This bird is about a foot long, with a wing of six inches.

The species is properly speaking a native of Tibet, but it has strayed into our territories, one having been got by Mr. Wilson in the Bhagirathi valley, when shooting chukor in the autumn of 1841. It appears to be a bird of very high elevations. Its eggs have been taken in Tibet in July; they were ten in number, and of a pale drab tint without spots.

THE CHUKOR.

Caccabis chucar, Blanford, Faun. Brit. Ind., Birds, Vol. IV, p 131.

Native names:—*Chukar*, Hind; *Kabk*, P.; *Kau-kau*, Kashmir; *Chukru*, Chamba.

The chukor is one of the group of red-legged partridges to which the well-known "French partridge" (*Caccabis rufa*) belongs, and much resembles that bird. The cock and hen are alike in plumage, but the former may be distinguished by having a knob or blunt spur on each leg.

The plumage above and on the breast is of a plain grey without any markings, with a tinge of reddish in places and sometimes verging on olive brown; the throat is white or buff, surrounded by a black band. The lower parts below the breast are buff, and the flanks very beautifully banded vertically with grey, buff, black and chestnut. The bill, legs and eyelids are red, and the eyes themselves dark or orange.

The cock, which is a little larger then the hen, is about fifteen inches long, with the wing six inches and-a-half, tail just over four, shank nearly two, and bill just over one.

The chukor has a very wide range, from Greece to China. It is a lover of open hilly ground, and with us is found on the Himalayas, in the hilly parts of the Punjab and in the higher hills of Sind west of the Indus. According to the country it inhabits, it is found from the sea-level up to 12.000 feet, and in Tibet even to 16,000. Himalayan birds are darker and browner in in tint, but in Ladak, the Western Punjab, and Sind—in dry open tracts, in fact—are paler and greyer. The birds haunt open hill-sides among grass and scattered bushes, but may also be found in more or less wooded country and in cultivation. In winter they go in coveys or even flocks, but in the breeding season in pairs. The said season is from April to August, varying according to the elevation; for birds at high levels of course breed later. The eggs are up to a dozen, cream-colour with brown or lilac spots. The chukor is a noisy bird, and its two syllabled note has given origin to its name. It is a fairly good sporting bird, but not so good to eat as some other partridges. The ancient Greeks, judging from a passage in Xenophon, appear to have been in the habit of riding it down, a sport which is still practised in Yarkand. Chasing partridges to kill them with a whip does not sound very sportsmanlike, but the awful ground over which the flying covey is pursued requires the sure-footed Yarkand pony to negotiate it properly, and thus introduces a pleasing element of uncertainty which redeems the sport from the imputation of poaching.

The chukor is a good bird for introduction abroad where partridges are required, as its adaptable constitution makes it bear captivity well. It was tried in New Zealand, and bade fair to succeed, but the birds were not sufficiently protected, and were all shot off almost at once. It would hardly be worth while to turn it out in England, as we have already the very similar red-legged partridge there. Indeed, I have been asked whether the two were not identical. But the red-leg or "Frenchman" at home is a brown-backed bird, not greyish, and has a number of black spots bordering the black necklace outside, and thus is easily distinguishable from the chukor.

The Seesee.

Ammoperdix bonhami, Blanford, Faun. Brit. Ind., Birds, Vol. IV, p. 133.

Native names:—*Sisi*, Punjab and Sind; *Tihu*, P.

This is a short-tailed little desert partridge, with plumage beautifully adapted to conceal it in its natural haunts. The cock and hen differ somewhat in colour, but neither has any spurs.

The cock is of a grizzled sandy hue above, with a grey head and fore-neck, and the under parts below this pinky buff. There is a black streak along each side of the head with a white one under it, and the flanks streaked with black and chestnut.

The hen has no black and white markings on the head nor chestnut on the flanks; the lower plumage is barred with brown and buff.

The bill is orange, the eyes yellow or brown, and the legs yellow. The cock, which is rather larger than the hen, is ten inches long, with a wing of five-and-a-half. The Seesee inhabits hilly deserts, avoiding cover, though it may be found on grassy slopes. In India it inhabits the Salt Range and Khariar Hills in the Punjab, Hazara, and all the Sind and Punjab ranges west of the Indus It is also found in Baluchistan, Afghanistan and Persia; and has been reported from Aden.

It has a soft clear double note, recalling its name; and is not usually gregarious, though small coveys may be found in winter.

The breeding season is from April to June, and as with the chukor, the eggs may be as many as twelve in number, but they are creamy-white in colour without any spots. As an article of food the Seesee varies somewhat; it is not much of a runner, and when it wants to conceal itself has only to sit still, its plumage being its best safeguard against detection by its enemies.

VI.–EXTRACTS, NOTES AND QUERIES.

Fungus Notes.*

INFECTION EXPERIMENTS WITH UREDINEÆ.—Tubœuf has infected plants of *Epilobium angustifolium* successfully with *æcidiospores* of the fir. The spores of *Cæoma Abietis pectinatæ* grew on *Salix capræa.* The witches broom æcidium of the fir had been proved by Fischer to be connected with the fungus on *Stellaria nemorum.* Tubœuf injected also *Stellaria media* and *Cerastium semi-decandrum* with the same fungus, and in each case reproduced another stage in the life-history of the parasite.

DEMATOPHORA IN FRUIT.—Ed. Prillieux has discovered the ascomycetous fruit of the fungus *Dematophora necatrix*, which attacks and destroys the roots of fruit trees, but of which the perfect form has not hitherto been known. Some roots infested by the fungus were kept in a suitably moist condition for several years, and the mature perithecia were at last produced. Careful examination proved them to belong to the genus *Rosellinia*, and the author has given them the specific name *necatrix.* When Prof. Hartig first described *Dematophora*, he was impressed by the resemblance of the hyphæ to those of species of *Rosellinia*, and he was then of opinion that the mature fruit would be one of that genus. The perethicia are globose, brown, about 1·5mm. in diameter. The spores are very dark coloured when mature.

EXPERIMENTS WITH RUSTS.—Klebahn continues in the *Zeit für Pflanzenk*, XII, the account of his various culture experiments with the rusts of conifers. He has established satisfactorily the connection between various life-stages of the fungi. He also made successful experiments with *Æcidium Pastinaceæ, Puccinia Angelicæ-Bistortæ,* the rusts of *Ribes* and *Carex,* and the *Puccinias* of various grasses.

GERMINATION OF BASIDIOSPORES.—Margaret C. Ferguson has studied the conditions most favourable to the germination of spores of various forms of Basidiomycetes, more especially those of *Agaricus campestris.* In Bulletin No. 26, U. S. Department of Agriculture, she gives an account of the methods employed, the different media used, the conditions of temperature, etc. It was found that the presence of a bit of the mycelium of *Agaricus campestris* made possible the germination of all the spores in the culture. The writer closes with a historical account of previous work.

SILVER LEAF DISEASE.—J. Percival finds that this disease of *Prunus* is due to a fungus in the roots. It is characterised by a peculiar grey appearance in the leaves, though no fungus is present in the leaves, nor, as a rule, in the stem or branches. In all the cases of disease examined, the tissues of the root were found to be permeated by fine hyphæ, and in one case the fruiting bodies of *Stereum purpureum* were found on a branch of a tree affected with silver-leaf. On inoculating healthy trees with *stereum* the disease was again produced. The author is of opinion that the fungus secretes an oxidase, which in a short time pervades the branches and leaves, and causes by its action the silvery look on the leaves. The affected trees produce little or no fruit, and are always sickly and unprofitable.

---

* From the Journal of the Royal Microscopical Society for December 19 2.

DISEASES OF PLANTS —A paper on larch and spruce fir canker by G. Massie in the Journal, Board of Agriculture, IX, gives the results of the observations and experiments of many years. He discusses the various stages of the diseases and the probable manner of infection. He considers them to be entirely wound parasites, all infection experiments having failed on uninjured bark. The larch canker is caused by *Dasyscypha calycina*; the fungus causing the spruce disease is *D. resinaria*. The latter is frequently enabled to enter the tissues of the host through wounds made by a small parasitic fungus *Exosporium* sp. Methods of prevention and cure are suggested. The paper is well illustrated.

CANKER IN APPLE TREES.—In Bulletin No. 70, Univ. of Ill., Agr. Station. Hasselbring has discussed the various diseases affecting the bark of apple trees popularly described as canker. The most common instance of the disease in Illinois, U.S., is due to a fungous parasite *Nummularia discreta*. It is a wound parasite, and gains entrance to the tree through openings in the bark caused by pruning or by accidental injuries. It produces extended blackened areas, and the bark cracks and finally crumbles away. Badly diseased limbs should be cut and burned, and wounds in the tree should be painted with some antiseptic solution.

ECONOMIC FUNGI.—There is a considerable number of the smaller fungi that are used in the manufacture of various articles of commerce, and Prof. Wehner has given an account of some of the most important in *Zeitschr. angew. Mikro.* VIII, 1902. He cites some of the forms of yeast used in brewing, in the East, as well as *Aspergillus Oryzæ*, which is used in Japan in the making of Soja sauce. *Aspergillus niger* is used for the production of oxalic acid; *Citromyces pfefferianus* is employed in the manufacture of citric acid. He takes note also of *Penicillium glaucum*, which is mixed with the cheese curds to form the green veins of Roquefort and Gorgonzola. The Chinese make a red colouring matter from *Monascus purpureus*, but the method employed remains a secret. The author also mentions some other fungi which are used as colouring agents.

FUNGAL DISEASE IN HORSES.—J. de Haan has investigated a disease of horses in Batavia. He found that it was caused by the presence of a fungus in the skin, more especially in the mucous membrane of the mouth, lip and nose. In the later stages the bones of the head are also attacked. An examination showed the presence of yellowish-grey lumps of a somewhat hard formation, varying in size from the head of a pin to an egg; and traversed in all directions by a well-developed mycelium, which also penetrated the surrounding tissue. The writer has named the fungus *Hyphomycosis destruens equi*, and he is of opinion that it is the sole origin of the malady. Infection comes from the food, and the fungus gains entrance to the tissue through some small wound in the mucous membrane caused by the grasses, etc., that compose the fodder. In the external skin the fungus would similarly find entrance through some abrasion. De Haan made cultures of the fungus. and with these he re-infected the mouth and neck of healthy horses. The experiment was unsuccessful.

WEATHER AND PARASITIC FUNGI.—Karl Sago has collected facts and statistics on the appearance and disappearance during certain seasons of various fungal diseases, especially those that occur on the vine. He finds that the direction and force of the wind has a great influence on the spread of disease, and that hail showers render the host plant more liable to attack. More work is required to determine the weather conditions that affect special forms *Alternaria solani* spread with great rapidity in dry weather that supervened on a rainy season. During a warm damp summer it was noticed that there was very little disease.

Analysis of Soils in Sal Forests.

Analysis of Samples of Soils from the Dholkot (Sal) Forest in the Dehra Dun District.

Sample No.	Total nitrogen.	Available phosphoric acid.	Total phosphoric acid.	Calcium carbonate.
Sample 1. Surface soil from an open glade surrounded by seed bearing sal trees, but without any reproduction.	0·043	0·026	0·105	0·187
Sample 2. Surface soil from a similar locality, but with young growth of medium quality.	0·101	0·028	0·112	0·233
Sample 3. Surface soil from under a very thick growth of young sal trees about 25ft. high.	0·152	0·048	0·144	[illegible]

Dr. Leather, who made the analysis in 1897, remarks that the soil from sample 3 is the richest and No. 1 the poorest in plant food, which probably explains the absence of reproduction in the latter.

VII.—TIMBER AND PRODUCE TRADE.

Churchill and Sim's Circular.

4th March 1903.

East Indian Teak.—The deliveries in February consist of 999 loads against 1617 loads in February last year, and for the first two months of 1903 they are 1566 loads against 2670 loads for the same two months of 1902. The stock remains at about the level of last month, being the smallest held here for some years past, and the additions to it are of a miscellaneous character from Java, etc., good enough in themselves, but rather foreign to the minds of consumers. There is still no prospect of any normal supply, and prices remain without change.

Rosewood, East India.—The demand is limited to prime logs of large dimensions, and no other sorts should be shipped.

Satinwood, East India.—The stock in first hands is quite sufficient for present requirements, as the demand is not active and sales are only effected occasionally.

Ebony, East India.—Sizeable logs would sell well.

PRICE CURRENT.

Indian teak, logs, per load	...	£10 10s. to £18 10s.
„ „ planks „	...	£15 10s. to £20.
Rosewood, per ton ..	...	£8 to £11
Satinwood, per s.ft. ...	...	6*d*. to 8*d*.
Ebony, per ton ...	...	£9 to £12

Denny, Mott and Dickson, Limited.

WOOD MARKET REPORT.

London, 3rd March 1903.

Teak.—The landings in the docks in London during February consisted of 763 loads of logs and 421 loads of planks and scantlings, or a total of 1184 loads, as against 2110 loads for the corresponding month of last year. The deliveries into consumption were 515 loads of logs and 363 loads of planks and scantlings—together 878 loads, as against 1359 loads in February, 1902.

The dock stocks at date analyse as follows:—

	5413	loads of logs, as against	8727	loads at the same date last year.
	2693	„ planks „	3776	„ „ „
	—	„ blocks „	—	„ „ „
Total	8,106	loads „	12,503	loads „ „

The above arrivals of logs and planks, although very inadequate, have been a welcome addition to the rapidly dwindling stocks. Prices for all descriptions of teak again advanced during February, and consumers, who have held off buying in hope of some reduction in price, have suffered. The facts of the position are so inexorable, that consumers who even now promptly cover their irreducible requirements for all this year will be only acting prudently. It is, however, much to be regretted that the present indisputably high cost of teak is surely, if slowly, causing it to be displaced wherever possible by other material; and this lost ground will not easily be made up, should the supplies again become sufficient in ensuing seasons to make shippers eager, rather than reluctant, sellers as is now the case.

Business was fairly brisk during February in respect to forward contracts where, as in the case of Canadian woods, the supplies at the shipping ports are known to be small. Where, however, as in the case of Baltic woods, the supply is likely to be sufficient for the demand, higher prices are stoutly resisted, and business is much hampered. Home stocks are moving off regularly, but consumers are cautious and do not care to commit themselves further than their actual necessities.

Market Rates for Products.

TROPICAL AGRICULTURIST.

2nd March 1903.

Cardamoms	...	.. per lb.	1s. 6*d*. to 1s. 10*d*.
Croton seeds	...	... ,, cwt	15s to 25s.
Cutch	...	... ,, ,,	25s. to 30s.
Gum Arabic	...	... ,, ,,	15s. to 25s.
Do. Kino	...	.. ,, lb.	4*d*. to 5*d*
India-rubber,	Assam	.. ,, ,,	2s to 3s.
Do.	Burma	... ,, ,,	2s. to [illegible]
Myrobalans,	Madras	... ,, cwt.	5s. to 6s. Nom.
Do.	Bombay	... ,, ,,	4s. to 7s. 6d.
Do.	Jubbulpore	... ,, ,,	4s to [illegible] 6d.
Do.	Bengal	... ,, ,,	3s. 6d. [illegible] Nom.
Nux Vomica,		... ,, ,,	7s. [illegible]
Oil. Lemon-grass	...	.. ,, lb.	5d. to 5½d.
Orchella weed	...	... ,, cwt.	10s. to [illegible] 6d.
Sandalwood, logs	...	... ,, ton	£15 to [illegible]
Do.	Chips ...	... ,, ,,	£4 to £8.
Sapanwood	...	... ,, ,,	£5 to £8 10s.
Seedlac	...	... ,, cwt.	117s. 6*d*. to 120s.
Tamarinds,	Calcutta	[illegible] ,,	8s. to 10s.
Do.	Madras ...	[illegible] ,,	[illegible] 6*d*. to [illegible]

THE

INDIAN FORESTER.

Vol XXIX] June 1903 [No. 6.

Tour of the English Arboricultural Society in the North of France, August 1902.

THE English Arboricultural Society, which was started 21 years ago, now numbers about 600 members, and comprises numerous important landed proprietors and their agents or foresters, professors of various colleges, and many other persons of importance

The headquarters of the Society are at Hayden Bridge, in Northumberland, where the Honorary Secretary, Mr J. Davidson, resides, and who is also the manager of the confiscated estates of the Earl of Derwentwater, who came to grief in the great Jacobite Rebellion of 1745, and whose estates were then made over for the maintenance of the Greenwich Hospital for old soldiers.

The object of the Society is to collect and stimulate the application of the knowledge of a certain class of forestry, specially applicable to the management of the great landed estates in England

With this object in view a general conference is held once in the year, when the accounts are presented and all important matters discussed; the tours for the succeeding year are also arranged, and the subject for essays, etc., decided upon.

The Society is supported by an annual subscription from each member, which goes to pay the Secretary, defray the cost of publishing the Transactions, which appear in the form of a book once in the year, and contains an interesting record of the Society's proceedings, notes on forestry, essays, etc.

Last year the Society having reached its majority of 21 years it was decided to present a suitable testimonial to Mr. Davidson, the Honorary Secretary, and to celebrate the event by a tour to some of the northern French forests.

A general meeting was therefore held in London on the 18th of August, on which occasion a handsome testimonial, valued at £120, was presented to Mr. Davidson, and Mr. George Marshall was elected as President of the Society *vice* Dr. Somerville, resigned.

On the following morning about 60 members of the Society started *viâ* Folkestone and Boulogne for France, where we were met by Mr. Fisher on his return from his annual tour with the Cooper's Hill students. The journey was a pleasant one, and the North of France, with its carefully cultivated fields, interspersed with occasional clumps of woods, looked picturesque and prosperous.

After an interesting run, part of which was through the Government forest, we duly arrived at the town of Compiègne situated on the Oise, about 50 miles north of Paris, and soon settled down for the night at the Hotel de la Clôche.

The next morning we proceeded by train to Villers Cotterêts, in the neighbourhood of which is situated the important Government forest of Retz.

The town of Villers Cotterêts is also the place which for many years contained an important Secondary Forest School for the training of the subordinate establishment of the Forest Department, but this has now been abandoned for other more suitable arrangements made elsewhere.

The morning of our visit was devoted to an inspection of the large timber yards and saw mills of Monsieur Carpentier, who is one of the most important timber merchants in the North of France.

At this yard we saw a large quantity of fine timber, principally oak, ash, beech, spruce, Scotch fir, etc., in logs and sawn scantlings and specially suited for railway waggon construction, house building and railway sleepers.

We found the sawmills of M. Carpentier to comprise all the most important kinds of modern saws, etc., for the most expeditious and economical conversion of timber.

About 100 workmen are employed at this establishment, and it was most interesting to note the energetic and careful manner in which the men handled the timber under the dangerous teeth of the rapidly moving circular and hand saws, and few accidents are said to occur.

One important and interesting branch of wood industry we saw here consisting in the manufacture of the soles of wooden shoes from beech timber.

The rough blocks of wood, after passing through the hands of numerous workmen and various machines, were being turned out all ready for having their leather uppers attached in a most expeditious manner.

We were informed that this establishment manufactures about 400,000 pairs of wooden soles annually, and that they are extensively used, even by the better classes of peasantry, during the winter months, and are said to be found much more suitable and cheaper than leather-soled boots for farm work.

The commoner kind of wooden shoes called *sabots* are cut out from one block of wood, no leather being required. These are generally manufactured in the forest and in minor establishments situated close at hand, and, though decidedly clumsy, are cheap and serviceable, especially for rough farm work during the winter.

After completing our inspection of the various interesting details of this establishment, we next proceeded to the sleeper depôt of the Chemin de fer du Nord.

At this depôt we found that the principal broad gauge sleepers used on this railway consist of creosoted oak and beech, and larch sleepers, which are so much appreciated on English and Scotch lines, are not much in request.

Here we were shown the latest and most improved method of creosoting oak and beech sleepers, after which operation the former are said to last from 20 or 25 years and the latter from 13 to 17.

We observed that considerable latitude is allowed in the dimensions of the sleepers on this line, though the average scantling is about the same as Indian broad gauge sleepers.

At least this is the case as far as four-cornered sleepers are concerned, for I noticed that many semi-circular and pentagonal sleepers were also used.

We noticed what is said to be a good plan for preventing the splitting of sleepers at their extremities, and which consists in driving into their ends an S shaped piece of hoop-wire about 5 inches long, 1 inch broad and ⅛ of an inch thick.

These hooks are sharpened down to a fine edge on one side and are then driven into the timber at each end of the sleeper.

We also saw a good plan for recording the year when the sleepers are laid down, by means of a zinc nail 2½ inches long with a square head, on which the year is stamped, and which seems to be a much better plan than the old branding or stamping arrangement.

We next proceeded to inspect some of the most interesting parts of the forest of Retz, situated on the river Aisne, a tributary of the Seine, and extending on three sides of the town of Villers Cotterêts.

I may here state that the following notes on the French forests visited have been mainly obtained from information kindly supplied to the members of the Society by Mr. Fisher, and from conversations with the local forest officers.

The average elevation of the forest of Retz is about 500 feet, and the climate is considered temperate and very suitable for the growth of broad-leaved species, such as oak, beech, hornbeam, etc.

The geological formation consists of Tertiary limestone, above which are found beds of sand in which large Sarcen stones are found, and which are much used for street cobbles in the neighbouring towns.

The forest soil consists of sandy loam about 20 inches deep, lying on the top of the sand, and which, except on the higher ridges, is on the whole very suitable for forest growth.

The area of the forest is 32,550 acres. It is sub-divided into 15 working circles of 2200 acres each, and each working circle is divided into five periodic blocks, each of which is regenerated in 30 years, the revolution of the whole forest being 150 years.

This forest formerly produced very fine oaks, which were extensively used for the construction of the French navy, and from the year 1672 up to 1830 it was treated on what is called the system of "Tire and Aire" with a few acres under coppice.

The method of treatment called "Tire and Aire" consisted in a kind of clear-cutting system, eight oaks or beeches being left per acre with the object of sowing up the clearings.

No thinnings were made, and under this treatment the beech were found to increase and the oak diminished.

From 1830 the forest began to be treated on the Compartment method, but it was not till the year 1857 that a regular working-plan was drawn up, which has worked very well, but is now being revised.

The forest of Retz is much subject to damage from strong westerly gales, on the occurrence of which the reserved trees in the coupes suffer considerably. Much damage has also been caused to the young plants by rabbits, and special arrangements have to be made to keep them down and to protect the young growth by means of wire netting, etc.

There are also a good many red deer or European Sambur in this forest, which do a good deal of damage to the surrounding crops, for which the lessees of the hunting have to pay compensation under the terms of their leases.

The stags are hunted by means of dogs and horsemen, and this forest during the winter season forms one of the principal "rendezvous" of the hunting fraternity of Paris, the numerous roads rendering access to most parts of the forest fairly easy.

This forest forms part of the conservatorship of Amiens, and is under the direct charge of an Inspector, the forest being further sub-divided into two cantonments or ranges under a Sub-Inspector or Ranger.

Under these officers there are six brigadiers or Deputy Rangers and 21 forest guards During certain seasons each forest guard is allowed 20 labourers, who work on the repairing of roads, plantations, etc.

The forest is managed on the Shelter Wood Compartment system, having a rotation of 150 years.

Preparatory seed-fellings are commenced in the second oldest blocks, *i.e.*, those containing trees from 91 to 120 years, or on an average where the trees are about 110 years old, so that 40 years are nominally allowed for the completion of the three regular sowing coupes.

We were, however, told that the condition of soil, climate, etc., are so favourable in this forest that nearly always complete regeneration actually takes place in 20 or 25 years.

The principal species of trees cultivated are beech, oak and hornbeam, and the method of marking the trees for felling is practically the same as that now followed in India, but the volume of the trees to be felled is always calculated in a most careful manner and based on thoroughly reliable data.

At the annual sales, which take place in September, the trees are sold by Dutch auction, the upset price having been previously arranged at a certain per cent above the sale price and the auctioneer calling down the price till the would-be purchaser cries out, "I take."

The merchants are allowed 18 months for the cutting and removal of the main fellings and 12 months for the removal of the thinnings.

In the first seed-felling about one-third of the trees are removed, the oaks being of course preferred as reserve trees.

It is to be noted that throughout the forest there are still reminiscences of the old system of "Tire and Aire" to be seen, in the form of many huge old beech standards, many of which are now too old to give seed, so are being removed as promptly as possible.

Notwithstanding all precautions bare spots in the coupes occasionally occur, and soon become thickly covered with brambles, sallows, birch and aspen, so that clearing and planting up with 5-foot oak plants—about 400 being used to the acre—has to be resorted to.

The next operation is the cleaning of the young woods, and especially the relieving of the young oaks from the influence of the more rapid-growing trees and shrubs.

The first cleaning is done by the brigadiers and forest guards, after which the guards are allowed a gang of 20 men to assist them.

These cleanings are made quite irregularly and where and when they are wanted, and continue till the woods are about 25 years old, after which regular thinnings every 10 years are undertaken.

As a result of the revisal of the working-plan the amount of wood to be felled annually is now fixed at 50½ cubic feet per acre. To this must be added the amount of thinnings, which extend over 2600 acres annually and produce about 29½ cubic feet per acre

Hence the total volume of wood to be felled annually is 80 cubic feet per acre.

There is usually a good beech mast once in seven years, the last having occurred in 1898, when the value of oil manufactured from the beech seed amounted to £6000, equal to about 1½ lakhs of rupees.

The average annual yield of timber from 1898 to 1900 was 684,400 cubic feet, valued at £24,613, or about Rs.3,70,000.

During the year 1900 the total revenue amounted to £28,441, of which £1380 was on account of hunting and shooting, or at the rate of about two shillings per acre

The total expenditure during the year amounted to £4743, the principal items of charges being rates and taxes £2501, woods £579, establishment £949, etc.

Besides the above, works such as the repairs of roads and ditches, plantations, etc., valued at £1192, were executed by the purchasers of the coupes in accordance with their agreements.

Finally, from what we saw of the forest of Retz or Villers Cotterêts we were convinced of the opinion that it is probably one of the finest and best managed oak and beech forests in France.

The next day, August 21st, we started in waggonettes on a tour through the forest of Compiègne, which as before stated is situated in the immediate vicinity of that town.

We found the numerous roads which traverse the forest all in excellent order, and the main thoroughfares were even paved with rough cobblestones, which naturally facilitates much the transport of timber, etc., during the winter.

At several points we left the carriage and walked through the forest, when various interesting details were pointed out and explained to us by the local forest officers.

The area of the forest, which is situated on the river Aisne, a tributary of the Seine, is 36,072 acres, the average elevation being about 500 feet above the sea.

Most of the forest lies on fairly level ground, the geological formation being Eocene, and consisting of beds of the Upper Chalk and Nummulitic limestone, above which are more recent deposits of sand, gravel etc.

The soil is generally poor and shallow, except in the part called the Beaux Monts, which will be described later on.

The forest of Compiègne consists mainly of oak, beech and hornbeam, with a few larch and Scotch fir. The total area is 32,292 acres, and it is divided into ten working circles managed on the high forest principle, with a rotation of 150 years.

There are also two sections comprising 2007 acres worked on the coppice-with-standards system, the rotation being 35 years.

Besides the above 12 working circles there is one more called the Artistic working circle, which is known by the name of the Beaux Monts, and which comprises an area of 1753 acres.

This compartment is worked on a kind of Jardinage system, its object being mainly picturesque, or as a game preserve, and it is much frequented by artists and tourists.

The annual outturn of timber from this forest is 992,911 cubic feet or 31 cubic feet per acre, to which must be added 700,000 cubic feet from thinnings, so that the total annual yield is 52 cubic feet per acre.

The annual average revenue during the last 10 years has amounted to £33,480, including £3880 from hunting and shooting leases.

During our inspection we were shown the operation of lopping the beech and hornbeam so as to relieve the suppressed oak, which operation is done by the forest guards themselves.

In the area being operated upon the young growth was about 10 years old, and we were of opinion that the operation had been too long delayed and might with advantage have been taken in hand sooner.

In some parts of the forest we noted the unsatisfactory state of the growth of the old oak, due to a mistake having been made in attempting to grow the species pure, and we always noted much better results in the places where it was mixed with beech and hornbeam.

Another important point to be noted about the treatment of this forest is that on account of its importance as a happy hunting-ground for the nobility and millionaire members of Paris society, the game question has to receive a considerable amount of attention, whereas in most other parts of France more distant from Paris, this matter receives much less consideration.

As a result of the preservation of game, and especially rabbits, it becomes necessary to fence with wire netting most areas under reproduction, which of course adds considerably to the cost of management.

About midday we arrived at the village of Pierrefonds' where there is a famous old castle of the same name.

During our return journey we visited the famous Beaux Monts, where we met M. Daubrée, Inspector General of Forests, and other state officials from Paris.

This compartment, which occupies a low undulating plateau, consists of a splendid sessile oak, beech and hornbeam forest, and contains many fine trees of unusually symmetrical form.

One of them called "La Tsarine" measures 17 feet in girth at five feet from the ground and is 118 feet high.

The bole is 46 feet to the first branch, and the whole tree contains 1120 cubic feet of timber and firewood, and is valued as it stands at £100 or Rs. 1500.

After much scientific discussion on the vigorous and healthy appearance of the forest growth we emerged on to a capacious cut line or avenue 150 yards wide and about 5 miles long.

This line was cleared by the first Napoleon in order to furnish a pleasing vista from the Palace of Compiègne, which is situated at the end of it.

A little further on we passed an enclosed portion of the forest, containing about 2000 acres, which is specially reserved as a game preserve for the shooting of the President of the French Republic and his state guests.

On the following day Mr. Fisher, the undersigned, and about half a dozen members proceeded to Valenciennes in order to see the State forests of St. Amand and the private forests of Raismes, belonging to the Duchess d'Aremberg, the other members of the Society, preferring to visit Paris.

These two forests lie contiguous to each other, the State forest, comprising an area of 8290 acres and the private forest 3500 acres.

The soil of both forests consists of a sandy loam and Tertiary sand, and immediately beneath are found the French coal measures.

In close proximity to the forests there are numerous coal mines, the excavations extending in all directions underneath the forests, which has resulted in the sinking of the ground in many places and the formation of *jhils* or marshes.

The principal species are oak and hornbeam, with some portions under Scotch fir.

Both forests are managed on the coppice-with-standards system, the Scotch fir parts being subject to high forest treatment.

There are 15 working circles in the State forest, the rotation of the underwood being 25 years, whereas in the private forest the rotation of the coppice is only 14 years.

In the State forest cleanings are made at 6, 12, and 15 years respectively, whereas in the private forest only one cleaning, at the age of seven years, is made.

In places where the oak coppice is insufficient 4½ to 6 feet plants are planted out, in some case, with balls of earth, or without, according to the distance from the nurseries, and with care both succeed very well.

As regards the standards there is no fixed rule as to their number, the guiding idea being to leave 1400 cubic ft. per acre at the end of the first felling of 25 years.

The result is that in the Government forest very little coppice is to be seen and the forest more resembles an understocked high forest. On the other hand, in the private forest the standards left are much fewer and much more attention is paid to the coppice growth.

Having found myself at this stage of my tour quite near the Belgian frontier, I decided to avail myself of a longstanding invitation to visit the private forest of Mirwart, belonging to Dr. Schlich, late Inspector General of Forests, and situated in the Belgian Ardennes.

The run from Valenciennes to Grupont, which is the nearest station to the Mirwart forest, was through an undulating and well wooded country, interspersed with cultivation and containing many coal mines.

The coal from some of these mines was being transported to the railway by means of aerial wire tramways, and as far as I could see the lines were always straight, without curves and with a gradient of about 15 or 20 degrees, and they seemed to work in a satisfactory manner.

There is one thing which strikes one forcibly in travelling through this part of Belgium as compared with the appearance of similar coal districts in England, and that is there are fewer, or apparently fewer, of those dreary heaps of slag and pit rubbish, which are so unpleasantly conspicuous in the Stafford and Lancashire coal-mining parts of England.

This is mainly due to the fact that energetic means are taken to plant up these unseemly mounds with larch, birch and other trees, which seem to grow well even on such uninviting and sterile-looking *debris*, and the result is said to be fairly profitable to the owners of the mines and highly beneficial to the general public from an artistic and health point of view.

That such enlightened and practical treatment of these depressing looking heaps might easily be carried out in England, where they are said to cover an area of about 14,000 acres in Staffordshire alone, has been demonstrated by Mr. Fisher in his articles in the *Forester* on the "Black Country," which appeared some time ago, and which suggestions are now actually carried into practice in the neighbourhood of the forest of Dean, and the plantations are already paying their expenses in a satisfactory manner.

After six hours' run by train and an hour's drive I arrived at the forest of Mirwart, in the middle of which Dr. Schlich's residence, which may be described as a modernized feudal castle, is most picturesquely situated.

The region of the Ardennes in which the forest lies is situated half in France and half in Belgian territory and extends over an area of 100×40 miles.

It is mainly drained by the river Meuse, a large tributary of the Rhine, down which stream timber and fuel from the Ardennes forests are floated to Holland.

The Ardennes consist of a series of plateaux, the elevation varying from 900 to 1300 feet above sea-level, and are much cut up with deep ravines and valleys.

The geological formation of this region consists of clay slate, which gives a stiff loamy soil of a cold and rather barren nature. One peculiarity about this clay soil is that the only other place where it is found is in the London basin, from which geologists conclude that in ancient times the rivers from the Ardennes region deposited their silt on the present site of the city of London.

A considerable percentage of the Ardennes, both in France and Belgium, is covered with oak forest and belonging to the French and Belgian Governments, village communities, hospitals and private persons.

These forests are mainly managed on the mixed and simple coppice systems, and one interesting fact about their former treatment is that they were subject to a special mode of management called "Sartage," but which is not now so extensively practiced as formerly.

This method consisted in spreading all the small branches and twigs over the felled areas after the removal of the timber and fuel, and when sufficiently dry in the autumn or early spring, setting fire to the inflammable material.

In the burnt soil and ashes thus obtained fine crops of potatoes and rye were raised, and disposed of under certain conditions to the villagers, who much appreciated the system.

The result of the firing had of course a specially stimulating effect on the coppice shoots, in the same manner as in the case of burnt coppice areas in the Indian forests, but for various reasons the system is not now so much practised as formerly, at least in the State forests.

As regards the private forest of Mirwart, it consists of 5 or 6 blocks and comprises an area of about 2875 acres.

It is situated on an undulating plateau of average Ardennes elevation, and the geological formation is the same as that already described.

At the time Dr. Schlich acquired possession of this forest, now about 11 years ago, the whole area was in a most irregular state, and consisted of about 2700 acres of mixed forest of oak, beach and hornbeam of all ages, 100 acres of Scotch fir, and 60 acres of oak coppice. After careful consideration and a valuation survey remarkable for its expertness and correctness, Dr. Schlich soon decided the difficult question of the future treatment of the forest, and which has mainly consisted in the following operations.

It having been observed that a few experimental patches of spruce fir had grown remarkably well, also that this kind of timber was very much in demand in the neighbourhood for pit props, the advantage of transforming the greater part of the forest into spruce became apparent.

It was therefore decided to replace the inferior parts of the mixed oak and beech forest with spruce plantation and to reserve only about 500 acres of the former forest round about the castle.

Extensive thinnings out of the oak and beech, and underplanting with spruce, have therefore been carried out since 1894, the age of the plantations now varying from nine to one year and they now cover an area aggregating 2000 acres.

Several of the plantations I examined in company with Dr. Schlich were found to be in a most flourishing condition, and

I observed that the planting had been done 4½ × 4½ feet apart, and that many of the trees in the oldest area were already 12 feet high. In some low-lying and exposed places, however, we observed a good deal of damage done by frost, but as severe frost only occurs once in five or six years, it is anticipated that most of the trees will soon get beyond its influence.

The cost of these plantations, including fencing, amounts to about 100 francs, or 60 rupees, per acre, and owing to the careful manner in which the work is done and the generally favourable conditions, only about five of renewals are required.

As regards facility for inspection, transport of materials, etc., most parts of the larger areas are well intersected with cut lines 50 feet broad, which also serve as fire-lines.

In proportion as the young spruce grow up, the old oak and beeches are to be removed, so that at the end of 40 years the greater part of the forest will consist of spruce with an undergrowth of beech, there being numerous seedlings of this species already on the ground, and which, like the silver fir of the Himalayas, can survive for years in deep shade.

As regards the 500 acres of oak and beech it is to be treated on the high forest principle, careful thinnings being carried on over a certain area annually, so as to encourage the existing young growth of oak and beech and equalise the stock, the whole area being worked over during the next 40 years.

The principal dangers are damage done by the red deer, which have a great weakness for the young spruce shoots, and this is to a certain extent prevented by sprinkling the young trees with whitewash at certain seasons, more especially during the spring.

Large flocks of wood pigeons often visit this forest when there is a good beech "mast" and devour immense quantities of the seed, and the means adopted to save some of it is by hoeing it into the soil immediately it falls.

The damage done by frost has already been referred to, and occasional fires have occurred, due to carelessness of workmen, but have not up to the present been of an extensive nature. As a new departure in the matter of fire conservancy it is interesting to learn that certain Belgian insurance offices undertake to insure forests against damage from fire, and that Dr. Schlich has in this case availed himself of this precaution by insuring his forest at a moderate rate of premium. As regards the growth of larch, it has been found to be a failure, about 200,000 plants having been planted out during the last 50 years, but all with the exception of about 500 have been killed by the larch fungus disease or destroyed by deer.

Up to the present the operations have been carried out in accordance with a rough preliminary working-plan. but now that the forest has been got into something like order, a regular 40 years' working-plan is being prepared, which will be subject to revision at the end of ten years.

As regards the financial aspect of this forest, up to the present it has proved satisfactory, all the timber, fuel, oak bark, etc., meeting with a ready sale.

As regards the future, Dr. Schlich calculates upon 3 per cent interest on the capital already invested, and that this rate will be maintained from the fellings of the remaining mature timber, and from the thinnings during the next 30 years, when the new spruce regular fellings will commence. As already explained, these fellings will begin when the spruce attains the age of 40 years, and then the sale of the standing trees is expected to realize at least 1600 francs, or 1000 rupees, per acre net.

From that time forward it may be assumed that the interest on the invested capital will at least be equal to 6 per cent., which may be considered a very satisfactory result.

After a most pleasant and instructive visit I proceeded by train to Brussels, passing through on the way the fine forest of Soignes, situated about 10 miles from Brussels, and on the borders of which the battle of Waterloo was fought.

This forest, consisting of oak, beech and various conifers, extends for about 5 miles × 2 miles on the south-western side of Brussels, and besides supplying a considerable quantity of timber and fuel to the town forms, on account of its proximity and being intersected by many fine roads, an important park and recreation ground for the inhabitants of the Belgian capital.

E. McA. M.

The Insect World in an Indian Forest and how to Study It.

BY E P. STEBBING, F.L.S., F.E.S.

Continued from page 186.

PART VII.

THE ORDER *DIPTERA*.

THE *Diptera* comprise the two-winged flies, including also the fleas, which are wingless, and the parasitic wingless insects such as the sheep ticks. The exceptions to the general two-winged rule in this Order are very few, although there are some 40,000 species known and an enormous number still unknown.

The Order has never been a popular one either amongst entomologists or with the general public. The scavenger-like habits of some and the annoyance caused by others have rendered the insects unpopular and caused their study to be neglected, nevertheless they may perhaps be classed as actually the highest insects physiologically, for in them the processes of a complete life-history are carried on with the greatest rapidity. A maggot hatching from the egg is able to grow with such rapidity that the work of its life in this respect is completed in a few days; then forming an impenetrable skin it dissolves itself almost completely; it then solidifies to a sort of jelly, and in a few days reconstructs itself as a being of totally different appearance and habits.

The wings of flies are usually transparent and never very large; they have a small piece attached to their lower inner angle called the 'alula'; behind the wings there is situated a pair of small erect capitate bodies called the halteres, which are often concealed under membranous hoods and are used for balancing purposes. There is no distinct prothorax present, the thorax being an immovable mass. The head is very mobile and is connected with the thorax by a slender concealed neck. A large part of the head is occupied by the big compound eyes, which are usually larger in the male than in the female. The antennæ vary in structure, and are of importance as we shall see, the classification of the Order being based upon them. In some a long jointed antenna which may be whorled is present. The majority of flies have, however, an antenna peculiar to the Order, consisting of three segments, the outer one of which is of diverse form and bears upon its front a fine projecting bristle, frequently feathered and often distinctly divided into two or more joints. This form of antenna is found in the series *Aschiza* and *Schizophora* and is present in the common house fly. In the Order generally the two basal joints of the antennæ are called the 'scape;' the part beyond this is called the 'flagellum,' an appendage of the flagellum being termed the 'arista' if bristle-like, or if thicker the 'style.' The mouth parts are formed for suction and consist of a sucking tube of varying form which sometimes ends in a flat pad as seen in the common house fly. The legs are long and slender and terminate in claws with one or more pads between them, which are covered with a sticky fluid which enables the insect to walk on glass surfaces, etc. The abdomen is conical and usually sessile. The larvæ are invariably maggots, *i.e.*, they are legless. Some, however, still possess a hard chitinised head furnished with eyes, antennæ and mouth parts. In others the head is not well marked, eyes are absent, antennæ absent and mouth parts represented by a pair of darkly coloured chitinous hooks. On account of the presence of such weak mouth parts the grub feeds upon decaying filth and refuse and other soft matters.

In those *Diptera* whose larvæ have well developed heads the pupæ are like those of the *Lepidoptera*, the appendages lying close to the body; in those with 'headless' grubs the pupæ remain within the last hardened larval skin, and the pupa is then called 'coarctate.' In these latter no appendages whatsoever are to be seen on the outside, the chrysalis being generally blunt ovate in form.

The *Diptera* are divided according to the nature of the antennæ present into five great series, a few families of each of which will be considered below. Although members of the Order have not as yet been reported as committing much damage in Indian forests, it is not unlikely that we shall find, as our knowledge increases, that the gall-making ones are of considerable importance. It may be mentioned here that the teak trees in the Melghat forest in Berar are badly attacked by a dipterous gall-making fly. Under its attack the branches swell up into rounded lumps, which sometimes completely encircle them, and these are at times so numerous as to distort the branch with irregularly-shaped swellings for some inches up, the galls often coalescing. It would appear that when the gall completely encircles a branch or leading shoot of a young sapling the portion above it dies. The writer bred out two of these flies from galls at the end of July in the Melghat, but unfortunately they got injured in transit home and their identification was impossible. Teak in Madras, especially young plants, would appear to be affected in a similar way, but the writer has not been able to procure any mature specimens of the insect in spite of several attempts which the Conservator of Forests in Mysore has kindly made to obtain them for him. There can be little doubt that the pest is capable of committing considerable havoc.

The habit of blood-sucking from vertebrates is, among insects, of course confined to those with a suctorial mouth, and is exhibited by various *Diptera*. It is however indulged in by but a small number of species, and these do not belong to any special division of the Order. The habit is as a rule confined to the female sex, and a large proportion of the species with this propensity have aquatic larvæ.

SERIES I.—ORTHORRAPHA NEMOCERA.

Antennæ consist of more than six segments and are not terminated by an arista. Palpi slender and flexible, four or five-jointed.

FAMILY CECIDOMYIIDÆ (GALL FLIES).

An extensive family of very minute and fragile flies, the wings of which are provided with only a few nervures; the antennæ are rather long and are furnished with whorls of hair upon them. In some species the antennæ are beautiful objects when seen under a magnifying glass. The larvæ are of importance as their habits are very diverse. They are short maggots, narrowed at either extremity, with a small head and 13 segments. The majority live in plants and form galls or produce deformations of the leaves, stems, flowers, buds and roots in many ways. Others live under bark, whilst others are predaceous, feeding upon *Aphidæ* or *Acari* or even other *Cecidomyiidæ* The larva of an India species (*Cecidomyia oryzæ*) have proved very dangerous to rice, feeding in the stalk and killing off the plant. The insect known as the Hessian fly, *Cecidomyia. destructor*, of Europe and America, is frequently excessively injurious to crops of cereals, committing at times the most serious depredations.

FAMILY CULICIDÆ (MOSQUITOES, GNATS).

Slender insects with very long legs, the antennæ being provided with whorls of hair or plumes on them, generally very long and dense in the male. The head is furnished with a long projecting proboscis The larvæ live in stagnant water. They have a largely developed head and thorax, and so can be distinguished form other dipterous larvæ. The pupæ also live in water and move about in it.

Much has recently been written on the genera *Anopheles* and *Culex*, and it has been practically proved that species of the former can induce malarial fever in man. The larvæ live in water, floating flat upon the surface. The perfect insect is the well-known mosquito. The life-history is as follows* :—

The eggs are deposited on the surface of the water, where they float in raft-like masses. They hatch in a very short time, generally—in warm climates—within 24 hours, giving rise to small wriggling worm-like creatures, which feed either on minute water plants or on decaying organic matter. They breathe air, and must repeatedly come to the surface for that purpose. Their mouths are provided with a pair of brush-like organs which they keep in rapid motion, producing a miniature vortex which draws floating particles within reach of their jaws. After a period varying from 7 to 15 days, during which time they undergo some four or five moults they assume the pupal stage, when their form is again changed. They now appear something like minute tadpoles or—still more—like animated commas, with a globular anterior portion and a thin-curved tail. They take no food in this stage, but are very active, progressing through the water with a wriggling motion. Their breathing organs are now transferred to the front of their bodies and appear as small ear-like structures, and the insect rests in a more or less erect position, head upwards. In about three days' time the skin of the back splits and the mature mosquito emerges, resting upon the empty skin of the pupa, as upon a raft, until its wings are firm and dry, when it flies off.

---

* *Vide* Royal Botanic Gardens, Ceylon, Circ. Ser. 1, No. 25, "Mosquitoes and Malaria." E. E. Green.

The differences between *Culex* and *Anopheles* are well marked and may be shown as follows:—

Culex.	*Anopheles.*
Eggs: agglutinated into raft-like masses on the surface of the water. Each egg placed vertically.	*Eggs*: separate, floating horizontally on surface of water.
Larva: with long breathing tube at end of body. Floats head downwards	*Larva*: without prominent breathing tube. Floats horizontally
Adult insect: with palpi much shorter than proboscis. Wings usually clear and colourless. Rests with body parallel with support.	*Adult insect*: with palpi as long as proboscis. Wings usually spotted or clouded. Tilts the body at an angle to the support.

Thus by observing the position of rest taken up by the perfect insect on alighting upon one's hand one will be able to determine in most instances as to whether the insect is an *Anopheles* or not. The organism responsible for malarial fever is an animal organism named *Hæmamœba*. It is small and unicellular, and is found in the blood of a patient suffering from malarial fever. If left undisturbed the disease will be confined to this one man. If the latter is bitten by a certain kind of mosquito of the genus *Anopheles*, the mosquito takes in with the blood some of the *Hæmamœba*. These now undergo a true sexual cycle and the ♂ and ♀ parasites collect in the glands at the base of the proboscis of the mosquito. Should this latter then bite another person the parasites are injected into his blood and thus go through their asexual cycle in him and induce an attack of malarial fever in him. It thus becomes obvious that persons suffering from malarial fever should be carefully protected from the *Anopheles* mosquito by means of mosquito curtains, etc., or they themselves become a centre from which others are infected.

FAMILY SIMULIIDÆ (SAND FLIES).

Small fat flies with humped back, rather short legs and broad wings, with short straight antennæ destitute of setæ; proboscis not projecting.

There is only one genus, *Simulium*, of this family, but it is very widely spread and will probably prove to be nearly cosmopolitan. Some of the species are notorious for their blood sucking habits and in certain seasons, multiplying to an enormous extent, alight on cattle in thousands and induce a disease that produces death in a few hours. *Simulium columbaczense* has occasioned great losses in this way near the Danube. In India the family is represented by the well-known *potū* fly (*Simulium indicum*) of the North-west Himalayas. This insect is plentiful in the summer in the chir *P. longifolia*) and deodar (*Cedrus deodara*) forests of these mountains: the species found in Assam may be identical. It is most troublesome in the N.-W. Himalayan forests, as its bites are very irritating and produce blisters. The flight of the insect is noiseless and its bite at first so painless that the creature is seldom noticed until it has absorbed the blood from the wound. Brushing it away is then of no use. It leaves a characteristic mark due to the presence of a little globule of blood, about the size of a pin's head, beneath the skin. This rapidly turns black. The irritation produced varies in different people, but the insect has been known to drive whole camps of sawyers from the forest and to stop all work.

SERIES II.—ORTHORRAPHA BRACHYCERA.

Antennæ variable. Palpi only one= or two-jointed. The system of nervures in the wings is complex and there is no definite arched suture round the insertion of the antennæ.

FAMILY TABANIDÆ (GAD FLIES).

The proboscis in this family is fleshy and projecting, the antennæ are said to be three-jointed, but the last joint is constricted, and therefore consists of apparently more than three joints. The head is short and broad, with very large eyes; mandibles (biting jaws) are only present in the female. The abdomen is flattened. The larvæ are cylindrical, some of them being aquatic, others living in the earth or in decaying wood; they are of predaceous habits, attacking and sucking insect larvæ or worms. The female flies suck the blood of Mammalia and are a great plague to horses, cattle and animals of all sorts in India.

Species of this family are very plentiful in India, and the large horse flies of the forest are well known to all foresters. It is these insects which drive large game, such as elephants, sambhur, etc., living at the foot of the Himalayas and other mountain ranges, to seek the higher hills, and consequently cooler climate, during the hot weather months in India, during which season the flies are particularly abundant.

FAMILY BOMBYLIIDÆ.

Body is frequently fringed with down or covered in large part with hair. The legs are slender, claws being small, with only minute pulvilli. Proboscis very long and moderate, antennæ three-jointed, terminal joint not distinctly divided, sometimes large sometimes hairlike. This is a large family of flies and is of great importance to both naturalist and economist There are two well marked types of fly in the Order (1) the *Bombyliides* with very long exserted rostrum and humped thorax; and (2) *Anthracides* with a short beak and of more slender thorax and graceful form. None of these flies are blood suckers; they frequent flowers only and use their long rostrum in a harmless manner. The wings are usually ornamented with a pattern, and the clothing of the body is frequently variegated. It has recently been discovered that the larvæ of various species of *Bombyliidæ* are of great service in that they devour locust eggs, whilst a species of *Systropus* has been recorded as destroying the larvæ of *Limacodes.*

FAMILY ASILIDÆ (ROBBER FLIES).

This is one of the biggest families of flies, including over three thousand described species. In these flies the mouth forms a short projecting horny beak, the palpi being small. The body is elongated and hairy, and the feet have powerful claws, which are often thick and blunt. The insects are predaceous in the winged state and devour numbers of other insects. They prey upon large species and fear none, attacking wasps and other stinging insects and capturing even dragon flies and tiger beetles. Little is known about their larval stages in India.

SERIES III.—CYCLORRHAPHA ASCHIZA.

Antennæ with not more than three joints, and these are furnished with an arista which is not terminal. Front of head has no definite arched suture over the antennæ.

FAMILY SYRPHIDÆ (HOVER FLIES).

Flies of moderate to rather large size, frequently spotted or banded with yellow, having very short, three-jointed antennæ and a cleft on the underside of the head in which the proboscis, which is thick and fleshy, can be withdrawn. This family is one of the largest and best known of the flies. Species abound in gardens and glades of the forest, where in sunny weather they may be seen hovering over flowers or in the rays of sunshine which pierce through the leafy canopy of the trees. The larvæ are very diverse in appearance, and they live either upon plants or in water. Some feed upon *Aphidæ* or plant lice, and they may then be found on bushes or trees attacked by these blights devouring them with great voracity and in enormous numbers. The larvæ of *Syrphus nietneri* Schiner MS, and *Syrphus splendens* Dolesch, are said to prey in this way upon the coffee louse *Aphis coffeæ* in Ceylon.

SERIES IV.—CYCLORRHAPHA SCHIZOPHORA.

Antenna has three joints and is furnished with an arista. The frontal suture over the antenna is often well marked. The nervures in wings are not so complex.

FAMILY TACHINIDÆ (PARASITIC FLIES).

This is an enormous family of flies, the larvæ of which live parasitically on other living insects, lepidopterous caterpillars being especially attacked. The antennal arista is bare, and thus these insects may be distinguished from the house fly, where it is plumose. The upper surface of the body is bristly. The insects of this family have in many cases a very great resemblance to the common house fly. Many have been reared from the insects on which they live, but beyond this little is known of their life histories. The eggs are usually desposited by the flies near or on the head of the victim. The grub on hatching out burrows into the caterpillar's body, but avoids the vital organs, so that the parasitised larva usually lives on until the dipterous grub is full fed, and it may even change into a pupa before death ensues. In the latter case the pupa will be found to contain one or more small fly pupæ according to the number of eggs laid upon or in and developed in the caterpillar. No moths will of course issue from pupæ attacked in this way. If the caterpillar dies before changing to the pupal state the fly maggots will cut their way out and change into pupæ on the outside alongside of the dead caterpillar skin, or they may burrow into the ground and pupate there. From the above it will be seen that these flies are of the very greatest importance and service to man, owing to their habit of destroying caterpillar, larvæ and thus keeping down swarms of defoliating larvæ. We are only just at the commencement of our researches in this respect in India, but there can be little doubt that these insects will well repay study. The writer has bred an as yet unnamed species out of the caterpillar of the destructive teak tree defoliator *Hyblæa puera* in the Nilumbur Plantations.

Members of the family are a serious nuisance to silkworm rearers, as unless special precautions are taken they destroy the worms wholesale. *Trycolyga bombycis* is parasitic upon the Eri and mulberry silkworms of Bengal and is very destructive. It is very like a large house fly in appearance. It in its turn is parasitised by a smaller fly named *Phora cleghorni*, which attacks it in much the same way it attacks the silk caterpillars.

A closely related family *Anthomyiidæ*, which has much the same characters as the *Tachinidæ*, contains the important fly *Anthomyia peshawarensis*, which is parasitic upon the eggs of the migratory locust *Acridium peregrinum*.

FAMILY MUSCIDÆ (HOUSE FLIES).

The arista is feathered, and by this they can be distinguished from the Tachinid flies, which they otherwise resemble. This family contains many of the most abundant species on the face of the earth, including the house fly, blue bottles or blow flies, and other forms. The larvæ live on carrion and decaying or excrementitious matter.

The common house fly, *Musca domestica*, runs through its life-history in a very short time. It lays about 150 very small eggs on dung or any soft damp filth; the larvæ hatch out in a day or two and feed on refuse; they may be full grown in five or six days, and then pupating, may emerge in another week as perfect flies. This accounts for their enormous and rapid increase when dirt and decaying matter is abundant. It has been calculated that one female of the common house fly may have 25,000,000 descendants during one season.

The grubs of the fly *Rivellia persicæ* have been reported as seriously affecting the growth of the peach (*Prunus persica*) fruit in Chota Nagpur, whilst those of *Dacus ferrugineus* live in and considerably damage mangoes.

FAMILY OESTRIDÆ (BOT FLIES).

This is a small family of flies, the larvæ of which live in the bodies of vertebrates. The insects are large flies with very short antennæ, bearing a segmented arista; the front of the head is prominent, and the posterior part of the wings is often rough, and with very few veins. The family is of small extent, less than 100 species being known, yet it is of interest owing to the habits of its numbers. Some (*Gastrophilus*, etc.) live in their larval stage in the alimentary canal; others (*Hypoderma*, etc.) are encysted in or under the skin; while others (*Oestrus*, etc.), occupy the respiratory passages. Many of them attack the domestic animals used by man, and some even man himself. The life-histories are still very incompletely known. They do not bite the animals they attack, but deposit the eggs upon the hair of the skin or the young larvæ, already hatched, in the entrance of the nasal passages. The larvæ always quit the bodies of their hosts to pupate.

Horses, oxen, deer, sheep, etc., are attacked by these flies.

SERIES V.—PUPIPARA.

Often wingless flies or the wings are reduced in size. The young are produced alive, full-grown, but have still to undergo a metamorphosis. They are found in connection with vertebrates, and the habit of blood-sucking is probably common to both sexes.

FAMILY HIPPOBOSCIDÆ.

The wings are variable:—sometimes present and large when the surface is waved and the nervures are thick and confined to the anterior and basal part; at other times mere strips, whilst occasionally they are entirely absent. The proboscis differs from that of other flies, consisting of two hard flaps fitting close together, which can be opened, allowing an inner tube to be exserted from the head.

The family includes the horse fly and sheep tick.

NOTE.—The Sub-Order *Aphaniptera* includes the family *Pulicidæ* or fleas, which are wingless insects having the body laterally compressed, so that the transverse diameter is small and the vertical one great. It is unnecessary to do more than mention these insects here. They are known to all.

USEFUL DIPTERA.

The Order contains some insects whose habits render them of the greatest use to man. Amongst the *Cecidomyiidæ*, a family containing some bad pests, there are some species which are predaceous, feeding actively upon *Aphidæ* or *Acari* and even upon their own relatives. The larvæ of the *Tabanidæ* are predaceous in habits, feeding upon other insect larvæ and worms. It has been discovered that some species of the *Bomby'iidae* are of great service, in that they devour locust eggs, whilst one has been recorded as destroying the larva of *Limacodes*. As the adults of this family frequent flowers it is probable that they are of some service as pollen distributors.

The *Asilidæ* are predaceous in the winged state and devour numbers of other insects, attacking all species without fear. They probably do some harm in this way by attacking useful species, it being known that they will feed upon useful predaceous tiger beetles and dragon flies.

Some of the larva of the *Syrphidæ* are known to feed upon *Aphidæ*, whilst the family *Tachinidæ* include almost entirely parasitic species which feed within other insects, chiefly perhaps the caterpillars of *Lepidoptera*. The *Amthomyiidæ*, a closely-related family, contains the important fly *Amthomyia peshowarensis*, which is parasitic upon the eggs of the migratory locust of India, and thus renders great service to man by checking to some extent the increase of this pest

THE ORDER THYSANOPTERA (THRIPS).

These are extremely abundant minute insects, which are to be found in profusion in flowers. They have four very narrow fringed wings and an imperfectly suctorial mouth. They are, as far as our present knowledge goes, of no importance to the forester, though species have been reported as injurious to turmeric, the opium poppy, and the leaves of the tea plant. It has been said that some feed upon *Aphidæ*, but the statement does not appear to be supported by sufficient evidence at present to render it of importance.

Effect of Leaf Covering on Soils

AN excellent article in the *Revue des Eaux et Forêts* for December 1902, by Professor E. Henri. of the Forest School at Nancy in France, brings to notice the different experiments which have been conducted with the object of finding out what is the effect on the soil when the dead leaves, etc., are removed. In the forests of Europe, during autumn, the leaves fall from the trees and are heaped in stratified layers, together with dead branchlets, strips of bark and the remains of flowers and fruits, and these layers, before being converted into humus, are generally known as "the covering of dead vegetation."

This covering of dead vegetation is the only manure that the forest soils get and the removal of it, which is some times carried out for "litter," manure, etc., is extremely prejudicial to poor soils; and the more frequent the removal, and the longer it is practised, the worse are the results. In bad soils annual removal of this layer causes malformation of the tree growth, and in some cases death of the trees: and between 20 and 25 years, if the removal has been annual, it causes a decrease in growth amounting to 40 per cent., if biennial 25 per cent., if quadrennial 20 per cent., if sextennial 12 per cent. Natural regeneration becomes quite impossible in poor soils, and extremely difficult in better soils, owing to the hardening and drying up of the superficial layer, and to the malformation of the growth. The effect of the removal is simultaneously chemical and physical. Chemically it impoverishes the soils, already poor in themselves, by depriving them of appreciable quantities of lime, phosphoric acid, potash, nitrogen, etc., which would have been sufficient to maintain, and even improve, the forest vegetation. Physically it plays a prominent part in the formation and maintenance of the porosity of the soil; and as pointed out by numerous experiments—notably those of Wollny—the variations of temperature are least in a soil furnished with a covering of dead vegetation, and the action of such covering on the moisture of the soil is considerable. This action has often been quoted, but until recently there have been no experiments by which a definite conclusion could be arrived at. Some persons believed intuitively in such a covering causing a great increase in the moisture in the soil, but had no proof, and could give no statistics. Others, on the other hand, relied on the statistics of Dr. Ramann, and came to the conclusion that such covering made very little difference. But there is not the slightest doubt that Herr Fricke's recent experiments are based on very much sounder principles, and that they firmly establish the fact that this covering is most effective in increasing the moisture in soils, and especially in soils which have been cleared of forest vegetation. This is such a very important matter that it will be as well to give an outline of some of the experiments that have been made, and their results.

Wollny studied the question of the extent of the influence of this covering on the moisture of the soil, but only in localities *outside forests*; but in the forests the tops of the trees form an obstacle to the wind and to the heat of the sun, and therefore have great influence on the moisture in the soils. Wollny found (1) that soil with "a covering of dead vegetation" is far moister in summer than a bare soil of the same composition; (2) that the percentage of water in a soil with such covering increased with the thickness, but not proportionately to the thickness of the covering; (3) that the effect of the covering was to diminish the direct action of the causes of evaporation, that the wind and heat of the sun cannot exercise directly their drying influence through the covering, and are the less able to exercise it as the covering thickens; (4) that one inch thickness of leafy covering was enough to reduce the evaporation sufficiently to keep the soil in a perpetual state of moisture; 5) that with layers thicker than this, up to four inches of thickness, the percentage of water does not increase, although the evaporation decreases, but keeps approximately the same, by filtration deeper into the soil; 6) that with layers exceeding 4 inches, the drainage water decreases, because large quantities of the water are absorbed by the covering itself. Wollny mooted the question as to whether the different effects of the covering on the moisture of the soil and drainage water were manifested in the same way in the forest, but as his experiments were made in areas of about two square yards, stocked with spruce of five years old, they could hardly be accepted as proper tests, but he found that, whereas the soils in previous tests gave 4 to 6 per cent of water, in the soil stocked with spruce without covering it amounted to 14 37 per cent. and with covering to 15 ·7 per cent.—an insignificant difference of 1 per cent.—and this slight difference he attributed to the more vigorous vegetation in the covered soil, as the trees find more humidity which they absorb, and more nutritive matter in the decomposing vegetable covering.

Dr. Ramann, Professor of the Forest Academy at Eberswalde, and Herr Schmidt, Inspector of Forests at Meiningen, made analyses of forest soils taken from the middle of the forests, and they both came to the conclusion that the covering made a difference of scarcely 1 per cent. of water; and it is due to these analyses that this opinion has become to a great extent the accepted one.

Herr Fricke, however, has recently pointed out that all experiments hitherto have been based upon the proportionate weight of the soil, and that this is by no means the proper method of computation by which to form a true idea of the percentage of water such as it exists in nature; that we do not want to know how much water there is in a given weight of soil, whose elements, consisting of pine needles, humus, vegetable mould, sand, pebbles, etc., have such different densities, but what quantity exists in a given space, taking into account their natural faculty of absorption; in other words, that the factor must not be computed by the weight but by the volume. This, of course, is a far more rational way of treating the subject than that of Dr. Ramann and Herr Schmidt, and the results of his experiment are very different.

On a sandy soil he took two sample areas, one with its vegetable covering, the other laid bare, in each of the following four types of forest: (1) old high forest 110 years old, trunks tall and straight, 60—70 feet high, but of medium girth; (2) pole forest, 50 years old, trunks 40 feet high, dense; (3) thicket, or sapling forest, 15 years old, fairly dense; and (4) a clean felled coupe. The experiments were conducted for 120 days, from April 19th to August 17th, during which 94 days (*sic*? 104) were without rain and 16 days with rain, the weather being exceptionally hot and dry, and the results of evaporation were as follows: *High forest* with leaf covering 35 per cent., bare 41 per cent.; *pole forest* with covering 40 per cent, bare 47 per cent.; *thicket* with covering 39 per cent., bare 80 per cent.; *clear felling* with covering 67 per cent., bare 102 per cent. This shows that in the clear felling, when the leaf covering was removed, the evaporation was greater than the rainfall; but when the covering was not removed it was only two-thirds of the rainfall, that the effect of forest growth on evaporation is greater as the forest is older, but that, on the other hand, the removal of the vegetable covering has less effect as the forest is older.

He continued his experiments, and found that in winter the moisture in the plots deprived of this covering is nearly 20 per cent. less than that of those with covering. He conducted his experiments only to a depth of 16 inches for two reasons: firstly, because below that depth it becomes very difficult to determine the volume of the soil; and secondly, because he found that trees obtain their nourishment almost entirely within that limit. Thus he discovered that 70 to 80 per cent. of the root system of an old pine in poor alluvial soil was to be found within 12 inches of the surface. It is further pointed out that these differences are most accentuated in hot climates.

A. W. L.

II -CORRESPONDENCE.

Our Neglected Commercial Side.

ADMITTEDLY a very large proportion of the area in the charge of the Indian Forest Department is now, through the reckless plunder of past years, in such a condition that revenue therefrom must be expected, not from timber, but from the exploitation of the various kinds of "minor" forest products. The forests have been depleted and the stock of timber has sunk far below the normal. It now devolves upon the forest staff to so protect these forests that the capital value be once more brought up to par.

This of course entails considerable unproductive (immediately) expenditure and a lengthy period of recuperative rest, during which little revenue can be expected from the extraction of timber.

Now, therefore, is the time to develop the exploitation of the minor products. Now must the Department deal with all the problems and overcome the difficulties that must arise in finding new markets and in fostering the growth of trade.

Already large profits accrue from such products, as from myrabolams, lac, paper grass, etc; but are there not many products in the forest little known, or that can be turned to uses not thought of in their connection and which remain as yet unexploited ?

The Divisional Officer is at a disadvantage in dealing with such matters. He is not in touch with any large commercial centre. He may feel sure that a certain product is a useful one and capable of producing revenue, if known, but he does not know how to place it, where to obtain information ; in short, he cannot push his wares. He must make experiments, possibly costly, certainly tedious, and frequently discouragingly inconclusive, to obtain data as to cost, season and method of extraction and to find the solution of sundry allied problems. Very probably all these experiments have been made before, and he could profit by the experience, the success and failure of others could he but readily lay his hands on information recorded.

This brings me to what I have to suggest, and that is the establishment of a central information office, which would deal with all these points as well as some others which I will refer to further on.

At first possibly one such office would be sufficient for the whole of India, and could form a branch of the Inspector General's office under the charge of a Deputy Conservator on special duty.

As the work increases provincial offices can be opened with a Deputy Conservator on special duty under the orders of the senior Conservator.

It would be the duty of this special officer to obtain full information on all points connected with the trade in minor forest produce of all kinds, to seek openings for developement, and to have the capabilities of any new product submitted to him thoroughly tested. Each article would be separately dealt with in detail, data being collected as to the most profitable market prices, firms trading in it, method of extraction, of preparation, of packing, cost of all operations in each locality where it occurs.

The Divisional Officer's duty would be to obtain full and reliable data as to cost of exploitation in his own division and of transport to the nearest railway station. He would supply this information, together with a statement of quantity available, to the special officer. The latter would compare the figures and advise on the subject, and if necessary undertake all outside arrangements, leaving the Divisional Officer merely to collect and deliver the produce

This central office would also be addressed by dealers in forest products, instead of, as at present, addressing the Divisional Officer direct for information, which he very possibly cannot give.

Divisional Officers would thus be prevented from entering into relations with undesirable parties, about whom they could otherwise learn little, and from offering or agreeing to rates below the market value.

Besides the above the proposed office could undertake the collation and compilation of sylvicultural data for the chief forest trees. Most officers have considerable knowledge as to the sylvicultural requirements of some one or two species of forest trees, but except in isolated cases, where a keen officer has placed his views on record, this knowledge is locked up in the brain of the observer, and not available for general information as it should be.

My central office would invite the collaboration of all officers. In fact Conservators could insist upon officers submitting short articles on definite species, each one being assigned a particular subject to report upon.

Similarly full record would be maintained of the many experiments in cultivation of exotics, etc., which are carried out from time to time independently by various officers, and which for want of proper record, accessible to all, are repeated possibly over and over again without reaching finality.

This seems to be a very real need for the Department. It may be objected that the pages of the *Indian Forester* are open to, and form the proper repository for, such sylvicultural and experimental notes. This would be so if all, or at least a sufficient proportion, could be induced to write of their own accord, but how many have done so in the past and how many will in the future failing some gentle pressure? Besides which the modesty of many, being aware that they have no claim to authority, prevents their placing the results of their observations on record. This obstacle would disappear where the action was purely official, and, besides, the Conservator could watch over progress and insist on definite results, which would be scrutinised and recorded.

The special officer would edit the various reports, and from time to time, when the information on each subject became complete, it could be printed in the form of a pamphlet and circulated.

MARCHONA.

The Flowering of Bambusa polymorpha.

THE last recorded flowering of the *Kyathaung* was, I believe, in 1853; it was expected to recur in 1883, and for some years after this an annual wave of suppressed excitement passed over Burma. We know the effect of "hope deferred," and now for some years past we have become so used to immunity that we seem to have partly lost our watchfulness. Are we sleeping on a powder mine?

It used to be handed down as a tradition that the Inspector General, on the first news of a general flowering of the *Kyathaung*, would transfer his Office Head-quarters to Burma; that gazetted officers of all ranks, knowing nothing of Burma, its language or its customs, would be sent to this Province on special bamboo duty; that coolies by the thousand would be sent down from India and a special grant of goodness knows how many lakhs of rupees sanctioned for the purpose of planting up the flowered area with teak. Tradition was probably guilty of gross exaggeration.

But there is no doubt that the long-deferred flowering will come on us in the near future, and it will probably find us unprepared. The earliest intimation will be given in August, and by the following April it will be too late to prevent the ripened seed falling. The present area of *Kyathaung* can be reckoned by hundreds, if not by thousands, of square miles, and these 8 months (as a maximum) do not leave us much time for deliberation as to ways and means. To allow the long expected time of seeding to pass by without taking adequate measures to foster teak reproduction would be a national calamity. Knowing and recognising this you would expect that all details would have been already arranged, that on the touch of a button the whole machinery organized for coping with the difficulty would be set in motion, each man knowing what to do and how to do it.

Is this so? As far as present tradition goes the earliest intimation of a flowering is to be wired to the Inspector General. Is the whole force of the Department in Burma then to sit and wait until the poor man has consulted with his colleagues how to act? If so, may not the greater part of the 8 months' grace that nature allows us be lost? Who is to decide what local action is to be, or can be, taken? Is valuable time to be wasted at the critical moment discussing how to set about the work? Every year brings the danger nearer, and we should not allow ourselves to be lulled into a sense of false security.

The matter seems of such importance and urgency that I would ask you, sir, to open your columns to a free discussion of it, that when the moment arrives we may find ourselves prepared. It is not fair to this Department that orders should be deferred till too late.

It seems to me that in each Division special maps should be at once compiled showing the area of *Kyathaung*; that it should be decided without delay what areas (if any) should be burnt before the seed ripens, and what areas should be left to be treated later. If fire is to be employed, the method of its application should be laid down clearly and precisely, so that each officer can set to work at the earliest possible moment. If the flowering is delayed, the scheme might be periodically revised. In the meantime experiments might be made as to the best method of planting, whether by seed sown broadcast or dibbled in, whether by transplants, or by some other method Opinions on this subject are many and varied. If your readers with experience of Burma would freely express their views, the discussion could not fail to be both interesting and instructive. But further than this I would urge that a scheme be prepared and officially sanctioned for each division, so that no time may be wasted in applying for orders and sanction once the first signs of flowering are observed.

20th March 1903. WATHÔN.

Grass for Paper Manufacture.

MR. G. W. THOMPSON, writing in the *Indian Forester*, February 1903, pp. 80-81, is puzzled as to the synonyms of 'Bhabar grass.' A reference to the F. Brit. Ind., VII, 129, would have put him straight.

I enclose further references to the literature which may be useful.

KEW, *4th March* 1903. W. T. THISELTON-DYER.

Subject Andropogon involutus and *Ischæmum angustifolium.—Indian Forester*, XXIX (February, 1903), p. 80.

The two names are synonymous, and the correct name is *Ischæmum angustifolium*. Cf. *Kew Bulletin* (1888), pp. 157-160 with plate, and Watt, Dict. Econ Prod., India, IV, 526.

ROYAL BOTANIC GARDENS, KEW; OTTO SCAPF.
Feburary 28, 1903

Anent my letter to you about "Grass for Paper Manufacture" in the *Indian Forester* for February last, you have got "Kamku Kopiri" for what I intended to be "Karukku Kopiri." My caligraphy was possibly not very legible. But it is just as well to point out the error.

Since writing my last letter to you I have discovered that what I had said was probably *Eriophorum comosum* (local Telugu "Nunta Kopiri") is not that grass. It is a different species. I am sending a flowered pressed specimen to separate post for identification if possible. The Bengal Paper Mills Company, Calcutta, to whom specimens of the bhabar grass and this species were sent, writes as follows: The two samples of grass are to hand. The sample marked A (*Ischænum angustifolium*) is equal to good Nagpur grass, and that marked B (the specimen sent) is equal to average Sahibgunge.

So that it seems possible that there is yet another species of grass likely to yield material for paper manufacture in the future, and this grass is plentiful in this (Vizagapatam) district. It may be possibly found in other localities also.

Since the cost of sending grass to Calcutta all the way from here is so excessive, will it be a difficult matter for any of the existing paper mills in Northern India to start a branch, say in Vizagapatam, or any other near East Coast port offering facilities for profitable business, if the District Forest Officers of the Northern Circar districts could guarantee a sufficient supply of grass for paper-making at a reasonable cost? I think it worth the while of the District Forest Officers concerned to do this, since there is prospect of a large revenue from this source to their Districts.

I am also sending another species of grass, which I think is of the genus *Paspalum*. As there is so much of research going on at present in regard to famine foods and fodder species. I thought it worth while to know what this species of the *Paspalum* is. The Australian species, *Paspalum dilatatum*, is said to be an invaluable fodder grass for livestock there, as it grows plentifully in the droughtiest localities and affords capital fodder for cattle. There is yet another species of the same genius, *Paspalum scrobiculatum*, which is cultivated as a cereal crop here and in Southern India. It will grow on the poorest soils. The specimen I am sending is much like it, but is not the same species.

NARSAPATAM, 23*rd March* 1903. GEO. W. THOMPSON.

[The specimens have been submitted to Major Prain for favour of identification.—HON. ED.]

III -OFFICIAL PAPERS AND INTELLIGENCE.

Damage to Babul Trees by Fomes Pappianus.

I ENCLOSE herewith for favour of publication in your journal copy of correspondence on the *Fomes Pappianus*, a most destructive fungus enemy of the babul, in the hope that foresters in other parts of India, where this tree forms groves or more or less extensive masses of forest, will communicate to us through your medium their own experiences

Babul grows like a weed in all the black cotton soil lands of Berar, and the rich Purna Valley would become a huge, more or less pure, babul forest if thrown out of cultivation for a few years; nevertheless it is chiefly in the Purna Valley that the fungus runs riot among the babul.

CAMP RANGRAO CHURNI: }
The 25*th March* 1903. }

E. E. FERNANDEZ,
Conservator of Forests, Berar.

Circular No. XLVI of 1902-03, dated the 25th March 1903, from Conservator of Forests, Berar, to all Divisional Forest Officers, Berar.

You have no doubt noticed the widespread and severe injury wrought in babul groves and plantations by a fungus, the *Fomes Pappianus*, Bres. The damage is most conspicuous in the Loni and Bhongaon forests in the Akola district, where crops only a few years old become infected and begin to languish and die, while older crops, apparently in full health and vigour, suddenly in the course of a single year or two enter on the decline, the trees becoming top-sore at first and then perishing rapidly. An invariable characteristic is that the wood of infected trees becomes extraordinarily brittle, large branches, and even the main trunk, snapping off in an ordinary wind. As the root apparatus also perishes at the same time. the trees are not unfrequently blown down, notwithstanding that there are few species more firmly rooted than the babul.

2. At my inspection of the Loni and Bhongaon forests in 1902 I was struck by the intensely sickly condition of most of the younger crops. The fungus infection did not, of course, escape my notice, but I attributed the unfavourable aspect of the crops originally to unhealthiness due to overcrowding, and hence considered the fungus invasion as a mere consequence, its rapid extension being directly favoured by the closeness of the growth and the resulting intimate root-contact between neighbouring individuals. I accordingly had the overcrowded crops in Loni thinned by Rai Bahadur Mansukh Rai and Mr. Martin, working together in consultation. Although a spirit of extreme caution governed the operation (no doubt because it had been recorded in the working-plan, and apparently accepted by the Inspector General of Forests, that thinnings in babul forests were harmful), nevertheless the beneficial effect of even this moderate opening out of the growth has, after so short an interval as a single season of vegetation, been most marked. The young babul, which had not only absolutely ceased to develop, but were already full of dead twigs, have expanded their crowns to the full extent for which there was room and have now a comparatively healthy appearance. This striking result seemed to confirm the conclusion provisionally arrived at that the fungus invasion spread mainly, if not entirely, by way of the roots The reply, received to a reference made to him on the subject, from the Cryptogamic Botanist to the Government of India, however, lends no support to this conclusion, although it does not entirely put it out of court (see attached copy of correspondence).

3. I would hence ask you to undertake, under your personal supervision, carefully conducted experiments with a view to ascertain and establish beyond question the way or ways in which the infection spreads. If, as we may assume for a certainty, the

spores at the commencement of an invasion gain entrance into a healthy individual through a wound above ground, it is still possible that further infection spreads below ground by means of the mycelia when the roots of the original victim come in contact with those of its neighbours. Should such prove to be the case, it is obvious that the mycelia-infested roots of the felled crop will always remain a certain source of infection in the soil for the succeeding crop, if this is raised before the mycelia perish, and the question then arises whether a sufficient interval of years should not be allowed to elapse between the felling of the one crop and the establishment of the other, the soil being further deliberately purified by taking off it a succession of agricultural crops, which would also compensate the Department for the period of waiting. I should be glad to be informed, as soon as possible and before the commencement of the operations, what you propose to do in your Division to promote these enquiries. The *Fomes Pappianus* is so great an obstacle to the prosperous growth of our babul forests and to the maintenance of trees until they attain the size of timber that a study of its life-history and of the most effective practical method of combating it cannot be undertaken too early or prosecuted with too much zeal

4. You will, at the same time, adopt without delay the plan recommended by the Cryptogamic Botanist (*i*) of having men constantly engaged in removing the sporophores as soon as they appear so as to endeavour to prevent spore formation, and (*ii*) of removing by preference in your thinning operations trees bearing sporophores.

5. In order to ensure systematic enquiry and work a special journal will be kept in your own handwriting, in which will be recorded clearly and in sufficient detail as regards dates, method, etc., all experiments and operations carried out and observations made. On the 1st June in each year a summary of these entries for the preceding twelve months, with the necessary commentary, will be submitted by you to this office.

Copy of demi-official letter, No. $\frac{234}{\text{VI}}$, dated the 5th March 1903, from the Cryptogamic Botanist to the Government of India, to the Conservator of Forests, Berar.

With reference to a parcel of specimens of a fungus and the attacked wood of *Acacia arabica* on which it was growing, received through the Superintendent of Royal Botanic Garden, with your letter to Doctor Cunningham (retired), dated Camp, 17th January 1903, I beg to say that the fungus is *Fomes Pappianus*, Bres., described by Bresadola on the trunks of acacia (species not mentioned) in Somalia in 1896. I have no information regarding it, and I doubt if it has been since mentioned by any one. Its action as a destructive parasite is not remarked on by Bresadola.

As, however, it is a close ally of *Fomes (polyporus) ignarius* and *Fomes fulvus* it is likely that, like them, it gains its entrance through wounds by air borne spores, unless you have some definite reason for believing that it starts underground. In the latter case the treatment proposed by you is likely to be efficacious, but in the former it will have no effect. The only course would then be to have men constantly engaged in removing the sporosphores as soon as they appear so as to endeavour to prevent spore formation; at the same time to fell by preference trees bearing sporophores.

Copy of letter, No. 464 (Camp), dated the 16th March 1903, from the Conservator of Forests, Berar, to the Cryptogamic Botanist to the Government of India.

I have the honour to acknowledge the receipt of your demi-official letter No. $\frac{234}{VI}$, dated the 5th current, for which and for the valuable information so kindly given please accept my warmest thanks.

2. I had no certain ground for supposing that the *Fomes Pappianus* gains entrance into its host by way of the roots. Having noticed that babul trees standing apart from one another are seldom attacked, whereas in a close plantation scarcely a single individual is free from the pest, I thought it likely that the infection spread underground owing to root-contact. And this belief was apparently supported by the fact that young babul crops that were suffering very badly before they were thinned last hot weather are now in a much healthier condition. I will now, however, as soon as I have the opportunity, explore the soil in infected areas and report to you the result. Moreover, an infected area of about 40 acres, which is being felled and will be put under field crops for three successive years, beginning from the coming rainy season, will serve as a *champ d'expérience*.

V.—SHIKAR AND TRAVEL.

A Dead Elephant.

As the discovery of the remains of wild animals seems to be a rare thing, possibly the following instance may be of interest.

Several days ago some of the coolies employed on working-plans by me in this division brought back to camp a fair pair of elephant's tusks and reported that they had found a large tusker lying dead in the sample area which they had counted out.

From their description and as they seemed to think that the elephant's death was due to an accident, I thought the remains might be worth visiting. Accordingly I went to the place next day and observed as well as I could, considering the smell, the position and surroundings of the carcase.

It was lying at the source of a small nulla. The surrounding jungle was densely evergreen, consisting of trees, canes and the creeping bamboo (*Dinochloa Maclellandii.*) A nearer approach revealed the swollen carcase of a full-grown elephant, lying on his back with the top of his shoulders wedged in between the banks of the streamlet, his legs in the air, his mouth open and his trunk hanging over in a down-stream direction—a disgusting sight.

The streamlet in question hardly deserved the name, being only the commencement of a little rivulet. It was about three feet deep and just wide enough to keep an elephant placed on his back (if such a thing can be imagined) in position. The elephant had apparently slid on his side down a steep bank about 10 feet above where he was found.

I do not think this elephant's death was due to his accidentally falling off the bank, getting wedged in the stream and being unable to extricate himself. From the appearance of the bank the ground had not given way, and the elephant appeared simply to have fallen on his side and slid gradually down the slope into the position in which he was found.

What further makes me be of opinion that the elephant was in a dying condition when he fell off the slope is that the banks of the stream being of a soft sandy soil by struggling an elephant could easily extricate himself, and there appeared to be no signs of any struggling having taken place.

Perhaps this was a case of an elephant's death being due to snake bite. There was a large swelling just above the knee of one hind leg, but this may have been due to putrefaction.

The lower part of the stomach and part of one hind leg had been eaten by a tiger, who had settled in the neighbourhood and was paying periodical visits to the remains, but it is improbable that the tiger had anything to do with the elephant's death.

SHWEGYIN : }
20th March 1903. }

H. W. A. WATSON.

VI.—EXTRACTS, NOTES AND QUERIES.

A Redwood Lumber Plant.

By Enos Brown.

One of the results of the prosperity which the State of California is now enjoying is the revival of the lumber interests and the remarkable demand for export of the product of its redwood forests. Conditions are quite unprecedented. The redwood is found only in California, and in but a comparatively contracted area even there. From Santa Cruz county on the south to the Oregon line on the north it attains full development, but lower than Medocino county, owing to vicinity of the great market, the forests have been about exhausted and these localties are no longer considered producers A considerable acreage in Santa Cruz county has been recently appropriated as public domain. The available redwood, therefore, is now confined to about 318 miles of coast. The annual product in this region is about 320,000,000 feet, and it is estimated at the present rate of consumption that enough standing timber exists to last for 150 years.

The redwood is rarely found beyond the reach of the ocean fogs, its extreme limit being thirty-five miles inshore, and then only when some valley-like depression prevents the entrance of fog to that distance. The tree seems to have an affinity for the salt sea fog, and attracts it about its lofty branches. There it condenses and falls to the ground in a gentle rain. The ground under the redwood tree is always moist.

The redwood is the *Sequoia sempervirens* of botanists, and is distinct from the *Sequoia gigantea* of the Sierras. The first is never found far from the sea, the latter always in the declivities of the Sierra Nevadas and seldom at an altitude lower than 4000 feet, and in a region where the rainfull is never excessive. In size they are much alike. The few remaining groves of the *Sequoia gigantea* are in Mariposa and Calaveras counties, California, and some of them are 400 feet in height and of tremendous girth. The timber is inferior to that of redwood, which is noted for endurance and strength. Its resistance to fire is no fable, but a sober fact. The lumber is becoming more in demand for decorative purposes. Its colour, a light salmon when first cut, afterwards turns to a deep red. When thoroughly dried there is no shrinkage, and it readily yields to the chisel of the carver. Piano cases made from the wood are said to give increased resonance to the instrument. Large quantities are consumed for interior finishing, with gratifying effects. In addition to other fine qualities the wood takes on beautiful polish, and even the stumpage, until recently considered worthless, is found to possess valuable qualities. The roots and woody excrescences at the base of the tree give fine effects in wavy outlines, and when polished the result is a material much valued for decorative purposes.

In the Eel River redwood district, Humboldt county, there are 80,000 acres of timber lands, which will produce at a low estimate 75,000 feet to the acre. In size the trees range from four to six feet in diameter; if below 18 inches they are left standing. Of the larger sizes from 8,000 to 12,000 feet is produced from each tree.

The tree illustrated was a growth of this valley and produced 80,000 feet of merchantable lumber.

Felling one of these enormous trees is an operation requiring great experience on the part of the woodsman. In the first place a tract is selected containing a goodly number of the proper sizes, as well as being advantageously located for getting the logs to the railroad for conveyance to the mill. The experience of the cutter will indicate the first and next in order to be felled. Each tree must lie in its own bed.

A platform is then erected surrounding the trunk from 6 to 8 feet above the ground. With a saw an undercut is made through the trunk, not quite to the centre, and from the opposite side a cross cut is sawed, ending a foot or two above the undercut and leaving a section of solid lumber between. The "gunsight," or the place where the tree is to fall, is then calculated to a certainty, and the ground cleared of all projections that would prevent the great trunk from falling flat on the earth. The woodsman who cannot calculate within a few feet the exact spot where the extreme top of a tree, no matter the height, will lie when down does not know his business. The rule is that when ten per cent. of a tree is "split" when felled, the chopper is incompetent and is discharged. When the exact place where the tree is to fall is selected, the choppers ascend the platform, and with axes hew out an angular shaped piece having the undercut as a base. When this cut is made the second, or crosscut, is wedged until the tree topples over and falls to the ground, the solid section of the trunk not pierced by the cuts, supporting the tree until the centre of gravity is passed, and then the mighty frame falls upon its prepared bed almost intact.

The next operation is performed by the "ringers" and "peelers." Every 12 or 14 feet, as required, a ring is cut around the circumference of the bark, and afterward the peelers with crowbars and wedges "peel" the bark from the prostrate trunk. Finally all of the trees are stripped, but surrounded with an immense accumulation of debris of bark and branches, which must be removed before the trunks can be sawed into suitable lengths for conveyance to the mill. The ground is cleared by fire, precaution being first taken to plug up the "splits" in the trunk with clay so that the fire may not reach the interior of the tree. A foggy day is chosen and a still one. Fire is started and in a short time the track is burning with a fierce heat that quickly reduces the piles of bark and brush to ashes, and leaves an unobstructed field for the removal of the timber, which has been scarcely charred by the intense heat to which it has been subjected.

The trunks as they lie are then cut into stated lengths with crosscut saws and then follows the arduous task of conveying these enormously heavy sections to the railroad. This operation is one of extreme difficulty, involving the transportation of the logs from the high and precipitous hillsides, and conveying them uninjured over long distances.

Temporary skidways are laid down and roads constructed. Chutes down which the logs pass have to be planned, and on these, guided by the skilful woodsmen, the unwieldy logs at last reach their destination. The work is laborious in the extreme, and is assisted by donkey engines on sleds, which are hauled to the top of the steep banks and into seemingly impossible situations. With the aid of these engines loading on cars is accomplished without special difficulty. Twenty-five miles of broad gauge track penetrate into all parts of this district, and 180 flat cars are employed in transporting the timber and finished products.

Scotia, the town where the immense manufacturing plant of the Pacific Lumber Company is located, is situated twenty-five miles from the mouth of Eel River. Schools, churches and dwellings are owned by the Company, as well as the land upon which they are built. It is a community prosperous and contented. The pond at the millside has room for 4,000,000 feet of logs, which are drawn upon when the rains of winter season render logging impracticable. The capacity of the mill is 175,000 feet per day, exclusive of 500,000 shingles and large number of railroad ties.—*Scientific American.*

Transvaal Forestry.

MR. D. E. HUTCHINS, the Cape Conservator of Forests, who read a paper before the Society in 1899 on "National Forestry," has lately addressed the Transvaal Section of the South African Association at Johannesburg, on "Transvaal Forestry."

He stated that before the war there was a yearly average of close on half a million pounds' worth of timber imported through Cape and Natal ports, and £140,000 worth through Delagoa Bay; the larger part of this going through to the Transvaal. Half a million pounds' worth of timber came through Cape ports during 1901. Of this the greater portion was soft wood used in house building, and most of the balance hardwood for sleepers. Return of timber imported into the Transvaal, 1897 and 1898 -1897: Manufactured, £258,741; unmanufactured, £178,145; total, £436.886. 1898: Manufactured, £217,447; unmanufactured, £130,013; total, £347,460. During the last 21 years the Cape Administration had spent over a quarter of a million on forestry. Timber was a necessity in a civilised country. Civilised man could no more do without timber than without air and water. It was not at all unlikely that the Transvaal during the next few years would require half a million pounds' worth yearly of unmanufactured timber or lumber. Was this to be brought 6000 or 7000 miles by sea from Australia or Europe? Obviously, the Transvaal could grow much of its own supply at a good profit. The Transvaal forestry possibilities can no more be allowed to lie idle than its mines. The Transvaal has a forest-producing power which is many times that of Europe, and every month that is lost in putting this forest-producing power into action is a dead loss to the country. What is required at once is the demarcation of the forest reserves, that is to say, the areas which will form the future national forests of the country, and the setting aside of funds, say £100,000 yearly, to afforest those reserves. After giving further details, the lecturer concluded as follows:—"Forestry should be regarded not as a branch of agriculture to be assisted by a benevolent Government, but as a great public work of pressing necessity. We have seen how, on the most moderate computation, most kinds of timber can be grown at a profit of 400 per cent., and the present high price of timber reduced by two-thirds. The good soils and fertility of the Transvaal are proverbial in South Africa. Foresters' measurements show how powerful is the vegetative process in the Transvaal, and how vast the wealth of its potential forests. The coal deposits are evidence of the rich vegetation of the past. And let us not forget the ennobling effect of forests, their fostering the love of the beautiful in Nature. Your coal is grimy, your gold is in the gloomy mines, but your forests should be the pastime and glory of your people, the health and wealth of your children."—*Journal of the Society of Arts.*

Retirement of M. Fliche

M. HENRI has been appointed Professor of Natural Science at the Ecole Forestière at Nancy in place of M. Fliche, who has retired after having tought Botany there for nearly 40 years. M. Fliche, who is a great expert in paleontological botany, will now have ample leisure to devote to that subject.

VII.—TIMBER AND PRODUCE TRADE.

Churchill and Sim's Wood Circular.

2nd April 1903.

East Indian Teak—The deliveries for the past quarter amount to 2,514 loads as compared with 3,436 loads for the first quarter of 1902, and for March this year they have been 948 loads against 766 loads for March, 1902. The stock remains at practically the same level as a month ago, having been fed in the meantime by small arrivals of Java wood Prices continue firm, though with hardly so much life as last month, and the position ahead remains totally unfavourable to any likelihood of a return to normal supplies.

Rosewood, East India.—For prime, large logs there is a fair demand, but inferior wood is of very slow sale; stocks, however, are quite moderate.

Satinwood, East India.—The stock is considerable, but for finely-figured logs good prices are freely paid.

Ebony, East India.— For sizeable and really good logs there is a fair demand.

PRICE CURRENT.

Indian teak, logs, per load ...	... £10 5*s*. to £18 10*s*.
„ „ planks „	... £13 5*s*. to £20.
Rosewood, per ton ...	... £8 to £11.
Satinwood, per s.ft. ...	... 6*d*. to 18*d*.
Ebony, per ton ...	... £8 to £12

Denny, Mott and Dickson, Limited.

WOOD MARKET REPORT.

London, 1*st April* 1903.

Teak—The landings in the docks in London during March consisted of 378 loads of logs and 524 loads of planks and scantlings, or a total of 902 loads, as against 139 loads for the corresponding month of last year. The deliveries into consumption were 510 loads of logs and 437 loads of planks and scantlings—together 947 loads, as against 1,002 loads in March, 1902.

The dock stocks at date analyse as follows: —

	5281	loads of logs,	as against	8031	loads at the	same date	last year.
	2780	„ planks	„	3609	„	„	„
	—	„ blocks	„	—	„	„	„
Total	8,061	loads	„	11,640	loads	„	„

As shown by the above figures, the demand for teak continues to be checked by the increased cost, but also continues to be consistently above the imports. Consumers are now facing up to rates which should tempt larger shipments, if they could be made; but the shippers are genuinely unable to meet the demand, and as the year advances the position must become more stringent, seeing that no fresh timber from the forests can come to hand for arrival in Europe before next year. The anxiety of all concerned in the market on this side is how to buy rather than how to sell, and business must suffer in volume accordingly.

Business for the quarter of the year just closed has been of a difficult and anxious nature. F.o.b. prices have been alarmingly high in most descriptions of wood goods, and with a sluggish consumption and a tight money market, wholesale buyers have been fairly intimidated and business has suffered accordingly. Yet, natural causes have reduced the supplies of many descriptions of timber at the shipping ports, notably in the case of Canada, America and India, and. consumer's ideas of prices must be adjusted accordingly. In respect to Baltic goods, the struggle between shipper and importer has been of a more even character, as there is little doubt that there is not sufficient shortage in the production to enable the shippers to starve the market here; and although the merchant on this side may overstate the sufficiency of stocks here to render him independent of fresh supplies, yet the shipper will be eventually forced to make some concession in price, if business is to flow into the usual channels.

Market Rates for Products.

TROPICAL AGRICULTURIST.

1st *April* 1903.

Cardamoms ...	... per lb.	1s. 6*d*. to 1s. 9*d*.
Croton seeds ...	... „ cwt.	15s. to 25s.
Cutch ...	... „ „	25s. to 30s.
Gum Arabic ...	... „ „	15s. to 20s.
Do. Kino ...	... „ „	75s. to 120s.
India-rubber, Assam	... „ lb.	2s. to 3s.
Do. Burma	... „ „	2s. to 3s.
Myrabolams, Madras	... „ cwt.	5s. to 6s.
Do. Bombay	... „ „	4s. to 7s. 6*d*.
Do. Jubbulpore	... „ „	4s to 5s 6*d*.
Do. Bengal	... „ „	3s. 6*d*. to 5s.
Nux Vomica	... „ „	7s. to 10s.
Oil. Lemon-grass ...	... „ lb.	5*d*. to 5½*d*.
Orchella weed, Ceylon	... „ cwt.	10s. to 12s 6*d*.
Sandalwood, logs ...	... „ ton	£15 to £30.
Do. chips ...	... „ „	£4 to £8.
Sapanwood ...	... „ „	£4 10s. to £5 15s.
Seedlac ...	... „ „	117s. 6*d*. to 120s.
Tamarinds, Calcutta	... „ cwt.	8s. to 10s.
Do. Madras ...	... „ „	4s. 6*d*. to 6s.

THE
INDIAN FORESTER.

Vol. XXIX] July. 1903. [No. 7.

Notice to Subscribers.

The *Indian Forester* Committee of Management mentioned in the issue of May last (No. 5) has now been formed. It consists of Messrs. Manson (Burma), McIntosh (Dehra Dun School Staff and Madras), and Stebbing (India), with Mr. Stebbing as Honorary Editor. Until the return from leave of Mr. McIntosh another officer of the Dehra Dun Staff is acting for him.

The Committee intend to consider fully the present position of the Magazine, and will publish the decisions and proposals arrived at with a view to making the *Indian Forester* interesting and worthy of the Department it represents.

In the meantime they would ask Members of the Service and others interested in the Magazine to endeavour to contribute articles with greater regularity. It is well known that vast stores of valuable information are month by month and year by year accumulated in notes, letters, and reports which never get beyond the offices of the Division, Circle or Local Administration, and yet much of the material contained in them would be of great interest to officers working in other parts of the country. Again, men serving in the north of India know little of what their brother officers are doing in the south, or in Burma, and nothing of the conditions under which their work is performed. Notes on these and cognate subjects would be of great interest and, whilst serving to bring the Members of the Service more in touch with one another, would raise the status of the *Indian Forester* and make it a worthy exponent of the work and thoughts of the great Scientific Department it represents. The Committee of Management trust that their endeavours in this respect will receive the loyal support of the Subscribers to the Magazine.

All contributions should in future be addressed to the Honorary Editor, E. P. Stebbing, Indian Museum, Calcutta.

The American Bureau of Forestry.

The American Bureau of Forestry came into existence a little over a year ago, and its first year's work is treated of in a Report published by its Chief. In this paper * we propose to glance at the year's work and to show what the objects of the Bureau are. We may premise by saying that the Bureau is under the Agricultural Minister, and that it has charge of the scientific and technical work of the Government. It consists of a Chief called the Forester, under whom are a number of specialists who study the numerous important technical questions which, if a good and successful forest management is to be ensured, require to be worked out.

Amongst the scientific problems which call for the services of specialists may be mentioned the following:—The careful study of the various forests with a view to the preparation of working plans, the study of commercial trees and minor products, fires and grazing, chemical questions, planting, forest entomology, etc. One and all of these subjects are in America studied on the spot by men who devote their whole time and energies to the particular branches they have made their own. To facilitate the research work the Bureau has certain small but important Reserves under its management where experimental work is being constantly carried on.

It can scarcely be doubted, I think, that this is the way to ensure the best results being obtained—both monetary and otherwise—from the forests of a country. Enquiries so carried out and recommendations made, based on the broad views formed by men with a knowledge of the requirements of the country as a whole and not upon an acquaintance with small local areas only, are likely to prove much more satisfactory than the unavoidably narrower ideas of the local officer in charge who naturally works for his own forest with but little idea as to what may be being done in the same direction, with a better chance of success, elsewhere.

The work of a coterie of specialists has been found to be a great success from a commercial point of view, as the cost of upkeep of such an establishment is soon repaid by the greater revenue which their researches and recommendations enable the local officers to obtain from the forests under their charge.

During its first year as a Bureau, what was known in America formerly as the Division of Forestry has rapidly assumed the character and functions of its new position. With the increased capacity to do its work, the Bureau has gained in stability and effectiveness, and in the character and value of its results. While, owing to the lack of American foresters, it yet falls below a

---

*This article is based on an excellent summary of the Forester's (the Chief of the Bureau) Report in our contemporary 'Forestry and Irrigation.'—Hon. Ed.

high standard of equipment in trained men, a larger proportion of educated foresters than ever before was engaged in its work, both in the office and in the field during the year. The organization of work made possible by the change from a Division to a Bureau has been of capital value throughout the year.

The progress of public interest in forestry during the year far more than kept pace with the growth of the Bureau. The demands for advice and assistance increase from month to month, and continue to outstrip more and more the ability of the Bureau to meet them. The time for the general introduction of practical forestry in the United States has evidently arrived, and the difficulty experienced is to meet all the calls now made upon it. The inability of the Bureau of Forestry to meet this demand because of inadequate resources is thus the most serious bar to the protection and perpetuation of our forests. With, however, the rapid extension of professional education in forestry, the need of the Bureau for trained foresters can, it is hoped, next year be met more nearly than ever before In view of the increasingly rapid destruction of the forests, it is most fortunate that the imperative demand for assistance in checking the loss is paralleled by the opportunity to supply the demand. A money grant is required for the work.

Division of Forest Management.

Private lands.—Of course private forests are numerous and of great value in the United States, and the demands for assistance in introducing practical forestry on these private lands increased during the past year almost as much as during the three preceding years. These applications have now reached a total of 4,709,120 acres, under an arrangement by which the owners pay all expenses of the field work except the salaries of members of the Bureau.

The total area of private forests under conservative management, however, reached only the comparatively insignificant total of 372,463 acres, or 7·9 per cent of the total applications. The Bureau has thus been obliged, owing to lack of men and money, to neglect or defer over 90 per cent of its opportunities to introduce practical forestry on private lands.

As the greater bulk of the forests in the United States are in private ownership, it follows that forest protection by the Government, while absolutely of vast importance, is relatively insignificant when compared with the action of the lumbermen and other private owners. In the light of these facts, the inability of the Bureau to respond to more than 8 per cent of the requests for advice in applying the principles which it continually advocates is seen to be the most dangerous of all checks on the progress of forestry.

Field work on seven large forest tracts was completed during the year. and preliminary examinations were made of 1,620,000 acres. The amount paid by the owners for the preparation by the Bureau of working plans for their forests was $13,325.

Public lands.—The preparation of working plans for conservative working in the public forest reserves has, at the request of the Secretary of the Interior, continued throughout the year. The total area of these reserves on September 1, 1902, was 58,850,925 acres. Field work was carried on during the past year in five reserves. In addition to field work and the computation of results in the office, the force of the Bureau was drawn upon to supply the entire number of trained foresters required for the management of the national forest reserves.

During the year a request was made by the Secretary of War for working plans for eight military wood and timber reservations, with a total area of 117,468 acres. Among these is the military reservation at West Point, upon which field work will be begun without delay.

Field work was completed on townships 5, 6, and 41 of the Adirondack Forest Reserve, by the use of an appropriation of $3,500 made by the New York Legislature to cover the field expenses of the Bureau of Forestry.

Forest measurements.—The force employed in computing field results was thoroughly organized. It completed during the year computations of 16,678 acres, and measurements of the rate of growth of 10,786 trees, of 25 species, in 13 States.

DIVISION OF FOREST INVESTIGATION.

Commercial trees.—Measurements and sylvicultural facts were gathered for 20 species in various parts of the country. Studies of hardwood sprout lands were carried on in Massachusetts and other parts of New England, and promise valuable results. A special investigation of the Big Trees of California was begun, and is still in progress, and a preliminary study of the swamp forests of eastern Missouri and Arkansas was undertaken.

Studies of North American Forests.—The forests of Nebraska were made the subject of an elaborate report, and at the request of the Michigan Forest Commission an investigation of lands in the southern peninsula of Michigan was made, with special reference to the proper management of the Michigan Forest Reserve. Special studies of forest conditions were pushed forward in Kentucky, Ohio, and Texas, and of the distribution of forests in certain portions of New Mexico, Arizona, South Dakota, Wyoming, Montana, and California. In California the study of the relation of forest cover to the flow of streams was continued, and the results will shortly be ready for publication. In co-operation with the U. S. Geological Survey, the study of the Sierra Forest Reserve was completed. In Vermont a co-operative study of the forest resources and conditions of the State was completed, and in Maryland the mapping of the forests by counties, begun in 1899, was continued. Attention was given, both in the office and in the field, to the region of the proposed Appalachian Forest Reserve.

Fires and grazing.—Investigations of the effect of grazing on the forest were conducted in Washington, Oregon, Wyoming, New Mexico, Utah, and California. The study of forest fires was conducted in twelve States, and the preparation of a report upon this subject is in hand.

Chemical investigations.—Special attention has been given during the year by the Bureau specialist to the chemical investigation of tan extracts from native woods and barks, and of gums from the Philippine Islands. The study of pulp woods, with special reference to the qualifications of untried species, has been carried forward. The great commercial value of these investigations needs no dilating upon here.

Turpentine orcharding.—The investigation conducted by the Bureau into the methods of producing naval stores in the South-Eastern United States has resulted in the development of a method which it is believed will radically affect the whole industry. A report is in preparation describing its actual operation.

Forest entomology.—A commencement has been made in the investigation of insect damage to the forests with the direct purpose of devising remedies. The vast importance of the subject makes the continuance of this work imperative, and the work is being pursued with energy by a specialist.

Various studies.—Investigations of the lumber industry of the State of New York and the Maple sugar industry of the United States were completed, and a study of the osier willow industry was begun.

A careful investigation of the Eucalypts and Acacias cultivated in the United States was completed, and bulletins were prepared for each.

Timber conservation and supplies.—In co-operation with the Bureau of Plant Industry, great progress was made during the year in arousing the interest of mining and railroad companies in the preservation of timbers and in the sources of timber supply. The practical assistance of many railroads toward the establishment of conservative forestry was begun, and the work shows conspicuous promise.

Forest exhibit.—A forest exhibit was prepared and installed at the Pan-American Exposition, at Buffalo, and later transferred to Charleston, S. C.

TREE PLANTING.

Planting plans.—The co-operation of the Bureau of Forestry with the owners of timber land is paralleled by its co-operation with the owners of treeless areas who wish to plant. Up to June 30, 1902, there were received 262 applications for assistance, in response to 224 of which planting plans were prepared. In the course of the work 197,439 acres of land were examined. The area to be planted under plans already prepared is 6,474 acres. These plans cover 29 States and territories and 172 different localities.

Planted woodlands.—In order to use the information already at hand from previous planting, careful studies of 20 large plantations, 8 in the Middle West and 12 in the East, were carried on during the year. A similar study is now under way to find trees adapted for the south-western plains.

Forest extension.—Studies of the natural extension of forests were continued during the year. A careful forest survey of a large part of Nebraska was completed, and resulted not only in arousing great interest throughout that State, but in the creation of two forest reserves for tree planting, a most valuable contribution to the forest policy of the United States.

Reserve planting.—Preparations for planting considerable areas in the two reserves in Nebraska were made during the latter part of the fiscal year.

Sand dunes.—Investigations with a view to preventing damage from drifting sand dunes were begun during the year, both on the Atlantic and Pacific coasts, and promise results of great value, especially along the Columbia River.

OFFICE WORK.

The office work of the Bureau has continued to increase steadily in efficiency throughout the year.

The collection of forest literature from the Department library was transferred to the library of the Bureau, which now contains 1,120 bound volumes, 1,900 pamphlets, and numerous periodical publications.

Eight new publications and ten reprints were printed during the year with a total number of 77,200 and 127,500 copies respectively.

The photographic collection was largely increased, and is now serving as the source from which nearly all forest illustrations are derived. In this connection a photographic laboratory has been prepared at the quarters of the Bureau, and was nearly ready for occupancy at the end of the fiscal year.

Although American forestry is in its infancy, the above summary of the Bureau's report for the first year of its existence shows that the Forest authorities have thoroughly realized the position of affairs, and, headed by their President, himself an enthusiastic advocate of a broad and liberal forest policy and the prompt formation of large reserves as his recent speeches in Congress bear ample witness to, they are undoubtedly on the straight road which leads to success.

That they should thus have grasped so accurately the true lines upon which a broad and enlightened forest policy should be based is doubtless in part due to the great power the nation possesses of going unerringly to the root of a question and seizing and applying only the best of the methods practised by other countries to their own ends. Nevertheless we feel that to the fortunate possession of, and moral support given by, such a President as Roosevelt at this juncture the American Forest Department doubtless owe much of their present enlightened methods of dealing with the subject. An ardent sportsman and a deep and true lover of nature, President Roosevelt has roamed about the vast forests himself, and seen for himself the great necessity of their preservation and restoration to something of their prestine greatness. It was at once grasped that to carry out such a work satisfactorily, and to ensure a continuity in the careful study of each of its individual scientific and commercial aspects the services of specialists in each of these were necessary, and the securing of such and their collection together into one Bureau, after the manner of the great European Forest States, followed in the natural sequence of events.

We trust to give in our next issue 'Notes from an American Forest Reserve,' in which the local Forest Officer gives his opinion on the satisfactory position of affairs, and tells us about his side of the work.

Damage to teak by drought in the Panch Mahals of the Bombay Presidency.

A good deal has already been written with regard to damage done to forests by drought during the famine year of 1899-1900. I however venture to add some further remarks regarding the damage done to teak in this division, hoping it may interest some foresters who have to deal with forests under similar circumstances.

The Panch Mahals are situated on the extreme northern limit of teak growth in western India, and consequently trees of large dimensions are not found. The soil varies from sandy loam to black soil. The country is generally speaking flat, except in the extreme north where small hills occur, caused by outcrops of granite, gneiss and small quantities of slaty schists. The depth of the soil varies from 1 to 5 feet, after which rock or hard murrum is found. The rainfall is about 40 inches and the altitude [illegible] ft.

The forests consist of nearly pure teak and teak mixed with various other species, which need not be specified, as I only propose to speak of teak. It will be sufficient to state that nearly every forest contains at least 40 per cent of teak.

Of the standing teak in these forests an average of 45 per cent of the trees have been either killed outright or so much damaged that they will never improve. In some forests the drought has killed 90 per cent of the trees and over, while others have suffered less, but there is hardly an acre untouched.

When walking through these jungles the first point which strikes one is that trees of approximately the same age and size, standing within a few yards of each other, often give absolutely different results; one being completely dry and the other quite flourishing and untouched by drought. In other places you find patches of living trees covering an area of, say, 100 yards square and surrounded by dead trees, the surface soil being to all appearances similar and on the same level.

Where trees were found green, I put it down to a local depression of the subsoil. It however being unlikely that the level of the subsoil would vary from yard to yard, this would not hold good for trees standing side by side. The only way left to determine the cause was to dig up a number of trees in different forests, standing on different soils. This was done, taking whenever possible an entirely dead tree standing close to a living one, so as to compare the depth of soil and their respective root systems. As an example a few of the measurements of the sample trees are given below :—

No	Soil.	Age	Diam.	Height.	Depth of soil to rock or murrum	REMARKS
		Ft	In.	Ft.	Ft.	
1	Black .	26	6	26	3	Stem dry, roots green.
2	Do	27	9	3·	3	Quite green.
3	Do	35	9	27	2½	Stem half green, crown dry.
4	Do ..	28	10	31	2½	Entirely dry, both stem and root.
*5	Do .	25	7	30	2½	Ditto,
*6	Do	30	9	40	3	Quite green.
7	Sandy loam.	16	7	40	3	Ditto.
8	Ditto ..	28	6	35	2	Quite dry, both stem and root.
9	Ditto .	29	7	45	2½	Ditto.
*	*	*	*	*	*	

The ground below the depth given above was found to be either rock or hard murrum. It will be seen the soil does not vary in depth more then 6 inches except in No. 9.

---

* Illustrations of the root systems of these two are given.

Now a variation of 6 inches could hardly account for a tree being completely dry or green, so the cause had to be looked for elsewhere One had not far to search, for, firstly, those trees which were found green had central or tap roots going down to the hard layer, and, secondly, their large spreading roots were generally speaking found to be sloping downwards in the subsoil and to be more vigorous. On the other hand, the dry trees were found to have practically no tap roots and their spreading roots were lying only a few inches below the surface. The two illustrations,* one of the roots of a green tree (Fig. 1), and the other of a completely dry tree (Fig. 2), are fairly typical examples, and will better explain the condition of the root systems, though the roots of the green tree shown do not slope downwards as much as some of the other sample trees dug up.



Fig. 1 *Roots of a Green Tree.*



Fig. 2 *Roots of a Dry Tree.*

So severe has been the damage that it has been deemed necessary to suspend the proper working plans† and introduce temporary plans for cutting out the dead and half dead teak and other species. Luckily there is an excellent demand for fuel and rafters, so that the work can be carried on rapidly, and will probably be completed by the end of 1905. Had the demand been poor, most of this wood would have been destroyed by fires, which are extremely hard to keep out of these very inflammable jungles.

---

* The illustrations are from drawings made from photographs sent by the Author.—HON. ED.

† We believe we are correct in stating that this had to be done in the Seoni Teak Forests of the Central Provinces in 1901 for similar reasons. It would be interesting to hear whether any examination of the root systems was made in that locality. Perhaps the Divisional Officer would kindly let us know in these columns.—HON. ED.

For the purpose of finding out the cause of death, the sample trees taken were of the two extremes, *i. e.*, quite green or entirely dry. The reader might therefore be wrongly lead to believe that all damaged trees were lost to the forest; the entirely dry ones are gone, but there is a redeeming point in the situation, and that is that of the greater percentage of the damaged trees though the stems are dry the roots generally speaking are green or partly so, so that, the forests being worked on a coppice system, the regeneration is secured, always provided the young shoots are not killed by fire.

R. S. P.

The Insect World in an Indian Forest and how to Study it.

BY E. P. STEBBING, F. L. S, F. E S.

(Continued from p. 238).

PART VIII.

THE ORDER *HEMIPTERA* OR *RHYNCHOTA*.

The *Hemiptera* or Bugs are perhaps better known as Rhynchota. They are insects whose mouth parts consist of a proboscis or beak (usually concealed by being bent under the body) which has the appearence of a transversely-jointed rod or sheath in which are enclosed long slender processes like horse-hair, which are used for piercing plant substances. The possession of this form of mouth parts renders it easy to distinguish the insects of this order. The Lice which belong here have not this jointed beak; these will be referred to later on. *Hemiptera* are without exception sucking insects, and the mouth parts of the individual are of one form throughout life, there being no pupal stage in the order. The thorax is always very distinct and often large, both the meso and meta-thorax being well developed and the scutellum of the former is frequently very large, at times covering the entire dorsal surface of the body. The wings are usually four in number. The upper half of the upper wing is in some cases horny, the wings then shutting flat on the back; or they may be membranous and fold on the back in a roof-shaped manner. The young resembles the adult in general form; the wings are developed outside the body by growth at the different moults.

There is often an ovipositor in the female About 18,000 species have been described, and there is probably no order of insects which is so directly connected with the welfare of the human race as the *Hemiptera*; it is probable that if anything were to exterminte the enemies of the Rhynchota man himself would be starved off the face of the earth in a few months. Their operations escape observation to a large extent, as they merely make pricks in the food plant and then suck away its sap without in many cases leaving any very evident marks of their former presence. Thus nothing being observable, injuries really due to *Hemiptera* often attributed to other causes.

For our purpose we will divide the order into two sub-orders. *Heteroptera* or true Bugs and the *Homoptera*, which include the scale insects, cicadas, blights, &c.

SUB-ORDER HETEROPTERA.

Front of head does not touch the coxæ (hips). The anterior wings are more horny than the posterior pair and fold flat on the back, their apical portions usually more membranous than the bases, which are horny. The lower portion of the right wing overlaps the left at tip.

FAMILY PENTATOMIDAE.

This is the largest family of the *Heteroptera*, including some 4,000 species The insects can be recognised by the large scutellum which is at least half as long as the abdomen and often covers the whole of the after part of the body and wings. Antennæ are often five-jointed and the proboscis sheath is four-jointed. Their ocelli are two in number, and thence there is an appendage to each tarsal claw. The colouration in these insects is often very vivid. This family contains a number of pests and one or two useful predacious insects.

An insect named *Ochrophara montana* has proved a serious pest to bamboo seed. The following is known about its life history:—It feeds in both larval and adult stages upon the developing seed of the bamboo, *Dendrocalamus strictus*. In 1900 it appeared in the Central Provinces in enormous numbers in the middle of January, and fed voraciously upon the ripening seed until the middle of March, and then disappeared, having probably laid its eggs somewhere first. Nothing further appears to have been recorded on the life-history of this pest *

Canthecona furcellata Wolff is a small active yellowish bug which is said to destroy tusser silk worms. It probably also feeds upon noxious defoliating caterpillars.

FAMILY COREIDÆ.

The members of this family are readily recognised by the following characters:—The scutellum is smaller than in the last and does not reach to the middle of the body; the proboscis sheath is four-jointed and ocelli are present; antennæ are generally elongate and four-jointed, and are inserted on the upper parts of the sides of the head. The femora of the legs are not knobbed at the tip.

---

* *Vide* Departmental Notes on Insects that affect Forestry, No. 1, p. 123.
Id. p. 126.

These insects are rarely of brilliant colours.

The family includes a very destructive species in India known in the Rice-sapper. An insect known as *Ceratopachys variabilis* feeds upon the jhand (*Prosopis spicigera*) in the Punjab and has the following life-history:—The bugs commence feeding in February, having hibernated through the cold weather months as half grown larvæ, becoming full grown in March. They then pair and eggs are laid. The next generation takes about ten weeks to pass through—two weeks being spent as a wingless larva, two with rudimentary wings and three whilst their rudimentary wings are becoming fully developed. The number of summer generations has not yet been ascertained. The insect finally hibernates at the beginning of November The eggs when first laid are of a brilliant green colour, which soon turns to reddish brown. The insect itself is green and red in colour. It appears to confine its attacks to one-year old coppice shoots.

FAMILY LYGAEIDÆ.

The characters of the members of this family are the same as those of the *Coreidæ*, the insects only differing in the insertion of the antennæ; the upper surface or face of the insect is not flat but is transversely convex, so that when seen in profile the antennæ appear to be inserted well down upon the sides of the head The family contains some injurious insects. Most of the known Indian species are reddish in colour such, *e.g.*, as the red cotton bug and other plant-feeding forms.

FAMILY REDUVIIDÆ.

These insects are easily recognisable by their freely moveable elongate head and by the short curved proboscis which does not extend on to the breast. They can at times inflict a wound with their proboscis. The eyes are placed much in front of the thorax and the ocelli when present are behind the compound eyes. The insects are only of importance owing to their predaceous habits. They feed upon other insects and probably destroy large numbers of injurious forms. Some members of the family live under bark and feed upon wood and bark-boring beetles. A species has been found engaged in this manner under spruce bark in N.-W. Himalayas.

FAMILY CAPSIDÆ.

These are moderate-sized or small bugs of delicate consistence. They have no ocelli present. The elytra and wings are usually large in proportion to the body. Antennæ are four-jointed, the second joint being usually very long and the terminal two more slender than the others. There is no groove on the under-surface for the proboscis to fit into. The scutellum is exposed and moderately large. Tarsi three-jointed. The female has an ovipositor which she can put out and draw in at will. The family is a large one, the insects being delicately coloured and never metallic. They frequent plants of all kinds and many of them skip by the aid of their wings with great agility in the sunshine. The majority suck the juices of plants, but some are known to prey upon other insects.

The best known Indian genus is *Helopeltis* to which the "mosquito blight" of tea belongs. These insects possess a knobbed spine projecting straight up from the scutellum. The egg is placed by the bug in the stems of the tea plant, but attached to one end of the egg are two long slender threads which project externally. The insects on hatching out suck up the juices of the plant.

Disphinctus humeralis Wlk. is a small insect which has been reported as attacking cinchona in Sikkim Little seems to be at present known about it

Note—The various bugs which live in water, known as *Cryptocerata*, belong to this sub-order. They are provided with swimming legs.

SUB-ORDER HOMOPTERA.

The front of the head is much inflexed so as to be in contact with the coxæ. The anterior wings are of the same consistency throughout and do not overlap at the tips. This sub-order is divided into three series according to the number of tarsal joints present on the feet of the insects—the *Trimera* having three, *Dimera* two and *Monomera* one tarsal joint respectively.

SERIES TRIMERA.

Tarsi usually three jointed.

FAMILY CICADIDÆ (CICADAS).

These insects are as far as is at present known seen above ground only in the perfect condition, spending the earlier larval stages in the ground upon roots. They can be recognised by having a head with three ocelli placed triangularly upon the summit between the compound eyes; the antennæ consist of a short basal joint surmounted by a hair-like process divided into about five segments. The front femora are more or less thickened and are armed with teeth.

The family consists of large insects with the four wings transparent and shining, the nervures being distinct and dark-coloured. The insects are sometimes brightly coloured, black and yellow being the predominant tints. The body is broad and robust. They are mostly tropical insects.

The cicadas produce the curious whirring sound which is so characteristic of the lower hill forests of India. The sound is produced by the male by means of a specially modified segments which can be seen at the base of the hind legs. The eggs are laid by the female in the branches of trees in which she makes incisions with her ovipositor. On hatching out the young larvæ crawl down to the ground and bury themselves in the earth, where they feed upon the roots and may spend several years in this stage of their existence. They usually, if not always, leave the ground before the last moult or shedding of the last skin, this being often done upon the trunks of trees, etc. After shedding this last skin the insects are fully developed; they then pair and lay eggs. The life-histories are little understood, but cisadas appear at intervals in swarms rather after the manner of the appearance of the N.-W. locust over India.

FAMILY FULGORIDÆ.

These insects can be best distinguished by the fact that the two ocelli present are placed beneath the eyes or near the eyes, usually in cavities of the cheeks. The antennæ are placed beneath the eyes and are very variable in form, usually consisting of two joints terminated by a very fine hair. The prothorax is not armed with spines, etc., and is of normal size. Some of the insects are very large, others quite small. The family includes the so-called Lantern flies, in which the front of the head forms a huge misshapen proboscis, which was formerly believed to be luminous. Many of the species are of bright colouration. A number have the power of excreting large quantities of a white floculent wax The wax of a Chinese fulgorid was used to make wax candles, in which there was a large trade before kerosine oil came into general use The insect known as White Insect Wax, *Ceroplastes ceriferus*, is an inhabitant of Central and Southern India. It secretes little conical masses of a sweet white waxy substance around it, and is to be found at times fairly numerous upon pipal trees. These white masses are sought for eagerly by jungle tribes, especially children. and eaten with relish. This wax was tried for candle purposes before the days of kerosine, as it was hoped that it would be able to rival the Chinese form, but it was found to burn with a smoky flame.

A large typical fulgorid was plentiful on the teak in the South Coimbatore forests in July 1902. Its history, which is likely to prove interesting, requires working out.

FAMILY MEMBRACIDÆ.

This family is of large extent, its members being chiefly tropical, and are specially abundant in America. and probably so in India, but little is known about them in this latter country. The insects are of curious form; the prothorax is prolonged backwards into a hood or processes of various shapes; the antennæ are inserted in front of the eyes, and there are two ocelli placed between the eyes. The young have but little resemblance to the adults, the great thoracic hood being absent, while on the back there is on each segment a pair of long half-erect processes having fringed margins.

FAMILY CERCOPIDÆ.

There are two ocelli (occasionally absent) which are placed upon the vertex, the antennæ are placed between the eyes. The thorax is not peculiarly formed

These insects are the common cuckoo-spits, so-called from the habit of the larvæ of emitting a liquid which it secretes in large amounts in the form of bubbles which accumulate round the insect and conceal it The adults are known as frog-hoppers, their power of leaping being very great Cercopidæ are common on the leaves of many trees in Indian forests, though at present very little is known about them

The eggs are laid upon the food plant, and the insect lives upon it in all its stages

A large cuckoo spit in its typical froth bubble was plentiful on the teak in the South Coimbatore forests in July 1902

FAMILY JASSIDÆ (CICADELLINÆ)

A large number of small or minute insects are included here The insects are usually of narrow parallel form and frequently excessively delicate and fragile Ocelli are two in number, placed just on the front margin of the head (almost in a line with the front of the eyes, or more in the front, or on the deflexed forehead) Hind tibiæ usually with many spines The mango jassids of which three species *Idiocerus niveosparsus*, *I. clypealis* and *I atkinsonii* are known, suck the juices of the young shoots, young leaves and flowers of the mango, at times to such an extent that light crops of fruit are the result

SERIES DIMERA.

Tarsi usually two-jointed.

FAMILY PSYLLIDÆ

Minute insects with usually transparent wings placed in a roof-shaped manner over the body, three ocelli are present and the antennæ are long and thin consisting of eight to ten joints. Very little is known about the Indian forms of this family. They are sometimes called springing plant lice as their habit of jumping distinguishes them from the *Aphidæ* They vary remarkably in colour, the latter apparently depending upon the age of the individual, the food plant the climate and more particularly the season of the year The insects probably pass through several generations in the year The young larvæ differ in form from the adult Psyllidæ excrete or exude from their bodies matter which is sometimes called honeydew; these exudations are often in large quantities, the substance raining down from the trees on to the vegetation beneath An insect named *Psylla cistellata* attacks and aborts mango shoots, whilst another, *Phacopteron lentiginosum*, forms galls upon the *Guruga pinnata* and a third galls upon *Diospyros melanoxylon*.

FAMILY.—APHIDÆ (BLIGHTS).

A large family of minute insects which are extremely injurious to vegetation, and are likely to be found very destructive in Indian forests when more is known about them. As usually met with they are destitute of wings, though many species have two pairs of transparent wings, which have a very characteristic neuration In the wing there is one main nervure which forks, and from the fork another forked vein is given off. This is characteristic of the Aphid wing. The antennæ are long or moderately so, and are from three to seven-jointed; the abdomen has often a pair of tubes or short processes upon the upper side of the fifth abdominal segment which secrete saccharine solutions. The first joint of the two-jointed tarsus is sometimes very short.

These thin-skinned insects are sometimes called 'blight,' and during the warm months of the year they are capable of increasing in enormous numbers This is due to peculiarities in their life-histories, which render this family a very important one in the economy of nature. The body is soft, often bulky, pear-shaped, and green, yellow, brown or black in colour. The surface is often covered with waxy blooms. Legs are feeble and the wings are often absent in the females. An Aphis is injurious owing to the enormous amount of sap it extracts from the plant on which it feeds, and also owing to the fact that it clogs up the stomata of a plant with the saccharine solutions which it exudes. A fungus often arises from this sticky solution. *e.g.*, in the case of the Bamboo Aphis, which is common in India, a black fungus grows in the sweet matter it exudes and forms a felt-like mass on the stems.

The eggs are laid on the plant in the autumn, and remain there till the spring, when there hatch out from them wingless females, which do not lay eggs but produce young parthenogenitically. This goes on till autumn, the young reaching maturity in a week or ten days under favourable circumstances, and bearing young parthenogenitically in their turn, the insect thus multiplying exceedingly rapidly and in very large numbers. In autumn the last brood produced are males and females, the latter being usually wingless These pair and eggs are laid. The winter is passed through in this stage, and the wingless stem mother hatches out in the succeeding spring. The life-history is sometimes varied by some of the females of the last generation having wings. These may then fly off to another plant, and lay their eggs on it. This occurs in the case of the genus Chermes, whose life-history we will shortly consider:—In this genus the winter is passed through by the stem mother, who takes shelter at the base of the shoots under a thick covering of wood, and can be found there in the spring, her proboscis buried in the bark of the shoot. She lays a number of eggs here, and these hatch out into larvæ, and the irritation caused by their feeding at the bases of the young leaves gives rise to a gall formed by the young leaves swelling up at their bases, the young larvæ becoming enclosed in chambers within it. The larva grow to full size here, and by the time the gall is ripe in the summer they have acquired wings, and when liberated spread over the plant. The effect of this gall is to cripple the shoots The insects which leave the galls are winged females, and a certain number of them migrate to another food plant, upon which they lay their eggs, which are covered with a cottony deposit. The males, which appear in the autumn only, pair with the females, and from the sexually produced eggs laid arise the stem mothers. The stem mother from the portion of the generation which flew to the second host plant lives through the cold weather under the bark and appears in the spring. The larvæ arising from the eggs she lays spread over the shoots and feed upon the juices of the needles, and winged individuals from these finally return to the first host plant. Thus we have two generations of the same insect feeding at different times on two different host plants and we get the phenomenon known as parallel series.

In Europe a well-known instance of this is provided by the insect *Chermes abietis-cmicis* which forms the well-known pseudo-galls upon the spruce during one of the generations or series, whilst the other is spent upon the larch. In the N.-W. Himalayas the writer has studied an allied species which he has provisionally named *Chermes abietis-piceæ*, which, whilst resembling its European confrere in forming pseudo-galls upon the spruce, migrates subsequently to the silver fir, as the larch is not found in these forests.

FAMILY ALEURODIDÆ.

These are minute insects with mealy wings, seventeen-jointed antennæ and two-jointed feet terminating by two claws and a third process. Little is known about them at present in India.

In some cases they form scales upon plants, as in the case of the *Coccidæ* (*vide* below). An insect named *Aleurodes eugeniæ* has been reported as infesting *Eugenia jambolana* trees in Poona in this way.*

MONOMERA.

Tarsi consist of a single joint only.

FAMILY COCCIDÆ (SCALE INSECTS).

The form in which these insects are most usually known is that of a small scale or shell-like body closely adhering to leaves, fruits, or to the bark of trees, shrubs, &c. The scales thus formed are of the most varied form, so that no general description can be given of them. The scale may be defind as an accumulation of excreted matter, combined with the cast skin or skins of the insect covering the body either totally or partially, and thus acting as a shield under which the subsequent development takes place. All coccids do not form scales, but the habit of excreting a large quantity of matter to the outside of the body is universal. The insects are usually minute with but a single claw to the foot. The male has one pair of wings, but no mouth parts; the female is wingless and usually so degraded in form that most of the external organs and appendages cannot be distinguished. When first hatched they are tiny little creatures, and it is only later on that the females lose the power of locomotion, although in certain forms the females do not lose their antennæ and legs. They have no distinction between head and thorax. The beak is three-jointed. It is as they approach the adult stage that they become stationary and their bodies swell up and legs diminish, and the excretions forming the scales are produced. The eggs are generally laid under the body of the female, and as she lays them her body gets thinner and dries up, forming a kind of dish-cover over them, above which are the cast skins of the moults, and above these the encrustations of the scale. When the male larvæ change, they change to a pupal stage which is exceptional amongst *Hemiptera*. In spite of the female being wingless these insects spread more and cause more damage than any other family of insects. The ability to spread depends upon the activity of the larva and on the facilities which exist for the transport of the eggs. Many of these, which are often laid inside cottony masses, are blown about by the wind, others are transported by birds, &c. Cocoanut palms in the Laccadive Islands, areca palms on the Bombay coast, and coffee bushes in Southern India and Ceylon are known to suffer to a serious extent from the attacks of *Coccidæ*, whilst mango and orange trees, tea bushes and other plants have been reported as harbouring various species.

---

* For a fuller account *vide* Departmental Notes on Insects which Affect Forestry, No. 1, p. 182. † *Ibid* No. 2, p. 185.

Information as to the attacks of coccids in the forest is at present very defective in India. A genus by name *Monophlebus* has within the last two years come to the front as containing serious forest pests. The life-history of one of the species, a new one named recently by Mr. E. Ernest Green as *Monophlebus stebbingi* has been to some extent worked out, and the observations noted have shown that this class of scale has serious destructive capabilities when it swarms in large numbers. During the last few years this coccid has swarmed in ever increasing numbers in the Siwalik sal forests and adjacent areas both to the west of the Jumna and east of the Ganges. Its life-history as far as at present known is as follows:—

The young female larva first appears upon the sal leaves during November as a minute yellow speck. This increases in size, and during February it quits the leaves and takes up its position on the twigs. By the end of March it has grown into a fat, robust scale, half an inch or even as much as ¾ in length, by ¼ or ⅓ in breadth, and covered with a white powdery substance, the colour beneath being orange or brown. The plate accompanying this number shows these insects feeding upon a sal sapling. The female is sexually mature about this time. During the whole of this period it retains possession of its legs and antennæ and walks about over the largest trees, but spends most of its time with its beak firmly embedded in the bark of the twigs and smaller branches, from which it sucks up the sap. It is also to be found in numbers on the upper portions of saplings. The scales are sometimes so thick on the stems and branches as to entirely cover the twigs, which appear as if encrusted with snow. During the whole of this period they exude enormous quantities of a saccharine solution, which coats the leaves and twigs, clogging up the stomata, and drops down on to the parts of the tree below, thoroughly wetting them and the ground beneath. When the insects are numerous this excretion can be heard pattering down like rain drops, and soaks everthing. The male larva has not yet been found, but the male pupa is known and the male adult, which is a small red fly with a pair of black wings and some appendages at the end of its body. It is ⅙th inch in length with a wing expanse of ½ an inch. It fertilises several females and the eggs are laid by the female in cottony sacs in crevices in the bark of the trunks and beneath fallen debris on the ground. They are crimson in colour and shining, and one female lays over 450 of these in the sac.

The damage done by the pest is serious, as young twigs and smaller branches dry up under the many tappings to which they are exposed, the crowns of the trees thus being thinned out saplings similarly suffer severely. Other species and varieties of monophlebus have been found upon sissu, teak, mango and *Prosopis spicigera*, but their life-histories have yet to be worked out.

Amongst useful species the lac insect, *Carteria lacca*, which secretes both wax and dye, the lac being poured out by glands on the back, must be mentioned. It lives upon the dhak, ber, pipal, kusum and other trees. The cochineal insect is another coccid which secretes a valuable dye.

USEFUL HEMIPTERA.

The family *Pentatomidæ* contains the soldier bug, an insect which is useful in India, as it destroys caterpillars. The *Reduviidæ* are predacious upon insects and probably destroy numbers of injurious forms. The Chinese insect wax (*Fulgoridæ*) was at one time a very valuable insect, as from it a large trade in wax candles sprang up, the world's markets being largely supplied from this source. It was thought at one time that the white insect wax (*Ceroplastes ceriferus*) of India would be utilizable for the same purpose, but its wax proved to burn with too smoky a flame, and the general introduction of kerosine caused the experiments being made with it to be given up. Its only use at present is that it is eaten when found by villagers. As already mentioned, there are two extremely useful insects in the family. The lac insect (C. lacca) secretes both a wax and a dye. The insect feeds upon the dhak (*Butea frondosa*), the ber (*Zizyphus jujuba*, pipal (*Ficus religiosa*), kusum (*Schleichera trijuga*), babul (*Acacia arabica*) and numerous other forest trees. It yields two crops in a year, the lac encrusting the twigs in large deposits, and forming a valuable article of forest produce, the world's supply being supplied from India.

The cochineal (*Coccus cacti*) secretes a valuable dye. An inferior variety in India lives upon the Opuntia (prickly pear).

II.—CORRESPONDENCE.

Ripening of Cones of Pinus longifolia.

There appears to be a mistake in Gamble's "Manual of Indian Timbers," page 706, regarding the period necessary for the cones of chil (P. longifolia) to ripen. This is given as 15 months, but I think it should be a year longer.

Cones of four different years are found on the trees at this time of year (April).

(1) The cones which were fertilised last month. They are green and are situated at the extremity of the current year's shoots. They are ½″ long and 1⅜″ wide at the centre.

(2) At the base of the current year's shoot is a cone which is still green and soft with the exception of the tips of the scales, which are brown and woody. These cones are almost spherical or short-ovate (in the specimens before me). They are 1¼″ long and 1⅛″ broad.

(3) At the base of the shoot which bears (2) at its extremity is a large cone. The scales are brown and are hard and woody. These cones are 3½″—4″ long and 2½″ broad, and more or less ovate in shape. They will open and shed their seeds in May.

(4) The empty cones whose seed was shed last May. Most will fall from the trees during the present hot weather.

I have before me a branch which bears cones (1), (2) and (3), and one twig on it bears all three, but (2) has withered. I have not yet seen a twig bearing perfect specimens of cones (1) to (3), but those with cones of alternate years are found in all directions, *i. e.*, cones (1) and (3) or (2) and (4). Apparently any particular twig only bears fertile cones in alternate years. The cone is situated at the extremity of the shoot of the year. The next year's shoot springs from below the base of this cone and pushes it on one side by its growth.

I give below a diagram of the twig before me, omitting the side branches.*

According to Kanji Lal's *Flora of the School Circle* the chil (called chir in that Circle.—*Hon. Ed.*) flowers in February—April, and the seeds are shed in October next year. In this Division (Kangra) the seed falls from the cones in May.

CAMP, *April 3rd*. E. M. COVENTRY.

The Monophlebus Scale Insect in the Kheri Sal Forests.

In his excellent "Notes on a tour through the Kheri Division, Oudh," in the May number of the *Indian Forester*, H. J. makes some remarks anent the dying back of the young sal saplings for some years after first germination from the seed. He also alludes to the periodic drying up and replacement of the leading shoot by extra vigorous side-shoots.

H. J. goes carefully through the possible causes of these two serious drawbacks to rapid regeneration and gradually eliminates clear and forceful reasoning the many reasons to which such might be attributed. Suppression from want of sufficient direct sunlight, failure to tap the permanent water-supply and consequent scorching by the dry winds of the hot season, frost, fires, grazing and injuries by men and other mammals—all are dealt with in turn and repudiated as unsatisfactory, since in every case examples where these causes could not be attributed are to be found in the areas under consideration. There remain insect attacks. The writer of the note says: "The scale insect swarms in the sal forest at certain times of the year, but so far no connection has been proved between its ravages and this habit of the sal tree. Common as it is, it is hardly credible that this insect should be so universal that no part of the forest should ever be left undamaged by it."

The scale insect here alluded to I take to be the *Monophlebus* so common during the last few years in the Siwalik sal forests. I would therefore draw the attention of H. J to the note upon this insect in 'Departmental Notes on Insects that Affect Forestry,' No. 1, p. 140 (as also to pp. 274-275 of the present number). It is there distinctly stated that the drying up of leading shoots and dying down of saplings and the drying up of twigs and smaller branches upon old trees is attributed to this scales. Since the observations were made upon which that note was writtten the writer has had the opportunity of spending a month in the Dun Forests in April, May (1902), the period when this scale's attack culminates; and anyone who has done this once in a year when the infestation is particularly severe will have little doubt as to the cause of the dying of young trees or drying up of leading shoots. When one remembers that from early in February on to the end of April the scales confine themselves entirely first to the young twigs, subsequently moving down, as they increase in size, on to the older ones, or in the case of a sapling shifting lower down the shoot, and that during the whole of this period they are continually tapping the twig, branch, or shoot, one can scarcely be surprised at these latter drying up. If H. J. systematically bled the leader of a healthy sal sapling, through the months when it was starting the new growth of the year and was full of sap, he would not be surprised at the top dying. And yet this is just what is taking place in the forest under the action of the scales. Further, the insects excrete during the whole of this period large quantities of a sugary material, which coats leaves, twigs, branches and shoots with a film which dries like varnish under the sun's rays, clogging up the stomata and pores, and thus interfering with respiration. The photograph depicted here is one of a young sapling taken by Mr. Milward in April 1901, when we were inspecting the scale attack in the Sabhhawala forest in the Dun. It shows the fully developed scale insect (over half an inch in length, oval, thick and fleshy) clustered in a serried mass for several inches on the lower part of the leading shoot. Earlier in the year the coccids would have been found near the summit. As they increased in size they moved down to the lower portion of the leader. The shoot thus dries up from the top downward. Mr. E. M Coventry has noticed this to occur in the Kalesar forest on the western bank of the Jumna River. (*vide* D. N 1, 140). I would not however be understood to make the sweeping statement that the scale is the sole cause for the lamentable state of affairs in these sal forests. We require a careful series of experiments to be carried out on sample plots through a number of years before such a statement could be made. The damage may however be entirely due to insects nevertheless. In the Dun the scale is apparently at times accompanied by another serious pest. This is a looper caterpillar, the larva of *Boarmia selenaria*, a moth of the family *Geometridæ*. It is a large caterpillar, which attains its full growth at the end of April. It spends several weeks feeding upon the sal, and is excessively voracious, eating down leaves, inflorescences, and all the green shoots of the year. I have seen young saplings from which every particle of green had been devoured, and this just after they had developed their spring foliage. Mr. Milward and the writer noted in 1901 that in a number of instances the scale and looper were present on the tree in about equal numbers. In the photograph these looper caterpillars will be seen at the top of the sapling from which they had stripped nearly all the green growth. At the time the photograph was taken they were engaged in eating down the remaining green shoots on the young tree. Young saplings attacked in this way by these two pests in the spring growing season were found, on being visited in the following September, standing black and

---

* We regret that we are unable to reproduce this diagram, but it appears to carry out Mr. Coventry's contention.—HON. ED.

S. B. Mondul del. From a Photo by R. C. Milward.

MONOPHLEBUS STEBBINGI, GREEN, AND BOARMIA SELENARIA, HUBN
ON A SAL (SHOREA ROBUSTA) SAPLING.

gaunt in the forest; the complete defoliation and heavy ta[illegible]ing to which they had been subjected in the spring had so reduced their vitality that they were quite unable to produce a second flush. As a result of that severe attack of these two insects many young saplings undoubtedly died down. As neither of these pests attack the roots so far as we at present know, these latter would remain unaffected, and the succeeding year would send up a fresh shoot. Further study will, I believe, show that this looper has a second or rains generation in the year which attacks the second flush of leaves. We believe that the *Boarmia* is present in the Kheri sal forests In Hampson's Moths in the Fauna series its distribution is given as general throughout India. With reference to the adaptability of spreading possessed by this scale I may add that each of the fat white insects, which are the females, is capable of laying over 400 eggs* (475 is the largest number yet counted as laid by one insect). With such remarkable powers of reproducing itself it is scarcely surprising that in favourable seasons it swarms in such large numbers.

From the above remarks I think it will be considered as more than possible that the state of the young sal in the Kheri forests *may* be due to insect attacks. A few dry years, whilst lowering perhaps the vitality of the tree, would favour the increase of its insect aggressors.

This question, whilst being a most interesting one scientifically, is at the same time one of such sylvicultural importance that we trust divisional officers in charge of the N. W. Sal areas will look at it from the point of view to which H. J. has drawn attention and study the action of these two pests both generally over their whole forests and more closely in small specially selected areas.

Grass for Paper Manufacture.

Major Prain, I.M.S., has very kindly identified for us the grasses alluded to by M. G. Thompson in his letter in the last (June) number of the Magazine.

The one resembling sabai or bhabar grass (*Ischæmum angustifolium*) is *Pennisetum Alopecurus* Stend. The Bengal Paper Mills Company have reported it to be equal to average Sahebgunge sabai grass.

The second grass sent, which Mr. Thompson thinks might form a useful fodder grass, Major Prain has identified as *Paspalum scrobiculatum* Linn. var. *Kora*.

These grasses would seem to be both worthy of attention with a view to their inclusion amongst the exploitable minor products of the areas over which they grow.

---

* *Vide* Departmental Notes on Insects that Affect Forestry, No. 2, p. 312.

III.-OFFICIAL PAPERS AND INTELLIGENCE.

The Board of Scientific Advice.

Perhaps one of the most important departures in the line of Scientific and Economic Research made by the Government of India is the formation of the Board of Scientific Advice.

The following extracts from the Resolution No. 22, General, of the Government of India, R. and A. Dept., dated 28th August 1902, whilst proving of interest to our readers, should undoubtedly be recorded in our pages.

The organisation and work of the Indian Agricultural and Scientific Departments prior to 1897 have been fully described in the important series of resolutions which issued in that year, and specially in the fourth and fifth resolutions of the series. These contain a clear exposition of the policy of the Government of India in establishing departments of scientific research to promote the industries of the country and investigate its undeveloped resources, and they describe the means adopted to give effect to that policy. They further show how undue prominence had been given in the past to pure science, to the neglect of its economic application, and they affirm the necessity of extending the economic side of enquiry, and of co-ordinating the labours of the different departments on the basis of a well-considered working plan.

The policy laid down in these resolutions has been steadily pursued, though its development has been retarded by an unfavourable cycle of seasons, which seriously affected the financial resources of the Government of India. To the Geological Department two practical mining experts have been added, while each year a portion of the scientific staff devote themselves to enquiries connected with the mineral resources of India. A cryptogamic botanist has been appointed, whose special duty it is to study the fungoid diseases of agricultural staples, such as rust in wheat, which causes such serious and widespread loss in the country. In Madras a botanist has been permanently entertained, whose attention will be mainly devoted to economic enquiry. And of late years the attention of the officers of the Botanic Survey has been more and more directed to questions of practical importance to the country. The establishment of the Reporter on Economic Products has been strengthened, and a Curator with special qualifications as an economic chemist has been added to it and provided with a laboratory, while one agricultural chemist pursues his enquiries at Dehra Dun, and it is proposed to procure another for Madras. An entomologist has for some time past been added to the staff of the Indian Museum; a specially qualified forest officer has been deputed for investigation of the insect pests which devastate the forests, while the Secretary of State has been asked to secure the services of a skilled entomologist in order to conduct similar enquiries in connection with the agricultural and industrial staples of India. .....

The Government of India now desire to provide, as far as possible, for that co-ordination of scientific enquiry which the development of the machinery of the various departments has rendered more than ever essential .. ..

The subject has received the careful consideration of the Governor-General in Council, and he has arrived at the conclusion that a central authority is needed to ensure that the work of scientific research is distributed to the best advantage, that each investigator confines his researches to the subject with which he is most capable of dealing, and that energy is not dissipated by the useless duplication of enquiries or misdirected by a lack of inter-departmental co-operation. The various departments of science are not self-contained, but closely interlinked. Agriculture needs the aid of botany, botany the assistance of geology, geology of chemistry, and an endeavour should be made to combine the different departments in a system of mutual assistance. The Governor-General in Council has no wish to imply that there has been any disposition on the part of one department to hold itself aloof from another. But the institution of an authorised scheme of mutual assistance will result in a closer co-operation for the purposes of effective research, than has been possible in the past.

A further reason exists for the constitution of a central advisory authority. Though greater prominence has been given in recent years to the practical or economic side of enquiry, its importance is not even yet always adequately recognised. The Government of India fully realise the great value of the work effected in the past by their scientific departments, in the shape of scientific exploration and systematic work, and they recognise that such enquiries must necessarily precede any attempts towards the solution of more practical problems. But in those departments there has been a not unnatural tendency to give the claims of abstract science precedence over the more practically important demands of economic or applied science. In making these remarks, the Governor-General in Council has no desire to underrate the importance of original research for purely scientific objects, or to assert that the practical application of science should be the sole aim of technical departments. It is his wish that the high reputation which has been gained by more than one branch of scientific work in India should be maintained, and that the Indian departments should retain touch with scientific progress in Europe and America. But in view of the fact that the Indian Government own the largest landed estate in the world, that the prosperity of the country is at present mainly dependent upon agriculture, that its economic and industrial resources have been very imperfectly explored, and that the funds available for scientific work are limited, the importance of practical research is pre-eminent, and a central authority, which can speak with knowledge upon scientific questions, will be in a position to enforce the repeated declarations of the Government of India on the subject.

The Governor-General in Council proposes therefore to constitute a Board of Scientific Advice comprising the heads of the Meteorological, Geological, Botanical, Forest, Survey, Agricultural and Veterinary Departments, together with such other scientific authorities as may from time time be invited by the Government of India to serve upon it. These latter will include scientific officers in the service of the Imperial and Provincial Governments, whose special attainments render their assistance desirable. The Government of India hope that the Trustees of the Indian Museum, who as custodians of the National Scientific Collections have always shown an active interest in the prosecution of scientific work, will associate themselves with the scheme, and they will be addressed separately on the subject. The Secretary to the Government of India in the Department of Revenue and Agriculture, to which the scientific departments concerned are administratively subordinate, will be *ex-officio* President of the Board, and the Secretary to the Board will be selected, subject to the approval of Government, by the Board from amongst its members. The Board will review and advise generally upon the operations of the departments, with due attention to the economic side of their work, and will serve as a referee in all matters connected with the organisation of scientific enquiry in this country. It will annually receive and discuss the proposals of each departmental head in regard to the programme for investigation in his department. In cases where inter-departmental co-operation is necessary, it will rest with the Board to advise as to the lines on which mutual assistance should be given and the department to which the inquiry should primarily appertain Where the proposed investigation falls exclusively within the domain of a particular department, the function of the Board will be confined to examining and criticising the proposals. It is not intended that the directing influence of the Board should in any way weaken departmental executive control or responsibility, and the precise manner in which and the agency by which any required information is to be collected or investigation carried out must be left to the heads of the departments concerned.

The Board will submit annually to Government a general programme of research which will embody the proposals of departmental heads in so far as its subjects are to be exclusively dealt with in one department, and its own proposals in cases where two or more departments are to co-operate. At the end of the year it will submit to Government a brief review of the results obtained in all lines of scientific investigation based upon the annual departmental reports and upon any papers published by individuals. Generally, the Board will act as an advisory committee to the Government of India and as an intermediary between the Government of India and their scientific officers in respect of all questions of technical research which are dealt with in the Department of Revenue and Agriculture. The Royal Society have already been good enough to offer their aid in furthering scientific work in India, and their invaluable advice and assistance will be freely invoked by the Board now constituted.

[The first Annual Report of the Board (for 1902) and the programme of work drawn up for the present year (1903) will be considered in subsequent issues.—HON. ED.]

IV.—REVIEWS.

Forest Flora of Bombay.*

The first edition of this work was reviewed in the *Indian Forester* a few months after its publication in 1894. The following may be said to be the chief differences and additions in the volume at present before us:—

1. A 'dictionary' of technical words comprising 7 pages.

2. The recasting of keys in what may be termed the 'graded' form.

3. Short notes on distribution outside the Bombay Presidency.

4. Mention of economic uses and also of biological peculiarities in respect of the more important plants.

5. The addition of four natural orders and several genera.

6. The consecutive numbering of genera and species.

In reviewing the present edition we may therefore confine ourselves to an examination of the above points since it will be unnecessary to touch upon the portion already previously dealt with.

The Dictionary.—This is a welcome addition, but it is not perhaps as full as it might be, for a certain number of technical words appear to have been omitted; the definitions, also, are not, in some instances, as clearly expressed as they might have been, *e.g.*, of such words as apocarpous, coriaceous, diœcius, saccate, &c.

The definition given of 'acuminate' would be correct for 'acumen.'

---

* "Trees, Shrubs, and Woody Climbers of the Bombay Presidency," by W. A. Talbot, F. L. S. (Second edition.)

The definition given of 'carpel' is likely to lead to confusion. Generally an ovary is said to consist of several carpels. This sense is implied by the terms 'apocarpous,' 'syncarpous,' 'bicarpellary,' etc., when applied to the ovary.

A drupe need not have only one stone. In his definition of 'pyrenes' and description of Ilex and Ilicineæ (page 87), the author admits that a drupe may sometimes have several stones.

'Palmate' and 'digitate' are scarcely synonymous.

The Keys.—The present form was recommended by the writer of the previous *Indian Forester* review, and it is gratifying to note that the author has acted upon that recommendation. Not only in this respect, but owing to a much larger number of characters having been incorporated in the keys, they have been improved out of all recognition, and should now prove very useful in identifying plants. It is a pity that more care was not taken in the revision of the proofs of the 'graded' keys given on pages 1, 71, 123, 174, 205, 301, 315, 325 (first part) and 338, as they are to some extent unintelligible owing to irregularities in their printing.

Distribution outside the Presidency.—In a flora entitled, and intended to be, a local one the distribution of the trees and plants mentioned should, we think, be strictly confined to the area described. We cannot but consider it a mistake to endeavour to trace their distribution beyond these limits. In so doing the flora loses its individuality, and instead of being an exceedingly useful and correct local one, proving a valuable reference book for the locality treated, it runs the risk of becoming a very incomplete flora of the larger area referred to. For instance, the distribution of the following appear to need some alteration or revision: *Mærua arenaria*, *Eurya japonica*, *Kydia calcina*, *Butea superba*, *Acacia eburnea*, *Rubus lasiocarpus*, *Melastoma malabathricum*, *Jasminum arborescens*, *Leptadenia reticulata*, *Gmelina arborea*, *Streblus asper*, *Ficus glomerata*, *Phœnix acaulis*, to mention a few.

Again, since distribution outside the Presidency has been attempted, we would point out that no remarks under this head are made as to the range of such trees as *Lagerstrœmia parviflora*, *Hymenodictyon excelsum*, *Calotropis gigantea*, *Lycium europæum*, *Macaranga indica*, *Sapium insigne*, which are common in other provinces. The distribution of *Tiliacora racemosa* appears to have been omitted.

Economical and Biological Notes.—These have greatly enhanced the value of the work, and are a most welcome addition.

Additional Natural Orders, etc.—The natural orders added to the work are—

Violaceæ. 72. Aristolochiaceæ. 73. Piperaceæ. 86. Pandanaceæ —none of any great importance, except perhaps the last named.

Consecutive Numbering of Genera and Species.—The omission of this numbering in the first edition was probably due to an oversight. The numbers will be found of great help for reference, especially in the case of the genera.

Miscellaneous Remarks.—Page 22. "Chenapodiales" should be "Chenopodiales.

Page 2 Under *Clematis gouriana*, we read—"Flowers small, 3-5in." Evidently the decimal points have been missed out.

'Lenticellate' would perhaps be the proper word in place of 'lenticular' under *Euonymus* on page 88.

In the keys given on pages 122, 123, 135 and elsewhere is found the expression "trifoliate leaves." The correct terminology is, we believe, "trifoliolate."

Should a future edition be required, the author would be doing a great service to his readers if the spelling of the vernacular names were punctuated so that their correct pronunciation might be facilited for readers both in and outside the Presidency.

Having made the above few remarks upon the additions to the second edition of Mr. Talbot's excellent work, we have nothing but praise to give the author of this extremely useful handbook, and we congratulate the Presidency on having such a valuable vade mecum to turn to. We cannot but commend the example to the Provinces in India still destitute of local floras.

The Forest Flora of New South Wales.*

This is the first part of a work issued at the cost and under the auspices of the Forest Department of New South Wales. The object of the work is, as the author's preface states, to depict the botanical characters of each tree and to furnish all the available information in regard to it. As there are about four hundred and fifty trees in New South Wales, it will be gathered that the undertaking is not a light one. To judge from part I, however, the task which Mr. Maiden has set himself to do is likely to be thoroughly well done. Part I is of quarto size and contains four clearly drawn full-page plates with floral dissections of *Grevillea robusta* A. Cunn., *Ficus rubiginosa* Desf., *Syncarpia lamifolia* Ten. and *Pittosporum phillyraeoides* D. C. Thirty-two pages of letterpress are devoted to those four plates. Each species has a full but simple botanical description of the genus, followed by a similar description of the species. The derivation of the botanical name and the English and aboriginal names are then discussed. Then come the botanical synonyms followed by general remarks on the foliage, flowers, fruit, fibre, etc. Special attention is given to the timber, its appearance, qualities, uses, and exudations. The description of each species ends with remarks on its height, its distribution, habitat, and mode of propogation. Forest officers familiar with the forest floras of Brandis and of Kurz, may find the title of Mr. Maiden's work somewhat misleading, as though full and excellent descriptions of individual species of forest trees in New South Wales are given, they are not being published in the order of the Genera Plantarum. Mr. Maiden's flora is more akin to the *Flora Sylvatica* of Beddome, with however more detailed descriptions than are given in the latter work. Botanists who have had experience of the production of a work of a similar nature to Mr. Maiden's need no reminding that one must figure a plant when one can, not when one would. Doubtless Mr. Maiden will complete his work when all the plates and descriptions have been finished by furnishing a synopsis of the orders and keys to the genera and species. The work should prove of great value in stimulating interest in the forest resources of New South Wales, and is one which the Indian Forest Officer who desires to keep abreast with the advances of Forestry in other countries cannot afford to neglect.

---

* By G. H. Maiden, Director of the Botanic Gardens, Sydney. Part I, 1902. pp. 1—32, pl. 4. (Sydney: William Applegate Gullick.) Price 1s. per part.

Indian Museum Notes, Volume V, Number 3.

The third number of Volume V of 'Indian Museum Notes' has been recently issued under the editorship of the late Mr. de Nicéville and contains a large amount of information concerning insects of the Indian region, especially with reference to those destructive to crops. This number opens with a series of original communications, four descriptive of insects new to science and one summarising the information with regard to pests of sugarcane in India. The latter subject is also dealt with in one of the later sections on crop pests, and these two papers together bring this important subject up to date.

The remaining and larger part of the number deals with insect pests of the more important crops.

It is perhaps unfortunate that the first section should deal with forest pests, as it would seem more natural to confine this subject to Mr. Stebbing's *Departmental Notes on Insects that Affect Forestry*,* reserving 'Indian Museum Notes' for scientific descriptions of new Indian species, crop pests and miscellaneous insects.

The crop pests are treated under their food-plants, so that the information is readily found and is easily attainable by those interested in particular crops. The section headings comprise fruit trees, plants, vegetables, cereals and crops, indigo, sugarcane, cotton, opium and tea, and there are two final sections, one dealing with the insects found in the Calcutta water-supply and the Colombo Lake, the other with a tineid moth attacking blankets. The most important sections deal with pests of sugarcane and indigo, and these deserve the careful attention of those engaged in the cultivation of these plants. Sugarcane planters in particular will evidently have to devote very careful attention to the methods of treatment of their pests. It is useful to know what insects attack all important crops, but this knowledge is only of real economic value when it enables the pests to be satisfactorily dealt with. This has been recognised in other parts of the world, where practical remedies are now in use, and there would appear to be the same necessity for dealing with these pests in India as elsewhere. Successful planters will be those who realise this fact, and make themselves masters of practical methods of spraying and otherwise preserving their crops.

---

* This will be done in future.—Hon. Ed.

As in preceding numbers of 'Indian Museum Notes,' a mass of scientific information is here collected, but a greater feature consists in the attention given to remedial measures. This would be expected from the hand of the late Mr. de Nicéville, and this number represents the last piece of work carried out by him before his death. Throughout, the work is sound and excellent, and the great advance made will stand as a memorial to its editor. We commend it to the attention of all who are interested in agriculture in this country, with the assurance that much practical and scientific information may be obtained from its pages.

V.—SHIKAR AND TRAVEL.

England to Burma via Canada, Japan and China.

The crowded 'Special' from town, bearing the passengers for one of the enormous Atlantic liners and a Canadian steamer, has just arrived at the wharf along side which the steamers are lying, and rapidly disgorges its living freight and baggage. The quay is soon overcrowded; with difficulty passengers strive to direct porters with their coveted belongings to the proper ship; rapidly the gangways and the deck of the Canadian ship become almost impassable. Indignant and perspiring porters carrying huge trunks and boxes endeavour to force a way up the gangways. An agitated and somewhat corpulent lady remembers when wedged half-way up the thronged gangway that she has left her umbrella in the train, and vainly strives to retrace her steps. Once on deck matters are little improved; it is crowded to suffocation with heated passengers, emigrants, stewards, visitors, and those loving friends who 'kind only to be cruel', refuse to leave the traveller till the last moment. Meanwhile practised hands are quickly transferring the heavy baggage to the holds and, considering the quantity to be shifted, in an incredibly short space of time the booming of the foghorn gives notice of immediate departure, and shortly afterwards the ship swings free from her moorings. And what a ship! When about ten days previously I had endeavoured to purchase passage tickets by one of the floating palaces to New York sailing in about twelve days' time, the agent met me with an incredulous stare "Why," he gasped, "I doubt, Sir, if you can get across the Atlantic for the next three months. All passages are taken. Captain's cabins, steward's cabins, everything is booked for at least three months. What with the ordinary autumn traffic and the Coronation as well, all the boats are absolutely crammed." "But," I said persuasively, "I must have a passage about this date in order to connect with the steamer for Japan." "Well," he said, "your only chance is to get an outside liner to Canada, although I doubt if you will get even that However, I'll do my best for you." He succeeded, and it was in this way that I found myself standing on the upper deck which formed the limited accommodation for upwards of 100 first class passengers. The ship was a large one as far as tonnage went, and its usual vocation was to carry cattle. On this occasion, however, apart from the 1st class passengers, she was carrying some 1,200 emigrants: and gazing at this pitiful crowd of ill-clad, dirty and disreputable-looking humanity, disgorged no doubt from the slums of many continental cities, for almost all races from Europe seemed represented in that motley crew,' I fell to wondering what poor Canada had done that these apparent outcasts, this mass of human flotsam and jetsam, should be flung helpless on her shores. Could she indeed from such doubtful-looking material mould useful and law-abiding citizens?

The steamer had little accommodation for the passengers: a small shaped smoking room for the men, but nothing for the ladies. As the dining saloon could only accommodate half the passengers at a time, there was a continuous run of meals, hence the ladies could seldom have the meagre accommodation it afforded. There was indeed 'a ladies lounge,' one small bench at the bottom of a dark gangway. The food was execreable and was served through a small hatch into the saloon. The stewards crowded and hustled round this small aperture, one bawling perhaps 'beans for the Captain,' another 'kidneys for a lady, 'three cauliflowers and a ham,' and so on. The cook's galley occupied a prominent position on our limited promenade deck, and from it at all hours would arise a delicious fragrance of frying onions, recalling the happy Spain of their origin, and, alas, with the motion of the ship recalling things we would have fain left undisturbed! The gloomy skies and heavy seas of the N. Atlantic were not much conducive to gaiety, but we formed nevertheless a pleasant litte coterie in the smoking room; but I could not help commiserating the helpless ladies, many of them missionaries who, too ill to stop below, could get but scanty shelter from the showers of spray and piercing winds that constantly swept the exposed decks.

But the smoking room was hardly the place for ladies; there were one or two whose language and manners hardly indicated a high state of breeding. One, a short, puffy and enormously stout man, whose capacity for whiskey appeared to be limited only by the volume indicated by his bulk, would sleep off the effects of his potations on the smoking room couches. I can see him now, the fleshy amplitude of his sides hanging in heavy pendulous flaps; with each stertorous breath he exhales on the already overladen air thick vapours of whiskey, until soon, with alarming choked gurglings, he struggles suddenly to consciousness again only to murmur weakly for more whiskey. The passengers were, however, generally speaking, a very pleasant lot. From one gentleman who was returning to Minneapolis after a visit to his old home (Holland I think he said) I gleaned much interesting information. He was one of those valuable citizens to whom the United States must be largely indebted for their wonderful and rapid progress: men whose concentrated energies are devoted to the welfare and expansion of the particular cities they live in, and who exhibit an absorbing interest in the country of their adoption. He was never tired of dilating on the progress of Minneapolis, its institutions, buildings, railways, trade and general prosperity. He was a type, and a good type, and the wonderful rise and growth of the great cities of America must, I think, be greatly due to such men. It seemed that Minneaplolis had taken for its motto 'The best of everything,' and in pursuance of this lofty ideal it had not unnaturally advanced with great rapidity till the city occupied its present proud position. In such minor things as fruit, for instance, exhaustive experiments had been made until the best apple, the best pear, and so on had been obtained For a long time there had been a determined rivalry with the adjacent city of St. Paul, but Minneapolis, true to its motto, got 'the best' of St. Paul. One day the gentleman from Minneapolis said quaintly "I wonder whether I shall be your table or your chair" I looked at him enquiringly. "Oh, you know," he said, "when Goethe wanted any article of furniture he used to 'write up' one of the leading citizens, and with the money so obtained buy what he required, so he would afterwards, pointing perhaps to a fat burgomaster or whoever it might be), say, there goes my table, or four poster, or whatnot." I had then no intention of 'writing up' the gentleman from Minneapolis, so could not tell him what particular form of furniture he might assume. As we neared

Labrador and Newfoundland considerable anxiety was exhibited regarding the possible meeting of icebergs, a passing ship having signalled that she had seen several. Heavy fogs and the awe-inspiring muffled booming of the foghorn at frequent intervals created an additional sense of insecurity. The possibility of meeting one of these irresponsible icy wanderers of the deep in the fog, or at night, was the subject of much gloomy speculation.

However we only sighted one during the day, far away on the horizon, with a suitable foreground of 'blowing' whales.

Passing safely through the Straits of Belle Isle, and then going by the Island of Anticosti, the Gulf of St. Lawrence is entered. Steaming up the River St. Lawrence is the most pleasant part of the journey, land is seen on both sides, and nearing Quebec the picturesque villages and farms, and the quaint little churches, dotted at frequent intervals over the landscape, form an agreeable change from the dull seascapes of the Atlantic. Quebec is one of the quaintest old-world towns imaginable, and the old-fashioned Caléche is still a familiar sight in the streets. The falls of Montmorency can be seen as the ship enters Quebec, as also the Chateau Frontenac, an imposing building of Norman design which is one of the hotels of the Canadian Pacific Railway Company. With what eager haste we ascended the hill and entered its hospitable portals for a luncheon after many 'Banyan' days!

A few hours in the steamer from Quebec, and Montreal is reached, a city of magnitude with many fine buildings and an excellent club, equal in its cuisine and appointments to a good London one.

From Montreal three of us took the night mail for Toronto en route for the Niagara Falls, and I had my first experience of the wonderful railway cars of the country. As you enter these cars you are so struck by the luxurious magnificence, so ostentatiously apparent, that you do not stop to consider if the comfort is real.

A palatially carved, decorated and upholstered drawing-room by day is converted by great ingenuity into a sleeping car by night. At one end is a smoking room and lavatory for men, whilst at the other is the lavatory for ladies. The sleeping berths are constructed each to hold two; there is a row of upper and lower berths on either side of the car. When made up for the night, heavy tapestry curtains hooked down the middle screen the berths; you enter an upper or lower berth by unhooking your share of hooks, leaving the others undisturbed. But here comes the difficulty—*you have to dress and undress in bed!* On this occasion I had an upper berth, whilst the lower was occupied by a man and his wife. I shall not readily forget the following morning. I had retired late, the smoking-room proving attractive. When I awoke, I peered cautiously through the curtains, and found to my dismay that all the other berths had been put up for the day, and the passengers were all dressed and seated in the cushioned lounges into which the sleeping berths had been transformed. The ladies did not look as if they had dressed in bed! I proceeded to dress as hastily as possible, and having succeeded in scrambling into a certain quantity of clothing I screwed up my resolution to descend from my berth I gently unhooked the curtains and stole a glance to see if the ladder to descend was handy; it was nowhere to be seen, nor was Sambo, the conductor. I listened; there was a buzz of conversation. I determined to descend the best way I could. Gently I protruded a long leg and began feeling about for something to rest my foot on. It seemed to me the conversation suddenly stopped. I became desperate, and shooting out the other leg made a combined search—it was useless I finally dropped to the ground, grabbed up my coat and waistcoat, and conscious of my collar waggling loose at the back of my neck, fled along the centre of the car to the safe sanctuary of the smoking room.

From Toronto we went on to Niagara. The Falls are indescribably beautiful—the sight of a lifetime. We crossed the suspension bridge and entered the United States. Returning *via* Toronto we took train to North Bay, on the main line between Montreal and Vancouver. I regret time did not permit me to visit Ottawa, as this is one of the most important timber centres in Eastern Canada. Enormous quantities of timber, mostly coniferous, are floated down the tributaries of the Ottawa River to Ottawa, and thence to the St. Lawrence, whence it is shipped to England. There are still immense areas of pine forests in Eastern Canada, as also of oak, maple, beech, birch, etc., but the supply needs to be inexhaustible, since it is said that England imports some £22,000,000 worth of timber, mostly coniferous, annually.

Large quantities of pulp and paper are made mostly from spruce and poplar. The paper is used for newspapers, etc.

The railway journey across the Canadian Continent is roughly made up of three sections—

(i) Montreal to Winnipeg	...	1,424 miles
(ii) Winnipeg to Calgary	...	840 "
(iii) Calgary to Vancouver	...	642 "

The first section is comprised mainly of cultivation, forest, meadow land and lakes, and excellent views are obtained of the great Lake Superior, the train passing along its shores for several hours. Saw mills and grain elevators are common sights.

Between Winnipeg and Calgary is the prairie section, and the quaint names of several of the stations remind one vividly of those entrancing stories of our earlier days. Portage la prairie, Elkhorn, Red Jacket, Indian Head, Qu'Appelle, Moose Jaw, Swift Current, Crowfoot and Medicine Hat: with such names what can one think of but Red Indians and scalps and so forth, and one actually occasionally sees a hatchet-faced copper-coloured Indian of the great Cree nation.

As a matter of fact the billowy prairie is somewhat monotonous and disappointing, and we welcome with pleasure our near approach to the third section, the Rocky Mountains and the Selkirk Range. The scenery of this portion of the journey is really magnificent and impressive, that of the Selkirks being however even more striking and imposing than the Rockies. There is a continual changing panorama of snow-capped mountains and appalling precipices, deep gloomy canyons and roaring torrents; enormous glaciers are passed, at times the train in its wonderful sinuous course passes through dense forests of Douglas fir, spruce, cedar, etc., many of the trees of enormous girth and height. Near Bear Creek on the slopes of the Selkirks the railway is protected from avalanches by open-work tunnels made of large baulks of timber bolted together. There are several places to break the journey, notably Banff and Glacier; here there are excellent hotels, and Swiss guides are obtainable for mountaineering. I was much struck with the natural reproduction of the pine and fir forests; many areas were passed which had all the appearance of successful plantations, although from their position it was evident they were natural and not artificial. Fire would appear to be the greatest difficulty the Government has to cope with, and steps have been taken in the direction of fire conservancy. Notices are posted up at the railway stations regarding the lighting of fires and burning of forests, and fines are the penalties for infringing the rules. As Vancouver is neared, the snow-capped Mt. Baker (14,000 feet) can be seen; gigantic trees and stumps of forest monarchs are frequently observable as the coast is neared. It is said that some of the Douglas firs reach 50 feet in circumference with a height of 300 feet. The finest forests are along the coast, and near Vancouver a large area of primeval forest has been set apart as a park; here I saw a number of trees of enormous girth.

TAUNG-GYI.

(To be continued.)

Indian Pheasants and their Allies.

By F. Finn, B.A., F.Z.S.

(*Continued from page 210.*)

Chapter VII.

THE FRANCOLINS AND SPUR-FOWL.

The partridges to which the above names are applied form two very distinct groups, the spur-fowl in particular being very easily recognizable. They are smallish birds, quite partridges in size, but with longer tails than partridges usually have, and as they sometimes raise these in a folded form, they remind one much at such times of small bantam fowls, their resemblance to these being increased by the bare red skin which, as in fowls, surrounds their eyes. The cocks are always quite different in plumage from the hens, and have two or three spurs on each leg, the hens having one, two or none.

The birds are perhaps just as much miniature Jungle-fowl as Partridges, but they have not the hackle or long tail of the Jungle-cocks, so that they may as well be classed with the partridges as anywhere else, the various groups of the pheasant family being inter-related in such a complex way that it is quite impossible to arrange them naturally in a line, so to speak—a difficulty which besets all classifications.

The Spur-fowl are only found in India and Ceylon, three species being known; they all keep much to cover and are difficult to flush.

The Red Spur-fowl.

Galloperdix spadicea, Blanford, Faun. Brit. Ind. Birds, Vol. IV., p 106.

Native names:—*Chota jungli murghi*, Hind. in Central Provinces; *chakotri*, *kokatri*, Mahrattas in the Syhadri Range; *kustoor*, Mahrattas of the Deccan; *sarraoa koli*, Tamil; *yerra-kodi*, *jitta-kodi*, Telugu.

The general colour of the male of this species is chestnut the female being mottled black and buff; the legs and base of the bill are red, as well as the naked skin round the eyes.

The cock is about fourteen inches long, with a six-inch tail, and wing exceeding this by half an inch; the bill from gape is an inch in length, and the shank nearly twice this. The hen is a little smaller.

This Spur-fowl inhabits the base of the Himalayas in Oudh, and is found in the peninsula south of the Indo-Gangetic plain wherever the locality is suitable, for it avoids cultivated and open country, frequenting hilly forest land.

It varies a good deal in plumage, birds from Mount Abu and the neighbourhood being paler, especially the females, in which the black pencilling on the back is very scanty, and the ground-colour pale and greyish. About Matheran and Mahableshwar also hen birds are very lightly pencilled, although the ground-colour is as rich as in typical specimens.

This bird is shy and often solitary, a great runner, and seldom seen on the wing; the call of the male is said to be well imitated by the Mahratta name *kokatri*, being a kind of crow; the general note is a harsh cackle. It breeds between February and June, and possibly again towards the end of the year; three to seven eggs are laid, of a buff or greyish colour. If is good eating in the cold weather, but requires hanging a few days.

THE PAINTED SPUR-FOWL.

Galloperdix lunulata, Blanford, Faun. Brit. Ind. Birds, Vol. IV., p. 108.

Native names:—*Kaingir*, Uriya; *Askaol*, Orissa and Singbhum; *Hatka*, Gond in Chanda; *Kul-koli*, Tamil; *Jitta-kodi*, Telugu.

This bird is slightly smaller than the last, the male being little over a foot in length; it also shows very little red round the eye. Its colour however makes it easily distinguishable from any other partridge-like bird The general colour is chestnut, with white black edged spots, the head is speckled with black and white, the crown being glossed with green, the shoulders are also dark glossy green, the tail is green-black and the breast buff with black spots.

The hen is of a uniform sooty brown, with the head mostly chestnut. The bill and feet are dusky in both sexes, not red as in the other species. This beautifully-marked bird especially affects rocky hills, and is somewhat locally distributed. It appears not to occur at all on the Malabar Coast, nor in North-Western India, nor is it found in the Bombay Presidency north of Belgaum, nor anywhere north of the Ganges. Although it occurs in some parts of the Red Spur-fowl's territory, it does not extend so far to the west or north. Its breeding season is from March to May, and the eggs, which are glossy and pale drab in colour, do not exceed five in number.

THE CEYLON SPUR-FOWL.

Galloperdix bicalcarata, Blanford, Faun. Brit. Ind. Birds Vol. IV., p. 109.

Native names:—*Haban* or *Saban-kukula*, Cingalese. In size this bird is intermediate between the last two but has a shorter tail than either of them.

The cock has a speckled appearance, being streaked above and on the flanks with white on a black ground; the neck in front is white with black edgings and the breast pure white, the rump is chestnut, and there is an intermixture of this colour on the shoulders; the tail and most of the wings are black and the lower part of the belly dark brown with pale spots.

The hen is of a dull chestnut brown, and both sexes have red bills and feet as well as a red space round the eye.

This is the only Spur-fowl found in Ceylon, and it is confined to that island. Even there its range is not universal, for it is absent from the dry northern portion. Being, like the rest of the group, an inveterate skulker, and having a cackling note, it is more often heard than seen. It breeds from April to August, the eggs being cream-coloured, and usually only four in number.

The Francolins are a numerous group of partridges mostly found in Africa; five species are, however, Indian, and these include the most widely-spread and best known of our partridges. They are of the typical partridge form, with tails of meduim length, and no bare skin about the eye. In all the cocks differ from the hens either in plumage or by possessing spurs; these are always absent in the hens. The Francolins are inclined to affect cultivation, and are the best of our partridges for sporting purposes.

The commonest of all is—

THE GREY PARTRIDGE.

Francolinus pondicerianus, Blanford, Faun. Brit. Ind. Birds, Vol. IV., p. 139.

Native names:—*Titar*, *Ram titar*, *gora titar*, *safed titar*, Hind. *khyr*, Bengali, Uriya; *Gowjal huki*, Canarese; *kondari*, Tamil; *Kawunzu*, Telugu; *Oussa* and *watuwa*, Cingalese.

Both sexes are alike in colour in this species; the upper parts are brown, boldly pencilled with dark-edged, creamy white bars, and the lower buff with fine dark transverse pencilling; the throat is buff surrounded by a broken blackish band, and the outer tail feathers chestnut. The bill is dark grey, the eyes dark, and the legs dull red. The cock is distinguished from the hen by being slightly larger and by having a sharp spur on each leg.

The cock is just over a foot long, with the wing nearly six inches, and the shank about an inch and a half.

This bird is found almost all over India, but it avoids swamps and thick forest, and does not usually ascend hills to a higher level than 1,500 feet. It is absent from Lower Bengal and from the Malabar Coast south of Bombay; and it is not found east of India. Westwards, however, it ranges as far as the Persian Gulf. It is most abundant where cultivation is interspersed with bush jungle, and its harsh shrill call, beginning with single notes, and continued in trisyllables, is familiar to every one, for it is as well known in towns as in the country, being a favourite cage-bird with the natives. Some of these latter like the note, but the great reason for keeping partridges is the sport they afford as fighting birds. So pugnacious are they, that I have seen two birds let out of their cages near a lawn which had no idea of "going to grass," but flew at each other straightway; and they are commonly caught by putting out a tame cock in a cage garnished with nooses, in which his wild assailants are caught. To make him call and challenge them, he is blown upon, an act which excites him to the greatest fury. Many birds also, at Calcutta at any rate, are brought in as mere chicks, and brought up by hand. It may be such specimens are the very tame ones one sees following their owners like so many little dogs, when let out; but possibly this partridge, like the chukor, can be easily tamed when adult. Double-spurred birds now and then occur, and are naturally preferred by the natives for fighting, but I have never seen such a one.

For ordinary sporting purposes, amongst Europeans, this partridge is not much esteemed; it is hard to flush, being an inveterate runner, and when you have got it is apt to be dry and flavourless. The best time to get it in good condition is in the early part of the cold weather. It has a very bad reputation as a filthy feeder, but both Pea-fowl and Jungle-fowl, when found near villages, are not by any means blameless in this respect, so that very possibly the humble grey is not so very much worse than his betters in this respect.

The breeding season of this bird is an extended one, for while they usually go to nest between February and June, many breed a second time between September and November; the eggs are brownish white, and six to nine form the clutch.

THE SWAMP PARTRIDGE.

Francolinus gularis, Blanford, Faun. Brit. Ind. Birds, Vol IV., p. 141.

Native names:—*Kyah*, *Khyr*, *Kaijah*, Bengali; *Koi*, *Koera*, Assamese; *Bhil titar* of the Cacharis. Formerly sometimes erroneously called the *Chukore*.

This species is easily distinguished from most of our partridges by its large size and comparatively long legs; as in the last species, the sexes are alike in plumage, but the cock is easily distinguishable by his spurs. The upper plumage is brown barred with buff, and the outer tail feathers chestnut, as in the grey partridge; but the throat is bright rust-red, and the rest of the underparts brown longitudinally streaked with white, so that the effect is very different. The bill is blackish, the eyes dark, and the legs dull red.

The cock of this species, which is a little larger than the hen, will measure fifteen inches, though his tail is only a little over four; the wing is more than seven inches, and the shank measures two and a quarter.

The Swamp Partridge, as its name implies, has a quite different habitat from our other species, affecting high grass and cane-brakes near the edges of rivers and jheels, though it will come into cultivation to feed. It haunts the alluvial plains of the Ganges and Brahmaputra, extending from Pilibbit to the extremity of Assam and Cachar, and even occurs occasionally on the Khasi plateau; it is, however, absent from the Sundarbans. Very little is known about its breeding, but on two occasions five eggs belonging to the species have been taken in April; they were cream coloured and slightly speckled.

Owing to the localities which it frequents, the Swamp Partridge is usually shot from elephants; but Dr. Blanford states that he has shot it on foot near Colgong, in grass only three or four feet high. He states that it much resembles the common grey partridge in its edible qualities, as it also does in its call; and it is equally pugnacious. Mr. Hume, in the 'Game Birds of India,' falls foul of his artist for representing this species standing in water like a wading-bird. No doubt the draughtsman represented it thus in ignorance; but it would be interesting to know if this, one of the very few swamp-haunting birds in the Pheasant family, ever does go voluntarily into water in the wild state. The keeper of the aviary in which this species was confined in the London Zoo told me that he had seen it standing in water, and the white-winged Pheasant (*Phasianus principalis*) which inhabits the Bala-Morghab river's reed-beds, is known not only to wade but to swim, if necessary.

THE BLACK PARTRIDGE.

Francolinus vulgaris, Blanford, Faun., Brit. Ind. Birds, Vol. IV., p. 135.

Native names:—*Kala titar*, Hind., *Kais-titar* (the female) Nepal; *Tetra*, Garhwal; *Vrembi* of the Manipuris.

In this species the cock is spurred, and his plumage differs conspicuously from that of the female. His general colour is black with a long white patch on each side of the face; large white spots along the sides, and close white barring on the lower part of the back and the tail. There is a chestnut collar round the neck, and a patch of the same colour under the tail; the shoulders and most of the wings are brown marked with buff, the markings following the edge of the feather; the quills are barred with buff. The belly is pale chestnut marked with white; the crown streaked light and dark brown.

The hen is somewhat like the cock above, but the barring of the back and tail is coarser, and brown and buff instead of black and white. She shows no black on the head or below, and no chestnut on the neck except at the back. She has the eyebrows and sides of the head buff, the throat nearly white, and the rest of the lower parts buff irregularly pencilled with brown.

Young cocks are more spotted with white than the old birds, and young hens also are spotted on the breast, not pencilled like old ones.

The bill is black in the cock and dark brown in the hen; the eyes dark and the legs orange-red in both sexes.

The sexes both vary in size, but the cocks are the largest; one will measure about thirteen and a half inches, with the tail four inches and the wing just over six; the shank about two.

The Black Partridge with us inhabits Northern India from Sind to Manipur; its southern boundary runs south of Cutch and north of Kattywar, and thence to the Chilka Lake in Orissa. To the northward it ascends the outer slopes of the Himalayas, following the river valleys to about five thousand feet; Manipur is its eastern and southern limit, but it has a wide range to the west of India, ranging through Persia and Asia Minor even to Cyprus. It formerly inhabited Greece, Italy, Sicily and Spain, and appears to have been the bird known to the Greeks and Romans as *Attagen*, and was much esteemed for the table. It has, however, become extinct in these western countries, and is evidently a bird which needs careful preservation. This it well deserves, as it is an excellent sporting bird, and very good eating; in fact, one of the most desirable of all partridges. Its stronghold in India is the Indo-Gangetic plain and the regions adjacent; it especially affects high grass and tamarisk scrub near water and cultivation, and often cultivation itself. It is generally met with singly or in pairs. The male has a terribly harsh call-note or crow, which he is fond of uttering from an anthill. There is a pretty native legend which renders the call as "*Subhân, teri kudrat*," but I have never been able to fit these pious words to it, or any others. The Black Partridge breeds from May to August, most nesting in June: the eggs are fairly numerous, six to ten in a clutch, and drab in colour.

THE PAINTED PARTRIDGE.

Francolinus pictus, Blanford, Faun. Brit. Ind. Birds, Vol. IV., p. 137.

Native names:—*Titar*, *kala titar*, Maharatta; *kakhera kodi*, Telugu.

In this species neither sex possesses spurs, and the hen and the cock are much alike, though not indistinguishable. It is rather smaller than the Black Partridge. The cock is not unlike the male of the Black Partridge above, but very different below, being so heavily spotted with white that there is only enough black to separate the spots; there is no chestnut collar round the neck, but the eyebrows, face, and throat are chestnut. In the hen the throat is whitish, and the bars on the back are buff, and wider apart than in the cock. The bill is blackish, the eyes dark, and the legs orange-red.

This bird occupies a territory south of the Black Partridge's, the southern limit of that bird being the northern frontier of the painted species; this becomes rarer towards the south, and is absent from the Malabar Coast south of Bombay, as also from Mysore. Nor is it found in the Peninsula south of Coimbatore, although occurring in Ceylon on some of the hills west and south of Newera Eliya. It is not found east or west of India. It meets the Black Partridge on the boundary of that species, and hybrids between the two are occasionally found. Its general habits and its qualifications as a sporting bird and table delicacy are much the same as those of the Black Partridge, and it may be regarded as one of our most desirable game birds It is more often found in cultivation than the other species, and also more frequently found in dry grass land at a distance from water, so that it would appear to be of a more adaptable nature. Another detail of its habits which differs from those of the other species is its partiality for perching on trees, whence the male frequently calls; he has a different and less harsh note. Its nest and eggs are much like those of the Black Partridge, but it seems to breed somewhat later.

THE EASTERN OR CHINESE FRANCOLIN.

Francolinus chinensis, Blanford, Faun. Brit. Ind. Birds, Vol. IV., p. 138.

Native name : —*Kha*, Burmese.

This species is intermediate in size between the black and the painted francolins; the sexes differ in colour nearly as conspicuously as those of the black species, and the male only possesses spurs. The general colour of the cock is black spotted with white, these spots becoming broad bars on the belly. The top of the head is brown with pale edges and black forehead and eyebrows; there is another black band from the corner of the mouth to below the ears, and between this and the eyebrow a white streak covers the side of the face, the throat being also white. The lower back is black with close narrow white bars; under the tail is a chestnut patch, and the shoulder feathers and innermost wing quills are edged with chestnut and have the spots buff.

The hen is brown above, with a pale mottling; the lower back is barred with buff and brown; the chin and throat dirty white, and the underparts below this buff barred with dark brown, and plain chestnut under the tail. On the head the eyebrows and cheek-stripes are brown, and the light-band buff. The beak is dark brown, eyes light hasel, and the legs orange.

This Francolin is found, in our limits, only in certain parts of Burma, and in Karennee. It is common in certain localities north of Prome in the Irrawaddy valley; it has also been obtained in Toungoo and the Thounggyen valley. Outside Burma it inhabits South China Cochin China and Siam. Its general habits resemble those of the two previous species; it haunts forest clearings and waste land, and is also found in bamboo jungle. In Burma it breeds in June and July; as many as eight eggs may be laid, and they are pale buff in colour.

(*To be continued.*)

VI—EXTRACTS, NOTES, AND QUERIES.

"Spike" in Sandal Trees.

I READ your interesting article on "Spike" disease in sandal some weeks ago. May I venture to say something about it in your valuable paper. I have read with great interest Mr. Barber's Report on the above subject in the *Indian Forester*. Some very interesting experiments might be tried and noted I have been stationed in this Taluq (Hunsur for 1½ years, and have noticed the alarming extent the spike disease has taken hold of the sandal. In Mr. Barber's Report in the *Indian Forester* he quotes Mr. McCarthy, who says that the spike disease "originally came from Mysore in to Coorg." This I beg to differ from, because near the Coorg boundary the disease seems to me worse than towards the east. True, just outside the town of Hunsur the disease has got a thorough hold of the trees, but how far east this spike disease extends I cannot say. I would be very much obliged to some Forest Officers in the Mysore service who would give me some data on this subject in their respective districts. Mr. Barber seems to be in some doubt whether sandal trees with the disease produce flower and fruit. I say they do, as I have seen it. I hope to get photographs of it, and if Mr. Barber would care to see them I will very gladly send him a copy.

Another interesting thing I tried was how long sandal trees with spike live. In August last I marked three trees which were all in a line about 15 feet apart. I marked the trees as follows:—Nos. 1, 2 and 3. No 1 tree had the disease when I marked it, No. 2 had *just* begun spike. Nos. 1 and 3 were on the left and right and No. 2 was in the centre. From time to time I used to inspect these trees and watch their progress. Some time in November I inspected these trees again, and found No. 1 tree was dying fast. No 3 the disease was spreading rapidly all on the tree. No. 2 tree no spike, but dying in a different way. On the 1st February I had a look at them again, with the result that No. 1 tree was found quite dead, No. 3 tree in a very bad state;

No 2 tree dying, but still with no appearance of spike. How can Mr. Barber account for No. 2 tree not getting spike? Just before writing this I had a look at Nos. 2 and 3 trees (No. 1 I had dug up). No. 3 tree is all but dead, and I would venture to say that it will be quite dead by the middle of next month. No. 2 tree has no appearance of spike as yet. So in this individual case the life of this tree, since it started getting spike, is eight months. I hope to try this experiment in other localities in this range so as to strike an average to find out the length of time they live after once getting the disease.

As regards Lantana having anything to do with spike is, I think, doubtful, as for instance, in a certain gentleman's compound here, where Lantana has never been known to exist, certain sandal trees have been watched by him from time to time. There is certainly an appearance of spike on them. I don't think any one can say for certain now that Lantana is the cause of this.

Is spike a new disease? Sandal has been in existence for years and years in the Mysore Province. The disease may have existed some time or other, but whether it did or not, it is of a very virulent type at present. Some one laughed at me at the idea of having mentioned this subject, and said that the disease must have been going on for years and yet there is sandalwood to fill our *koties* with. Let that be as it may, but if any one would care to come round with me I will show them what havoc the disease is doing at present. Trees of all sizes, except saplings, get it, but at what age it makes its appearance, I would not venture to say.

The question now is, what is to be done to check the spread of the disease? In Coorg I believe they uproot all sandal trees with the first appearance of spike. It is all very well to do this in Coorg, where the area of sándal is not great, but in Mysore it is of a very different matter. Sandalwood is *the* chief source of revenue for the Mysore Forest Department, and I think the Mysore Government should go in to the matter at once and see what can be done. I think it is of a far more serious matter than some people think. Young trees die off in hundreds with no heartwood and are only useful for firewood. If this be the case, how long will sandal last at the present death-rate?

P. E. BENSON, in *Indian Planting and Gardening.*

HUNSUR.

President Roosevelt on Forestry.

ON the 26th March last the versatile President of the United States found leisure to lecture before the Society of American Foresters at Washington on "The Importance of Practical Forestry."

His lecture forms a clear and concise statement of the value and the aims of scientific forestry, and as such may be read with as much edification in India as on the spot where it was delivered. After laying down the theorem that the forest policy of any country must be an essential part of his land policy, Mr. Roosevelt went on :—

First and foremost, you can never afford to forget for one moment what is the object of the forest policy. Primarily that object is not to preserve the forests because they are beautiful, though that is good in itself; not to preserve them because they are refuges for the wild creatures of the wilderness, though that, too, is good in itself; but the primary object of the forest policy, as of the land policy, of the United States is the making of prosperous homes. It is part of the traditional policy of home-making of our country. Every other consideration comes as secondary. The whole effort of the Government in dealing with the forests must be directed to this end, keeping in view the fact that it is not only necessary to start the homes as prosperous, but to keep them so. That is where the forests have got to be kept. You can start a prosperous home by destroying the forest, but you don't keep it prosperous.

And you are going to be able to make that policy permanently the policy of the country only in so far as you are able to make the people at large, and above all the people concretely interested in the results in the different localities, appreciative of what it means. Give them a full recognition of its value, and make them earnest and zealous adherents of it—keep that in mind, too. That is the only way in which, permanently, this policy can be made a success. In other words, you have got to convince the people of the truth, and it is the truth, that the success of homemakers depends in the long run upon the wisdom with which the nation takes care of its forests. Now, that seems a strong statement. It is none too strong. There are small sections of this country, as of every country, where what is done with the woodland makes no difference; but over the great extent of the country the ultimate well-being of the homemaker is going to depend in a very large part upon the intelligent use made of the forests. Now, in other words, you yourselves have got to keep this practical object before your mind. You have got to remember that a forest which contributes nothing to the wealth, progress, or safety of the country is of no interest to the Government, and should be of little to the forester. Your attention must be directed not to the preservation of the forests as an end of itself, but as a means for preserving and increasing the prosperity of the nation.

. . "Forestry is the preservation of forests by wise use," to quote a phrase I used in my first message to Congress, and keep before your minds that definition, that forestry is the preservation of forests by wise use; not by abbreviating the use, but by making the forest of use to the settler, the rancher, the miner, the man who lives in the neighbourhood, and, indirectly, the man who may live hundreds of miles off down the course of some great river which has had its rise among the forest-bearing mountains.

The forest problem is in many ways the most vital internal problem of the United States. The more closely this statement is examined, the more evident its truth becomes. In the arid region of the West, agricultural prosperity depends first of all upon the available water supply. Forest protecion alone can maintain the stream flow necessary for irrigation in the West, and can prevent the great and destructive floods so ruinous to communities farther down the same streams that head in the arid regions.

The relation between the forest and the whole mineral industry is an extremely intimate one, for, as every man who has had experience in the West knows, mines cannot be developed without timber, usually not without timber close at hand. In many regions through the arid country ore is more adundant than wood, and this means that if the ore is of low grade, the transportation of timber from any distance being out of the question, the use of the mine is extremely limited by the amount of timber available close at hand.

The very existence of lumbering of course—and lumbering is the fourth great industry of the United States—depends upon the success of your work, of our work as a nation, in putting practical forestry into effective operation.

As it is with mining and lumbering so it is in only a less degree with transporation, manufactures, commerce in general. The relation of all of these industries is of the most intimate and dependent kind to forestry.

It is a matter for congratulation that so many of these great industries are now waking up to this fact, the railroads especially, managed as they are by men who are obliged to look ahead; who are obliged by the very nature of their profession to possess a keen insight into the future have awakened to a clearer realisation of the vast importance of economical use both of timber and of forests. Even the grazing industry, as it is carried out in the great West, which might at first sight appear to have little reference to forestry, is nevertheless closely related to it because great areas of winter range, ranges available and good for winter grazing, would be absolutely useless without the summer range in the mountains where the forest reserves lie.

As all of you know, the forest resources of our country are already seriously depleted. They can be renewed and maintained only by your co-operation, by the co-operation of the forester with the lumberman, with the practical man of business in all his types, but above all, with the practical man of business whose profession is lumbering. And the most striking and encouraging fact in the forest situation is that lumbermen are realising that practical lumbering and practical forestry are allies, not enemies, and that the future of each depends upon the other. The resolutions passed at the last meeting of the representatives of the lumber interests, which occurred here in Washington, were a striking proof of this fact, and a more encouraging feature of the present situation. As long as we could not make the men concerned in the great lumber industry realise that the foresters were endeavouring to work in their interests, and not against them, the headway that could be made was but small, and we will be able to work effectively and bring about important results of a permanent character largely in proportion as we are able to convince those men, the men at the head of that great profession, of that great business, of the practical wisdom of what the foresters of the United States are seeking to accomplish.

The last analysis, the attitude of the lumberman toward your work, will be the chief factor in the success or failure of that work. In other words, gentlemen, I cannot too often say to you—as, indeed, it cannot be too often said to any body of men of high ideals and good scientific training who are endeavouring to accomplish work of worth for the country—that they must keep their ideals and yet seek to realise them in practical ways. The United States is exhausting its forest supplies far more rapidly than they are being produced. The situation is grave, and there is only one remedy. That remedy is the introduction of practical forestry on a large scale, and of course that is impossible without trained men—men trained in the closet and by actual field-work under practical conditions. You have created a new profession—a profession of the highest importance, a profession of the highest usefulness toward the State; and you are in honour bound to yourselves and to the people to make that profession stand as high as any other—as the profession of law; as the profession of medicine; as any other profession most intimately connected with our highest and finest development as a nation. You are engaged in pioneer work in a calling whose opportunities for public service are very great. Treat the calling seriously. Remember how much it means for the country as a whole. Remember that if you do your work in a crude fashion, if you only half learn your profession, you discredit it as well as yourselves. Give yourselves every chance, by thorough and generous preparation and by acquiring, not only a thorough knowledge, not only the knowledge that goes deep, but a wide outlook over all the questions on which you have to touch. The profession which you have adopted is one which touches the Republic on almost every side—political, social, industrial, commercial—and to rise to its level you will need a wide acquaintance with the general life of the nation and a view-point both broad and high. Any profession which makes you deal with your fellowmen at large makes it necessary that if you are to succeed you should understand what those fellowmen are, and not merely what they are thought to be by people who live in the closet or the parlour. You have got to know who the men are with whom you are to work, how they feel, how far you can go, when you have to stop, when it is both safe and necessary to push on. You have got to know all of those things if you are going to do work of the highest value.

I believe that the foresters of the United States will create a more effective system of forestry than we have yet seen. If not, gentlemen, if you do not, I will feel that you have fallen behind your brethren in other callings; and I do not believe that you will fall behind them. Nowhere else is the development of a country more closely bound up with the creation and execution of a judicious forest policy. This is, of course, especially true of the West, but it is true of the East also. Fortunately, in the West we have been able, relative to the growth of the country, to begin at an earlier day, so that we have been able to establish great forest reserves in the Rocky Mountains, instead of having to wait and attempt to get Congress to pay a very large sum for their creation, as we are now endeavouring to do in the Southern Appalachians.

After congratulating his hearers on the good start that had been already achieved, the President ended by saying:—

Twenty years ago a meeting such as this to-night would have been impossible, and the desires we here express would have been treated as having no possible relation to practical life. We have reached a point where American foresters, trained in American forest schools, are attacking American forest problems with success. That is the way to meet the larger work you have before you. It will be a difficult work. Which, again, is true of almost any work worth doing; it will be a difficult work, and all the more so because precedents are lacking. It will demand training, steadiness, devotion, and *esprit de corps*, fealty to the body of which you are members, a desire to keep the ideals of that body high. The more harmoniously you work with each other, the better and more effective your work will be; and a condition precedent upon your usefulness to the body politic, as a whole, is the way in which you are able to instil your own ideals into the mass of your fellowmen with whom you come in contact, and at the same time to show your ability to work in a practical fashion with them, to convince them that this is a business matter. It will be for them to co-operate with you to convince the public of that, and above all, so to convince the people of the neighbourhoods in which you work, and especially the lumbermen and the others who make their life-trades dealing with the forests.—*The Pioneer.*

Forestry.

(From the Timber Trades Journal.)

In the House of Commons on Tuesday night, Mr. Herbert Lewis (Flint Boroughs) urged "that it is expedient to give effect as early as possible to the recommendations of the Departmental Committee on Forestry"* There were two cardinal facts in connection with the question which, he said, deserved the attention of the House and the country. The one was that the United Kingdom paid the enormous sum of £26,000,000 for imported timber, and the other was that the country contained 21 million acres of waste land on a large proportion of which afforestation could be undertaken with satisfactory financial results. The evidence that was given to the Committee on afforestation unanimously favoured some immediate and effective provision of bringing systematized instruction within the reach of owners, agents, foresters, and woodmen. That was a cardinal point of the recommendations of the Committee, and he was glad to believe that the President of the Board of Agriculture was himself in full sympathy with the spirit of that recommendation.

Mr. Hanbury said afforestation was a very important question, in which he had taken considerable interest When we saw how the supply of the rest of the world was gradually diminishing, and with the possibility before us of something like a timber famine in the not very far distant future, it behoved us to look more carefully than we had done in the past to our own timber supply. There was a good deal of land in the country which hardly brought in any agricultural returns, and he thought it very probable that much of that land might pay better under timber In various parts of the country they heard about the water supply becoming very scarce, and it was quite possible that a greater growth of timber in this country might go some way to remedy even that defect. (Hear, hear, The Departmental Committee had evidently conducted their work with the greatest possible care, but the evidence had not yet been published, and the hon'ble member had the advantage of him, so that he would not expect him to express now any definite opinion as to how far their recommendations should be given effect to. The recommendations would undoubtedly receive his very careful consideration, and if supported by the evidence he had no doubt they ought to receive the attention of the Government.

Mr. Lewis asked leave to withdraw his motion.

The motion was by leave withdrawn.

Mr. Nolan (Lough, S.) rose to call attention to the importance of this subject, when

---

* *Vide* No. 4, p. 155, of this Magazine (April 1903).

Notice having been taken that there were not 40 members present, and a quorum not being formed after the usual interval,

The House stood adjourned at 11 o' clock.

VII.—TIMBER AND PRODUCE TRADE.

Churchill and Sim's Circular.

4th May 1903.

East Indian Teak.—The deliveries for April amount to 1,160 loads as compared with 1,022 loads for the same month last year, making the deliveries for the first four months of 1903 3,674 loads, as compared with 4,458 loads for the same period of 1902. There is no change to report in the London market, which remains very bare of stock and at a high level of price. A little Java timber has been cleared up cheaply during the month Prospects of further supplies from the regular ports remain quite indefinite, but shippers are beginning to look forward to some period in the dim future when exports may possibly be resumed.

Rosewood, East India.—There is a fairly good demand for prime, large logs, but inferior wood is not easily sold; stocks, however, are not accumulating.

Satinwood, East India.—The demand is rather quiet, and only small sales have been made, but prices are steady, finely figured logs commanding most attention.

Ebony, East India.—There is a fair demand for wood of good sizes.

PRICE CURRENT.

Indian teak, logs, per load	...	£10 5s. to £18 10s.
„ „ planks „	...	£13 5s. to £20.
Rosewood, per ton ...	...	£8 to £11.
Satinwood, per s.ft. ...	...	6d. to 18d.
Ebony, per ton ...	...	£8 to £12.

Denny, Mott and Dickson, Limited.

Wood Market Report.

London, 4th May 1903.

Teak.—The landings in the docks in London during April consisted of 663 loads of logs and 366 loads of planks and scantlings, or a total of 1,029 loads, as against 203 loads for the corresponding month of last year. The deliveries into consumption were 882 loads of logs and 244 loads of planks and scantlings—together 1,126 loads, as against 989 loads in April 1902.

The dock stocks at date analyse as follows:—

5,062	loads of	logs,	as against	7 353	loads at the same	date	last year.
2,901	,,	planks,	,,	3,581	,,	,,	,,
—	,,	blocks,	,,	—	,,	,,	,,
Total 7,963	loads		,,	10,934	loads	,,	,,

The European landed stocks show a further considerable reduction all round, and the bulk of fresh supplies continues to go direct into consumption. The enhanced rates are now freely paid by consumers, as it is fully realized that the increased prices do not bring forward a sufficient supply to meet the requirements of the market. Supplies at the shipping ports, as already foreshadowed, cannot be augmented for many months to come.

Business during April has been quiet, the holidays at the commencement of the month causing the usual trade dislocation Stocks all round are not excessive, and business continues steady —although of a hand-to-mouth character.

Market Rates for Products.

TROPICAL AGRICULTURIST.

1st *May*, 1903.

Cardamoms ...	... per	lb.	1s. 6*d*. to 1s. 9*d*.
Croton seeds ...	... ,,	cwt	15s to 25s.
Cutch ...	... ,,	,,	25s. to 30s.
Gum Arabic ...	... ,,	,,	15s. to 20s.
Do. Kino ...	... ,,	lb.	4*d*. to 5*d*.
India-rubber, Assam	... ,,	,,	2s. to 3s.
Do. Burma	... ,,	,,	2s. to 3s.
Myrabolans, Madras	... ,,	cwt.	5s. to 6s.
Do. Bombay	... ,,	,,	4s. to 7s. 6*d*.
Do. Jubbulpore	... ,,	,,	4s. to 5s. 6*d*.
Do. Bengal	... ,,	,,	3s.
Oil. Lemon-grass ...	... ,,	lb.	5*d*. to 5½*d*.
Orchella weed ...	... ,,	cwt.	10s. to 14s.
Sandalwood, logs ...	... ,,	ton	£15 to £50.
Do. chips ...	... ,,	,,	£4 to £8.
Seedlac ...	... ,,	cwt.	115s. to 120s.
Tamarinds, Calcutta	... ,,	,,	8s. to 10s.
Do. Madras ...	... ,,	,,	4s. 6*d*. to 6s.

CORRECTION SLIP.

In the paper 'A Note on the Sandal Wood Boring Insects of Madras' by E. P. Stebbing, published in the July number of the Indian Forester (Appendix Series), page 1, line 16, for 'per maund' read 'per ton.'

THE
INDIAN FORESTER.

Vol. XXIX.] August, 1903. [No. 8.

Harry Charles Hill.

By Sir Dietrich Brandis, K.C.I.E., F.R.S.

The excellent notice of my dear late friend, which appeared in the *Indian Forester* of January last, has given me great pleasure, and I wish to supplement it by a few recollections of my own.

Hill was educated at the Sutton Coldfield Grammar School. At the entrance examination for the Indian Forest Service in 1869, he was only 17 years old, and was one of the youngest who competed at that examination. Nevertheless he came out not far behind the first successful candidate, beating several men from public schools and others considerably older than himself. Hill had passed in French, and hence was among those who were sent to study Forestry in France under the arrangements which I had been permitted to make while on furlough at home in 1866. Under these arrangements the students were in the first instance sent to Haguenau in Alsace for a course of practical work under Clément de Grandprey, who was then in charge of those forests. On the outbreak of the Franco-Prussian war this work came to an end, and in August 1870 the English students were sent home, where they were employed under Dr. Cleghorn's guidance in studying Natural sciences, Hindustani and Surveying, first at St. Andrews and afterwards at Edinburgh. At St. Andrews Hill obtained the prize for Practical Chemistry, and at Edinburgh he was first in the Surveying class. The students returned to Nancy in August 1871, and completed their course there in October 1872, working steadily and without any holidays, as the ordinary course of the Forest School was of two years' duration and they had barely 15 months to do it in. At that time I was in England on my second furlough, and went to Nancy to see the students. On this occasion the Professors told me: "*Tous ces jeunes Anglais sont de bons garçons, mais Hill c'est le vrai Forestier.*" At my suggestion the Right Hon'ble Sir Mountstuart Grant-Duff, then Under-Secretary of State for India, also went to see the English students at Nancy and he was greatly struck with Hill, whom he only met on that occasion. He retained a vivid recollection of him and has asked me to say that he was deeply grieved when he heard of his death.

After working in Oudh for two years, Hill was attached to the Forest Survey Branch, which in 1873 had been organized by Lieutenant-Colonel F. Bailey. In consultation with that officer I conceived the idea of attaching temporarily one or two professionally trained men to the Forest Survey. Several young officers, to whom I made proposals to that effect, raised objections: "We have learnt surveying and do not require further practice in that work. It is more useful for us to stick to Forest work proper." Bailey, while at home on furlough, had visited Nancy, and Bagneris, one of the Professors, had recommended him to get Hill for the Forest Survey. When the proposal was made to Hill he agreed at once, and his joining the Forest Survey has proved most useful to himself and to the public service. Colonel Bailey writes: "During the time Hill was under me, I formed a high opinion of his ability and devotion to his duties; he quickly picked up the work, and in due course rendered valuable assistance in the development of the Survey Branch."

In 1876 Hill was transferred to Burma, where he was first employed in Tharawaddi and Prome on demarcation work and afterwards held charge of the Toungoo Division. At this transfer he did not grumble for he realized that service in Burma was a necessary preparation for advancement to higher and more responsible positions. In 1866, when I had the good fortune of selecting two distinguished young German Foresters for the Indian Forest Service, Dr. Schlich and Mr. Ribbentrop, my idea was that, if all went well, the former would eventually succeed me; accordingly I arranged that he should be posted to Burma and afterwards successively to other Provinces. Again, in 1874, when we were together in Jaunsar, I informed Mr. Ribbentrop that his time had come to go to Burma.

My reason for this action was, that the forests of lower Burma had since 1856 been worked on a well-considered plan and had ever since that time yielded a steadily increasing annual crop of teak timber and of revenue, while in other Provinces similar results had been attained at a much later period. Now, since the annexation of upper Burma, the net annual revenue produced by the Burma forests equals the net forest revenue of all other Provinces taken together. It stands to reason that service in Burma must be regarded as a necessary preparation for employment in the highest appointments.

Hill soon distinguished himself in Burma. From 1881 to 1884 he was acting as Conservator, first in Tenasserim and afterwards in Pegu. Subsequently, in 1885 and 1886, he was

Conservator of Forests in the Punjab, until, after the annexation of Upper Burma, he was sent back as Conservator of Forests and *ex-officio* Secretary to the Chief Commisioner in the Forest Department for Upper Burma. In August 1889, he was appointed to act as Inspector-General of Forests. The remainder of his career is well-known to the readers of the *Indian Forester.*

He was on furlough at home from March 1891 to March 1893, and on that occasion (summer of 1891) I had the privilege of his company on a three months' tour with the Cooper's Hill Forest students. This was the fourth tour I had undertaken, and my experience had led me to the conclusion that these three months' tours were to a great extent a waste of time and money. Hill at once understood the position. He saw that, though the students had had the inestimable privilege of Dr. Schlich's excellent teaching, the majority of them did not realize the importance of their own profession and did not fully understand what they saw on these tours. It was due mainly to his influence that the new system, which I had advocated, of sending the Cooper's Hill Forest students to Germany for actual service under Prussian Forest officers, was sanctioned, and this period of preparatory service has now fortunately been extended to nine months. Under this system, which was established with Dr. Schlich's full concurrence, the students now derive the full benefit of his excellent teaching, and this probably is now acknowledged by all those who have had the privilege of studying at Cooper's Hill.

Hill fully realized the necessity of making Forestry indigenous in India and the drawback of its remaining an exotic plant. He appreciated the advantage of inducing young Native gentlemen of the more influential classes to enter the Forest School and the Forest Service. He strongly supported the proposal to class Forest Rangers in the Provincial and not in the Subordinate Service. In this respect he did not succeed, but in course of time Forest Rangers will doubtless be classed in the Provincial Service.

Hill did not claim to be a scientific man either in Botany or in Zoology. He was familiar with the trees and animals of the forest, and he approached the manifold questions, which the treatment and management of forests present in India, from a scientific point of view. We all know that he was truly great as a sportsman, and this was an important advantage to him in his work.

A Forester, more than almost anybody else, must use his eyes and must be able on the spot to draw conclusions from what he has observed, and the training of a sportsman is an excellent help in his work. It makes life in the forests delightful to him, it induces him not only to *visit* the forests, but to *live* in them. He becomes much easier familiar with the development of the growing stock and its requirements, than a man who is not a sportsman. It gives me great pleasure to call to my mind the great achievements in Indian Forestry of Colonel Pearson, Colonel Doveton, Colonel F. Bailey and the late Colonel Peyton. These eminent men had not had the privilege of a regular training in their profession, but their love of sport made the forest their home, and this is the first condition of success in our business.

The readers of this paper will not misunderstand me. I have often heard people in India, as well as in England. say that a keen sportsman must necessarily be a good forester. This is about as absurd as the idea which, until a short time ago, was current in England, and which to this day is held by many English botanists, that a good botanist must necessarily be a good forester. Both love of sport and devotion to Botany or Entomology are most useful helps, but they are not Forestry. The forester's business is to solve the problems of sylviculture and of forest management in a practical manner, and Hill realized this to the fullest extent.

Hill loved his profession: success in sylviculture, in forest management and in adminstration, was the aim of his ambition. He was strong and determined in endeavouring to carry what he considered necessary for the welfare of future generations in India. At the same time he had great tact and he readily gained the confidence of those who were associated with him in public affairs. I am proud of having had the privilege of his confidence and his friendship.

Recollections of the early days of the Indian Forest Department, 1858—1864.

By Colonel G. F. Pearson, I.F.S., Rtd.

In the year 1858, when the embers of the Mutiny were still smouldering in the country, I was in command of a regiment of Military Police at Seoni in the Central Provinces. The corps consisted of a squadron of Cavalry and four companies of Native Infantry, in all about six hundred men with three English officers. It was in September of that year that Tantia Topee made his celebrated raid into the Deccan During the raid he halted for three days with three thousand Cavalry at a place, on the Pench river, not sixteen miles from my station. We fortified the public offices as best we could with entrenchments and sandbags, but whether his horses and men required rest, or whether he considered us too insignificant to claim his attention, he did not attack us, but retreated across the Nerbudda on learning that a British regiment and at least two batteries of Artillery were stationed at Nagpore, which was without doubt his real objective. He was not long after captured in Rajputana and his followers broken up and dispersed. While he was near us we had an anxious time; I can vouch for it that there was little sleep for any one in Seoni until he retired across the Nerbudda.

My principal duty while in command of this force was to patrol the country, rout out any mutineers and disaffected natives who might be skulking in the hills or forests, and it was while employed in this way that my attention was first directed to forest conservancy.

As soon as the Mutiny was suppressed the railways were taken in hand and the timber merchants and sleeper contractors raided the forests for timber, felling trees wherever they liked, generally finding they could not remove them after they were down. It was only necessary for a contractor, whether European or native, to obtain a parwana or order from the civil authorities to cut timber for him to set to work, and as every Gond carried an axe it was not long before the forests were strewn with fallen logs, no attempt being made to collect or store them. In fact in many cases it was impossible to do so, with the result that the greater part of the timber was either totally or partially destroyed when the forest fires set in. I continually brought this to notice in my reports, and my having done so, no doubt paved the way to the formation of a department whose duty would be the preservation of the forests from ruin It may be of interest to mention that the granting of these parwanas was not without its after-use, as when the rights of Government to the forests and timber in them were questioned, they helped to prove a claim. The use of the term 'Conservator' was also deliberately adopted at this time by Government, as indicating more strictly the first duty of the Forest Department. Then, as now, there was a disposition in some quarters to insist on its being a revenue-producing department, an idea which, if carried out, would necessarily end in forest destruction.

In the spring of 1859, under instructions from Mr. A. Cox, Officiating Commissioner of Jubbulpore, I made a thorough inspection of the forests of the Mundla plateau and of those along the Meykeel range as far as Bundhara. Starting from Mundla in March, I marched through the Khormeyr country, which forms the upper basin of Nerbudda, to Amar Kantak, from near which place that river takes its rise. To this point the Satpura and Meykeel ranges converge, forming the two great plateaux of Amar Kantak and Goura Dadur at an elevation of 3,5 0 feet above sea level, and I have a vivid recollection even at this distance of time of the grand view obtained from them, standing out as they do like great headlands into the plains of Chattisghar and Paindra, fully 2,000 feet below them I remember, too, on the Choura Dadur falling in with a splendid herd of *bara singah* or Indian red deer, in the open, and by careful stalking I managed to secure the stag, whose horns—with those of a large buffalo I shot near Raigur Bitchia—are now on the walls of the hall in my brother's house in North Wales.

From Amar Kantak I turned back to the S. W., following the ranges for nearly 200 miles, visiting every hilltop and dadur, exploring the forests, noting their contents and getting as far as possible into touch with the Bygars and Gonds inhabiting them, so as to endeavour to learn something of their habits and customs. I need not speak in detail of the forests I visited as they are now well known, but I may mention that while the mature teak in the Bormeyer and Khormeyr valleys was nearly all destroyed and burnt in the same way as in Seoni, the sal forests on the upper plateaux and on the Kunjar river were practically untouched. There was splendid shooting to be got in this country. I succeeded in securing several good heads from amongst the herds of red deer and buffalo which roamed about amongst the glades between the forests almost unmolested by man, and which, until I came, had probably never heard the crack of a rifle. While I was making my way south along the Meykeel hills I got news of a man-eating tiger which infested a pass over the hill range dividing the upper waters of the Halon river from those of the Bunjar river. I determined to try and shoot him. Just before reaching the place I met a party of Gonds who had crossed the pass at a village called, I think, Bheenlat in the upper Bunjar valley. When crossing the pass they had with them a poor woman carrying her two-year old son in a cloth on her back, who probably being tired had fallen behind the rest of the party, and had become a prey to the tiger who, as usual, was on the lookout for stragglers. The Gonds at first ran away, but returned later armed with tom-toms and matchlocks to try and recover the bodies. On arriving at the place where the woman had been seized they found the boy sitting almost unharmed within a dozen paces of the spot where the tiger had dragged and was eating his mother. I could find no father to claim the boy so I pensioned him off on Rs. 2 a month to an old couple who brought him up until he was able to earn his own living and when I last heard of him he had grown into a fine strong boy well able to take care of himself. I had several tries at finding this tiger but was always unsuccessful as he had probably been frightened away for the moment by the return of the Gonds. I believe he was afterwards shot by Mr. Jacob.

It was about this time, too, that the famous Doomah panther played havoc with men, women and children in the northern part of the Seoni district. This beast was credited with no less than ninety-three human kills, reported at my police station in Doomah, in one year. Certain it is that he killed three people in one night in the immediate vicinity of the village, one of them being the mother of one of my sowars whom he dragged out of a hut in the police lines. Both Captain Thompson and myself had many tries for her, but always failed to kill her, though Thompson missed her once She was eventually killed by a native shikaree, to whom the reward of Rs. 500 was paid, after no more kills had occurred for six months. The panther's range was from ten to fifteen miles round Doomah and he seemed almost ubiquitous, killing in one place one night and in another ten miles off the next. There were many stories afloat amongst the natives about this panther, the favourite one being that he had been a Bygah priest, who by means of taking a powder had the power of turning himself into any animal he liked, and by taking another powder of returning to human shape While travelling through the jungle with his wife, finding their road blocked by a panther, the priest took one of the powders to turn himself into a panther and drive off the intruder, at the same time giving his wife instructions to give him the other powder when he returned from having done so; but his wife, on seeing him in the form of a panther, was so frightened that she dropped the powder and ran away, causing him to remain as he was. The priest's rage at this was so great, so the native story ran, that out of spite he killed every man, woman or child he could find. But against this theory was the fact that the true culprit was a female and the question was asked: "Had the powders the effect of changing the sex as well as the form?"

In August 1860 I was appointed Conservator of Forests in the Saugor and Nerbudda territories and had two assistants allowed me. I selected Lieutenant Forsyth of the 26th Punjabis and Lieutenant Douglas of my own regiment, the 33rd Madras Native Infantry, for these posts. They both turned out excellent men for the work, Forsyth being one of the ablest men I ever had under me; indeed, so able a man was he that three or four years after he was singled out by Sir Richard Temple for civil employ and appointed Deputy Commissioner and Settlement Officer of Nimar. His settlement report of that district was, I believe, considered second only in importance and ability to that of Sir Charles Elliott for Betul and Hoshangabad. Forsyth's early death, brought on largely no doubt by exposure and overwork, can never be too deeply regretted either by his friends or by the public service.

Our first work was to collect in depôts at Jubbulpore and Mundla as many of the half-burnt logs, which were strewn over the forest, as was possible. We soon had many thousands of logs collected and the proceeds of the sale of these furnished the funds of our first modest little budget for 1861-62.

In 1861 the Central Provinces were constituted as a Chief Commissionership under Sir R. Temple, and the Southern Province was added to my charge, and in the following year the Berars with the valuable Melghat forests were also placed under me. The whole of these years were spent in exploration, and much year I marched over two thousand miles, besides doing the forest work. I twice visited Puchmuree during this period and negotiated with the Takoor for the lease of the plateau to the British Government. In all this work I was ably seconded by Forsyth and Douglas; Forsyth building the forest bungalow on the Pachmuree; Douglas examining and reporting on the teak and sal forests in Mundla while I was working in the Boree and Betul forests. Forsyth's share of the work is admirably told in his well-known book "The Highlands of Central India."

At that time the jungles of Betul and Hoshangabad were literally swarming with tigers, and I soon got in touch with them while doing my work. I once came across four full-grown tigers lying in the shade of a rock by a pool on the Machna river, six or eight miles below Sharpur. I was liberally supplied with Commissariat elephants and besides had my own excellent shooting elephant, Fulty Ranee, so that I never had any difficulty in following tigers. Perhaps one or two stories of man-eating tigers I shot may not be without interest.

The worst man-eater in the district was a tigress infesting the ghat on the road from Sharpur to Betul. She had killed over sixty people in eighteen months and had twice taken the dâk runner, so that it was difficult to find any one to carry the mails. As she killed cattle as well as men, which is not usually the case after a tiger has taken to man-eating, I determined to try and find her near one of her kills as soon after it had taken place as possible. I soon got news of her having killed a buffalo and at once set off on Fulty Ranee accompanied only by one or two natives who knew where the kill was, as she was reported to be very bold and not at all afraid of the approach of man. No sooner had I got there than I saw her move out of a nullah, into which she had dragged her kill, and across some open ground perhaps a quarter of a mile wide, to a small isolated hill covered with grass and low scrub, sitting down near the top of it and watching me. Not wishing to risk the lives of any of the men by trying to drive her, and also to see what she would do as the country behind her was rather open, I determined to see how near she would let me approach her. She allowed me to come to the foot of the hill without moving, so I told my mahout to advance very slowly up the hill. I had my smooth bore gun loaded with a single bullet in the right barrel and two bullets in the left, a practice I always adopted when after tiger. We continued to mount the hill step by step, expecting the tigress to charge at every moment, but still she did not move but crouched on the ground facing me, and therefore offering a very bad shot, especially as she was above me. When within twenty yards of her I judged it better not to delay any longer, lest she should take the initiative and charge, as a couple of bounds would have brought her on top of us; so aiming between the eyes I fired the right barrel at her. I hit her lair and she came rolling down the hill like a shot rabbit, passing within a few feet of the elephant, and roaring fearfully as she passed. I fired the left barrel, with the two bullets in it, hitting her under the shoulder and killing her dead. There was great rejoicing in Sharpur that night.

Had I not seen it myself I would never have believed that a tiger would act as this one did, never moving when attacked. My mahout and elephant both behaved with the greatest coolness and pluck under very trying circumstances, never faltering or showing sign of fear at any time. I missed the tigress' male companion two days afterwards in a miserable manner, but as no more men were killed I felt more or less consoled.

Soon after shooting this tiger, and while still in the neighbourhood of Sharpur, I received a message from Sir Charles Elliott, the Settlement Officer, who was then encamped at Rajaborari on the extreme western border of Betul, telling me that a tiger near there had killed ten people in as many days and asking me to try and shoot it. It was then late in May and very hot, and having from twenty to thirty miles to go I determined to march at night, making a halt to feed and rest my elephants in the early morning. I arrived at Rajaborari about three o'clock in the afternoon and determined to try and find the tiger at once, before he began moving about in the cool of the evening. I learned that he had killed a boy on the previous evening and was probably lying up in a dry nullah not far off, so taking the village policeman, who had been with the boy when he was killed and knew the place, I proceeded to the spot I found the tiger's lair to be an insignificant nullah covered along the bottom with 'jhow,' and with several shallow pools of water in it. I had not gone twenty yards up the nullah when the tiger slowly raised himself into a sitting position just in front of me, offering me a full chest shot. I fired both barrels at him and he fell dead by the side of his victim, whom he had devoured up to the armpits, the head and shoulders alone remaining—a truly ghastly spectacle to look at. He was, I think, the longest tiger I ever shot, being considerably over 10 feet, though I do not recollect his exact measurement, but he was miserably thin and was suffering from a festering and jagged wound reaching from the shoulder to nearly the tail, caused evidently by an iron bullet from some native shikari's matchlock. I believe that this tiger had taken to man-killing because he was unable to kill animals on account of his wound and was slowly starving to death. I received a considerable reward (Rs. 500 or more) for killing these two tigers, which I spent in founding a school for Gond villagers in Upper Machna, where the schoolmaster had not yet made his appearance. I daresay by this time they are so educated that I should not recognise them as the same people as I knew. I wonder if there are now any Gond rangers at the Dehra Forest School?

In 1863 Doctor (now Sir) Dietrich Brandis was appointed the first Inspector-General of Forests in the early months of that year. I was summoned to meet him at Nagpur. We marched together to Allicutta on the Pench river, and from there I conducted him through the teak and mixed forests at the foot of the Korai Ghat range as far as the Wyngunga, and then for a short tour in Mundla. I remember that he was greatly pleased at my being able to go through the forests without a guide, but I should not have been able to cover a quarter of the ground that since my appointment to the department I had explored, nor should I have been able to acquire the knowledge of the forests and their contents, as well as of the tribes that inhabit them, which I possessed had I not early learned to do so. It is a habit which every Forest Officer should cultivate.

It was in conversation between Sir Dietrich and myself during these marches that the main points of our forest policy were discussed and laid down in a preliminary manner, and it may be said that ever since then they have governed the working of the Forest Department. These points were: -

I.—Demarcation of reserves.

II —The protection of forests from fire.

III.—Sources from which a forest revenue might be raised.

It was then decided to select two blocks of forests in which practical experiments in protection from fire should be carried out. After mature consideration I selected for this, and Sir Dietrich fully concurred with me, one block in the Boree forest at the foot of the Puchmuree hills, and the other block in the Jugmundel forest on the Khormeyr plateau of the Mundla hills. Both were forests capable of isolation by the natural features of the country and were in other ways well adapted for the experiment. For carrying out the work in the former I obtained the services of Lieutenant Doveton, 1st M. N. I., and it is to his unremitting zeal and watchfulness, as well as to the tact he showed in dealing with natives, that this work was carried to such a successful conclusion. It is impossible to overestimate the importance of this success as most foresters and every civil officer in the country scouted the idea of forest protection from fire and everything connected with it, and had the attempt been a failure, any progress in fire-protection elsewhere would have been rendered immeasurably more difficult. As it is everyone connected with Indian forests knows what a large part fire-protection now plays in forest conservancy, and it is to Colonel Doveton that this is largely due. I am glad to think that he succeeded me as Conservator in the Central Provinces on my transfer to the N.-W. Provinces in 1868. During the twenty years he held that appointment, he built up the efficient forest department existing there now.

The Jugmundel fire-protection reserve was placed in charge of Lieutenant Douglas, but it was not at first attended with the same success as in the Boree reserve. This was in no way due to any want of attention or care on the part of that officer, but solely to the hostility of the Ahirs in charge of cattle brought up from the lowlands to graze in the Mundla uplands, who wanted to burn grass for their own purposes.

From Mundla Sir Dietrich and myself visited the Beejarngoghur sal forests on the Rewah frontier, where Lieutentant Douglas was arranging for a supply of sleepers for the railway in course of construction from Allahabad to Jubhulpur. I recollect that on our arrival in Douglas' camp we found waiting for us an excellent breakfast, carefully laid out by his Madras servant on a white table cloth with real bread and butter—a luxury we had not had for some time. Sir Dietrich was much pleased at this and remarked to me that Douglas would made a good forest officer 'for he pays attention to details.'

The Inspector-General and I parted company here. I returned to spend the hot weather in the Boree forest to start the fire-protection schemes. The next year was chiefly spent in the Berar and Melghat forests, and in June I went home, not seriously ill, but in need of a rest after seven consecutive hot weathers spent in the plains, and all the early portion of the rains spent in camp or in huts, with constant work and little rest.

With all the means of locomotion that now exists forest officers of the present day can hardly know how rough the life was in those early days of forest work. Still, there were many compensations. We had less office work to do and a liberal supply of Government elephants at our disposal, and a good supply of tigers and other game in the forests whenever opportunity offered to go after them, and it may be of some comfort, even now, to some fever-stricken forest officer to know that, although in my 77th year, and over thirty years after I have left India, and in spite of my being saturated with fever when in India, I am thankful to say I am quite as active as any of my neighbours of the same age, who have never left England.

Notes from an American Forest Reserve.

By Charles Howard Shinn,

U. S., Head Forest Ranger.

The American forest reserve system is unlike any other known to me, and though now only in its beginnings, has large possibilities of future usefulness to the nation. The method followed has been to withdraw from sale all Government land within certain desired limits, and after careful examination of these lands has been made, the President of the United States sets them apart as Forest Reserves. Following this plan, fifty-six such reserves now exist, all under the care of the Commissioner of the General Land Office, who is the chief of a bureau in the Department of the Interior, one of the eight great executive departments of our Government.

On June 30th, 1902, when the last annual reports were issued, these reserves numbered fifty-four, and embraced a total area of considerably over sixty million acres. If a number of new reserves now proposed are created, the area will be carried up towards eighty-five million acres. The withdrawals preliminary to the establishment of new reserves, and additions to those existing, numbered nineteen in 1902, and two more withdrawals had been made for the creation of state forest reserves, making a total of twenty-one possible additions.

Besides these forest reserves there are a number of National Parks in the charge of the War Department and patrolled by soldiers. Then, too, the Bureau of Forestry of the Department of Agriculture, which has charge of the scientific and technical foresty work of the Government, has certain small but important reserves where experimental work is constantly being carried on. The Bureau also advises and plans for many lumbermen, and other owners of vast tracts of forest land.

It may be that all the forest responsibilities now scattered through three departments of the federal Government will finally be drawn together in some shape so as to be subject to one authority. We may come at last to have a Secretary of Forestry and Water Supplies sitting in the President's cabinet, but that time now seems remote.

The reserves are widely scattered, from Alaska to New Mexico; but most of them are necessarily in the west and on the Pacific Coast, though a great struggle is now going on to create a magnificent reserve in the heart of the Appalachian Range—in the famous mountains of Virginia, the Carolinas, Tennessee and other old States. California now has eight reserves, and the land for several more is withdrawn from sale, so that it is likely that a long chain of such forests will some day extend along the entire length of the Sierra Nevada mountains.

The largest California Reserve, named the Sierra, is that where I am stationed, and covers 4,096,000 acres; four others in America are somewhat larger. It is a great land of foothills and mountains, rising from an elevation of about 2,500 feet on the western slope of the Sierra Nevada, to the eternal snows of such peaks as Lyell and Whitney nearly 15,000 feet high and extending far down the eastern slopes. It contains enormous bodies of very fine timber, much of which is however inaccessible until roads have been cut or lumber flumes have been built from the valley. Its problems of management, exploitation and development into almost continuous forests are peculiarly those of a very wild mountain region.

The leading timber tree is the Yellow Pine of the Pacific Coast (*Pinus ponderosa*), which, as one ascends towards the snow, changes to the higher mountain form, *P. jeffreyi*, often called but a variety. From the forester's standpoint the Jeffrey Pine differs little from the smaller-coned, more golden-barked and larger *P. ponderosa*, but it is even hardier, and is the great timber tree of the Carson mountains in Nevada, of the Lake Tahoe basin, and of many other districts.

The superb Sugar Pine, *P. lambertiana*, is beyond question one of the lordliest and most valuable of California trees, but it does not occur in such forests as does the Yellow Pine, nor is it capable of such easy and rapid reproduction. The same is true of the small-coned or Little Sugar Pine (*P. monticola*), which belongs to the higher ridges, usually above 6,000 feet, and occupies about the same relation to the large Sugar Pine that P. *jeffreyi* does to *P. ponderosa*.

The two great Firs of the Sierra Reserve are the Red, (*Abies magnifica*) and the White (*A. concolor*). Both form great bodies of timber and will in time have much commercial value, but now can seldom be profitably cut. The same is true of the abundant Western Tamarack (*Pinus murrayana*) that grows in moist meadows at great heights. In Nevada this pine, also the Mountain Hemlock (*Tsuga mertensiana*), and even the fir, are cut for firewood, and thousands of cords are annually flumed down to the valleys. But California, with its great supplies of firewood. petroleum, etc., is not yet ready to utilize these coarser woods for any purpose, excepting the fir for paper pulp, and to some extent for shingles.

The deciduous forest here is a beautiful one, including several fine species of Oaks, besides the Western Ash, the giant Dogwood (*Cornus Nuttalli*) and lesser trees The oaks are as yet unused except for firewood, but experiments made upon their timber show that they possess remarkable beauty and grain, so that this forest-asset will in time become very valuable.

All of the reserves contain private holdings, as men had settled there and had "taken up" land under the American laws before the reserves were created. Some of these holdings were used for pasture, some for farms. The policy of the Government has been gradually to exchange lands elsewhere for these holdings. The rules and regulations of the reserves are of course enforced throughout the entire area. In fact, the reserves contain miners, prospectors, cattle men, hunters, farmers, lumbermen cutting their own timber, and in summer many campers and pleasure-seekers. The officers in charge of a reserve must deal with many subjects, and must meet many people. Their professional duties of surveying the timber, clearing brush, making firebreaks, thinning young forest, burning waste and trash, gathering seed and planting it, keeping records and maps, and all the daily details of forest life, are mingled with care for the needs of many persons. Free firewood and free timber for the actual use of the applicant, but not to sell, free pasturage for the number of horses and cattle that the range is estimated safely to carry (but usually not for sheep, goats or hogs), come within his daily duties, and many similar items could be mentioned if space permitted.

The sale of "down or dead" timber is going on in various reserves, and the sale of ripe but growing timber is beginning. Preliminary surveys and actual working-plans are being made, and the United States Geological Survey has published stately volumes, with abundant maps, upon the topography, soil and tree-growth of a large number of these reserves. This preliminary work is still going on, and will cover the entire system.

At the present time, the lowest forest worker is the Ranger of the third class, who receives $60·00 a month and furnishes his own camp outfit, including saddle and pack horses. Above him are two grades of Forest Rangers, receiving respectively $75 and $90. Over these are the Head Forest Rangers, who are assigned to different reserves and whose salaries vary according to their duties and responsibilities. Some of the reserves have another officer known as a Supervisor; in some cases the Head Rangers take the place of the Supervisors. Each of the Forest Superintendents have charge of a number of reserves. There are two such in California, one north of the Tehachipi, one south. The Forestry Division of the Office of the U. S Land Commissioner at Washington is the head of the whole system.

The total force of the forest rangers of the three lower classes is about 425 in the summer, when the danger from fire and trespassers is greatest, but it is considerably reduced in the winter. This force is of course inadequate to do very much besides making trails, and patrolling and preserving the forests, though by careful organization some thing is being done with forest surveys, fire-breaks, brush-clearing, the thinning of young pine thickets, etc. The rangers are, as a rule, hardy and intelligent young Americans, full of enthusiasm for the work.

As the force increases, and as timber sales and paid-for cattle-range leases on a large scale begin, the reserves will become self-supporting.

This brief paper is only a glimpse of the beginnings of a great forest system. The work presses, the labourers are few, and there is no time for writing long articles. California already has nearly nine million acres of forest reserve, all in the high mountains. A forest officer must make a number of headquarters at various elevations for summer and winter; wagon roads are few and the pack-mule is his main dependence for supplies; a hundred miles on horseback "across country" down into cañons a thousand or more feet in depth, or over snow-covered ridges above fair vales of the grape and olive, is but a little journey in this land of the Sierra Nevada, this mighty rock-wall of the western third of North America. Still there is fellowship here, in the snows of March, with foresters all over the world; still the *Indian Forester* brings to this mountain cabin the fascinating story of your lowlands and uplands and white Himalayan ridges; of your great and long-disciplined forest army welded together for the service.

Forestry in America.

BY H. J.

There was published in the *Pioneer** a short time back a report of a speech made by the President of the American Republic to the Society of American Foresters at Washington—(Why is there no Imperial Society of British Foresters?)

---

* *Vide* p. 301, July number of this Magazine.—HON. ED.

The speech shows the great interest taken in the United State in forest matters, and the importance attached to the preservation of forests by the administration of the country.

After stating that a conservative forest policy is an essential part of the government of the country, the President defines the object of forest conservation to be the making of prosperous homes. Like Sunlight Soap, it "makes homes happy." He then insists that the success of home-makers depends in the long run upon the wisdom with which the nation takes care of its forests.

Forestry Mr Roosevelt happily defines as "the preservation of forests by wise use," and then proceeds to mention some of the aspects in which the utility of forests is most conspicuous. Forest protection alone, he says, can maintain the supply of water in the streams necessary for irrigation, and can prevent destructive floods and erosion of the ground. Then the relation between the forest and the mining industry is a very close one; mines cannot be developed without timber, usually not without timber close at hand, and in many regions of the West, ore is more abundant than wood.

The forest resources of the United States have been, the President said, already seriously depleted, and they can be renewed and maintained only by the co-operation of foresters and the timber-traders. He ended by counselling the foresters to seek to realize their ideas in practical ways. and said that the forester's profession is one of the greatest importance, of the highest usefulness to the State, and stands as hgih as that of law or medicine.

The forester should acquire not only a thorough knowledge, a knowledge that goes deep, but also a wide outlook over all the questions which have to be touched This profession concerns the State in many ways—politically, socially, industrially, and commercially—and requires a wide acquaintance with the general life of the nation, and a view-point both broad and high.

It is no new thing for us to admire the thoroughness of our trans-atlantic cousins, and their businesslike practical methods, and there seem to be clear indications now that the Americans, after having learnt everything that the Old World has to teach them in the matter of forestry, are coming to lead the way among the nations of the earth in this profession which they esteem so highly.

A most interesting and valuable book, called Economics of Forestry, has been written by Dr. Fernow, Director of New York State College of Forestry, and late Chief of the Division of Forestry, United States Department of Agriculture *

---

* This book was published last December by Thos. Y. Crowell & Co., New York—$1·50.

This most excellent and comprehensive work, without being a manual of forestry, is intended as a reference book to lay and professional students of forestry and political economy.

A brief review of its contents may be of interest:—

Chapter I. Introductory.—Relation of the State to Natural Resources.
" II. The forest as a resource.
" III. The forest as a condition.
" IV Forest, and forestry, defined.
" V. Factors of forest production, and business aspects.
" VI. Natural history of the forest.
" VII. Methods of forest crop production. Sylviculture.
" VIII. Methods of business conduct. Forest Economy.
" IX. Principles and methods of forest policy.
" X. Forest policies of foreign nations.
" XI. Forest conditions of the United States.
" XII. The forestry movement in the United States.

Chapter I explains how the natural resources of the earth, so long as their exploitation is left unrestricted in private hands, have always been squandered by man with a wanton disregard of the future; for private enterprise knows only the immediate future, and has but one aim to obtain from the forests the greatest possible personal and present gain. The necessity for the limitation of private rights finds expression in the old Roman law—*Utere tuo ne alterum noceas*, in which *alterum* may be taken to include the citizen of the future as well as of the present time.

The permanency of the State makes it the guardian not only of present communal interests as against individual interests, but also of future interests as against those of the future.

There is no doubt that the importance of the economy of resources has not hitherto been sufficiently recognized, although it is admitted that man is constantly modifying the earth, and making it more and more uninhabitable: he goes over the rich portions, and leaves behind him a desert.

Increase of population, and increased requirements of civilization, necessitate an increased intensity in the management of our resources; although, as individuals, the knowledge that the coal fields cannot last for many centuries more, does not induce any one to deny himself a single scuttleful of coal, until this knowledge is reflected in increased price. Resources may be classified as—

(1) Inexhaustible, such as land, water, air, and the forces of nature.

(2) Exhaustible, and non-restorable, such as coal, silver and gold mines, and oil-wells.

(3) Restorable, but liable to deterioration under private activity. This class includes the forest, and its game, the water power of its streams, which depend on the condition of the forest; the fisheries, and local climatic conditions. Both in Europe, Asia, and America, vast regions have been transformed into lifeless deserts by the destruction of forest cover.

The 4th class of resources are restorable, but yielding increased returns under increased activity; these resources are mostly the product of human labour, industry and ingenuity, such as wealth, the means of public education, and other conditions of civilization.

Again, resources may be distinguished as either objects of industrial enterprise, yielding the necessaries or conveniences of life, or else as serving, perhaps indirectly, for the comforts of society, industry and progress of civilization, while offering little or no incentive for private action.

Thus the forest, so long as it merely yields timber and useful materials for the arts, is an object of private industry; but when from its position on a watershed the forest becomes an important factor in the water conditions of the plain, it may still be an object of private industry, yielding gain and wealth, but its indirect significance for society at large exceeds the private interest.

The policy of Government control over waterways, roads, and lands falling under the operation of "eminent domain," the right of the State to restrict private owners in the use of their property for the sake of the common weal, is well established everywhere, and should be extended with even more reason to all exhaustible, non-restorable, resources.

The three great resources upon which mankind is most dependent, are the soil as food producer, the water, and the climatic conditions.

The fertility of the soil can generally be said to be restorable, and may therefore be left to private enterprise so long as the soil is utilized, but not otherwise. A rational management of the water capital of the world in connection with the agricultural use of the soil is an economic problem of the very highest importance, as the necessity for increased food production calls for intensive methods, and without forest management no satisfactory water management is possible for any length of time, no stable basis for continued productive agriculture, industries, or commerce.

To the individual, it is the timber, the accumulated growth of centuries, which is of interest in the forest; whereas the function of the forest as a soil cover by preventing erosion of the ground, by regulating the water flow, by its relation to local climatic conditions, pre-eminently renders it an object for the exercise of the providential functions of the State, to counteract the destructive tendencies of private enterprise.

CHAPTER II.—THE FOREST AS A RESOURCE.

No material, outside of food products, is so universally used, and so indispensable in human economy, as wood: and it is estimated that over 99 % of all wood is used to supply real wants, and less than 1 % to supply luxuries, such as fancy articles, carvings, and other decorations.

These figures refer of course to the net wood product after conversion, as the unavoidable wastage, which is in most cases a total loss, amounts to about 50 °/o.

This waste per cent. diminishes as the size of the timber increases, and in the case of a log of 3 ft. diameter, for example, will amount to about one-half of the waste per cent with logs of one foot diameter.

The innumerable uses of wood required in every sphere of human civilization are briefly referred to, and are shown to be constantly increasing, as is exemplified in the modern manufacture of wood pulp for making paper, etc.

It is estimated that in the United States, each family uses on an average about 2,000 c. ft., or about 80,000 pounds, of dry wood per annum, the annual product of at least 50 acres of forest.

The reasons for this universal and varied application of wood are briefly gone into, and the technical and physical qualities of wood as compared with iron and other substances are described. In the combination of strength, stiffness, elasticity, and lightness, wood excels all other known materials, and it is further recommended by its ease in working, and above all things, by its cheapness.

In addition to timber and fuel, and wood pulp (from which both collars and car-wheels are made!), the forest furnishes other materials of no mean value, such as tan bark, turpentine, varnishes, sugar, alcohol and fruit, and other minor produce.

From the standpoint of wealth production, the relative position which the forest resources, and their working, take in the household of a nation, can best be learned from a comparison with other sources of wealth and their production, taking into consideration the different revenues, the capital invested, the value of the product, the number of people employed and the wages paid. In the States, it is estimated that the net money value derived annually from the forests is equal to a two per cent. dividend on the entire wealth of the nation; and this unfortunately is largely paid from capital stock, whose deficiency future generations will have to make good.

An estimate of the potential forest area over the earth's surface, shows that about 60 per cent. of the total land area is capable of forest growth. and that this percentage, or 18 billion acres, has to be divided between agriculture and the forests.

An estimate of the world's requirements of wood material is given, showing that in North America the wood requirement per head is 500 feet board measure. (Board measure means converted timber; 100 c. ft. of timber unconverted being figured as producing 600 feet board measure sawed material.)

In Europe, and in all other countries, the corresponding wood requirements in board measure, are respectively 60 and 4 feet. The average for the world's population of 1,600,000,000 inhabitants is about 38 c. ft. of wood per head, of which between 6 and 7 c. ft. are timber, equivalent to 40 feet board measure.

A table is given, showing the different quantities of timber furnished by different countries. Out of the estimated total of 66,500 million feet board measure, the United States produces 37,000, more than half; Russia comes next with 12,000; then Austria, 3,500; Germany, 3,000; Canada, 3,000; Norway and Sweden, 2,000; China and Japan, 2,000; France, 1,500; South America, 1,000; and India, 500.

In the United States, the use of wood per head is about 350 c. ft., and exceeds that of all other civilized nations; about one quarter of this wood, or 85 c. ft., being timber.

England (Great Britain ?), importing all her requirements, wants only 18 c. ft. of timber, and Germany, who imports 25 % of her requirements, needs 48 c. ft. of wood per head, of which 15 c. ft. is timber.

In the natural uncared-for forest, the production is always much smaller, and the produce of an inferior quality, than in a well-managed forest, and the wastage in conversion is very considerably greater.

The natural forest resource, as we find it, consists of an accumulated wood capital lying idle, and awaiting the hand of a rational manager to do its duty as a producer of a continuous highest revenue.

Rational management will not consist in simply extracting the more valuable portions of the growth, as is done in the crude exploitations of newly developed countries, but rather in preparing first for the desired reproduction by cutting out the useless kinds and the brush, and then felling only those mature trees of the better kinds which will surely be replaced by young growth. Thus, by wisely utilizing the resource, the produce can be harvested and at the same time a new and improved crop is secured.

The extent to which the yield of the forest may be increased by good management can be well judged from the results of German forest administration. The more extensively managed Prussian State forests, with an area of 6¾ million acres, lately produced, as an average for a series of years, 42 cubic feet of timber (over 3 inches diameter) per acre per annum; while the most intensively managed State forests of Saxony (probably also with better soil and climate) produced 90 cubic feet of wood per acre per annum, of which 68 cubic feet was timber.

A financial calculation shows that this States property has not only paid 3% continuously in revenue, but has risen in value 24 per cent. by mere accumulation of material.

Meanwhile private forests in the German Empire seldom produce more than 30 cubic feet of wood per acre per annum, of which about 12 cubic feet is timber.

In considering this revenue of 3 per cent, it must be remembered that the forest areas are mainly confined to non-agricultural lands.

In conclusion, *per aspera ad astra* (which we may take as the American equivalent of *meliore speramus*) is given as the history of the settling of the backwoods of the United States which the pioneer woodsman has accomplished.

CHAPTER III.—THE FOREST AS A CONDITION.

It has been already stated that 60 per cent. of the entire land surface of the earth may be classed as actual or potential woodland, and, except under unfavourable conditions of soil or climate, the forest, by virtue of its perennial life and persistent height growth, will, wherever it is allowed, drive out other forms of vegetation. Fortunately, many soils and situations which are not fit for agriculture will still yield forest crops of useful description, and in reducing the woodland condition to one adapted to the highest civilization, the relegation of the different soils and sites to the different uses to which they are best adapted, as fields, pastures, or forest, is a problem of true natural economy.

While the most economical use of the soil, for material production, necessitates the relegation of forests to the poorer soils, protective considerations necessitate its relegation to certain localities, and so we have *supply* forests, whose function it is to supply wood material, and, secondly, *protective* forests, which, apart from any yield of produce, are necessary to cover the soil and to regulate local temperature and water conditions.

Dr. Fernow then traces, from the time of Homer downwards, the recognition by men of different ages of the utility of woodlands, until the time came when Sully declared that "La France périra faute des bois," and Colbert's forest ordinance of 1669 was made.

The disappearance of the mountain forests of Italy, France and Germany, and the simultaneous loss of both wood and water, continued apace until the beginning of the XIXth century, when public interest was aroused, and systematic attempts were made in France, Bavaria, Switzerland and Austria, to establish by experiments the exact truth with regard to the influence of forests on soil, climate, and on water supply.

These experiments, however, yielded no very satisfactory solution. Rain-gauges are never to be relied upon, especially where the wind blows, and it is almost impossible to find stations within and without the forest which differ absolutely in no other respect than the forest cover.

The problem is too complicated for our present means and methods to be settled mathematically, and we are thrown back on the method of general observations in the field, and the application of reasoning from well-known physical laws.

The immaterial influence of the forest is claimed to extend in at least four or five separate yet closely related directions.

These are:—

1. Upon the climatic conditions within its own limits, and beyond.

2. Upon the distribution and character of the water flow.

3. Upon the mechanical condition and erosion of the soil under its cover.

4. Upon the health conditions.

5. Upon the ethics of a people.

This last influence is one which may be appreciated only by some, and it certainly cannot be argued about.

In either of the other directions in which the influence of forest cover is asserted, the mechanical obstruction which it represents is the principal effective element.

It is the effectiveness with which wind and sun are excluded from the soil, and thereby the air temperature and humidity modified, that determines the degree and the distance to which this modification is felt. Moreover, the influence is always local, and must only be discussed with reference to local conditions.

Briefly stated, the general tendency of a forest cover is to reduce extremes of high and low temperature, especially of the former, so it has generally a cooling effect. The forest also acts as a windbreak and by checking the velocity of dry winds, and rendering them cooler and damper, the rate of evaporation over neighbouring fields is reduced, and this protection will show itself in increased crops.

The influence of forest cover on waterflow depends on the topographical and geological structure of the ground, but rests mainly on the fact that the rain and snow waters penetrate more readily a forest-covered soil than a bare one.

The action is threefold; first, the mechanical obstruction offered by the foliage makes the water reach the soil more slowly, and the foliage and litter on the forest floor protect the ground from being beaten hard, and keep it loose and moist; secondly, the mechanical obstruction which the litter and low growth on the forest floor, offer to rapid surface drainage, lengthens the time during which the percolation takes place; and thirdly, the network of deeply penetrating roots, living and dead, offers additional channels for a change of surface drainage into underground drainage.

With regard to the second of these three actions it is evident that the condition of the forest floor is of more moment than that of the leaf canopy, so that grazing and fire will very considerably modify, or may even largely counteract, this influence.

This distribution of the water, which lengthens the time during which the atmospheric precipitations can be usefully employed, and may lengthen the supply for years, renders the riverflow independent of wet and dry seasons, and equalizes its flow.

The influence of the forest on the stability of the soil is very similar, and here too it is the condition of the forest floor rather than of the tree growth which is the effective element.

When the ground is not too steep a simple grass cover may suffice to protect the soil from being washed away by the water; but the forest alone is capable of obstructing the mechanical effect of the rainfall on the soil, and retarding the rapid surface drainage, which becomes the carrier of the débris

In the United States, it is estimated that the annual amount of erosion amounts to 200 square miles, which shows the importance of a conservative policy for the mountain forests.

In France, any one may see indisputable evidence of the effectiveness of a forest cover, both in arresting the progress of erosion, and also in the fixing of loose shifting sand-hills.

Regarding the sanitary influence of forests, it is probably not true that they increase perceptibly the proportion of oxygen in the air, and their sanitary influence is mainly of a negative character.

The forest air has been found to be free from pathogenic microbes, and the bacilli of cholera, typhus, yellow fever, etc., and in the forest soil the least favourable conditions for development and distribution.

Here again, it is the condition of the forest floor that mainly determines the degree of effectiveness.

In the appendix of this book, fifteen pages are devoted to a useful and interesting resumé of the details of the meteorological conditions established by experiment in Germany in connection with the influence of forests on soil and climate, both within and without the forest.

CHAPTER IV.—FOREST AND FORESTRY DEFINED.

This chapter begins with a discussion of the etymology of the word *forest*, and traces the historical development both of the word and of the thing thus designated.

The term *woodland* is suggested as the best generic term for land naturally covered with woody growth, in contradistinction to land not so covered; and *forest*, as the specific term for woodlands either natural or artificial, considered from an economic point of view as being placed under management for *forest purposes*, and exhibiting *forest conditions*.

These limitations exclude coffee plantations, orchards, roadside plantings and parks, etc.

The first purpose of a forest growth is to supply wood material, or at any rate part of the wood substance, such as tan bark; but in addition, it is now generally recognized that forest growth serves an object in the economy of nature and of man which may be of even more importance than this direct primary one.

The forest, therefore, has a second important use as a protective cover, and a climatic factor, influencing the soil, temperature, and water conditions of the country in its neighbourhood, and according to whether the one or the other purpose is more prominent, we may distinguish *supply forests* and *protection forests*, and finally when mere ornament, or game cover, are the main object, *luxury forests*.

The forest as an economic factor is not a mere collection of trees, but an organic whole, composed of close crops which exclusively occupy the ground, largely preventing by their shade lower vegetation.

Further, with regard to the first function, it is not merely wood, but wood of useful size and quality, which is required.

The trees must therefore be grown in a close crop, so that all their growth-energy may be utilized in the trunk, resulting in long, clean, cylindrical boles.

A dense crop, and the soil completely shaded, are also the conditions most favourable for the second function of the forest as a regulator of waterflow and climate.

Forestry is defined comprehensively as the rational treatment of forests for forest purposes— not such a good definition, we venture to think, as Mr. Roosevelt's).

Forestry represents a policy, a science, an art, and a business,

A policy, because first of all we have to determine our general plan of conduct with regard to our forests, the motives and object of our programme, and to make up our minds *what* to do with them. Such policy is based on our knowledge of forest growth, in every particular, and in all varying circumstances,—the *why* to do. Formulating this knowledge into rules of procedure, and applying them to our treatment of the forests, we begin to practise the art of forestry—we learn *how* to do; and finally, by applying this art systematically for money results, we practise the business of forestry.

Forest crop production is the business of the professional forester.

A forester, then, is not merely one who knows the names of trees and flowers; nor even one who knows their life-history; nor one who proclaims the need of preserving them; nor one who makes a business of planting parks and orchards; nor one who cuts down trees, and converts them into timber; nor one appointed to prevent fires or depredations in forests; nor even one who knows how to produce and reproduce forest crops; but in the fullest sense of the word, a forester is a technically educated man, who, with the knowledge of forest trees, their life-history, and all that pertains to their growth and production, combines further knowledge which enables him to manage a forest property so as to produce certain conditions resulting in the highest attainable revenue from the soil by wood crops.

Before the finer methods of forest management become practicable, the protection of the natural forest from fire and grazing is the first thing to be done, and this is for the present in many countries the only forestry practicable under existing circumstances.

SYSTEM OF FORESTRY KNOWLEDGE.

I.—FOREST POLITICS.

ECONOMIC ASPECTS.

(The Condition.)

Basis.

1. FORESTRY STATISTICS.—Areas: forest conditions, distribution, composition Products: trade, supply and demand, prices, substitutes.
2. FORESTRY ECONOMICS.—Study of relation of forests to climate, soil, water, health, etc. Study of commercial peculiarities and position of forests and forestry in political economy.
3. HISTORY OF FORESTRY.—

Application.

4. FORESTRY POLICY.—Formulating rights and duties of the State, forest legislation, State forest administration, education.

II.—FOREST PRODUCTION. TECHNICAL ASPECTS. (*The Crop.*)	Basis.	5. FOREST BOTANY.—Dendrology, systematic and biologic forest geography, forest weeds.
		6. FACTORS OF SITE.—Soil physics: soil chemistry, meteorology and climatology, with reference to forest growth.
		7. TIMBER PHYSICS.—Physical structure and technical properties of wood. Diseases and defects.
		8. WOOD TECHNOLOGY.—Application of wood in the arts, requirements. Working properties, use of minor and by-products.
	Application.	9. SYLVICULTURE.—Methods of producing the crop and influencing its progress.
		10. FOREST PROTECTION.—Forest entomology, climatic injuries, fires, etc.
		11. FOREST UTILIZATION.—Methods of harvesting, transporting and preparing for the market.
		12. FOREST ENGINEERING.—Road building, water regulation, sand dunes, swamps, moors, denuded slopes.
III.—FOREST ECONOMY. BUSINESS ASPECTS. (*The Revenue.*)	Basis.	13. FOREST SURVEYS.—Area and boundary, topography, forest conditions, units of management and administration.
		14. FOREST MENSURATION.—Methods of ascertaining volumes and rates of growth of trees and crops, and determining yields.
		15. FOREST VALUATION, STATISTICS AND FINANCE.—Ascertaining money value of forest properties, and financial results of different methods of management, and comparing the same.
	Application.	16. FOREST REGULATION.—Preparing working-plans, determining possibility, and organizing for continuous wood and revenue production.
		17. FOREST ADMINISTRATION.—Organization of a forest service, business, practice and routine, including forest law, and commercial law applicable to forest practice.

(*To be continued.*)

The Insect World in an Indian Forest and how to Study it.

(*Concluded from page 276.*)

PART IX.

SUMMARY.

IN the preceding papers on this subject an attempt has been made to briefly describe the various orders of the Insect Kingdom, particular attention being paid to the families of more especial importance in the Indian Forest. If there be any merit in the method in which the subject has been dealt with, it is perhaps to be found in the fact that the writer has confined himself for examples and illustrations of life-histories of the various insects alluded to under the different Orders and families described entirely to the Indian Region. Elementary works on Entomology are numerous, but it will be found that the authors usually lay under contribution the whole insect world for the representatives they require to illustrate the various families, genera and species described. This is as it should be when the student wishes to study the subject from a general standpoint and not with especial reference to one particular region of the world, and as in the present case with especial reference to the special insect inhabitants of certain definite areas within this region. The task the writer set himself to carry out, as was mentioned in the Introduction, was to consider the subject entirely with reference to the requirements of the Forester in India. The insects mentioned will pratically all be found in one or other of the various forest tracts in the country and all the ones at present known to be of importance have been alluded to in short notes upon what is known of their life-histories, and have been incorporated in their proper places under the genera to which they belong. The writer therefore holds the opinion that the papers may be looked upon as to a certain extent briefly summarising what has been published up to date upon the subject of our more important forest pests.* If the articles are read from this point of view, it will be seen how much remains to be done before we can claim to have any real acquantance with what are our forest insect pests, much less to have a practical working knowledge of their life-histories. That a really good start has been made by the Department in this direction the writer will be the first to readily acknowledge. Several officers are now enthusiastically interesting themselves in the study and it may be said that it was the knowledge that such was the case that led to the necessary time being ungrudgingly given to compile the papers.

But whilst the aim has been chiefly to enable workers to place the insects found by them into their families, this being sufficient for ordinary working purposes, some portions of the various Parts have a much more important significance and this we would wish to briefly draw attention to.

No remarks are necessary upon the Introduction or Part I. Under the *Orthoptera* (Part II) some original information is given in the families *Acridiidæ* and *Gryllidæ*. In the former various locusts are treated of and remedies given for combating their attacks—remedies which it is important that every Forest Officer should know, since he will certainly be called upon to take action when the great migratory locust (*Acridium peregrinum*) is out in its millions, devastating the continent from end to end. In the *Gryllidæ* the large cricket *Brachytrupes achatinus* is alluded to as a pest to young plants.

---

* Our knowledge is progressing at such a satisfactory rate however that were the author to rewrite some of the earlier Parts he could include notes upon several other recently discovered important insects.

Amongst the *Neuroptera* (Part III), the only really dangerous pests are the *Termites*, or so-called white-ants, concerning whose actions some remarks are made, with suggestions or protective measures against them.

In Part IV (wrongly called Part III), the *Hymenoptera*, some important original observations are given upon species of the families *Siricidæ* (wood-wasps), *Tenthredinidæ* (saw-flies), Chalcid parasitic flies, Ichneumon parasitic flies (two of which parasitise the teak defoliator, *Hyblæa puera* var. *nigra* Steb. MS., in the Nilumbur Plantations) and Bracon parasitic flies.

In the great order *Coleoptera*, or beetles (Part IV), original observations on life-histories are numerous. They occur under the families *Lucanidæ*, *Carabidæ*, *Staphylinidæ*, *Histeridæ*, *Bostrichidæ*, *Cleridæ*, *Elateridæ*, *Tenebrionidæ*, *Chrysomelidæ*, *Cerambycidæ*, *Curculionidæ*, *Scolytidæ*, *Platypodæ* and *Coccinellidæ*. Of these the habits of some new important predacious *Histeridæ* are described in the papers for the first time. The discovery of a very important predacious clerid insect which feeds upon various bark-borers (an insect closely allied to and which takes the place in our coniferous forests of its German confrére, *Clerus formicarius*, in European continental forests) is alluded to, as is also that of an equally important predacious coccinellid beetle. Amongst pests new bostrichids (*Bostrichidæ*), weevils (*Curculionidæ*), bark-borers (*Scolytidæ*), wood-borers (*Platypodæ*) are discussed. The writer would especially draw attention to the treatment of the family *Scolytidæ*. Up to the end of 1901 but three species of this exceedingly important forest group were known in the Indian Region and practically nothing was known about their life-histories. Notes upon the habits of some 20 (probably) new species have been recorded since that date, of which 14 are alluded to under this family, whilst another four are treated of under *Platypodæ*. In addition some 40 other species have been found, most of which have proved new to science. These still remain to be dealt with, nothing having as yet been published on them. It will be evident that this section alone of the papers is one of the highest importance, since it forms a good basis upon which to build up our knowledge of these minute but dangerous pests.

Amongst the *Lepidoptera—Heterocera* (moths), some original notes are recorded under the families *Sphingidæ* (hawk moths), *Psychidæ* (bagworms) *Lasiocampidæ* (eggers), *Geometridæ* (geometers), *Noctuidæ* (noctuids), and *Pyralidæ*.

The valuable observations made by Mr. T. R. Bell in Bombay, by Mr. R. S. Hole in the Central Provinces, Mr. S. Carr in Burma and others our knowledge of the life-histories of the two well-known teak defoliators *Hyblæa puera* and *Pyrausta machœralis* is becoming rapidly more complete.

The *Diptera* (two-winged flies) require study since it is becoming apparent that this family contains important gall-making pests. The one infesting the branches of old teak and the leading shoots of saplings in Berar, Madras (Coimbatore), and Mysore especially requires serious attention. This order also includes the *Tachinidæ*, an extremely important family of parasitic flies, which are probably of great use to the forester. One of these has been discovered to infest the teak defoliating pest *Hyblæa puera* in the Nilumbur Teak Plantations.

Lastly, we come to the great order *Hemiptera* or *Rhynchota* (Part VIII), which contains some of the most serious insect pests known in the world. Original observations will be found under the families *Pentatomidæ, Coreidæ, Reduviidæ, Aphidæ* and *Coccidæ*. These latter contain pests whose presence in the forest cannot be looked upon in any but the most serious light, even though our knowledge concerning them is at present but small. The black Aphid upon the Blue pine (*P. excelsa*), and the *Chermes* upon the spruce and silver fir, require most careful study, whilst the Monophlebus scale insects amongst the *Coccidæ* have undoubtedly proved their great capabilities of spreading in a most wholesale manner and committing great havoc over the areas they infest. The Dehra Dun white scale of the sal tree appears to be spreading right through the sal areas of North-West India.

In conclusion the author wishes to express his regret that he was unable to illustrate the articles. He had the intention of doing this since he is well aware of the fact that illustrations are of the very first importance in papers of this nature. The monthly appearance of the Magazine unfortunately precluded all possibility of carrying out this idea. Should it be found possible to re-issue the papers in the form of a small hand-book for convenient use and reference,—and he must leave it to the consideration of his brother officers to say whether it would be useful in this form,—illustrations would be certainly incorporated in the pages of the work.

II.—CORRESPONDENCE.

Improvement Fellings in Deodar and Blue Pine Forests.

It would be interesting if officers who have had experience of deodar forests would give their opinions on the point raised in your review of my Annual Report in the *Forester* for May 1902, namely, whether improvement fellings in mixed deodar and blue pine, in favour of the former, are of much use. In Hazara I find that where the two species are of about the same age and form thickets of saplings and poles, the pine, owing to its more rapid growth, tends to kill out the deodar; instances can be seen of pole crops in which the dominant stems are all pine, under these are a number of suppressed and dead deodar of about the same age. No doubt the pine forms an excellet nurse if considerably older than the deodar; thus, under canopied crops of blue pine of 1st and 2nd class trees, whose crowns are at some height above the ground, with a few deodar seed-bearers, there will be found masses of seedlings of deodar to the exclusion of the blue pine, which cannot stand as much shade, but even here, when once the deodar is established, they will be all the better for the removal of the old pine. There seems no reason why the mixed pole thickets, if properly treated at the right time, should not turn into crops of this sort and thus, from containing pine with a small proportion of deodar, would finally consist of pure or nearly pure deodar.

I may note that the area over which improvement fellings were attempted was 755 acres, not 15,000 acres, see para. 38; also that, as noted in para. 59 of the report, there was a surplus of Rs 31,294, not a deficit of Rs.8,325. A considerable part of the revenue of the division, namely, from the sale of the Kagan timber, is collected in the Jhelum Division of the Punjab, and this has to be credited to Hazara in order to obtain the true result of the year's working.

F. V. MONRO,
Deputy Conservator of Forests,
Hazara Division.

ABBOTTABAD:
23rd *May* 1903.

[We trust that those of our readers who are in a position to do so, will fall in with our correspondent's wish and give their opiouions on a subject as important as it is interesting—HON. ED.]

Shrinkage in Timber during flotation.

I notice with surprise a remark made by the Conservator of Forests, Punjab, in his Annual Report of 1901-02, to the effect that in the Bashahr Division, for every 100 c. ft. cut in the forest and exported by river in the log, not more than 72 c. ft. are received in the depôts, giving a loss of 28 per cent., out of which 19 per cent. are attribued to shrinkage; whilst for every 100 c. ft. cut and exported in scantling, only 48·5 c. ft. reach sale depôts, giving a loss of 51·5 per cent.

I am unable to understand how a loss of 19 per cent. can be attributed to shrinkage, as one would naturally suppose that timber which had been lying in water for several months would increase in bulk. Possibly it is due to breakage of the ends of the logs and to general wear and tear.

The percentage of loss in transit, especially in the case of scantlings, is so enormous that one wonders that it pays to use this means of transport.

In the Jaunsar Division, where nearly all the transport is by river, I find that from the year 1890 to 1903, 18,14,874 sleepers and scantlings were launched into the rivers, 17,86,070 reaching the sale depôts, giving a loss of 1·58 per cent. The sleepers and scantlings are not remeasured at sale depôts, but in order to allow for wear and tear sleepers are made ¼ inch broader and ¼ inch deeper than the the usual size.

J. C. TULLOCH,
Deputy Conservator of Forests,
Jaunsar Division.

The Susceptibility of Silver Fir (Abies Webbiana) to damage from Fire.

There appears to be but little doubt that the Silver Fir suffers more than any of the other commoner conifers, in the Himalayas, from fire. From observations extending over several years, it has been found that, where a fire has taken place in a silver fir forest, practically every tree scorched has died, which is not the case amongst deodar, *Pinus excelsa* and *Pinus longifolia*. The Spruce Fir (*Picea morinda*) is perhaps the next species to suffer most, then the three species above-mentioned in the order given. The mere fact that silver fir requires a colder climate may perhaps account for the fact that it appears to be liable to damage from fire to a greater degree than some of its confréres which can stand greater heat. Structural peculiarities may have something to do with the question, but I am not in a position to speak definitely upon this subject.

There is one thing, however, that may account for this susceptibility of the tree to fire, and that is its shape. The branches hang down, the lowest ones often sweeping the ground. Underneath these densely needled branches are numbers of dry twigs which have died from want of light. It is easy to suppose that when the long summer grass is set alight these small dry combustible twigs are the first to catch fire, and the natural shape of the tree being like a chimney, the flue being represented by the trunk, the flames are drawn up by the enormous draught of air which must be formed on all sides of the trunk, literally baking the tree to death. The baking, too, of the ground must also have a great effect on the roots. It should, however, be interesting to hear other foresters' views on the subject, as my own observations seem to show that there is no doubt that other trees do not fall such easy victims to the fire-fiend as the *Abies Webbiana*.

CAMP KOOMBREAL ;
KASHMIR, *June 1st*, 1903.

E. RADCLIFFE,
Forest Department.

Unusual development in leaves of Soymida febrifuga.

Hooker's Indian Flora, Cooke's Bombay Flora declare the leaves of *Soymida febrifuga* to be *entire*. I herewith send samples collected from the Kurnool Nallamalais, which show that they are also sometimes *serrate*. It will be seen that there is a serrature of about ⅛ of an inch at each principal lateral nerve.

A. W. LUSHINGTON.

Major Prain, I. M S., to whom the specimens sent were submitted, says that among the specimens in the Herbarium at the Botanical Gardens, Calcutta "which come from 20 different localities, there are none of *Soymida febrifuga* with leaves so distinctly serrated as the ones enclosed. Only two specimens are other than entire—in one of these the leaflets have undulate, in another very slightly crenated edges. Both are from Central India."—HON ED.

III.—OFFICIAL PAPERS AND INTELLIGENCE.

We regret to report the death of Mr. R. H. B. M. Dobrée, Assistant Conservator of Forests, at Dehra Dun, on the 16th May from cholera. He was taken ill in camp on the 13th and brought into Dehra next day. Mr. Dobrée, who was first of his year and an F. C. H., joined the United Provinces in 1899. He was a young officer of great promise in his profession.

Report on "Spike" disease among Sandal-wood Trees in Mysore and Hunsur Taluks.

From the Proceedings of the Government of H. H. the Maharaja of Mysore.

1. *May 22nd*, 1903.—Inspected the Yelwal Residency compound sandal plantation, covering an area of about 500 acres. The plantation was opened about 13 years ago and three-fourths of the area stocked with sandal and *Cassia florida* (Sime tangadi), the latter as a nurse. The plants were raised by direct sowings, partly in patches under shelter of shrubs and Lantana bushes, and partly in open ploughed-up furrows. The latter have mostly

died out for want of shelter. The cover throughout is very scanty, and those plants which have come up in the open and under the partial shelter of *Acacia leucophlœa* (toppale), *Cassia florida* (Sime tangadi), banyan, casuarina and Lantana are fast dying out, scarcely 10 per cent. being in a healthy condition. Those entirely surrounded by thorny growth have fared better, and on the whole look healthier. At least 95 per cent. of the stock in the open and under partial shelter have either died or are suffering from "spike" At the southern end, under the heavy shelter of mango and other trees, and in low ground, the great majority of the trees are in a healthy condition, but it is scantily stocked.

The locality is outside the natural habitat of sandal. It is higher than the surrounding country and fully exposed. The soil is grayish, consisting of a large proportion of sand and gravel; and the whole area is overgrown with Lantana, which is impenetrable in the southern and western portions. Four diseased trees were marked here in order to study the progress of the disease.

2. At my inspection of this plantation on the 11th May 1901, I recorded the following observations about its condition:—

"In the afternoon inspected the sandal plantation in the Residency compound. Nearly three-fourths of the ground, covering an area of 520 acres, had been stocked with sandal, but during the last two years the deaths have been so heavy that hardly 15 per cent. of the plants are alive at present, due to the same causes as those mentioned already in the case of Hosurmarigudi plantation (*viz*, drought and absence of shelter). The area presents a sad spectacle with its numerous dead and dying saplings. I fear that the whole plantation is doomed, unless there is a change immediately in the climatic condition."

Since then the plantation has changed from bad to worse, and I fear, ere long, sandal will be completely extirpated from the bulk of the area.

3. About 300 yards from the northern limit of the plantation there is a fruit garden in low-lying ground enclosed by a live fence, consisting of Lantana and other species. In this fence and here and there outside it, there are a large number of extremely healthy but pollarded sandal trees, but not a single dead or diseased tree was observed.

4. *May 23rd*, 1903.—Explored the country lying between Yelwal and the village of Dod Margoudanahalli, 8 miles due south of Yelwal. Noticed a number of healthy trees in garden hedges, as well as within and outside gardens. All of them, however, have been heavily pollarded, this pernicious pratice apparently having come into vogue within the last ten years, judging from the length of bole and general condition of trees. No one seems

to have thought it his duty to bring this wilful damage and mischief to the notice of the authorities, and the people themselves do not seem to be conscious of the seriousness of the offence, so free have they been to mutilate this valuable tree without let or hindrance.

5. To the south-east of Bommanahalli, 2½ miles to the south of the Residency compound, there is a date tope of about 150 acres in extent, densely stocked with young sandal, partly natural and partly artificial. The whole area is overgrown with Lantana and thorny growth. At the lower or southern portion of this tract the growth of date is rather sparse and the soil very sandy. Here many dead and a larger number of diseased plants were noticed. Higher up, where the growth of date and other trees is denser and the soil apparently is better, there were very few dead or diseased trees.

6. One large tree over 2 feet in girth, suffering from the "spike" disease in an acute stage, was found about quarter of a mile from the above tract standing in close proximity to two other healthy trees of almost the same size and age. The diseased tree had been cut half way into the trunk and had been otherwise injured.

The diseased tree was marked for observation in order to watch whether it would die or recover, and whether the two healthy trees would get infected by it. It may be noted that all the three trees are situated on low ground in the open, unprotected by any other tree and in close proximity to Lantana bushes. If the disease is infectious, as has been asserted, it must spread to the healthy trees sooner or later. A large dead tree was also noticed within 10 yards of the diseased tree.

7. *May 24th*, 1903.—Explored the country lying between Yelwal and Belagola on the Seringapatam road and Kuraghalli plantation. All along garden hedges, and both inside and outside gardens, sandal occurs in great numbers; and without exception is as healthy as it possibly could be. As a rule, the trees are well sheltered, but sometimes are exposed and isolated. The best bit of natural sandal I have ever seen was met with in a thick date tope which crosses the Seringapatam road at the 87th mile and runs in a narrow strip following the course of a stream north-eastwards.

8. The Kuraghalli plantation, referred to above, is to the right of the Seringapatam road and is only 2½ miles from Yelwal. It has an area of 80 acres and is fully stocked with sandal, which was raised by sowing in open ploughed furrows. The plants are on an average about 5 feet in height. There being hardly any other trees to shelter them, they are fully exposed and consequently are dwarfed and stunted; but no sign of "spike" was noticed. Under shelter near the southern hedge

a few very healthy trees up to two feet in girth were noticed, so also in an adjoining cocoanut garden.

If the "spike" disease is really infectious as has been stated, it is strange that it did not spread to the adjoining gardens and the Kuraghalli plantation.

9. *May 25th*, 1903.—Explored the tract of country lying to the south of the Yelwal-Bilikere road. No sandal occurs from Yelwal to Handanhalli, a distance of 5 miles, but at the latter village there is a patch of natural sandal covering an area of about 600 acres, resembling an artificially stocked plantation. The area forms the head-waters of a small stream, the ground is depressed, forming a sort of dip, and the soil, which is stony, consists of gravel and sand.

Sandal, though not presenting the same healthy appearance as in more favoured regions, does not show any sign of "spike" or any other diseases, though it has been hacked and pollarded for goat-browsing The trees rarely exceed 15 feet in height and two feet in girth Saplings under one foot in girth predominate.

The auxiliary and accessory species with which sandal is found associated are: *Anogeissus latifolia* (dindiga), *Celastrus montana* (dante), *Ixora Parviflora* (gorvi), Lantana, *Acacia catechu* (kagli), *Acacia leucophlœa* (toppale), *Pavetta indica* (pavate), *Diospyros ebenum* (tupra) and several other species, the whole forming a fairly dense scrub The growth of Lantana is nowhere heavy and parts here and there are free from it. All the trees, including sandal, are stunted and deformed, a condition due, undoubtedly, to the poverty and shallowness of the soil.

10. From Handanhalli to Chika Bichanhalli, and from the latter to Dod Bichanahalli and Yelchodi, a large number of healthy, but heavily pollarded and scattered trees, were noticed in the open fields, gardens and date topes. Those in the open seemed less healthy, evidently owing to the clearing of the surrounding vegetation and isolation. As stated elsewhere, the people have been openly lopping off branches of sandal trees for feeding goats, with impunity. That none of these tracts had ever been visited by any Forest official is clear from the fact that the patel of Dod Bichanahalli could not make out that the Forester and two Forest Guards accompanying me, and who were in full uniform, were Forest employees. The shekdars and village officials apparently think that it is not their business to prevent such wanton damage and mischief. The matter will receive my earnest attention and a regular crusade will be waged against goat-herds.

11. *May 26th*, 1903.—Explored about 40 square miles of country to the south of the Bilikere-Hunsur road.

. Scattered and pollarded, but perfectly healthy sandal trees were noticed in the gardens, fields and gomals of Jinhalli and Dallal. In the gomal lands of Chilhalli there is a dense strip of sandal mostly young, but with big trees here and there in a small valley, growing in the midst of dense scrub and Lantana. The soil and composition of the stock are the same as in Handanhalli already described, but the sandal looks healthier and more vigorous, especially in the dense thickets. Healthy and scattered sandal is met with in the fields and gardens throughout, those in the gardens being healthier and more vigorous than those in the open fields. Nearly all the latter appear to have grown up under the shelter of trees and shrubs in hedges. With the extension of cultivation and adoption of improved methods of farming, the hedges and trees have been removed and the sandal now stands isolated and exposed.

12. Immediately to the south of the Hunsur road and in the midst of dense scrub and thorns an extensive area covered with excellent sandal, composed of all ages and sizes, is met with. This area forms part of the proposed Arabitittu reserve. Further south the vegetation is stunted, soil more exposed and the sandal occurs sparingly.

Wherever the vegetation is healthy and dense and the soil fairly rich and deep, sandal is met with in its healthiest state, and where the vegetation is stunted and sparse and the soil hard and shallow, it looks sickly, being clothed with pale-coloured narrow leaves.

13. We came this day across two trees with characteristic spiky leaves, one near a hut with all but one or two roots cut off, and the other an aged one, growing by the side of a sheet rock. Both the trees had been heavily pollarded and looked very aged. They are slowly dying out, and the small diminutive leaves are evidently indications of impaired health and vigour and not of any specific disease.

14. *May 27th*, 1903.—Inspected the Hosurmarigudi plantation and the forest to the north of the Bilikere-Hunsur road. The following notes were made about the condition of the Hosurmarigudi plantation at my inspection on the 9th May 1901:—

"Inspected the Hosurmarigudi sandal and gallnut plantation (500 acres). Judging from the number of dead and dry saplings the plantation appears to have been thickly stocked with sandal at one time, but now hardly 10 per cent. are alive. Those in sheltered valleys and under shelter have not died to the same extent. Mr. Theobald, who accompanied me during the inspection, attributes the heavy casualty to the disease which Mr. McCarthy calls "spike." I think it is more due to the severe drought experienced during the past three years. The subject will be further investigated and a report submitted on the result of the investigation."

The plants were raised partly by dibblings under the shelter of bushes and date trees and partly by sowing in open ploughed-up furrows with *Cassia florida.* The *cassia* has died out, and the sandal that was raised with it is stunted and unpromising. The dibblings under bushes and trees have given better results, and the saplings on the whole are as healthy and vigorous as could be expected, having regard to the poverty of the soil and stunted scrubby vegetation. The whole area of the plantation and surrounding tracts were carefully searched in separate parties by myself and Messrs Benson and Muthiah, but not a single spiked tree was noticed. Nearly all the plants which looked half dead at my inspection of two years ago have recovered. And the plantation has now the appearance of a well-stocked area.

15. Sandal is found scattered throughout from Bilikere to Hunsur, but hardly any dead and no diseased trees were noticed.

16. In the evening I was taken over by Mr. Petrie Hay, who takes a keen interest in the "spike" disease, and shown an acutely infected area, a mile to the west of the Hunsur Travellers' Bungalow on the Coorg road. All the trees that stood on it have died or are dying out, but hardly any diseased trees are noticed between the Travellers' Bungalow and the infected area. To the west and south of the latter, also, there are a few or no diseased trees, while to the north they are found sprinkled here and there. The tract is covered with Lantana.

The diseased and unhealthy condition of the sandal in this tract, apparently, is due to frequent fires in Lantana thickets, in the midst of which it grows, and unsuitability of the sub-soil, which here consists of a substratum of "Kankur." All the other species associated with sandal have also a sickly look and are more stunted than sandal. It is, therefore, no wonder that sandal, the most sensitive of all, has suffered to a greater extent.

17. *May 28th,* 1903.—Explored the tract of country lying between the Hunsur-Bilikere and the Hunsur-Heggaddevankote roads.

There is a scrub jungle consisting of the usual deciduous species and Lantana thinly scattered Sandal is met with here in great abundance, and in places forms 50 per cent. of the stock. The growth is nowhere dense. About half-a-dozen dead trees were noticed, but no diseased ones, except in a small patch on the slope of a low hill where all the trees have died or are dying. The soil in the patch referred to is hard and stony. It is surrounded on all sides by perfectly healthy trees growing on deeper and better soil.

Also noticed two sandal trees in the midst of healthy ones entwined and suppressed by thorny climbers bearing the characteristic spiky leaves, showing that the spiky condition of the leaves is not the characteristic feature of any particular disease, but is only a sign of natural decay owing to old age, enfeebled condition of the root system, strangulation or suppression.

18. In the evening Mr. Petrie Hay again took me and showed a number of trees about 2½ miles to the south of the Hunsur town on the Heggaddevankote road, suffering from the "spike" disease. We saw 3 or 4 trees growing under favourable conditions and in the midst of perfectly healthy ones with markedly spiky leaves. The locality is overgrown with Lantana and is subject to annual fires. I am inclined to attribute the diseased condition of the trees referred to to the effect of fire on the surface roots of sandal.

19. *May 29th*, 1903.—Explored the country lying between the Hunsur-Hanagod and Hunsur-Coorg roads.

Fine healthy sandal trees were noticed up to a mile of the Hunsur Travellers' Bungalow. Afterwards a number of dead and diseased trees were noticed for quarter of a mile along Lantana hedges and in the adjoining scrub jungle, very few being noticed to the south of the Hanagod road. Then, no diseased trees were observed until the 6th mile from Hunsur, where a few diseased and dead trees were noticed in the fields. All the dead and diseased trees were standing exposed and isolated, and from their position it would appear that they grew up in the midst of other growth. Not a single tree growing in the midst of shrubs and trees was found diseased. Again, a large number of dead and diseased trees was met with in the fields of Tattekere village. To the north of this village up to Kallabetta on the Coorg road sandal abounds in the scrub jungle, but no diseased trees were observed. Sandal also abounds in the scrub jungle in the vicinity of the Kallabetta Police Station, but no spiked trees were noticed. The soil throughout this tract, as may be judged from the condition of the vegetation, is poor, stony and shallow, but the forest growth is better than that met with in the diseased tract further east. There is also less Lantana.

Noticed a fairly big tree completely encircled and covered by a thorny climber, bearing spiked leaves.

20. *May 30th*, 1903.—Inspected the Kallabetta State Forest to the right of the Coorg road and the sandal growth from Hunsur to Periyapatam.

In the State Forest, for about 2 miles from the Hunsur Travellers' Bungalow, diseased trees are frequently met with and form about 5 per cent. of the stock, but beyond that no diseased trees were met with. In the State Forest, the forest growth associated with sandal is extremely scrubby and stunted, all the trees having a sickly look with the leading shoots and tips of branches dead. Sandal towers above all, and may be seen from a distance, so there is very little protection for it. This miserable condition of the entire stock, undoubtedly, is due to the poverty of the soil, which is stony and shallow. Where the trees are fully sheltered, sandal is as healthy as could be desired.

21. Sandal is found scattered along the edges of fields and in gardens between Kallabetta Police Station and Periyapatam. Those on fields are generally exposed, and consequently bear pale-coloured leaves; while in the gardens they are invariably healthy, the best and most vigorous trees being found there.

Most of the isolated and exposed trees have had their outer bark and cortex facing south-west scorched, so as to leave the heart-wood along the whole length of the bole bare, a result due to severe exposure to sun and wind.

22. Examined the sandal trees in the Periyapatam Travellers' Bungalow compound and in the gardens close by. At the southern boundary of the compound a number of unhealthy-looking trees were noticed in the Lantana hedge, unsheltered by other trees, but they did not seem to be suffering from any particular disease. Along the northern hedge of the compound there is a row of very vigorous sandal trees in the midst of *Cassia florida* and banyan.

In the hedge of a garden to the west of the compound there was a suspicious looking tree which was marked for observation.

All the exposed and isolated sandal trees have had their bark and cortex along the whole length of the bole facing south-west scorched and peeled off, leaving the heart-wood exposed. Some splendid specimens of sandal trees were found in the hedge of a garden below the Periyapatam tank.

23. *May* 31*st*, 1903.—Explored the country lying to the south of Periyapatam and situated between the Hunsur-Anechowkur and Periyapatam-Anechowkur roads.

Sandal is found in great numbers at the edges of fields and in the scrub jungle outside them. Those in the fields stand exposed and isolated or in the midst of Lantana. Only 4 or 5 dead and a dozen diseased trees were noticed, all of which were either standing in the midst of Lantana or once were growing in that condition. Also noticed a number of trees killed outright by recent fires. I have little doubt that the diseased condition of the trees noticed by me is due to the annually recurring fires which are purposely started by the villagers in the hot weather to destroy the Lantana. In the scrub jungles which are subject to heavy grazing, and where Lantana is not much in evidence, fires do little or no harm; and here no diseased trees are met with.

24. In the Panchwalli plantation covering an area of about 100 acres, which is fairly well stocked, three young saplings were found in the midst of healthy ones with spiky leaves. Similarly,

a few diseased trees were noticed about 2 miles from Periyapatam in the midst of Lantana hedges and thickets.

25. *June 1st*, 1903.—Explored the country lying between the Periyapatam-Virarajendrapet and Periyapatam-Fraserpet roads.

Fine healthy sandal trees were noticed for a distance of 5 miles from Periyapatam in fields and garden hedges and a few scattered trees to the north-east of Muttur village. Then we came across a small patch of diseased and dead trees in the fields of Lalapur village. To the north and east of this patch healthy trees again occur up to the Fraserpet road. From the 127th mile to the 129th mile of this road a large number of dead and diseased trees were noticed in the midst of Lantana, forming about 40 per cent of the stock, except to the south of the 129th mile, where an acutely infected area in the midst of dense Lantana thicket is found. It was also noticed that sandal trees-under the heavy cover of fig trees in the avenues had died off, apparently from heavy cover, dampness and drip. The surviving ones have an extremely unhealthy look, with the top branches dead and scanty leaves, but none of the leaves had the appearance of "spike." Near the 130th mile a splendid specimen of sandal was noticed with spiky leaves and with its whole crown covered by a thorny climber. Close to it there were a number of fine healthy trees.

From the 131st to the 135th mile at the Cauvery, very few sandal trees dead or diseased were noticed on the roadside, except in an Inam jungle, where a number of healthy and diseased saplings were observed. The disappearance of the sandal in this locality might be traced to severe fires in Lantana thickets, it being the usual practice in these parts to get rid of this pest by firing in the hot weather.

26. *June 2nd*, 1903.—Explored the tract of country lying between the Cauvery river and the Fraserpet road up to the northern boundary of the Dodharve State Forest. This tract of country is very familiar to me, having passed and repassed through it scores of times between the years 1878 and 1885 on my way to the Coorg Forests further south. Then it abounded with most vigorous sandal trees; but Lantana had not invaded to such an extent as at present Now the whole tract, except the cultivated fields, is covered with a dense tangled mass of Lantana, which year after year is burnt down to come up again with renewed vigour at the beginning of the following monsoon. The fires have almost exterminated the sandal. I noticed only a few healthy trees on the banks of the Cauvery and in a small patch under heavy shelter between the villages of Girgur and Dodhosur. Trees standing on the edges of fields had a spiky or diseased look about them, which may be due to isolation and exposure or fire.

Further south, where tree growth is fairly dense, sandal is met with sparingly, and only two diseased saplings were noticed; thus showing that where the cover is fairly dense and forest fires are not severe by reason of the comparative absence of the undergrowth, sandal is not subject to any disease to any appreciable extent.

27. *June 3rd*, 1903.—Explored the tract of country lying to the north of the Fraserpet road from the 135th mile to the 130th mile.

On the bank of the Cauvery there are two sandal trees under the shelter of a bamboo clump. In one of them half the branches contain the characteristic "spike" leaves and the other half healthy ones. In the other only twigs, here and there, are affected. Both these trees have been marked for observation. In the same row there are five or six healthy trees, but at some distance from the two unhealthy ones. Further on, towards the north and east to a distance of two miles from the Fraserpet road, not more than half-a-dozen diseased trees were met with. Here sandal, though not plentiful, is met with in fairly large numbers, especially in the hedges. Where the hedges consist of trees and shrubs with or without a mixture of Lantana, the sandal, as a rule, is extremely vigorous and healthy—especially where the soil is rich and deep. We came across several saplings in Lantana killed outright by fire. In the tract inspected not even one tree in a thousand was diseased.

28. *June 4th*, 1903.—Explored the tract of country situated between the Periyapatam-Hunsur and Aneehowkur-Hunsur roads.

Sandal is met with scattered in the fields, exposed and isolated, and consequently in a sickly condition.

The scrub jungle outside the fields is rich in sandal, but the trees are usually stunted with contracted crowns, the latter condition evidently being due to heavy pollarding for goat browsing. The other species composing the stock are also stunted, deformed and unpromising.

Some healthy and vigorous sandal trees were noticed in the midst of bushes towards the Panchwalli road. Two exposed trees with spiky leaves were noticed in close proximity to other healthy trees. These were the only diseased trees noticed during the day.

Under the heavy shade of fig trees in the avenues a number of dead and dying trees were met with, they having died apparently from the same causes as those mentioned under date 1st June.

29. At Hunsur, examined a number of healthy, diseased and dead trees experimented upon by Mr. Benson under my instructions, the details of which are as follows:—

(*a*) One perfectly healthy tree standing in the open was girdled in order to watch the formation of new shoots and leaves and changes in their appearance and size.

(*b*) One perfectly healthy tree standing in the open had all the lateral roots cut out and the excavation filled up with stone and earth.

(*c*) One perfectly healthy tree standing under shelter was similarly treated.

(*d*) Several diseased trees were uprooted in order to see to what distance the roots extend and ascertain the cost of uprooting. The root of one tree was found to extend as far as 55′, crawling just below the surface, and afterwards was lost in the bund of a tank Judging from its thickness, its total length cannot be less than 100′. In another case the root extended to 45′. The tap-root as a rule is not more than 5′ from the surface.

The cost of thoroughly uprooting diseased trees of about 2′ in girth amounts to about 12 annas per tree. If the work is conducted on a large scale it could, probably, be reduced to about four annas. Dead trees would cost much less.

(*e*) Examined also the root system of two healthy seedlings in order to see how the "haustoria" of sandal roots attach themselves to the roots of other trees.

30. *June 5th*, 1903.—At Yelwal I had some diseased saplings cut, in order to see how their wood differed from that of healthy ones. Twelve diseased and one healthy saplings were cut; five of the former had holes bored right through the entire length of the stem, showing that some boring insect was at work, while the latter was in perfect condition.

Specimens of sandal borers recently sent to the Indian Museum at Calcutta from the Devarayadurg Forest of the Tumkur District were identified as the larvæ of the moth *Zeuzera coffea.**

The insect attacking the sandal trees at Yelwal probably belongs to the same species. Whether the insect begins its attack when the tree is in a healthy state or after decay or disease had set in, is a moot point and requires further investigation.†

31. A map illustrating the areas inspected and the distribution and condition of sandal trees is appended to this report. A study of this map will not fail to lead to the conclusion how erratic the course of the "spike" disease is, if it is, at all, a specific disease. A number of photos and a water-coloured sketch,

---

* The specimen sent was in a small top or branch which it had hollowed out.—HON. ED.

† We would refer the Acting Conservator to the note on sandal-wood borers published in the Appendix Series with last month's number of the Magazine.—HON. ED.

showing the condition of spiked leaves and trees, kindly lent by Mr. Benson, are also submitted herewith.

CONCLUSIONS.

32. After a careful study, extending over 15 days, of the diverse conditions under which sandal is found to grow in the tracts inspected, I have arrived at the following conclusions:—

(*a*) That "spike" is not a specific or definite disease.

(*b*) That the narrow, diminutive and bristle-like leaves found in the so-called spiked trees are not peculiar to any specific form of disease, but are commonly found in all trees dying from the following causes:—

(1) Old age.
(2) Injury to the roots by fires or hurt.
(3) Suppression or strangulation by climbers.
(4) Fungoid, parasitic or epiphytic growth.

(*c*) That spiked trees are always met with only in heavy Lantana thickets, which are liable to be annually or periodically burnt.

(*d*) That poor or shallow soil or soil containing a great admixture of 'Kankur' or resting upon a substratum of 'Kankur,' induces premature decay of the root system and consequently of the tree.

(*e*) That areas liable to be submerged and water-logged soils are inimical to the growth of sandal.

(*f*) That sandal-wood sooner or later be exterminated in tracts containing dense growth of Lantana, owing to the liability of the latter to be burnt down by fire; sandal being a sensitive plant and surface feeder is least able to withstand the effects of fire.

(*g*) That "spike" is neither a contagious nor infectious disease, for if it were an infectious and communicable disease it is difficult to explain why it is confined only to particular localities or occurs only in scattered patches and amongst scattered trees in the midst of healthy ones. It cannot be said that the disease has not had enough time to spread to other trees or other areas, because according to all accounts it has been in existence for at least seven or eight years.

(*h*) That trees standing in the midst of thick scrubby growth or under the shelter of light-crowned trees and in the rich soils of gardens enjoy a total immunity from the disease.

(*i*) That sandal has always an unhealthy look where the vegetation associated with is unhealthy; and where the latter is healthy and vigorous, diseased trees are never met with.

MEASURES UNDERTAKEN FOR THE ERADICATION OF DISEASED TREES.

33. Whether the disease is infectious or not, it is beyond doubt that once a tree shows signs of spiked leaves in an advanced stage, it never recovers. It has, therefore, been considered advisable to uproot all such trees. For this purpose I have posted two intelligent and active Rangers, two Foresters and eight Forest Guards to the Hunsur Range with instructions to carry out the following operations:—

(*a*) To carefully explore the sandal tracts in the Mysore and Hunsur Taluks and show their exact positions in the taluk maps, using distinctive symbols to indicate healthy and diseased trees as well as density.

(*b*) To prepare a descriptive account of each tract, stating the conditions of soil and vegetation in which healthy and diseased trees are met with.

(*c*) To uproot all dead and diseased trees in the two taluks and any that may be noticed in the adjoining taluks within 5 or 6 miles of the borders.

(*d*) To burn all the debris and unmarketable portions of the trees on the site, and to hand over to the custody of village officials all marketable wood.

34. As the number of trees to be uprooted is not large and is confined to particular localities, I do not anticipate that the cost of the operation will exceed three thousand rupees, which will be repaid ten times over by the sale-proceeds of the marketable wood which, if not removed promptly, stands in imminent risk of being destroyed by fire. The whole operation, I expect, will be completed in three months. Stringent instructions have been given to the local staff to uproot all the dead and diseased trees within a radius of 5 miles of the Hunsur town within one month.

35. Detailed instructions have been issued to all District Forest Officers to make a close inspection of sandal tracts with a view to discover whether the disease has made its appearance in their districts and to uproot any diseased tree that may be met with.

IV.—REVIEWS.

Progress Report of Forest Administration in the Andamans for 1901-02.

THERE are 156 square miles of Reserved forests and 1,795 square miles of Unclassed forests in the Andamans.

The Indian Forest Act, it is stated, does not apply. We conclude that its provisions are not considered necessary in a colony consisting primarily of convicts.

An initial difficulty for the Forest Officer in the Andamans is the want of proper maps. The only map available is on a very small scale with meagre topographical details. As the islands are an unbroken sheet of forest the survey of these details will not be a quick process. Moreover, judging from the experiences of Mr. C. G. Rogers, the Forest Officer, it will be likely to be a rather dangerous business. Mr. Rogers and Mr. Vaux, Assistant Settlement Officer, had to make reconnaissances into the haunts of the Jarawas, a tribe who, to obtain iron, twice attacked the convict gangs working for the Forest Department. In one of these reconnaissances Mr. Vaux was killed and it fell to Mr. Rogers to bring the party back.

No working-plans exist in the Andamans, but valuation surveys to ascertain the approximate yield of certain areas were made during the year. The valuation appears to show that ·15 ton of padouk over 6 feet girth per acre is available in the forest valued, and this, it is believed, excludes 50 per cent. of the trees as unsound. As it is stated further on that a rich padouk forest is one containing one tree per acre, this is explained.

For reserved forests at least, which are only 156 square miles in extent, one would have thought that a working-plan of a simple kind might be made.

A considerable amount of botanical work was done, chiefly by Mr. Heinig, who held charge at the beginning of the year.

There are no annual plans of operations and the Divisional Officer does not think them necessary, because the amount of work done depends on the amount of convict labour available, a varying factor. The Government of India, however, thinks that at least a forecast should be drawn up. The Divisional Officer is quite plaintive about the lack of convicts. Could not the Courts in India do something to help ?

Vigorous work on steam tramways was done during the year, Rs. 5,028 having been expended : 55 extra men, "including sick," were sanctioned for this, which was doubtless very useful. There appears to have been careless work in the past, necessitating a good deal of work being done over again. We gather that there are considerable difficulties in making this line, but we feel sure that the present energetic Divisional Officer will overcome them all. The maximum gradient is 1 in 120, and 5 miles have been completed so far. There appear to be now 9 miles of tramway and 5 of temporary fuel lines in the Andamans forests. In addition there are elephant dragging paths.

There is, to judge from this report, practically no difficulty in regard to forest offences and fire conservancy.

While Form 34 shows all the forests to be open to grazing, they are not really so. Why should not Form 34 be drawn up correctly ?

It is reported that padouk reproduction is practically *nil*, which is extremely serious, since the *raison d'être* of the Andamans forests is its padouk. Yet practically no artificial means to regenerate the padouk is undertaken. A little planting work with mangrove was undertaken, which seems unnecessary. Also some mahogany was successfully planted. The padouk is, like the teak and the sal, much hampered in its regeneration by bamboos, as well as other things, and it would appear highly advisable to lose no more time in clearing round parent trees and expending considerable energy in cultural operations of this nature, rather than in planting, which seems to present much difficulty. We believe, in fact, that nothing effective will result until the idea is accepted that bamboos should be eradicated round seed-bearers, whether of padouk, teak or sal, in coupes under regeneration where bamboos are very numerous In the present instance, perhaps, it is the deplorable lack of convicts that stands in the way, but something evidently badly requires to be done for padouk regeneration. Probably "wounding the soil" near seed-bearers in good seed years would be advantageous. This measure, which is so often advocated, is, we believe, rarely carried out in India, though it would probably be very successful.

Over 12 lakhs of cubic feet solid of fuel were supplied to the Settlement, which is a falling off due to the importation of coal. It looks as if coal were coming in to stay, yet it is surprising considering that something like 86 cubic feet solid are given for the rupee. It is stated that the lead for fuel carriage has now become long.

Out of 322.517 cubic feet of timber exported over 300.000 cubic feet (16,000 tons) were due to Government Agency. This is an increase of over 52.000 cubic feet of Government Agency timber, which is due to a great increase in the number of padouk felled The Government timber is removed in log by elephants and tramways to the creeks, down which it is floated with the assistance of boats and the steam launch "Eileen" Another launch appears to be required. Eventually the timber reaches the saw-mills, of which the Chatham mill is worked by the Forest Department, at Port Blair. It seems that more elephants, as well as more convicts, are required, though there are already 39 of the former. The purchase of nine more tuskers has been sanctioud.

The charges for removal of produce by Agency amounted to Rs.2,05,446, but some Rs. 60,000 of this is debitable to the elephants, of which 13 new ones were purchased during the year.

The local cost per ton was Rs.13·3. Under "Minor Produce". is *gurjan* oil, of which 52,848 lbs. were collected by tapping. The revenue from this source was Rs. 3,303, and the expenditure Rs.1,873.

The only other minor product of interest is mangrove bark for tanning, and whereas some 730 maunds were exported free of cost by convict labour, the surplus is only Rs. 171.

A good deal of timber, fuel, etc., appears to be given away free, but on what principle is not clear.

Perhaps the most important items in this Report are that the first contract for 1,600 tons of padouk has been completed, and the second contract for a similar amount put in hand. Though the Report is anything but concise, this matter has been dealt with but shortly.

The financial results were, compared to other years as follows:—

			Rs.
Receipts	...	...	2,57,136
Expenditure	...	...	2,11,950
	Surplus	...	45,186

The surplus has fallen by Rs 85,598, which is chiefly due to the purchase of a number of elephants, to much works on tramways, to increased expenditure on timber export, to the fact that padouk sales in London and to the Indian Marine were less, while there was a considerable outstanding due for padouk timber.

The net result of the year's working, however, is shewn to be Rs. 1,59,837, thus:—

Cash surplus Rs 45,186; add, increased value of stock Rs. 1,12,051, increased revenue outstandings Rs 2,600. Last year the net results of the year's working shew a profit of Rs. 12,471, worked on the same lines.

The Report, while containing much that is interesting, is perhaps in places unnecessarily detailed and in others clogged with petty matter which should not find a place in an Administration Report. For example, the detailed description of the death of the elephant doctor, who "against orders" went to sleep on an elephant and fell off, is, though no doubt pathetic, not of great importance in connection with the administration of the forests. But though there is some lack of discrimination in compiling the report, the enthusiasm and energy with which the year's work, and that a full one, was carried through is clearly visible.

Annual Administration Report of the Forest Department of the Madras Presidency for the year 1901-02.

The Madras Forest Administration Report, though reduced to two-thirds of the length of the report of the previous year, is considerably larger and more elaborate than the ordinary provincial report, and consists of 50 pages, followed by 115 pages of appendices.

The total area of Reserved forest is now given as 19,566 square miles, of which only 770 square miles have not yet been brought under settlement.

The preparation of working-plans seems to be in rather a backward state, as there are 13,796 square miles of forest for which no working-plans have yet been taken in hand.

In Madras, as elsewhere, the necessity for a special staff of working-plans officers appears to be felt.

Under the head of Communications and Buildings, an expenditure of Rs. 1,13,838 was incurred, showing an increase of Rs. 32,000 over that of the previous year.

To render this large outlay necessary, the development of roads and cart-tracks in the forests was evidently not sufficiently pressed forward in past years.

The eleven miles of tramway in the Nellore District worked satisfactorily."

During the year under report the enormous number of 23,750 cases of offences against the forest laws came under observation.

Of this number, more than half were compounded, generally for very small sums, though occasionally serious offences were also compounded. One timber theft case is reported as having been compounded for Rs. 3,000.

As a rule, only serious cases were taken into court, and since the prevention of offences is of even more importance than their detection, it would seem as if the wholesale compounding of offences, failed to produce a sufficiently deterrent effect. Fire conservancy was generally successful throughout the Presidency, with the exception of one range (Sandur).

5,550 square miles were attempted to be protected (a little over one quarter of the total area of reserves), and the protection was successful in 96 37 per cent. of this area.

The average cost was Rs. 6-13-10 per square mile.

In addition, about 4,000 square miles of forest are reported to be naturally free from fires.

Under the heading of Sylviculture, nothing of much general interest is given in the report. Natural reproduction appears to be successful in most of the forests.

A good deal of work has been done in all three circles in the way of plantations of various kinds, and topes, both of exotic and indigenous species. Date cultivation has been attempted on a considerable scale, but has not met with much success.

Considering the great extent of forest land in the hands of the Department, the total timber outturn of the forests is small, being only a little over three million cubic feet: this includes all timber, whether extracted by Government, purchasers, free-grantee or right-holders, and is composed of 2½ million cubic feet o miscellaneous species, together with only 3,200 tons of teak, 2,12 tons of sal and smaller amounts of *Terminalia tomentosa*, *Xylia* *Pterocarpus marsupium*, *santalinus*, and other kinds.

In the Southern Circle, the present means of extraction an transport are inadequate, and a greater expenditure on them i required The total outturn of fuel for the whole Presidency fo the year was nearly 15½ million cubic feet.

Nearly 5½ lakhs of rupees were received from grazing fees and other minor produce yielded nearly 6½ lakhs.

The financial results of the year's working show a tota revenue of Rs. 24,96,494, and a total expenditure of Rs. 17,46,121, giving a surplus of about 7½ lakhs.

V.—SHIKAR AND TRAVEL.

England to Burma via Canada, Japan and China.

(*Concluded*)

FROM Vancouver one of the "Empress" steamers of the Canadian Pacific Co. takes us across the Pacific to Yokohama. Too much cannot be said in praise of these steamers Though built in 1891 they are probably still among the most comfortable steamers afloat. They are 6,000 tons and 10,000 horse power and are more like large yachts than passenger steamers. The appointments, cuisine and accommodation are excellent, and I hope the company will one day see their way to extending their service to India. With the rapid railway service across Canada, and the proposed accelerated mail service from England to Canada, the time occupied between India and England, *viâ* Japan, might be so reduced as to render this alternative and delightful route more practicable than it is at present to those to whom time is an object.

The course taken by the steamer in its great circle sailing takes us close to the Aleutian islands, which fringe the Behring sea.

The Pacific ocean however greatly belied its name—rough seas and magnificent wave scenery instead of placid waters. The passage to Yokohama occupied 14 days, the scheduled time; although the Empress boats have performed it in 10 days.

Although Yokohama itself gives one little insight into Japan and its people, it is a convenient centre for several interesting sights in the neighbourhood. So much has been said [illegible] written about the rapidly changing Japan, and the necessity for visiting the country with as little delay as possible if one wishes to see anything of the old life and customs of the country, that I was agreeably surprised to find that to all intents and purposes, as far as I could gather, the people still retained most of the quaint customs, ceremonies, and methods of living so characteristic of the country.

The fact is that whilst railways, telegraphs, electric light, and modern systems of government have affected the large towns to a considerable extent, the people still live evidently in much the same manner that their forbears did and follow the old habits and methods of life, in very much the same way that the national traits, characteristics and method of living have been retained by the Burmans, notwithstanding the many years occupation by the British Of course I do not refer to the great change that spread over Japan when in 1868 the Shogunate was abolished, and the Mikado once more was restored to supreme power. Up to the end of the 12th century the Mikado appears to have been more or less absolute; from that time onwards till 1868 the Mikado had only nominal power, the real power being vested in a succession of powerful military chiefs called Shoguns; under these were the great territorial lords, the Daimyōs, and their retainers, the Samurai. There must have been some wonderful sights to see in Japan in those days, not so very distant, for the feudal times are said to have lasted till 1871. Amongst other quaint customs was that of wearing two swords by the Samurai; the custom was abolished by Imperial edict in 1877.

Although the Japanese women still dress their hair in the quaint old fashion, the men no longer shave part of the head and draw the hair forward down the middle into a sort of roll, as one sees in pictures, but have adopted the European fashion. The costumes of both sexes are what I fancy they have been for generations—the costumes which we are so well acquainted with in pictures and on fans. Those who may have adopted European costume are so much in the minority as to be hardly noticeable.

It is quite feasible in a period of 3 or 4 weeks to see a great deal of Japan, although of course this time does not allow for much wandering off the beaten track. Railways, rickshaws and other conveniences of travel are available to see the following places, which among them can show most that is of interest and representative of Japan: Yokohama, Tokyo, Nikko, Miyanoshita, Kyoto, Osaka, Nara, Kobe. All the details of the various sights to be seen from these centres are fully described in the guide books, and at most of the hotels at these places convenient pocket guides are provided for visitors. Trained guides of the Guides Association will accompany the traveller throughout his tour at fairly moderate charges: under their direction little is missed and much time economised; they are by no means indispensable however. At the British Legation at Tokyo permits to visit the Imperial palaces and gardens at Kyoto should be obtained. I cannot linger here to describe the many wonderful and magnificent sights to be seen in the vicinity of the places mentioned above; the gorgeous and beautiful temples of Nikko are alone sufficient to repay a visit to Japan: the inconceivable wealth of detail that has been lavished upon these buildings is absolutely marvellous, and their setting amongst the dark giant cryptomerias (*Cryptomeria japonica*) adds much to their entrancing effect. At Nikko is, or rather was, the celebrated red lacquer bridge, a drawing of which is reproduced here: it was carried away by the stream during a terrific typhoon which occurred during our visit. Miyanoshita is a great summer resort with mineral springs: near it is a weird sight, the great 'Sulphur Hell'. From Lake Hakoné, in the vicinity, excellent views of the great snow-capped Fujiyama are obtained. Kyoto, the old capital of Japan, is full of most interesting and typical sights. Osaka is the great manufacturing centre; owing to its numberless waterways it is sometimes called the Venice of Japan. Its Theatre street at night is one of the most picturesque and striking sights imaginable. Japan at once conjures up thoughts of geishas and indeed there is no greater pleasure than watching these artless creatures in their effective costumes performing their floral dances—the Cherry Blossom, the

Wistaria dance, etc; between the dances, with dainty grace, they press one with tea and saki, the national drink. The majority of the geishas are very young, 12 to 14 years perhaps, and they display a charming grace and innocence which is irresistible.

The theatres are particularly interesting, as many of the pieces give one an insight into the manners of old Japan, the costumnes and acting being very exact representations of the periods they illustrate. The area that would correspond to the pit and stalls in an English theatre is divided into small squares by partitions about 1 ft. high; each square accommodates about four people: here the spectators sit with their pipes and smoking-boxes and tea things. Galleries surround the theatre on three sides and here are the higher priced seats. At the end of each act the children swarm on to the stage and lift up the curtain and generally amuse themselves unheeded.

The stage, or a large part of it, is made circular and revolves occasionally during a play, changing the scene with marvellous ease.

One piece we saw illustrated an extremely gruesome ancient custom of the Japanese. A minor poet who was with me at the time, composed the following verses which I venture to include here, not so much on account of their poetic merit as because the poet has followed with considerable fidelity the action of the play. I ventured to point out what seemed to me to be anachronisms and said that even the first line appeared capable of more than one interpretation. The youthful poet eyed me with a withering look. "A lot you know about poetry," he said scornfully. I disdained to reply. The acting was painfully realistic, the little boy being particularly pathetic.

THE SAMURAI'S FAREWELL.

The ambient air, with fragrance rare the cherry blossom fills.
The last soft rays of setting sun light up the pine-clad hills.
Belated birds across the lake are wending home their way;
And all around seems peaceful towards the close of day.

But, oh! in the Samurai's home, nor peace nor rest are there,
But sounds of bitter anguish float piteous through the air;
For his feudal lord hath called him. He to the war must go.
Nor may he linger thinking, when calls the Daimyō.

His wife with poignant sorrow rocks slowly to and fro;
His old sire's face is tight and drawn with unrepressed woe;
But sadder still his little son, a blithesome lad was he,
Clingeth with wond'ring terror unto his father's knee.

And now the final parting cup, (they'll meet on earth no more),
Is sadly drunk by all, and dropped unheeded to the floor.
The father gives the child into his grandsire's trembling hands.
Then with streaming eyes one moment he upon the threshold stands.

Thus, with one long despairing look departs the Samurai.
But hardly had he started ere his son's heart-piercing cry
Stays him, and he sees the boy, from his grandsire struggled free,
Who runs and soon doth cling again unto his father's knee.

Oh! who may know the anguish with which he unclasped those little hands,
Had his heart been bound with iron, it had surely burst its bands.
And so the child is handed back, yet *thrice* he struggled free
And tried to draw his father back, a piteous sight to see.

But now the awful deed may no longer be delayed.
With quiv'ring hands the grandsire draws forth the cruel steel blade
And plunges it deep, deeper still, into the lad's young breast,
Till with throat stifled gurgling he sinks to everlasting rest.

The grandsire to the mother turns, but grief had proved its might,
And when she saw her offspring killed her spirit winged its flight.
So he alone is left, with despair he turns the knife
Unto himself, and gruesome hari-kiri ends his life.

Afar off the father watches with grief-blinded eyes.
Oh cruel loyalty that asks so great a sacrifice!
But he who loves his feudal lord no sacrifice must mind,
And he may not fight the good fight who leaves home-ties behind.

With fragrance rare the ambient air the cherry blossom fills,
And dark and gloomy are the dense pine-covered hills.
The low'ring clouds are gathering fast, making darker still the way,
As the Samurai takes his leave towards the close of day.

Japan is a continual wonder and delight to the curio hunter; it would seem as if the nation as a whole were artists, the exquisite delicacy and finish of even the commonest articles is extraordinary. It is said that practically all the really valuable old curios have long since been bought up and have left the country. There is still, however, plenty of ancient and modern work to irresistibly tempt the traveller to buy. Gold lacquer, old and new, Damascene gold and iron, Cloisonnè, Satsuma ware, old sword ornaments, many of these of most exquisite workmanship, bronzes, ivory carvings, old and new silk embroideries, and quaint curios of all kinds too numerous to attempt to detail here.

I was particularly interested in gold lacquer and saw the work in its various stages on several occasions. The name is somewhat of a misnomer in the case of *all* gold lacquer, as there is little lacquer to be seen, nothing but pure gold, which is applied to the prepared surface in minute particles, and also in large pieces to form various designs. The work occupies a very long time even for the smallest articles; it will be readily understood therefore that this, combined with the value of the material, involves very high prices for the finished work.

Old gold lacquer is much sought after; many specimens of the less costly articles, like medicine and smoking-boxes, can be picked up in the old curio shops, some bearing the crests of the Shoguns or Daimyōs, which gives them a greatly added interest.

Railway travelling is quite comfortable; the excellent check system for baggage relieves one of any anxety on that score. In the first class carriages a little table is set out for tea, which is provided free. Excellent beer brewed in the country is obtainable everywhere and is sold at many railway stations.

One of the finest views of Fujiyama is obtained from the train at Gotemba. The general country scenery is very picturesque, the cultivation might almost be called carpet cultivation there is such a mixture of crops in close juxtaposition.

Small terraces of rice, wheat, barley, millett, sweet potatoes, beans, lily bulb, a little of each. The country is well wooded in most parts and a considerable amount of small plantations—pines, cryptomeria, etc.—are seen. Large forests of pines and oaks are said to exist in the island of Yezo.

The most generally utilised timber appears to be that of *Pinus densiflora* and *P. Massoniana*.

The wood of the cryptomeria has a good grain and takes a high polish, but I was much struck with the magnificent timber of the '*Keyaki*' (Planera japonica; the columns of the large new temple, the Higashi Hongwanji, at Kyoto are made of this. The Japanese, who are great admirers of the grains of the various woods, have left these columns plain and polished.

Another wood much used, remarkably white and close grained, is the '*Hinoki*' (Chamæcyparis obtusa); it seems to bear exposure, as the railings of the Yaami Hotel at Kyoto are made of this wood. A beautiful thatch is made of the bark of this tree; the thatch is made about 12 inches in thickness and is seen at its best in the many covered gateways of temples.

But the most remarkable tree of all is the '*Matsu*' (pine), very much like P. sylvestris in appearance; the reddish colour of the bark is still more pronounced, with a flattish umbrella-shaped crown. It takes to itself the quaintest and most bizarre shapes imaginable and is greatly admired by the Japanese for its contorted and grotesque growth; it is frequently dwarfed artificially and used in landscape gardening. The finest specimen I saw was when descending the Rapids of the Katsuragawa.

The dwarfing of trees is a great art with the Japanese and I went over several nurseries: cycads, cryptomerias and conifers were the species most commonly seen.

The Japanese strike one as a most adaptive people and once they have been instructed in any particular work are quite capable of managing and carrying it on without foreign assistance. Thus their railways, telegraphs, electrict lights, etc., appear to be under their own management entirely. One shudders to think of the confusion that would reign if similar works in India and Burma were left to the tender mercies of the natives. At present Japan is greatly hampered by the want of capital, although there would seem to be plenty of scope for capital in mines, minerals and industrial works. There is no doubt that foreign capital at present fights shy of the country: the fact is that the law and its administration are so remarkably lax and doubtful, that naturally no capitalists are willing to risk large sums under such unfavourable conditions. Commercial integrity, also, is not of that high standard which is necessary for successful development of trade. The policy of honesty which China has long since learnt to its advantage is at present a policy which is but dimly understood by the Japanese.

It is with unfeigned regret that we take leave of Japan and its people; the wondrous and entrancing country, the charming people and their quaint ways, are sights that no one who has the opportunity should miss seeing.

From Kobe to Nagasaki, through the picturesque inland sea, and thence on to Shanghai by an Empress steamer. We landed and went through the China town of Shanghai. The stench, the dirt and the filth are too appalling for words and we had no regrets in sailing for Hong-Kong.

Some of the buildings at Hong-Kong are remarkably fine; the Club, too, is a fine building. The view from the 'peak,' 1800 feet, in the day is beautiful; at night it is like fairyland: we look down on what appears to be a limitless expanse of illuminations. The large harbour is crowded with craft of all kinds from men-of-war downwards, and their lights reflected in the dancing waters, with the lights of the town itself, forms the most brilliant panorama imaginable. The Botanical gardens are excellent and well kept.

From Hong-Koug we continued the journey to Singapore, whence we visited Johore and went over the Sultan's palace.

The Botanical gardens at Singapore are also very interesting and well kept, the Malay vermillion sheathed palm (*Cyrtostachys* *lacca*) being a striking object. The yellow-belled *Thevetia nerifolia*, common in Burma, was flourishing here A very striking fan-shaped palm, the Travellers tree (*Ravenala Madagascariensis*) is common over the island.

On the way to Singapore we stopped at Saigon (Cochin China). Saigon is situated on flat ground little above the surface of the river. It is an extraordinary town: a theatre or opera house like the Grand Opera House at Paris on a small scale, radiating boulevards and cafés, elaborate public buildings and a well laid out town; there appeared to be little trade however.

From Singapore we had the pleasure of travelling in a cargo boat of speed 9 knots an hour; this was for some reason put on in place of the ordinary passenger mail boat. We stopped at Penang and had a few hours ashore and then pursued our slow course to Rangoon.

Once more the gilded top of the great Shuré Dagon Pagoda appeared in sight, in fancy I heard the tinkling bells of the many pagodas, as they shook tremulous in the breeze, the gay-coloured throng were no doubt crowding the sacred steps whilst the yellow robed monks were chanting their monotonous prayers. I had been round the world since last I saw this sacred fane, and now I must doff my globe-trotting garb and clothe myself in dignity, for am I not also a priest of a true religion * ?

TAUNG-GYI.

---

* "Every Forest Officer is the priest of a true religion."—"India revisited' Edwin Arnold, C S.I , 1886.

VI.—EXTRACTS, NOTES, AND QUERIES.

Prize Day at the Imperial Forest School, Dehra Dun.

On the last day of March, the annual prize-giving took place. The beautiful gardens of the Forest School always look their best at this time of the year, and offer a delightful place for social gatherings of any kind. All the principal residents of Dehra, both Military and Civil, European and Native, were present as usual on this occasion, and testified to the kindly interest they all take in the affairs of the school, at the same time enjoying a visit to the school gardens bright with flowers, and its buildings and museums, which are both interesting and attractive. Sir Edward Law, Financial Member of His Excellency's Council, was present at the prize-giving. A large tent was erected on one of the lawns in the garden, and the prizes were given from a small platform at one end.

The Board of Control was constituted this year by the following officers of the Forest Department in addition to Mr. Eardley-Wilmot, the Inspector-General :—Mr. F. B. Dickenson, from Oudh ; Mr. Lace, from Bengal; Mr. Hobart-Hampden, from the Central Provinces, who now succeeds Mr. Oliver as Director of the School ; and Mr. Lewis, Director of Public Instruction, United Provinces

The Director of the School, Mr J. W. Oliver, in his opening speech, spoke as follows : —

" It is a great pleasure to me to be able to report that the result of the final examination has, on the whole, been very satisfactory. The classes of 1901-1902 opened with 37 students in the Upper class and 8 in the Lower ; there were some alterations during the course, and the numbers who presented themselves for examination were 35 and 7, respectively. Of these four, Rama Iyengar, Venkata Rama Iyer, Kaushi Ram and Mr. A. M. C. Littlewood have gained the Higher Standard certificate with honours ; 27 have gained the Higher Standard pass certificate ; two, Sidiqui and Sidhu Ram, the Lower Standard certificate with honours, and 5 the Lower Standard pass certificate,—in all 6 honours and 31 passes out of a total of 42 As regards honours this is, I think, the best result on record. I trust the junior classes will follow the good example set them.

"At the Entrance examination held in October last, 43 candidates out of 96 qualified for admission, compared with 51 out of 81 in the previous year. I should here perhaps mention that the Bombay Government has decided to train its Rangers at Dehra Dun, instead of at Poona, so that in future we may expect an increase in the number of students in the Upper classes, and I hope also a greater degree of competition.

"There have been some changes in the teaching staff during the year. Mr. Hooper undertook the Physical Science lectures in place of Dr Leather, absent on leave; Mr. Duthie, who has been connected with the school from the very beginning, has, I regret to say, retired from the service, but he was nevertheless good enough to undertake the oral examination in Botany. Mr. Stebbing's term of deputation as Forest Entomologist came to an end in January last, when he left us to take up the acting Superintendentship of the Indian Museum, but I hope the post may shortly be restored to the school in order that the useful work initiated by him may be further carried on. By the unexpected death of Pandit Raghu Nath Pathak, the Vernacular class has been deprived of an efficient lecturer and the Provincial service of one of its oldest officers.

"The standand of athletics at the school has been fairly well maintained, and it is only due to the fewer number of European students now attending the course, that there has been a decrease in the enlistments in the Dehra Dun Mounted Rifles, to which at one time the school furnished a 'Forest troop.'

"There is, I think, nothing else for me to note, except to say that with the exception of one bad case of enteric, and two severe cases of malarious fever, all contracted elsewere than at Dehra, the health of the students has throughout the year been very good"

Mr. S. Eardley-Wilmot, Inspector-General of Forests to the Government of India, then spoke as follows:—

"Ladies and Gentlemen,— I have only a few remarks to make before we proceed to the distribution of prizes. I wish to most heartily congratulate the Director, the School Staff, as well as the students, on the very successful results of the examinations that have just been held. We have four honours' men in the Upper class and two in the Lower; whilst out of 42 candidates all but four have obtained certificates. Moreover, of these four, three came from Siam, and I am assured that want of knowledge of English and not want of intelligence and industry has been the cause of their failure. We do not claim to turn out experienced forest officers from the Dehra Forest School, but we do boast that those who obtain certificates have been well equipped for the profession they have chosen Their future must depend on the manner in which they use their equipment. I hope that the past students of 1903 will in remembering this speedily rise in the service.

"I have no desire to introduce any element of sadness into these proceedings, but I think that a passing tribute is due to the memories of two forest officers who were with us here last year In Mr Hill most of us have lost a personal friend, and Mr Fordyce, though not so well known in these Provinces, was a favourite with all who met him. It is gratifying to their friends and to the Department to know that their professional attainments and value to the State have been fully recognised by the Government under whom they served.

"Other changes are impending. Mr. Oliver, who has for the last six years so ably filled the post of Director, is now going on furlough, and this seems to be an excellent opportunity for wishing him a prosperous voyage and a happy time at home. He may be sure of a welcome if he returns, but if he has other plans he may feel certain that he leaves behind him, both in Burma and India, a host of friends as well as many memories of kindly actions unostentatiously performed.

"And now, ladies and gentlemen, thanking you for the interest you always take in these proceedings, we will go on to the distribution of prizes which is the main object of our meeting."

The prizes were then distributed by Mrs. Eardley-Wilmot. The following is the list: —

Higher Standard certificate with honours: B. V. Rama Ivengar (Mysore; K R. Venkatarama Iyer (Madras); Kaushi Ram (Punjab); A. M. C. Littlewood (Madras).

Lower Standard certificate with honours: Rahmatullah Siddiqui, Sidhu Ram.

Prizes —Best student of the year in the Upper Class: B. V. Rama Iyengar.

Best student of the year in the Lower Class: Rahmatullah Siddiqui

Prothero-Thomas Prize for the best student of the year in Practical Forestry: A. M. C. Littlewood.

Best Note-book in Forestry and Forest Engineering: A. M. C. Littlewood.

Best Note-book in Lower Class: Rahmatullah Siddiqui.

Best Student in Botany: B. V. Rama Iyengar.

Campbell-Walker Prize for the best student from Madras: Venkatarama Iyer.

Best Entomological Collection : Bejoy Chandra Sen Gupta.

Best Athlete of the year : Sitaram Puri.

The following prizes were also awarded from the Brandis Prize Fund for original articles published in the *Indian Forester* :—

Mr. Pranjpe, Extra-Assistant Conservator of Forests, for an article on the Tussar Silkworm.

Rai Sahib Upendranath Kanjilal, F. L. S., Extra-Assistant Conservator of Forests, for an article on the Jubal Forests.

LIST OF MEDALS AWARDED

Upper Class—For Forestry : K. R Venkata Rama Iyer

For Surveying and Drawing : Mr. A. M. C. Littlewood and Nai Tawng Kham (Siamese student).

For Forest Engineering : B. V. Rama Iyengar and Kaushi Ram.

Proxime accessit : A. M C Littlewood.

For Botany : B. V Rama Iyengar.

Lower Class —For Forestry : Sidhu Ram.

(From *The Pioneer*.)

The Forests of India and their Management.

A MOST instructive paper on the Management of the Forests of India was read by Mr. Gamble, F R S , C.I E., before a meeting of the Royal Colonial Institute, in January last. After touching upon the area and distribution of the forest tracts of the country, the lecturer pointed out that the great importance of, in his opinion the most important function of, the forests was their action in the preservation of the water-supply of the country. The forests preserved the catchment areas of the great rivers from erosive action and consequent drying up, and by receiving the amount of water caught in these areas, and consequently the amount contained in the great rivers, enabled the Engineer to obtain a permanent supply of water for his great Canals. Mr. Gamble then considered the question of timber export from the country, pointing out that the Burma teak trade was the only one of importance as far as export went. Other small exports were blackwood from Malabar and padonk from the Andamans, and smaller quantities of satin-wood, ebony, red sanders wood for dyeing, sandalwood, rattans and choice bamboo are occasionally sent out of the country. The teak sold yearly comes to between 200,000 and 300,000 tons, valued at about 1½ million pounds sterling, showing what a valuable property Government possesses in the forests of Burma.

The lecturer, proceeding, noted that attempts had been made to introduce to the trade a number of other fine woods, but 'that difficulty lay partly in the trouble that has to be taken to draw the attention of dealers to new woods, and partly owing to the maintenance of the supply being not easy to keep up in the case of species which are not gregarious. Mr. Gamble stated that improvement of communications should help this difficulty to disappear. He perhaps might have added that the establishment of some central scientific bureau where such questions could be threshed out by men specially qualified to deal with them for the country as a whole, would help to solve the difficulty still further. The lecturer then proceeded to show that the forests of India produced three categories of timber:—(1) export timber, chiefly teak; (2) timber for public and other large works and railway supply; and (3) small wood for the general supply of the great mass of the population: the working of the forests depended upon which of the above three formed the chief produce required from them. After describing the various classes of forest existing in the country, the lecturer alluded to the system of management, touched upon the constitution of the staff of the Department, and described how the various forest reserves were formed. The preparation of working-plans was glanced at and the various systems in force were reviewed. The training of the forest staff was described and in winding up the lecture Mr. Gamble gives the following points upon which he thinks more can be done, viz., (1) the afforestation of waste lands in the waste country; (2) the cultivation of India rubber, gutta percha, gamboge, etc.; (3) the endeavour to bring to the notice of the export trade some of the more valuable timber and furniture woods now too much neglected; and (4) the necessity of improving the forest staff as a scientific body capable of undertaking the position of advisers to Government in matters of forest-natural history and in all matters relating to trees and planting.

VII.—TIMBER AND PRODUCE TRADE.

Churchill and Sim's Wood Circular.

London, 4th June 1903.

East Indian Teak.—The deliveries for May correspond closely with those for May 1902, at 1,113 and 1,118 loads respectively. For the first five months of this year they are 4,787 loads, and for the same period of last year they were 5,573 loads. There is no change at all to report in prices and the market remains not only short of stock but still without any near prospect of any normal supply.

Rosewood—East India.—For large, prime logs there is a very fair demand, but inferior wood is not much [illegible]; there is, however, but little stock on hand.

SATINWOOD—EAST INDIA.—There is a considerable stock on hand and sales are slow as the demand continues very quiet.

EBONY—EAST INDIA.—Sizeable, sound wood is in fair demand.

PRICE CURRENT.

Indian teak, logs, per load ...	... £10 5s. to £18 10s.
,, ,, planks ,,	... £13 5s. to £20.
Rosewood, per ton ...	... £8 to £11.
Satinwood, per s.ft. ...	... 6*d*. to 18*d*.
Ebony, per ton ...	... £8 to £12.

Denny, Mott and Dickson, Limited.

WOOD MARKET REPORT.

London, 3*rd June* 1903.

TEAK.—The landings in the docks in London during May consisted of 626 loads of logs and 566 loads of planks and scantlings, or a total of 1,192 loads, as against 1,260 loads for the corresponding month of last year. The deliveries into consumption were 566 loads of logs and 459 loads of planks and scantlings—together 1,025 loads, as against 1,097 loads in May 1902.

The dock stocks at date analyse as follows :—

5,122	loads of logs,	as against	7 547	loads at the same date		last year
3,008	,, planks,	,,	3,550	,,	,,	,,
—	,, blocks,	,,	—	,,	,,	,,
Total 8,130	loads	,,	11,097	loads ,,	,,	,,

The above figures sufficiently show that even the present high level of prices for teak does not stimulate the Indian shippers to increase their supplies to Europe. It must, however, be borne in mind that, whilst the supply of teak logs of European quality cannot be supplemented at the shipping ports until the new season's outget from the forests commences to arrive in the late autumn, the present abnormally high rate for planks and scantlings should serve to stimulate their production from inferior ones.

Business during May has been of a normal character. The high f. o. b cost of most of our wood imports, although eased down by a continuance of exceptionally cheap freight rates, has continued to discourage large buying by importers here; and the consumer also continues to content himself with only just covering his actual need, so that, whilst a steady trade has really gone on, there is a sense of contraction and difficulty—with no need, however, for anyone to sell without a fair turnover profit, as stocks are not sufficiently heavy to cause financial difficulty. The inevitable outcome is the appreciable putting down of the f. o. b cost; but how long shippers can wait before recognising this remains to be proved, as so long as they can afford to submit to restricted sales, and abstain from consignments, will their hands remain unforced.

Market Rates for Products.

Tropical Agriculturist, 1st June 1903.

Cardamoms ...	... per lb.	1s. 6d. to 1s. 9d.
Croton seeds ...	... ,, cwt.	15s to 25s.
Cutch ...	... ,, ,,	25s. to 30s.
Gum Arabic ...	... ,, ,,	15s. to 20s.
Do. Kino ...	... ,, ,,	75s. to 120s.
India-rubber, Assam	... per lb.	2s. to 3s. 2d.
Do. Burma	... ,, ,,	2s. to 3s. 2d.
Myrabolams, Madras	... ,, cwt.	5s. to 6s.
Do. Bombay	... ,, ,,	4s. to 7s. 6d.
Do. Jubbulpore	... ,, ,,	4s to 5s 6d.
Do. Bengal	... ,, ,,	3s. 6d. to 5s.
Nux Vomica ...	... ,, ,,	7s. to 10s.
Oil. Lemon-grass ...	... ,, ,,	5d. to 5¼d.
Orchella weed, Ceylon	... ,, cwt.	10s. to 12s 6d.
Sandalwood, logs ...	... ,, ton	£15 to £30.
Do. chips ...	... ,, ,,	£4 to £8.
Sapanwood ...	... ,, ,,	...
Seedlac ...	... ,, ,,	115s. to 120s.
Tamarinds, Calcutta	... ,, cwt.	8s. to 10s.
Do. Madras ...	... ,, ,,	4s. 6d. to 6s.

PLATE SHOWING ROOT PARASITISM OF A YOUNG SANDAL SEEDLING ON THE ROOT OF STROBILANTHES CUSPIDATUS


Root of Strobilanthes cuspidatus
Sandal Seedling
Cushion formed on Strobilanthes by the haustoria of Sandal Seedling
A

Reference

A Sandal Seedling with its roots attached to root of Strobilanthes cuspidatus
B and C Sandal Seedlings without attachment to roots of any other plant but, showing small root fibres and root hairs

Del. E. Ebenezar Pillai. Lith. by A. C. Chowdhary.

THE
INDIAN FORESTER.

Vol. XXIX.] September, 1903. [No. 9.

Cooper's Hill as a Training College for the Imperial Forest Service.

A GOOD deal has of late appeared in the papers and elsewhere on the subject of the continuance of Cooper's Hill—that College on the Hill situated in one of England's fairest counties and overlooking one of the loveliest of the vales of Father Thames. All that has appeared on the subject, however, has been strictly in connection with the Engineering side of the College. Since this is by far the larger portion of the Institution, which came into being in order to provide specially trained Engineers for the Indian Service, this is perhaps only what was to be expected. At present, therefore, it would appear that the future maintenance of Cooper's Hill, whether it is to stand or drop, as in the case of Haileybury and other famous institutions of old, into the limbo of the past depends upon whether the officers of the Public Works are to be specially trained for that great Department at a Government college or whether they shall in future be recruited in the open market With the arguments for and against this side of the question we shall not here concern ourselves. It is our intention to examine the advantages of the College as a training ground for the Officers of the Imperial Forest Service and to compare the training obtained under the present régime with that available at one of the great Universities.

Since 1885, a period of 18 years, all the Officers of the superior branch of the Forest Service have been recruited from Cooper's Hill, *i.e.*, they have won their provisional appointments in public competition and have then been sent to Cooper's Hill to be specially trained in the work of their future profession. Until 1890 the period spent at the College was five sessions, followed by a four months' tour in the forests of Germany, two years in all The students who passed the public examination in 1890 spent eight sessions at the College, from September 1900 to March 1903, followed by a four months' tour in Germany, a total of three years. It having been decided that the German tour did not produce all the results desired it was abandoned the following year. Under the new régime the students remained in residence at the College during seven sessions only, proceeding to Germany in the January of their third year and spending six months working in pairs under specially selected German Forest Officers, their work being under the general supervision of that eminent forester, Sir Dietrich Brandis. This programme was again changed some years later, and the students now spend nine months in Germany, proceeding there at the beginning of the seventh session (October) and remaining until the middle of the following July. Of this period eight months are spent in pairs working under the supervision of a local German Forest Officer, whilst the ninth is devoted to touring, under the able guidance of Dr. Schlich, through specially selected areas in the Black Forest and elsewhere. Previous to 1891 the students used to visit at the end of their first year some selected Scotch forests. On the death of the owner this plan was altered, and the students of the 1890 year visited, at the end of their first year, some French forests in Normandy. This practice has been continued to the present day. In addition, various small forests of interest in England are visited from time to time during the sessions at the College.

The course of lectures at the College comprises Forestry, Botany, Entomology, Geology, Chemistry, Law, Forest Engineering, Drawing, Surveying, Accounts and German. Forestry in all its branches is taught by Dr. Schlich and Mr. Fisher, whilst carefully selected Professors teach the other subjects.

Owing to the wide range and nature of the subjects studied, the Forest students who obtain the College diploma have, we consider, received a scientific training which enables them to rank with any University graduate who takes a scientific degree, whilst the former are in addition equipped with information of a special kind which qualifies them to fill posts in a special Service. Whether the special training required to turn out the young Forest Officer could be equally satisfactorily given at one of the great Universities is open to considerable doubt. We propose to marshall a few reasons in support of this opinion, and also to point out some of the advantages of the present system of training as enjoyed at Cooper's Hill.

It has been suggested at various times that it would be better to send the Forest students to either Oxford or Cambridge, a special Chair of Forestry being created at one of these great Universities. At first sight this proposal appears both alluring and advantageous, but when subjected to careful scrutiny, there can, we think, be shown to be considerable drawbacks to its initiation. A large number—perhaps the greater number—of University graduates go up, not with the idea of qualifying themselves for a special profession, but with the sole idea of obtaining their degree. This is all that the College Lecturers aim at. The after-professions of these students do not usually interest them in any greater degree than they do the greater number of the Heads of Public Schools. The one idea of these latter is that their boys should obtain a scholarship at one of the Universities and go up there. This reflects credit on the School, and the subject of the real after-life's work of the boy is left out of consideration. The honour of the particular School or of the College or 'Varsity is the chief thought, perhaps naturally so, of both Head Master and College Professor. But this sort of teaching is hardly suitable for men who wish to follow a special course of study to qualify themselves for their life's profession, and more especially when that profession is one so little understood in England as that of a Forester, and is to be followed in a foreign land where conditions are so totally at variance with those amongst which they have been brought up Two instances of a similar nature may be mentioned. Neither the military nor the medical man goes to either of the great Southern Universities. Both have to render themselves efficient in a special profession and it has been long recognised that this cannot be accomplished at either Oxford or Cambridge. The training of the Forester is not one whit less technical than that of either of the above mentioned professions. The Government of India naturally expect and require that the men sent out should have been as fully and carefully prepared as can be done at Home. The Cooper's Hill course on its present lines would seem to afford such training in its highest and most efficient form.

In considering its advantages we may first briefly allude to a most important part of the training of all youngsters designed for a "Service," and that is the training in discipline. The College life affords opportunities of implanting early a sense of discipline in the future officer, whilst at the same time generating an *esprit de corps* which, whilst making for good in the Service itself, is, we think, a by no means negligable asset from a Government point of view in a body of its servants. The first point is one of the greatest importance. Whether the Service be a Military or Civil one, it is essential for its efficiency that discipline should be maintained within its ranks. To be effective it is necessary that this discipline should be inculcated at as early an age as possible. It is well known that the discipline maintained at or learnt at one of the Southern Universities is far from being all it might be. The under-graduate lives out in chambers, has practically no supervision exercised over him, and works or not pretty much as he pleases. The same with the *esprit de corps*. Men scattered through a number of distinct Colleges, or only meeting in lecture-rooms, are not bound together afterwards by that tie which unites men who have lived together under the same roof through three of what are perhaps the most impressionable and most receptive years of their lives. Both the discipline and the *esprit de corps* of the old Haileybury men are well remembered in India, and we think that much the same feeling exists amongst the men who come from the College on the Hill. Further, it by no means follows that by a sojourn at a 'Varsity any special social advantages are necessarily enjoyed. Having considered the efficiency of the students as affected by discipline and *esprit de corps*, we now come to a consideration of the efficiency of the training obtained at the Institution in question as compared with that obtainable at Oxford or Cambridge.

From the outset the important subjects of Forestry and Botany are dealt with in a full and broad manner, whilst the lectures in the former are rendered all the more valuable by the fact that they are delivered by Anglo-Indian professional Foresters, who after a distinguished career passed in actual charge and administration of the forests of India, have devoted themselves to the training of those who are to work in the field they themselves have spent so many years in. The accompanying subjects of Law, Geology, Chemistry, Forest Engineering, Entomology, etc., are all grouped round the above two, and are taught in a manner which at once shows their connection with the chief subjects—a point to which it is essential the Forest student's attention should be drawn. Drawing, Surveying, Accounts and German are other subjects included in the curriculum, and in two at least of these the Forest student requires not only a sound but also a special training. It would not be sufficient for him to learn elementary principles only, as imparted by the Lecturer in a University with a view perhaps to the student taking up subsequent research in this one particular branch. The Forest Officer does not require to attend a large number of lectures on elementary principles, followed by others dealing with the more abstruse portions of any particular subject. He requires these elementary principles, but he requires them to be given to him in the light of their bearing upon his future professional work. He does not require, *e.g.*, Botany lectures with a view to his becoming a specialist in that subject. Sufficient for him will it be if he is able to place his trees and plants into their families and genera. The Botanist is ready to do the rest for him should he come across new, or to him unknown, species. For this reason he requires a good, sound and to some extent a more or less special course in this subject. As it is with Botany so with Entomology, Geology and kindred subjects. The Forest specialist is necessary in these various subjects, but we are not here considering the question of the training or knowledge required by that officer, but of that of the men who will be actually engaged in looking after and working the forests. The question for consideration is, therefore, the pertinent one—Would students following the ordinary course of lectures at one of the Universities have as good a training, and therefore prove as good officers, as those who had followed what practically amounts to a special course in each branch of the various subjects taken up? This question is a most important one, for the well-being of the Service is closely bound up with the training received by the superior staff recruited from Home. The answer we think can only be given in the negative.

Having briefly considered how the theoretical part of the Forest student's training can be more advantageously given at such an Institution as Cooper's Hill, we now come to a consideration of an equally important part of the work, the practical course. It has been often advocated that such can only be really efficiently obtained in a Continental forest, and the acceptance of this principle has resulted in the practical German course at present gone through by the students and which has been declared sound by the experts—all former Inspector-Generals of Forests in India—who drew it up. A considerable amount of the more elementary practical work is however gone through at Cooper's Hill. Briefly, the practical work whilst at the College consists, as we have already seen, of short visits to various experimental areas of forests in England, paid at different periods during the College course, with a short tour to some forests in Normandy in France at the end of the first year, in addition to the work done at the College and in the neighbourhood. If Cooper's Hill and its neighbouring woods had been specially designed by Nature for the instruction of budding Foresters in the principles of elementary sylviculture they could have scarcely been bettered. Nurseries, young plantations, high forest (with many examples of how it should not be managed) and a profusion of exotic trees enable the Forest Professors to illustrate their lectures, or set the students to practical work, at the very doors of the College itself, and the students have thus the advantage of having these illustrations ever before their eyes. Areas further afield in the country serve to illustrate various other points brought out in the lectures. The training at Cooper's Hill used to include the management by the Forest professorial staff and students of the neighbouring Cæsar's camp forest. This formed a most valuable aid to the College curriculum as, in addition to obtaining in it much practical information about their work, the students used to prepare by themselves a working-plan for this area. Owing to the heavy rent demanded by the Commissioners of Woods and Forests for this forest it was given up, and an excellent training ground was thus lost to the students. This being the practical part of the course as obtainable at Cooper's Hill, we would ask—How could such be given at a University? It is the compactness of the present Institution and the close intimacy existing between teachers and taught which enable the students to so readily and easily absorb the mysteries of sowing and planting and the more elementary principles of sylviculture—all of which can be explained again and again, with numerous illustrations in the very grounds of the College itself or in the adjoining Windsor Park and Forest. Can, we would ask, either of the Universities show even a tithe of the peculiar advantages which Cooper's Hill affords for the instruction of the young Forester? Having followed this initial elementary course the students are then in a position to take the fullest possible advantage of the Continental practical work We are unable to see that such a training could be improved upon, or even carried on at all, upon its present lines at one of the Universities.

If there is a tiny rift within the lute at present, it is to be found, not in the training of the students after they have obtained their provisional appointments, but in the methods by which these are obtained. There are two points connected with the present manner of obtaining recruits for the Service which we think would bear revision. Until a few years ago nomination was necessary before permission was granted to appear at the competitive examination. This nomination was of value, since it permitted selection and thus enabled permission to appear to be refused to men who were obviously unfitted for a forest life. We should be glad to see this system of nomination returned to, since it has appeared that it was obviously a sound one. The second point is to be found in the examination subjects. In the old days the examination itself was of a nature to test a competitor's fitness for his life's work. Not only had he to take up subjects closely connected with his after profession, but the securing of an appointment could only be attained by obtaining certain minima of marks in these subjects Now the competitor can pass in on Classics and Higher Mathematics, only to find that he has no aptitude and no liking for the subjects of his profession. Such a one can neither be made nor make himself into a Forester.

We have endeavoured to show above that the training as at present given to Forest students at Cooper's Hill is eminently a satisfactory one,[*] and granting this, it follows that the question of the abolition of the College affects the Service in India very closely It may therefore not be out of place to briefly call attention to a point which is worthy of serious consideration. Would it be feasible, in the event of the Engineers required for the P. W. D. in India being no longer recruited from Cooper's Hill, to use the College as entirely a Forestry one, to form, in fact, an Imperial Forestry College for the Empire at large, a College in which young would-be Foresters could be trained alike for service at Home (under the new afforestation schemes we have read so much about recently in the Home papers), in India and the numerous Colonies? Indian Forest Officers, either retired or still borne on the Departmental lists, are now serving in several of the great Native States in India itself, in Ceylon, at the Cape, in Nigeria, Egypt, Trinidad, Straits Settlements, Siam, Federated Malay States and elsewhere about the world. Could not an Imperial Forestry College in the old country train the men required to manage these vast and valuable forest estates? Surely our great Colonial Secretary would be ready to stretch out a helping hand towards the maintenance of such an Institution, and Cooper's Hill and the Imperial Forestry College would not then be a burden to be borne by the Indian Government alone. The British Empire took up the Forestry question years before the Americans paid any attention to their forests, except to the details connected with cutting them down, and yet this latter nation bids fair to leave us far behind in this important branch of administration. For a search through the countries, cities and towns of our vast Empire will, we think, reveal but one Institution devoted solely to the teaching of Forestry and the training of Foresters, and that one the Imperial Forest School located at Dehra Dun, maintained by the Government of India and under the management and teaching of officers of the Imperial Forest Service. This School, as is well known, provides for the requirements of the Provincial Service in India and to a certain extent for those of some of the Colonies who are taking up the Forestry question. We would ask—Could not the Imperial Forest School of India be supplemented by the Imperial Forestry College of England, and would not the formation of such a College be worthy of, and in consonance with, the true needs of the Empire?

---

[*] It does not fall within the scope of this article to consider the great advantages which a further course of training on arrival in this country would confer upon the newly-joined young Forest Officers. An additional few months' course, with visits to selected typical forest areas in different parts of the country, would do much to prevent men from falling into the error of thinking that their own division and particular class of forest are the only ones they need think about or care to know anything about (a habit which one is perhaps only too apt to acquire), 'besides giving them a general knowledge of the various classes of forest and different conditions pertainable in different parts of the country.

The Kheri Trans-Sarda Forests (United Provinces).

BY F. A. LEETE, F.C.H.

THE May number of the *Forester* contains some "Notes" by "H. J." on his tour through the Kheri Division with the Forest School students in January last.

A little over two years ago I was in charge of the division, and the new working-plan for the Trans-Sarda forests was drawn up by me. I should like therefore to make a few remarks about the "Notes."

TRANS-SARDA FORESTS.

(a)—CONFIGURATION.

In the description of the sal forests given in the working-plan, an attempt is made to show that configuration plays an important part even in an apparently level country. Two types of forest, "High Level" and "Low Level," are recognised.

Although in one sense it is true, as "H J." remarks, that there is very little difference between the two types, yet, as the difference is a real one and not likely to disappear for some generations, if ever, it is worthy of some notice. Moreover, the distinction holds good in the other *sal* forests in Oudh. Based as it is on the configuration of the ground, and corresponding as it does to a difference of some 20 feet or more in the depth of spring water level, there is every reason to suppose that it is of universal application to alluvial formations.

For over three months I wandered about in the Kheri *sal* forests without being able to make head or tail of them. The country was apparently as flat as a table, the soil appeared to be everywhere more or less sandy, and yet the stock showed endless variations between the widest possible extremes.

One day, whilst attempting to work out how far a certain bit of poorly stocked forest extended, I found myself keeping closely to a gentle slope or bank some 20 feet high. The ground seemed to be flat both above and below, and there appeared to be no return slope in sight. The stock, too, seemed to be different in places. Curiosity led me to follow up the slope. I did so that day and the next, still without coming to the end of it. My map and compass had by that time made me realize that I was keeping constantly parallel to the direction of the drainage of the country, and at last it dawned upon me that I was simply following up a natural terrace with the ground on the one side everywhere a little higher than on the other side.

I had started a register of the depth of water in the numerous wells scattered about in the forests when I began field work, but at first it did not appear to be of much use, as the variations were as bewildering as those of the stock above ground. I now, however, set to work to locate the wells with reference to this internal slope. By the time I had done so it was hardly a surprise to find that all the deep wells were on one side of the bank and all the shallow ones on the other side, and that there was no general depth of water anywhere between 20 and 30 feet of the surface.

Better proofs than ocular estimates were necessary, however, to convince the Conservator and the Divisional Officer that the slopes and the differences in levels actually existed. I accordingly amused myself in my spare time with running levels along roads and with making cross-sections. The sections with which this article is illustrated may be taken as typical of the whole, and may be left to speak for themselves.



(*b*)—STOCK.

Configuration is all very well, but unless it can be shown that there is any connection between it and the state of the tree-growth, its sylvicultural value cannot be very great. With respect to this there are no dissentients. Reference is made to the superiority of certain localities in Mr. Keshavanand's working-plan of 1892. Much farther back than this it was recognized, as a perusal of past correspondence will show. These localities have turned out to be what I have called high level ground.

On the high ground there are practically no blanks; * on the low ground they are only too painfully conspicuous, the whole forest being honeycombed with them. On the high ground, protection has been speedily followed by the appearance of seedlings, rapidly overtopping the scanty growth of grass, and shooting ahead into dense thickets of saplings, wherever they have found an opening in the overhead cover. On the low ground, progress has been much slower. For years after the starting of protection from fires and cattle, in many places it was impossible to find a seedling at all. As late as 1892 ploughing up of the soil and artificial sowing were suggested as a possible necessity, if the backward localities were ever to be improved. Another ten years of protection has shown that this need not be done, but even now there are large areas where the seedlings are in their initial struggle for existence.

A good idea of the state of the forests with respect to the younger classes may be obtained by supposing that they were once very openly stocked, and that, at different intervals, small patches of *sal* reproduction have appeared or are appearing in irregular distribution all over the forests. In some places this occurred so long ago and the patches were so close together that there is now a completely stocked forest in which poles and saplings predominate, as on the high ground. In other places the date of appearance is so recent and the distance apart is so great, that there is nothing more to be seen than a number of isolated patches of advance growth scattered about in a poor and open forest. Between these two extremes there is an infinite gradation which it is impossible to definitely represent on a stock map or in a description of compartments.

Seeing that a study of configuration and water levels has been of so much assistance to a solution of the complex problem in Kheri, it may well be enquired whether these two factors do not play an equally important part in other *sal* forests. So far as I have been able to ascertain, the answer is everywhere in the affirmative. In all the divisions in Oudh terraces are to be found, marking off the limits of types of growth far more sharply than the insignificance of the slopes themselves would lead one to expect.

---

* Blanks cover 70 acres on the high ground and 7,337 acres on the low ground (exclusive, in the latter case, of the large grass plains of artificial origin).

The nearer one approaches to the hills, the more the problem becomes complicated. Nevertheless, the finest growth of *sal* is on flat alluvial plateaux or terraces, and undoubtedly the development of the forest following on protection has been far more rapid on these terraces than elsewhere in the hills. This is remarkably true in Garhwal. The *sal*, however, must be very accommodating as regards spring water level. There is nothing to choose, either way, between the vigour of growth of the *sal* on the high ground in Kheri and that on these boulder deposits in Garhwal, and yet in the one case spring water is from 40 to 50 feet below the surface, whilst in the other case it is anything from 100 to 150 feet below ground.

The *sain* (Terminalia tomentosa) is far and away inferior to the *sal* in Kheri, both in distribution and commercial value. Still, it is worthy of notice. "H. J." hardly puts the case strongly enough by stating that the present state of reproduction is poor. There is no recent reproduction at all in the areas under fire-protection. Inside the closed forests I only found one seedling during the whole time I was in Kheri; during the past twelve months I have found the same story to be true in Garhwal. There is a short article on the subject from my pen in the *Forester* for June 1900. In the north-west corner of the Kanjaria Range the reserved forests are separated from Nepal by a 66-feet fire line. On one side of the line there are old *sain* but no seedlings; on the other side there are both.

(c)—Exploitable size for sal.

"H. J." thinks it rather premature to raise the standard for *sal* from 6′0″ to 6′9″ in the absence of reliable data as to the size to which, under existing conditions, the *sal* will grow without becoming unsound.

If we were to wait for a sufficient number of reliable figures, the question comes in whether the standard would ever be raised at all. I doubt it. Our predecessors made the bulk of their revenue in the timber fellings in the *sal* forests from the big trees of, say, 8 feet girth and upwards. So do we now, to a considerable extent. But in the course of the next 20 or 30 years, with a 6-feet standard, this old stock will have been worked out in all accessible localities, and the next generation of Divisional Officers will have nothing bigger than 7′-6″ to sell. Raising the standard means temporary loss of revenue. Our successors will hardly be prepared to say that we have played fairly if we cut all the big trees and leave them to pay.

The proper procedure undoubtedly is to begin to store up our surplus old stock, *as soon as there are any indications at all that* *our standard is too small*. These indications need not be definite, they need not be conclusive. They should be acted upon at once, otherwise the opportunity may pass, never to recur.

Who can say how long a time will be required to exhaust the subject of conclusive data? It is now 23 years since the first sample plots for girth-measurements were started in Kheri, and yet we have very little to go upon with regard to this one detail of the many factors to be taken into account in the determination of the proper size of exploitability.

What special recommendation has the 6-feet standard for the *sal* that we should accept it as final for our time? None whatever. It was a pure guess by our early predecessors. On the other hand, have we any *indications* that this standard is too low in the better class of our *sal* timber forests? I cannot answer this question better than by enumerating the reasons which led me to suggest the raising of the standard in Kheri:—

(*i*) Sample plots show that, *of the trees we have had to measure*, the healthier ones have hardly passed their *maximum* rate of growth in girth at 6 feet.

(*ii*) The conical appearance of the crowns of many closely grown and healthy trees of 6 and 7 feet shows that they have not yet reached their *maximum* height-growth.

(*iii*) The trees in class III and upwards, *that we have so far had the opportunity of observing*, had to run the gauntlet of fires and want of protection generally during the earlier stages of their development. It is only reasonable to suppose that trees which have never been touched by fire or tapped for resin may grow faster and keep sound longer than their less fortunate predecessors.

(*iv*) The larger the girth, the less the proportion of waste in conversion.

(*v*) The trees of the future will be much better than those of the present in respect to the length of bole straight and sound enough for use as timber. This extra length will only be used to its full extent if the trees are allowed to stand until the girth at the upper end of the utilizable part of the bole is large enough. As the length of the timber-producing part of the tree increases, so must also the girth at the butt-end.

(*vi*) In the working-plans for the Kumaun, Garhwal and Ganges Divisions, it is recognised that a 6-feet standard is too small for *sal* in the better localities.

(*vii*) It is doubtful whether the demand for revenue will ever permit of a general raising of the standard throughout the United Provinces. This being so, there is all the more reason for pushing the change in one division at least, now that a favourable opportunity occurs.

(*viii*) Kheri has an excellent system of roads and a railway runs through the middle of the forests, so that the division is one of the most favourably situated ones for the export of large timber. In the hills, many a fine tree has to be cut up into small scantlings because of the difficulty of export; in Kheri carts can be run to the foot of any tree, so that the trade in logs ought to be fostered at the expense of that in sawn timber.

(*d*)—SYLVICULTURAL NOTES.

In the *Forester* for August 1899 there are some notes of mine on the subject of the root-system of the *sal* The opinion is therein expressed that no hard-and-fast line can be drawn between seedling and coppice growth. Theoretically, it may be more correct to say that the reproduction in the Kheri forests is from coppice shoots, but, for practical purposes, it is better to treat of it as reproduction from seed. It is the nearest approach to growth from seedlings that there is ever likely to be in nature. Until the root-system has been developed, growth above ground is out of the question for the *sal*.* This may as well be admitted and, at the same time, as the *sal* is such an important tree, we have cause to be thankful that the seedling is so accommodating that it will exist for a considerable number of years in dense shade patiently waiting until the opening out of the overhead cover gives it the chance to shoot ahead. In fact, it is chiefly owing to this characteristic that the holes caused by fellings so quickly fill up, and that the *sal* not only grows gregariously but that it does not give much chance to other competing species.

"H. J.'s" concluding remark, that any working-plan which ignores this habit of the *sal* of continually dying back is thereby likely to be upset, is hardly correct. Under any system of working depending on natural reproduction, the initial stages of the struggle for existence on the part of the seedlings which will form the crop of the future in any coupe, will have been passed when the fellings begin. The splendid young stuff that shows up within a year or two after a hole in the overhead cover has been made, by the removal of a big tree or two, does not as a rule originate from seed that dropped after the felling; more often than not it is from seedlings which began life some years earlier.

For example, Compartments 20 and 26, on the high level ground near Dudua, were heavily felled over in 1890-91: 3½ I class *sal* trees per acre were taken out of the former, and 2½ per acre out of the latter. The stumps of these trees are now hidden away in dense thickets of saplings, many of which are as much as 9" to 12" in girth. Obviously very few of these could have been more than small plants a foot or two high when the fellings took place, and so one's first idea would be to say that the saplings are now only 13 years old; but it would probably be much more correct to add "H. J.'s" 20 years and put it at 33 years All the same, 13 years would be much the more important figure for a working-plan.

---

* *Vide* the series of articles by Mr. Eardley-Wilmot, printed in the Appendix to the *Forester* for 1899.

Although the foregoing example is taken from a bit of extra good forest, the argument also applies to poor localities, provided that the fellings are based on sylvicultural rules suitable to the *sal*. On the low level ground there are many backward places where the stock consists merely of an open crop of old *sal* trees standing in heavy grass. Such trees should on no account be removed until a few seedlings at least are visible in the grass round about. By the time that a few have raised themselves above the grass, the chances are that there will be plenty more *in* the grass. The rate of growth after the removal of the big trees may not be as fast as in Compartments 20 and 26, but it should not be necessary for the Working-Plan Officer to make an allowance of more than 4 or 5 years over and above the interval since the felling.

The first sign of improvement in a bad *sal* forest is generally the appearance of miscellaneous undergrowth, chiefly composed of 'rohni' (*Mallotus philippinensis*). The cutting back of this shrub-growth should be regulated by a rule similar to that applying to the felling of mature *sal* trees. If the shrubs are so thick that all grass is killed off, the chances are that they will also prevent the appearance of *sal* seedlings; but, here and there, openings in such bush cover are sure to be found, and it may be taken as a standing rule that the time to cut back the undergrowth will not be until young *sal* have begun to appear in such openings.

In the Trans-Sarda Working-Plan it is assumed that the V class period is 35 years. All that this means is, that we are tolerably certain that, within 35 years of the felling of any mature tree that ought to be felled, the place of that tree will be taken by saplings and poles, of which a sufficiency will be fully 18" in girth. Nothing is said about the age of such saplings and poles. As "H. J." remarks, this has still to be even approximately determined.

In calculations of the "possibility," the V and IV class periods may be left out of account at present for all practical purposes. We know neither the normal class proportions nor the average percentages that pass from class to class. The lower we go down the scale the more we have to resort to mere guess-work.

Root-Parasitism of the Sandal Tree.

DURING my visit to the Salem Javadis (hills) in January last, I observed a sandal seedling, about half an inch in diameter, growing on a slope close to a clump of *Webera asiatica*. On digging along one of its roots, I came on one of the rootlets attached to a root of the Webera. At the point of attachment a white tubercle about $\frac{1}{8}$ inch in diameter had been formed on the host and the sandal rootlet penetrated the tissue of the host through the tubercle. I secured the specimen but it was subsequently lost.

I visited the hills again in the latter part of February last with the special object of inspecting the sandal tracts on the plateau. During my inspection, I noticed some young sandal seedlings under a parent tree which was growing on a slope about a yard away from a flat rock. The young seedlings were growing on a thin layer of loose soil, mixed with humus, on the rock and at its foot. I dug up two of the seedlings which were growing isolated and found no traces of root-parasitism. They were about six months old, with a good number of root-fibres and root-hairs. They are drawn to full size and marked B and C on the accompanying Plate No. I. About a yard away from these plants I found similar seedlings surrounded by a growth of Strobilanthes. I dug up these seedlings carefully and found their roots attached to a network of the roots of the Strobilanthes, which I afterwards ascertained with the aid of Hooker's *Flora* to be *Strobilanthes cuspidatus*. Plate No. I-A is a full-sized * drawing of one of these seedlings and illustrates the root-parasitism of the sandal even at the early age of six months.

Plate No. II shows another sandal seedling a trifle older. The attachment of its rootlets to the roots of the Strobilanthes is quite distinct at the points a a a. The leaves of the Strobilanthes are shown in the drawing smaller than their natural size, the sketch being taken from a dried specimen.

On the edge of the rock I found a much larger seedling, probably about three years old. This I also dug up, and at a point on the lower portion of its tap-root it was found attached to a thicker root of the Strobilanthes. While digging the tap-root snapped off, so its full length could not be secured.

Plate No. III is a drawing of this seedling and shows the attachment of the tap-root to the root of the Strobilanthes.

In all the above instances the tubercles, or cushions as Mr. Barber calls them, formed at the points of attachment, were of a

---

* In order to reproduce the plates for insertion in the magazine they have been reduced. The originals, which are coloured, are being sent Home to Sir Dietrich Brandis.—HON. ED.

PLATE SHOWING ATTACHMNT OF THE ROOTS OF A SANDAL SEEDLING TO THE ROOTS OF STROBILANTHES CUSPIDATUS (?)



Reference
A A Sandal Seedling
B B Strobilanthes cuspidatus
a a a Points of attachment of Sandal haustoria to the roots of Strobilanthes

Del E Ebenezar Pillai
Lith. by S C [illegible]

PLATE SHOWING ATTACHMENT OF SANDAL ROOTLET TO A ROOT OF STROBILANTHES CUSPIDATUS


Point of attachment of Sandal haustoria to the root of Strobilanthes
Host Root of Strobilanthes cuspidatus (?)

Del E Ebenezar Pillai

Lith. by A C Chowdhury

PLATE SHOWING ROOT PARASITISM OF SANDAL ON A ROOT OF ALBIZZIA ODORATISSIMA


A
B
b
a
Point of attachment of Sandal rootlet to the host
Scar left by a detached cushion formed by Sandal haustoria
Root of Albizzia odoratissima
Cushion formed by Sandal root and attachment of same to the host
Cushion formed by Sandal root and attachment of same to the host
a
B

Reference

a a a Scars of fallen off cushions formed by Sandal haustoria
b b b Points of attachment of Sandal rootlets to the host (Albizzia odoratissima)
A A Root of Sandal
B B Root of Albizzia odoratissima

Del. E Ebenezar Pillai Lith. by A C Chowdhary

dull white colour and more or less round or spherical in shape. They varied in size from about one-tenth to one-eighth inch in diameter.

In the course of digging up the above seedlings, I came upon a sandal root exposed on the surface of the ground about 20 feet from the parent tree, and noticed a tuft of suckers on the exposed portion. This root trailed down the slope and it was therefore easy to examine it I dug along this root to see whether it had attached itself to those of other species. It was about three-fourths of an inch in diameter at the exposed portion. As the digging proceeded I noticed small rootlets branching off. and following up one of them I found that. at a distance of 25 feet from the parent tree, it branched off into still smaller ones of which the ends were attached to the roots of an *Albizzia odoratissima*. At the points of attachment the cushions formed were large, ellipsoidal in shape and of a dark-red colour. They were more or less hard, woody and brittle when dry. Plate No. IV shows a drawing of one of the specimens I secured. In this plate, A A is the sandal root, B B the root of the Albizzia; a a are scars of fallen off cushions and b b b are points at which the sandal roots were attached to the host when the specimen was dug up. Plate No. V represents a couple of roots of *Albizzia odoratissima* which are covered with the scars of cushions formed by the sandal haustoria. The scars are of different shapes, varying from a circular to an elliptical figure The central part of the scars is depressed, with an elevated outline right round: sometimes the scars present the appearance of magnified stomata with a central slit, the depressions taking the place of guard-cells. These roots were obtained while extracting the specimen drawn in Plate No. IV and formed the roots of the plant therein figured.

I had some stems of the Strobilanthes dug up by the roots about 15 feet away from the sandal tree and found these roots were full of tubercles Suspecting that these latter might be naturally formed on the roots independently of the action of the sandal haustoria, I proceeded up the slope and pulled up some more Strobilanthes stems without finding a single tubercle on their roots. There being no sandal tree within 200 yards of these bushes, I concluded that this species did not naturally form tubercles on its roots, and that the presence of such tubercles on its roots lower down the slope was due entirely to the parasitic action of the sandal or other (?) roots.

While on this subject, I might attempt an answer to the two important questions suggested by Sir Dietrich Brandis in his note on the "Treatment of the Sandal Trees" in the January number of the *Indian Forester*. The first question suggested is—"Has the tree effective root-hairs, and is it capable of taking up directly from the soil a portion of the food it requires?" My answer to this question must be a partial one and confined to seedlings, as my observations so far are limited to the root-system of seedlings. In seedlings there is a fair development of root-hairs and root-fibres, which in some instances are numerous and dense. I have found minute particles of the soil sticking to these root-hairs and it required some amount of force to separate them. But in the case of seedlings which have already formed root-union with other species, root-fibres and root-hairs are comparatively scanty. As regards the presence of root-hairs and root-fibres in grown-up sandal trees, my observations were hitherto confined to the roots of trees growing amidst other species, with the roots of which the sandal roots had formed connections. In such sandal rootlets and root-ends I found no root-hairs but only a few root-fibres or thin thread-like rootlets. As this is an interesting study, I shall devote special attention to this point as opportunities offer, and the results will be communicated to the *Indian Forester*.

The second question suggested is—"Which species are the most useful companions of the sandal wood?" The sandal is associated with the following species on the Javadi plateau:—

(1) Albizzia odoratissima.* (2) Albizzia amara. (3) Litsæa zeylanica. (4) Litsæa tomentosa.* (5) Terminalia paniculata.* (6) Terminalia Chebula. (7) Terminalia belerica. (8) Terminalia ovalifolia.* (9) Anogeissus latifolia.* (10) Premna tomentosa. (11) Zizyphus Œnoplia.* (12) Zizyphus xylopyra. (13) Scutia indica* (14) Randia dumetorum. (15) Randia uliginosa. (15) Webera asiatica.* (17) Acacia coesia.* (18) Acacia pennata.* (19) Pterolobium indicum. (20) Pongamia glabra.* (21) Memecylon edule.* (22) Strobilanthes cuspidatus.* (23) Olea dioica.* (24) Flacourtia sepiaria* (25) 2 shrubs of the Anonaceæ, probably species of—(26) Polyalthia, known among the hillmen as *Pulicha** *Sedi* and *Kakanan** *Sedi*. (27) A tree, probably of the Myrtaceæ,* called *Porumbulu* by the hillmen. (28) Grewia asiatica (?). (29) Atalantia monophylla.* (30) Limonia acidissima. (31) Murraya exotica.* (32) Prosopis spicigera. (33) Acacia Sundra. (34) Bambusa arundinacea.* (35) Dendrocalamus strictus.* (36) Toddalia aculeata.* (37) Mallotus philippinensis.* (38) Morinda citrifolia. (39 Albizzia Lebbek. (40) Cassia auriculata.

Of the above species those marked with an * are found more frequently associated with the sandal than the others, and it is in the company of some of them that the finest and largest sandal trees are found on the Salem Javadis, notably at Kambugudi, Tagarakuppam, Chembarai, Puliyur, Nellivasal and Nellipaltu villages. My own observations have established beyond doubt the root connection of the sandal tree with the roots of Nos. 1, 16 and 22. Further observation will doubtless reveal the exact relationship of the other species with the sandal, with reference to the latter's growth and development.

PLATE SHOWING ROOTS OF ALBIZZIA ODORATISSIMA SHOWING SCARS OF FALLEN OFF CUSHIONS FORMED BY SANDAL HAUSTORIA



A and B Roots of Albizzia odoratissima
a a a Scars of cushion formed by the
haustoria of Sandal roots

Del. E Ebenezar Pillai
Lith. by S C Mondal

PLATE ILLUSTRATING ROOT ATTACHMENT OF SANDAL TO THE ROOT OF LIMONIA ACIDISSIMA



Reference
A A Root of Limonia acidissima
B B Sandal root
a a a Points of attachment of
Sandal rootlets to the host
b b Scars showing past attachment

Del. E Ebenezar Pillai

Lith by S C Mondul

I have found self-sown sandal seedlings growing in aloe hedges at Timpatur with *Morinda citrifolia* and *Melia indica* (nim). In the hedges of gardens at Salem it is found growing along with *Inga dulcis*, *Morinda citrifolia*, *Feronia elephantum*, *Alangium Lamarckii*, *Cocos nucifera*, *Mangifera indica*, *Psidium guava*, and *Moringa pterigosperma*.

The above answers to the questions raised by Sir D. Brandis are by no means full and satisfactory. I hope to furnish at some future date more information on these points after further observation and study.

Since writing the above note I have had opportunities of investigating this subject further.

While camping at Pennagaram on the 17th May last, I noticed some sandal trees growing in a forest tope, and selected for examination a sapling about 2½ inches in diameter growing in the fence of the tope, and at a distance of about two yards from it was a large *Albizzia Lebbek* and a tamarind tree. I dug along a root of the sandal and found it crossing a number of small tamarind roots, none of which were affected by the roots of the former. Further on I came on a small root of the Albizzia and found it covered with depressions exactly like those found on the roots of *Albizzia odoratissima* figured in Plate V, and I have no doubt that these depressions were the scars of the fallen off tubercles or cushions formed by the sandal "haustoria." The affected root of the Albizzia showed signs of exhaustion and approaching death. In this investigation I found no actual attachment of the sandal roots to the roots of the Albizzia or tamarind. The sandal sapling itself was stunted and unhealthy with a meagre crown and many dead twigs. Its root-ends were not vigorous and some were dead or dying.

On the 24th May I walked up the Shevaroys from the hill-foot along the old ghat road in the company of the Acting District Forest Officers of North Arcot and Chingleput. Where the road entered the sandal zone I carefully observed the cut side of the hill slope in hopes of finding some sandal roots, and came upon an exposed root of a white-brown colour, with a small dark-coloured root attached to it and bearing a small leafy shoot which, on examination, was found to be a sandal root-sucker. I then traced the larger root (host) to its source and found it to belong to a *Limonia acidissima* tree growing on the top of the cutting.

The sandal root was attached to the host at three points, at each of which a tubercle had formed. This specimen was shown to all the District Forest Officers, as well as to the Conservator of the Central Circle, who had assembled at Yercaud for a Forest Conference. The accompanying plate, Plate VI, is a correct and full-size drawing of the specimen and proves unmistakably the root parasitism of the sandal on the roots of *Limonia acidissima*.

Forestry in America.

By H. J.

(Continued from page 334.)

Chapter V.

Chapter V of Dr. Fernow's book, *Economics of Forestry*, is devoted to the factors of forest production, and business aspects.

Forestry differs from agriculture, and all other productive industries, principally in the time element; agricultural crops are harvested annually, or at most require only a few years for their production, but wood crops are only useful after many years' growth has been accumulated, and most timber-producing species require between 100 and 200 years to yield timber of the most useful size.

The quality of the wood, too, improves, within limits, with its growth in size, and the proportion of the timber of the bole begins to preponderate over the branch wood of the crown.

The rate of growth varies with the different species and with the soil, climate, surrounding conditions, and with the age of the tree.

Some soft light-wooded trees grow very rapidly up to forty years of age, and then soon cease to grow, and die; while the best timber-producing species, and the conifers, grow slowly at first, then faster, and continue growing at a more or less uniform rate till old age.

The study of the quantitative production of crops of different species, and of different ages—the mathematics of forest growth,—is of great importance. The determination of the exploitable age depends not only on the species, soil and climate, but also upon market conditions, industrial requirements, and economical considerations.

Beside the time element, there are three other factors of production, namely, nature, labour and capital.

In agriculture, labour is the most important, nature second, and capital last; while in forestry, nature comes first, then capital, and labour is the least important.

The labour required in forest work is, moreover, very simple, and involves but little technical skill. In Germany there is one guard to about every 1,000 acres, and in India, where the cost of the largest permanent forest establishment in the world amounts to about one quarter of the gross revenue of the forests, the total number of permanent employés of all ranks from the Inspector-General downwards, is about 10,500, or one to about 7,500 acres of forest.

It is evident that the use of both of the elements of nature and of labour differs widely in forestry and in agriculture, and that forestry can only be profitably practised over comparatively large areas.

The factors of soil and climate, too, have a different significance; agriculture deals mainly with vegetable products which originally came from different climates to those in which they are now grown, but have been adapted to their present conditions, and have been improved by man for his own use. A wood crop on the other hand is generally just as nature, unaided, produced it, during a long cycle of development, and the forester's influence does not extend beyond increasing the production of material of useful form and of useful species per acre.

But the greatest difference between the two industries, and one of the highest national economic importance, is the difference in the use of the soil.

Agriculture is engaged in obtaining food materials whose production relies largely on the mineral wealth of the soil, especially the phosphorus, sulphur, potash and nitrogen. Unless these are replaced by manures, or through a rotation of crops, the soil becomes exhausted and unfertile.

On the other hand, forestry is mainly engaged in the production of cellulose, which contains a minimum of these rarer elements.

The air supplies one half the constituents, namely, the carbon, and almost the other half is furnished by the water of the soil, while the wood, the final product, only contains about one per cent. of mineral ash.

The parts of the tree richest in minerals—the fruit, the flowers, the leaves, twigs and branches—fall to the ground, and not only return to the soil the fertility derived from it, but enrich its surface by the decay of the litter, through the vegetable humus and the nitrogen-condensing bacteria formed in the same.

Thus, while agriculture exhausts soils, forestry enriches them.

From the soil the forest crop derives mainly the water required for its biological processes, including the transpiration of its leaves and for the composition of its wood, and lastly the hygroscopic water which is finally lost when the wood seasons. Chemically, water forms 48 per cent. of the wood substance, while 60 per cent. more is hygroscopically bound to it in the living tree, ten or twelve per cent. remaining so in the wood after seasoning. The 8,000 pounds annual product on a fully-stocked acre thus divides itself up into 3,000 pounds dry substance, 1,250 pounds of water chemically bound, and 3,750 pounds of hygroscopic water. Forest crops can thus be grown on soils too poor for agriculture, and no manuring is required, provided the litter is left.

Soils and situations topographically unfit for agriculture may also be usefully employed for forest growth. Mountain slopes too steep for plough land, and even for pasture, are still suitable for forests, and it is precisely such places where, for the protection of the ground and for favourable water and climate conditions, a forest cover is most needed.

The annual production per acre, including the brushwood, may rise under favourable conditions to as much as 100 cubic feet; but for timber-producing forests, the average annual yield in large forest administrations, including everything down to 3-inch diameter, may be about 50 or 55 cubic feet.

The third factor of production, *capital*, must be divided between the fixed investment laid out as a basis for continuous production, and the current working fund required to carry on the business. The latter may often in any forest business be very small, as little is required usually in the way of machinery, buildings, tools, seeds, etc., but the amount and character of the permanent capital renders the regulated forest business unique. Both farming and forests have in common the soil as the basis of production, but in forestry the greater part of the fixed capital is represented not so much by the soil, but by the accumulated growing stock of wood, since the wood accretions of many years are tied up, as it were, as a fixed capital, accumulating with compound interest, until the exploitable age is reached.

Suppose, for instance, a forest which is best harvested at a hundred years of age; then, in order to fell every year a crop of one-hundred-year-old timber, we require a series of 100 crops, each one differing in age by one year, from 100 years down to yearling growth.

The contents of the 99 crops expressed in volume or in value are the wood-capital, and the hundredth crop is the interest or yield.

The capital stock of wood, which must be maintained, is evidently about equal to the increment occurring over the whole forest through half the rotation.

It is also obvious that in coppices worked under a short rotation, the wood capital is much smaller than in a timber forest worked on a long rotation.

As an instance, taking 70 cubic feet of wood per acre as the average annual production, then a coppice of 100 acres under a 20 years rotation would require as wood-capital 70,000 cubic feet, while the same area worked for timber with a rotation of 120 years, would require a wood-capital of 420,000 cubic feet, or six times as much as the coppice in volume, and many more times in value, since timber is much higher priced than fuel.

In actual practice the disproportion is generally even greater, and the wood-capital in the timber forest is often 10 or 20 times as large as in the coppice.

Finally, in a properly regulated forest worked for large timber, the soil and wood-capital combined will be between two and ten times the capital required in agriculture.

From what has been said above, two most important deductions from the standpoint of political economy follow :—

First, the time element, together with the large capital required to produce timber, renders forestry an undesirable business for private owners of limited means; only the State and, in a less degree, other permanent corporate bodies, can profitably engage in it.

Secondly, the fact that capital and interest are identical in nature and are mixed together, only to be distinguished by voluntary economic considerations and self-imposed saving, results in the fact that the systematic management for continuity may very easily be unbalanced by liquidating a part of the capital without immediately appreciable loss, and that consequently only the State and other communities who have an interest in continuity can safely (apart from considerations connected with the large capital required) be entrusted with the forestry business.

The dangers to the wood-capital from fires, storms and insects can always be reduced to a minimum of permanent injury, especially if the property under one management is large, and though the rate of interest, 3 or 4 per cent., derived from forests, is small, yet the safety of the investment is great, and it is certain that the price of wood must rise in the future, since the forest area rather tends to diminish, while the demand for wood increases.

CHAPTER VI.—NATURAL HISTORY OF THE FOREST.

The forester has to do with forest crops rather than with single trees, and he has the power, within limits, of influencing the composition of the natural forest, which is the result of an evolutionary struggle among the different forms of vegetation, into a form suitable for his purposes. The limits are set by the adaptability of the species to soil and climate, and by the forester's skill in recognizing and utilizing the laws under which the natural forest develops.

Temperature and moisture determine in the first place the natural distribution of the various species. A succession of different types of forest, and different species, are met with as we pass from the tropics to the northern latitudes; and similar zones of forest growth are also met in ascending from sea-level in tropical or sub-tropical regions up to the highest altitudes, where forest growth is found. The relative humidity, too, brings about changes in forest types, from the damp swamps near the seashore up to the dry and rainless interior of continents. Dryness, like cold, diminishes growth and reduces the number of species composing the forest.

Soil conditions, too, within the geographical range of the species thus limited, differentiate the distribution.

The frugal pines will subsist on the poorest, barest soils, other species prefer wet situations; a few will only thrive on rich loamy soils, while others will adapt themselves to almost any soil conditions. The absence of a species from any locality does not however necessarily mean that it cannot exist there, as there are mechanical barriers, such as wide oceans and high mountain ranges, or there may be absence of means of transportation for the seed. All such difficulties man can overcome, and in forestry acclimatization, so called, is practically confined to overcoming such mechanical barriers.

As a rule the forester relies on the species which he finds naturally growing in the locality, and he can do little to improve on the quality of the wood as nature produces it.

While the presence of a species in the composition of the natural forest is in the first place due to climate and soil conditions, its numerical distribution and the manner of its occurrence in the mixed forest depend primarily on two qualities in combination, namely, its relative rapidity and persistence in height-growth, and its relative requirements for light.

The character of the seed and the manner of seed-production and seed-transportation are additional factors.

Some species bear seed prolifically every year, while others only produce seed at intervals of several years. Some seeds are heavy and large, such as the walnut and acorn, and cannot travel unless squirrels, mice or birds carry them; while others, like the light-winged seeds of the birch and poplar, are easily carried by the winds, and so become ubiquitous. Some seeds, such as those of the willow, lose their power of generation within a few days, while others of the leguminous tribe preserve their seeds alive for many years.

After the peculiarities of the seed comes the peculiarity of growth. One species will grow very slowly during the first few years of its life, but will then be forming a stout root-system, which afterwards may give it a great advantage over a quicker-growing rival. A fast-growing species like the poplar may cover large areas, but its reign is short, and the slower-growing shade-bearing spruce will eventually by its persistency occupy the ground.

Capacity to resist frost, drought, fire, insect attacks, and other causes of injury will also affect the distribution of the different species, but finally the two qualities first mentioned, relative height growth and relative light requirement, are determinative.

Just as in a mixed forest the species are distributed according to their shade-endurance, so in a pure forest of one species, the individual trees of different sizes develop side by side according to available light, each crowding the other, until the laggards are killed by the withdrawal of light.

As an example, in a fully stocked acre of American white pine (a species analogous to the spruce) there may at first be 50,000 or more seedlings in a dense thicket, excluding all light from the soil. After a few years the lower branches, thus shut from the light, die and fall off; this natural cleaning of the bole takes place during the period of rapid height-growth, between the tenth and thirtieth years. At 30 years old the trees are slender poles of about 4 inches diameter and 20 to 25 feet in height; but different degrees of vigour of development, according to individual constitution and accidental opportunity, can now be recognized, and three classes may be differentiated: the predominant, with their crowns 5 to 10 feet above the general level, which are the trees of the future; the sub-dominant, ready to occupy the air-space of any of the superior class should accident remove any of them; and lastly, the suppressed ones, doomed to die.

Out of the tens of thousands which started, only 2,000 or 2,500 survive, and as each tree is striving with its neighbours for as much air-space and root-space as possible, the result is a continued diminution of the number of trees occupying the acre.

This decimation is in exact mathematical relation, barring accidents, with the development of the dominant class in height-growth.

At the age of 60, not more than 400 to 500 trees are left. After this age the diminution proceeds more slowly, until at last only 200 or 300 stems occupy the ground, the number varying with species, soil, and climate.

The height-growth is now practically finished, and the branches will no longer lengthen to occupy the air-space. No numerical change will therefore take place, except as the result of accidents, until the crop passes its age of maturity.

This factor of light is not only the most important one in bringing about the evolution of the natural forest, but it is practically the only one under the control of man. With the knowledge of the light requirements, and with the judicious use of the axe, the forester can suppress one species and stimulate another, can direct in quantitative and qualitative development the progress of his crop, and finally secure a regeneration in the most useful species.

Not only is the composition of the forest largely a result of changes in light conditions, but the actual amount of production is a function of the light, for the annual production of wood is in direct relation with the amount of foliage which the tree can exhibit to the influence of light.

The whole art of forestry is based upon the laws of accretion.

It is in the pole stage that the maximum rate of height-growth occurs, generally between the ten and fifteenth year with light-demanding, and between the twentieth and fortieth years with shade-bearing species.

The diameter growth proceeds slowly until a fully formed crown and root-system can elaborate the necessary material, and generally reaches a maximum between the fortieth and eightieth year, then very evenly declining into late life; the sectional area, however, will continue to increase some time after the diameter rate has begun to sink, as each year's deposit is made on a larger periphery.

The form of the bole, too, is of great economic interest. With trees growing in the open, with large crowns and low branches, so much food is elaborated that the lower portions receive an excess, and the trunk will taper rapidly upwards from a broad base, while trees grown in a dense forest crop will have small confined crowns, and long clean boles, which will be almost cylindrical in shape.

The mean annual increment of any individual tree growing in full enjoyment of light goes on increasing up till old age.

In the United States a good beginning has been made to follow German Foresters in trying to determine the volume development of crops; for this, both height and diameter, and volume growth of the various size-classes, together with the gradual diminution in numbers which takes place in a fully stocked crop, must be studied.

These measurements show that the same acre always produces annually the same *weight* of dry wood, with practically whatever species it may be grown, namely, from 4,000 to 8,000 pounds per acre, according to the quality of the ground. The volume may vary according to the specific gravity of the wood of different species, and according to the water contents. About three-eighths of this product is useful wood material, nearly one-half being roots and foliage, and nearly one-quarter brushwood and bark. The annual production of *available* dry wood substance above ground varies, according to the quality of the climate and soil ("site"), from 3,500 pounds on good sites to 1,200 pounds on the poorest. The number of trees to the acre is of no consequence, provided that a full crown cover is always kept.

The important factor in production is therefore the intensity of utilization of the light, and not the number of trees; the proper gauging of numbers is, however, one of the most important operations of the forester, because the question of numbers of trees affects the distribution of volume in more or less useful form.

We have already seen that in a dense young growth of nature's sowing there may be 50,000 or more trees per acre, which, by natural thinning after the twentieth year, are reduced to 2,000 or 2,500, and then diminish steadily at a slower rate, until, at the end of the hundredth year, only 200 to 250 occupy the upper crown level, or only 10 per cent. are left. Thus, while the mean annual increment has been increasing, there has been a constant loss by the death of the inferior trees, a loss in volume equal to 35 or 40 per cent of the final harvest, and which can, in part at least, be saved by timely interference and realization.

As standards of measurement of the rate of production of timber, yield tables have been compiled for fully stocked crops of each species and for five site-classes: the contents of the dominant growth are given in ten-year periods, and represent the attainable maxima.

The following two tables will serve as an illustration. Only timber, that is, wood of over 3-inch diameter, is stated; and the volume of the thinnings, which may be about 3[illegible] per cent. if the final harvest is omitted.

Both tables refer to first class sites, and show the difference between the production of the shade-bearing fir and that of the [illegible] pine.

"Site" means soil and climate conditions, or "quality of the locality."

YIELD TABLE OF FIR. SITE-CLASS I.

Age.	Number of trees.	Average height in feet.	Volume, cubic feet	Volume increment		
				Mean	Current.	Per cent.
20	5,300	17	990	50	197	20·1
30	2,210	31	3,550	118	317	8·4
40	1,220	43	6,530	163	224	3·2
50	750	50	8,615	172	172	1·9
60	540	65	10,280	171	144	1·4
70	410	73	11,675	167	125	1·0
80	325	81	12,890	161	110	·8
90	270	88	13,950	155	96	·7
100	230	95	14,890	149	86	·6

YIELD TABLE OF SCOTCH PINE. SITE-CLASS I.

Age.	Number of trees.	Average height in feet.	Volume, cubic feet	Mean	Current.	Per cent.
20	1,700	23	775	39	94	13·0
30	1,170	36	2,185	73	138	6·0
40	720	50	3,820	95	113	3·0
50	510	63	5,000	100	94	1·9
60	380	72	5,935	99	80	1·3
70	300	80	6,700	96	66	1·0
80	245	86	7,330	91	58	·8
90	200	92	7,840	87	50	·6
100	170	93	8,275	83	45	·5

The average maximum total wood production per acre per annum in a 100-year rotation under German conditions, for German species, German management for different site-classes, leaving out the yield of the thinnings, which may possibly amount to 40 per cent. of the final yield, is as follows, in cubic feet:—

Site-class ...	I	II.	III.	IV.	V.
Scotch pine	93	79	54	45	35
Norway spruce ...	154	127	99	78	58
Silver fir	158	128	102	77	54
Beech	105	85	70	40	25

The entire production of wood per acre of all the German forests is estimated at 50 cubic feet per acre per annum. For France it is less than 40 cubic feet.

The yield table may also be shown graphically.



[There is nothing absolute in these tables; they are merely given as specimens.]

While in the natural unmanaged American forests the final crop of marketable timber, often 200 years old, rarely exceeds 8,000 cubic feet per acre, in the managed German spruce forests, fully stocked, and cleared of all undesired species, 3,000 cubic feet of wood may be found at 30 years; over 9,000 cubic feet at 60 years; and 14,000 cubic feet at 100 years.

The rate of production under these conditions will be 70 cubic feet for the first two decades, 240 cubic feet for the third decade, and 267 cubic feet for the fourth decade, being a maximum. After this the rate will decline, so that in the ninth decade it may be only 100 cubic feet, and at 100 years the average rate for the whole period has come down to 140 cubic feet. On poorer soils, less, down to one-half, of this production may by expected.

In the natural forest the same laws would obtain, but the economic result would be different, since the crop would contain tree weeds as well as the valuable species.

The most rapid growers are not generally, in the long run, the largest producers. For example, the fast-growing poplar, which is near the end of its life at 80 years, will scarcely have produced by that time 7,600 cubic feet to the acre; while the slow, shady, but persistent, spruce has by that time accumulated over 22,000 cubic feet and is still growing at the rate of 80 cubic feet per annum.

On good sites, and with fast-growing species, the culmination of the rate of volume growth occurs early and then declines rapidly. Thus the Scotch pine on good sites will attain its maximum at about the 30th year, with over 160 cubic feet per acre, and on poorer soils, ten years later: while the slow-growing beech shows its culmination at about the 60th year, with 190 cubic feet per acre.

The mean annual increment of a crop rises more slowly than that of a single tree, and more regularly, since it expresses all the variable conditions.

The maximum mean annual increment of a crop occurs when it is equal to the current annual increment; that is, the highest average annual production per acre per annum has been obtained when the accretion occurring through a series of years, divided by the number of years, is as large as the increment of the particular year.

This often occurs before the fiftieth year with light-demanding species on good sites, later on poor sites, and with shade-bearing species; but the value increment, depending on the amount of large-sized material, culminates very much later.

If a group of some hundred trees have grown together in a close crop of the same age, they develop so regularly and interdependently that the following relations will prevail: the contents of the average tree will be approximately equal to one-tenth of the volume of the three stoutest and the seven slimmest trees of the dominant stage, and the volume of the crop is then found by multiplying this amount by the number of trees involved:—

$$\text{Volume of crop} = n \times \frac{3\text{ max} + 7\text{ min.}}{10}$$

If the trees are arranged in size-classes, the average tree will be found to be about 40 per cent from the largest. Thus in 500 trees, the 200th tree, counting from the stoutest, will be the average tree Moreover, if these trees, arranged in size-classes, be divided into 5 groups, the first fifth will contain 40 per cent of the total volume, the second fifth 24 per cent, the third 17 per cent, the fourth 12 per cent, and the last and smallest, only 7 per cent, of the total volume of the crop.

These interesting deductions from the yield tables are merely quoted to show that the forest grows under recognizable laws, by the help of which we can calculate not only the volume, but the value increment, and so obtain a basis for the management and development of the forest, and the realization of a given rate of interest on the capital involved in the forest

Forest Exploration in the Bahr-el-Ghazal (Sudan).

BY C. E. MURIEL, I F S.

I HAVE just received from Mr A. F. Broun, Director of Forests in the Sudan Administration, a copy of his report on the forests of the Bahr-el-Ghazal, and the following notes and extracts from that report may be interesting to the readers of the *Indian Forester*.

Mr. Broun left Khartoum on the 21st January 1902, by steamer to Meshra-er-Rek and thence commenced his land journey on the 5th February to Tonj, Wau, Chakchak, and Dem Zubeir; returning by a direct route to Wau, and by his former route thence back to Meshra-er-Rek, completing the journey of 700 miles by the 24th April 1902 The locality visited lies roughly between 26° to 29° E. and 7° to 8°-30′ N and forms the north-western portion of the Bahr-el-Ghazal Province drained by the Tonj, Wau, Pongo, and Chell rivers

Generally, the country can be divided into three zones: "Perennial swamps near the mouths of the rivers," "the somewhat raised alluvial flats further up, which are liable to inundation during the rains," "and undulating plateaux or hilly country in the upper reaches."

Mr. Broun divides the forest for descriptive purposes into three divisions, corresponding with the drainage zones above noted.

In the perennial swamps the Ambatch (*Herminiera elaphroxylon*) is the only woody plant It is reported to have become abundant only in the past few years. In the second zone tree-growth is scanty in portions periodically submerged, and the most common trees are *Mitragyne africana* (yielding most of the fuel at the Bahr-el-Homr wood station), *Sarcocephalus esculentus*, *Tamarindus indica*, *Crateva religiosa*, *Maba abyssinica*, *Cordia sub-opposita*. and on poor soil *Euphorbia candelabrum*.

On higher ground villages are dotted about and the country is generally open, with solitary or small groups of trees or bands of forest alternating with open country, such trees as *Ficus sycomorus*, *Ficus platyphylla*, *Kigelia æthiopica*, *Borrassus flabelliformis*, *Acacia albida*, and *Balanites ægyptiaca* predominating. "Fierce fires sweep everywhere, and it is not wonderful if the condition of the forests is, on the whole, bad, and that the trees are generally crooked and hollow, the young growth mostly consisting of tufted coppice-shoots, which get killed down to the ground year after year until chance affords them a few years respite, which allows them to grow strong enough to resist further fires but not to be uninjured by them."

The forests of the third zone are composed of *Parkia filicoidea* (one of the largest trees of the Bahr-el-Ghazal), *Prosopis oblonga*, *Tetrapleura obtusangula* (another large tree), *Afzelia africana*, *Daniellia thurifera*, *Berlinia acuminata*, *Erythrophlœum guineense*, two *Cassias*, *Pterocarpus lucens*. *Dalbergia melanoxylon*, *Anogeissus leiocarpus* (yielding most of the timber used in constructing houses in the military posts at Tonj, Wau, Chakchak, and Dem Zubeir), *Khaya senegalensis*.

Butyrospermum Parkii is widely distributed and Bamboo (*Oxytenanthera* sp.) grows in narrow belts lining the water-courses in the highlands.

" The quality of the forests is at present not high. The best forests are those found in the broad, uninhabited stretch between Dem Zubeir and the Pongo, but even here the frequency of fires has prevented the stock from being at all uniform." * * * * *

" It is however satisfactory to note that even in such fire-worn areas there are still to be seen scattered here and there enormous trees, such as *Shandé Homra*, *Bei*, *Nwana*, etc. * " *

" The most that can be said of these forests is that the large trees are very fairly represented, and that with proper treatment and protection some magnificent reserves could be evolved."

---

* Shandé = Daniellia thurifera
Homra = Khaya senegalensis.
Bei = Afzelia africana.
Nwana = Parkia filicoidea.

Khaya senegalensis, *Balanites ægyptiaca*, *Afzelia africana*, *Berlinia acuminata*, *Pterocarpus lucens*, *Tamarindus indica*, *Anogeissus leiocarpus*, *Borassus flabelliformis*, and *Lophira alata* are among the trees recommended by Mr. Broun for their timber.

The following trees and climbers yielding latex—producing rubber or gutta-percha—are mentioned: *Landolphia florida* and *owariensis*, *Ficus platyphylla* and *Butyrospermum Parkii*.

Mr. Broun found that from *L. florida* the latex coagulated very rapidly and the wounds became coated with a film of rubber rendering collection difficult; the rubber was however of excellent quality.

L. owariensis was more abundantly found and is a very large creeper yielding a more copious latex than *L. florida*, but the collection of the latex in a pure state was not easy, and the latex coagulates with difficulty and yields an inferior rubber.

Ficus platyphylla is a large tree and yields an abundant latex, but Mr. Broun found it difficult to coagulate, though later he received good samples from boiling the latex The supply should be valuable as the tree is reported to be abundant between Wau and Meshra-er-Rek.

Butyrospermum Parkii yielded but little latex and this produced a gutta-percha that was hard and not plastic. The chief value of the tree therefore appears to be its edible fruit and the oil obtainable from its kernel.

Mr. Broun proposes to exploit the rubber by leasing out fixed tracts of country to be worked in alternate years. Where little control can be expected this system is likely to result in the destruction of the trees and failure of future supply of rubber. Such is the experience in Burma.

Mr. Broun advocates the formation of Reserves first on the Jur river near Wau, extending gradually to Tonj, and later to forests between the Pongo river and Dem Zubeir.

Transport is bad at present and the future value of the Bahr-el-Ghazal forests (apart from rubber) depends on the opening up of waterways now blocked by "sudd."

The necessity of fire-protection for forests that are to be worked is rightly insisted on, but the difficulties in the way of such protection are great: everywhere Mr. Broun went he met with traces of fire; this is not surprising, as the Dinkas and other tribes owning cattle fire the grass lands near the rivers to provide more tender herbage for their herds; hunting parties use fire in the pursuit of game; and travellers fire the grass to clear their path and for security against sudden attack by wild animals.

These habits will not be easily or quickly changed, but the earlier tentative measures of fire-protection are commenced the sooner will the people become accustomed to the restrictions which will be necessary.

II.—CORRESPONDENCE.

Notes on Gelsemium elegans and the Bamboo Fungus of Burma

The following notes on *Gelsemium elegans* and *Polyporus anthelminticus* which have appeared in the *Pharmaceutical Journal* of this month, may perhaps interest Foresters and others in Burma.

Several species of the order *Loganiaceæ* yield poisonous alkaloids. Strychnine is contained in the seeds of the Khabaung tree, *Strychnos nux vomica* (¼ to ½ per cent. of their weight). It is also obtained from the Ignatius beans, the seed of a climber, *Strychnos Ignatii* Bergius, of the Philippine Islands. Gelsemine is yielded by *Gelsemium sempervirens*, a beautiful climbing shrub, known as Wild Yellow Jessamine, and a native of the Southern States of North America. Like Strychnine, Gelsemine in small doses is a useful medicine, but in large doses it is poisonous.

At first sight it seems incredible that the soft lining of the Bamboo joints and the thick, hard, irregularly-shaped mass of the *Polyporus*, which is found outside on the culms of bamboos near the ground, should belong to the same plant. I wish therefore to mention the analogous case of *Polyporus nigrescens*, which grows on old stems of the Elder (*Sambucus nigra*), and to which Mr. G. Massee has kindly drawn my attention. The mycelium of this fungus is frequently found in the pith of the elder, the dark threads of the mycelium contrasting with the white colour of the pith. In some cases the mycelium develops to such an extent as entirely to replace the pith in a portion of the stem.

KEW: D. BRANDIS.
June 1903.

A note on Gelsemium Elegans, by SIR DIETRICH BRANDIS, K. C.I.E., PH. D., F. R. S., F.L.S., *Honorary Member of the Pharmaceutical Society.*

Last year Mr. Smales sent me, among other important specimens from Upper Burma, pieces of the roots, stem, leaves, and flowers of *Gelsemium elegans*, Benth. (Loganiaceæ), a large creeper with bright yellow flowers, collected for him by Mr. A. English in the Katha district, in Taungya Ponzo (the second growth which springs up on deserted hill clearings), at 3,200 ft. His notes say: "Very deadly creeper; decoction of root kills instantly; leaves also fatal." I have the same species from Mr. Montague Hill, who collected it in February 1902, in fruit, in village jungle on the hills east of Bhamo, at 4,000 ft.

When I showed these specimens to Sir W. T. Thiselton-Dyer, the Director of the Royal Gardens here, he gave me a report of the Analytical Department, Government Civil Hospital, Hong Kong, dated January 1885, with an excellent coloured figure of the plant, and pieces of the root, which agree completely with the specimens received from Mr. Smales. Since then I have seen the interesting account of his poison given by W. E. Crow, M.P.S., in this Journal of 1887.

In a case of death from suspected poisoning of two persons, a man and a little girl, an alkaloid was detected by the Government Analyst in the contents of the stomach of the two persons, as well as in the tea which they had drunk. This alkaloid showed a reaction similar to those of gelsemine and strychnine, the produce of the North American *Gelsemium sempervirens* and of the Indian *Strychnos nux vomica*.

The alkaloid of the roots of *Gelsemium elegans* has, as far as I know, not yet been prepared in a pure state; its existence, as well as its affinity to strychnine and gelsemine, is concluded from the similarity of the coloration, exhibited when manganic oxide and sulphuric acid are applied; but it differs in not being associated with gelsemic acid, and in that, unlike strychnine, it will not bear the action of sulphuric acid at 100° C. (*Pharm. Journ.* [3], 17, p. 925.) In any case, this climber, which is well described by Kurz in the second volume of his *Forest Flora*, p. 249, and which has been found in several places in Upper Burma as well as (by Mr. C. B. Clarke) in Manipur, merits the attention of forest officers.

The Bamboo Fungus of Burma, by SIR DIETRICH BRANDIS, K.C.I.E., PH.D., F.R.S., F.L.S. *Honorary Member of the Pharmaceutical Society.*

Last year I received from my old friend and follower in the Tharawadi Forests, Ko Way, through the kindness of the late Mrs. Ingalls, a most remarkable specimen, a cylinder, about twelve inches high, and just under three inches in diameter, of a soft but tough white leathery substance; on the outside with a horizontal shallow furrow at the bottom, and many raised vertical lines on the lower portion, which evidently had grown on the inside wall of a bamboo joint.

Mr. G. Massee, F.L.S., head of the Cryptogamic Department at Kew, at my request, kindly examined the specimen, and from the structure of its tissue and the presence of characteristic conidia formed on the inner surface of the cylinder, he identified it with *Polyporus anthelminticus*, Berk., which was described by the late Mr. Berkeley on p. 753 of the *Gardener's Chronicle* for

1866. As a rule this *Polyporus* forms thick, irregularly-shaped masses on bamboo stems, bearing a round top or pileus, which, on its underside, has innumerable holes or small tubes, lined by the spore-bearing hymenium. Like the European *Polyporus officinalis*, which grows on larch trees, it is an effective anthelmintic, and is also known as "Than mo." The *Madras Quarterly Medical Journal*, Vol V, p. 146, contains an article on it by Dr. Packman, giving the detail of four cases in which this remedy had been employed with complete success.

In the present case the spores, or the mycelium, must have entered the bamboo joint, probably, either while the tissue was young and soft, or at a later period, through a hole made by an insect, and must have formed this peculiar lining of the inner surface of the joint. I have not been able to ascertain the species in the internode of which this remarkable lining was formed, but I am inclined to think it was either Tinwa (*Cephalostachyum pergracile*) or Kyathaung wa (*Bambusa polymorpha*).

This note may perhaps induce some of my younger friends in Burma to study this interesting subject, and to record the result of their researches in the pages of the *Indian Forester*. It would be important to know whether such a soft, leathery lining is frequently found in bamboo joints and under what circumstances it is formed, also the species in which it occurs.

Chemical Analysis of the Rubber of Wrightia Tinctoria and Ficus Infectoria.

A QUANTITY of the crude rubber of *Wrightia tinctoria* and of *Ficus infectoria* was sent lately to the Agricultural Chemist for analysis. I give below an extract from his report for publication in the *Indian Forester*. By a mistake the rubber of *W. tinctoria* was sent in place of *W. tomentosa*. The method of extraction was to inflict wounds on the bark of the trees with a sharp stone; from these the latex oozed out and was caught up in a cocoanut shell as it dropped off, or was scraped off with a leaf, or with the fingers, and dropped into the shell. In the case of the Wrightia, the flow of latex was more or less profuse and was easily collected as it dropped off the wounds, and such milk as adhered to the wounds was scraped off and dropped into the receiver. But with the Ficus the flow was never profuse and could only be gathered by scraping it off the wounds. The receivers when filled were allowed to stand uncovered three or four days to permit of complete coagulation of the contents. They were also put out in the sun for some time to effect this thoroughly. The contents were then removed from the shells before despatch. They adhered very closely to the shells, especially the rubber of the Ficus, and the shells had to be broken and some force used for separation.

Result of analysis.

	Wrightia tinctoria.	*Ficus infectoria.*
Water, gum, etc.	25·8	30·0
Resin	45·8	47·6
Caoutchouc	28·4	22·4
	100·0	100·0

"No 147 (referring to the Wrightia) consisted of the cream-coloured dry latex and was crumbly. No. 148 (referring to the Ficus) was a dark-brown coloured, sticky mass."

GEO. W. THOMPSON.

NARSAPATAM, MADRAS:
July 11*th*, 1903.

Ripening of Cones of Pinus Longifolia

WOULD you be kind enough to allow me a small space in the *Indian Forester*, as I wish to say a few words upon the question of the ripening of cones of *Pinus longifolia*, in reply to Mr. E. M. Coventry's letter in the July number of the Magazine.

During the last 18 years I have collected seeds of *P. longifolia* for the use of the Imperial Forest School, Dehra Dun. I have noticed that the flowers are produced on the extremities of the branches every year, from February to April, just as the fruit is about to form. The growth of the branch on which the flower appears is thus checked: a side bud is now produced and branches begin to grow again in the same way as before; and the following year the flowers are again produced at the extremities of the new branches, and the side buds are produced by the growth of the terminal one being checked. At the same time the fruit is not formed on every branch, but on alternate ones. The old opened fruit remainsthree to four years on the trees. The age of the fruit can be found by counting the number of whorls of branches on which it is produced, and in the same way we can find the age of the tree by noting the number of whorls of branches on the stems, and hence the age of the branch itself by counting the whorls of branches of the main branch. The fruit takes 12 to 15 months to ripen, and the seeds are generally and wholly shed in May of each year in Dehra Dun. It is true that there is an exception to this rule: the cones of which the ovules are not wholly fertilised, being weakly ones, do not open and therefore cannot shed their seed at the proper time or season and such cones remain unopened on the tree, and finally during the rains they begin to decompose or decay and the seed is not allowed to escape.

I have just examined a cone, 15 months or so old, which had nearly half of its ovules fertilized and nearly half unfertilized; the seeds were quite overripe, but the cone being in so weak a condition, was unable to allow the seed to escape. I then examined another cone two years old, which had never opened and would probably decay on the branch. From the above it will be seen that the cones do not take more than 15 months to ripen, but exceptionally some very few cones, say 2 per cent., remain on the tree unopened, and therefore do not shed their seed.

Mr. E. M. Coventry says (page 276): "There appears to be a mistake in Gamble's *Manual of Indian Timbers*, page 706, regarding the period necessary for the cones of *chil* (P. longifolia) to ripen. This is given as 15 months, but I think it should be a year longer."

I think my note has explained this period, but if there be any doubt, I should be much obliged if Mr. Coventry would kindly let me see specimens of the cones which take 2½ years to ripen, as I can count the age of the cones by looking at the branch on which they were produced. Such specimens would form an interesting addition to the museum of the I. F. School, Dehra Dun.

In the same article Mr. E. M. Coventry has pointed out: "According to Kanji Lal's *Flora of the School Circle* the *chil* (called *chir* in that circle—*Hon. Ed.*) flowers during February to April, and the seeds are shed in October next year In this Division (Kangra) the seed falls from the cones in May."

I have stated that the seeds of *P. longifolia* cones are shed in May of each year at Dehra Dun, and not in October, but I will point out at the same time that in his *Forest Flora*, page 507, Sir D. Brandis says: "*P. longifolia* flowers from February to April; cones ripen from 12 to 15 months and shed their seeds in May." Sir D. Brandis further says: "Ribbentrop (*Arboriculture*, page 178), states that in the Punjab the seeds ripen in October, and that the best time to collect seeds is to pick the cones from December to March."

BIRBAL,

17th July 1903. *Curator, I. F. School, Dehra Dun.*

Tanning Extract from the Heartwood of Xylia Dolabriformis.

IN the *Indian Agriculturist* it is stated that a tanning material can be manufactured from the heartwood of *Xylia dolabriformis*. The exact process to be adopted for the preparation of the same, without affecting its quality, is not however described. Under the orders of the Divisional Officer of South Canara, the above extract was prepared on the same lines on which the preparation of catechu is undertaken.

In the catechu preparation the heartwood of matured catechu trees is adzed out into uniform-sized small chips, which are then boiled in an earthen vessel a quarter filled with pure water.

After boiling the chips for two hours the solution is taken out and transferred to another vessel. Fresh water is again added to the boiling chips and the solution is again taken out at the end of 1½ hours. This operation is repeated twice or thrice.

The above solution is boiled for three or four hours till it becomes of a syrup like consistency. It is then allowed to stand through the night. In the early morning the above is kneaded into small balls, using the ashes of burnt catechu to prevent the extracts sticking to hand.

Thus catechu can be manufactured and solidified in a day or two. Xylia extract is prepared in the same manner, but it will have to be kept in the shade for about a week to get it solidified.

It is found impracticable to knead pure Xylia extract into balls, but this can be done if the Xylia is mixed with catechu in the proportion of 1 to 3 in volume.

The commercial and practical value of Xylia extract is very little known in these districts, although it is stated that the same can be used for tanning purposes.

I may venture to state that there is a fairly well distributed crop of *Xylia dolabriformis* on the borders of North and South Canara districts, and if a good market can be obtained for it, these forests can surely be worked to a very great advantage.

S. KUPPUSAMY CHETTIAR,
Forest Ranger.

COONDAPUR, S. CANARA.

III.—OFFICIAL PAPERS AND INTELLIGENCE.

The Institution of 'Arbor Day' in the Central Provinces.

THE following circular has been issued by Mr. A. Munro, Director of Public Instruction in the Central Provinces *:—

The Director proposes, with the approval of the Administration, to set on foot in the Vernacular Schools of these Provinces an institution known in the schools of the United States of

---

* We are indebted to Mr. A. M. Caccia, I.F.S., M.V.O. for, having drawn our attention to this new departure.—HON. ED.

America as "Arbor Day," which is devoted to the planting with trees of school-grounds, waste places and adjoining roadsides. He considers that it should be in commemoration of the birthday of His Majesty the King-Emperor Apart from its association with this auspicious occasion, there can be no doubt that the greatest benefit would result from the planting of trees in villages. Many of the villages in these Provinces are denuded of trees, and in the hot weather the heat is intensified by the absence of shade. School-compounds, camping-grounds and roadsides are in many places bare and destitute of shade. The planting of trees in such places would, in course of time, be of great advantage, not only in modifying the heat, but also in beautifying the village and school. Again, the planting of trees is held to be of great use in tending to increase and equalize the rainfall. Apart from these considerations, there would be the further benefit of providing the boys with healthy occupation out of school hours and in fostering a taste for nature study, which is specially desirable in an agricultural country.

2. The Director proposes that Arbor Day in the school of these Provinces should be in each year the 9th November, *viz.*, the birthday of His Majesty the King-Emperor. On this day trees should be planted, annually, in villages where it is possible to make arrangements to water them by the boys of the Vernacular Middle and Primary schools (outside municipal limits), to the number of four trees in each class, except the first and infant classes. For such trees it is necessary to dig a hole about 3 feet square and 3 feet deep. If possible, well-rotted manure should be mixed with the earth in about equal proportions. After the tree has been planted, a small earthen *ghara*, with a hole at the bottom large enough to admit of a grain of wheat passing through, should be sunk in the ground close to the roots of the tree. This should be filled with water at intervals of two or three days during the dry season. If the necessary saplings cannot be obtained locally, they will be supplied free of cost from the nurseries at the head-quarters of each district, and sent out by cooly to the schools concerned. Ordinarily, strong saplings about 3 feet in height should be selected, as smaller saplings need greater care. It will often be possible to raise such saplings in school gardens and school farms. The plants can either be grown in the ground or in pots. If the plan of planting in the ground be adopted, the seeds should be sown in lines about 4 inches apart. At the end of the year, the seedlings should be transplanted in rows, each plant having a clear space of 2 feet all round it. Such saplings should be ready to plant out at the end of 3 or 4 years. If pots are used, they should be of large size, so as to admit of proper root-growth, one pot being allowed for each plant. Each tree, after being planted, should be surrounded with a ring fence of earth about 2 feet high, on top of which thorns should be placed. The earth for the fence, which

is not provided from the hole dug for the tree, should be dug and carried from some distance, as a deep trench close to the plant tends to dry the earth round it. The hole should be dug and the fence prepared on or about the 8th November. Regarding the places in which trees may be planted, Deputy Inspectors should consult Malguzars and School Committees and make arrangements accordingly. Ordinarily, school-compounds, waste places, camping-grounds and roadsides should be selected. The sons of cultivators might plant trees in the waste places of their fathers, fields. The watering the trees and repairing the fences round them will be the duty of the boys, and masters will be required to see that this is done and to encourage them in the work. The Patwari, with the approval of the Commissioner of Settlements and Agriculture, will be expected to record in the khasra that such trees have been planted by the boys.

The trees that may be planted are the mango, mahua, pipul, banian, tamarind, neem, naranga and other good shade-giving trees that thrive in the locality. If the boys are too young to dig the necessary holes and make the ring-fence, the cost may be met from the school fees. Rewards to the boys for the best trees will be given from the school fees, and District Councils will be asked to offer small prizes for the masters.

3. Deputy Inspectors are requested to submit to this office by the end of July next, lists of villages in which trees may be planted, and to arrange for the trees being planted annually, on the 9th November, in accordance with the instructions given above. They will submit reports to this office on the results about the end of November in each year.

[We would like to draw the attention of the Directors of Public Instruction in the other Provinces of the country to the great usefulness and excellence of Mr. Monro's plan. If enthusiasm for the work can be aroused in the schoolmasters and boys, and a spirit of wholesome rivalry be induced, many fair groves and roads shaded from the scorching rays of the sun may be the result. We feel sure that Forest Officers would be most willing to further the good work with advice on the subject of best methods of planting, the best species to make use of and so on, and to prevent disappointment and waste of money it would certainly be advisable that their advice, where possible, should be sought.—HON. ED.]

IV.—REVIEWS.

Progress Report of Forest Administration in Baluchistan for 1901-02.

Area of Reserved Forests.—There has been no alteration in the area of Reserved Forests, which remains 203 square miles. The Forest Officer has selected for reservation two more unclassed forests situated near Quetta. A proposal to place under the management of the Forest Department certain unclassed forests within a circle of 30 miles of Loralai is under the consideration of the District Officers of the Zhob District.

The cases of reservation of Batsirgi, Khumak, Ghairgi and Chotiali, in the bed of the Narechi stream, remained pending with the Political Agent, Thal Chotiali, Mazar, a portion of the Central Zarghun Forests, called Babri, with the Political Agent, Quetta Pishin, while those referring to Taga Khur, Tur and Kup Mazar await final orders.

Offences.—There was an increase in the total number of cases. This was due to the scarcity of fodder, which resulted in a large number of grazing offences. The work of the Forest Department in detecting cases and bringing them to trial shows satisfactory results.

Grazing.—Owing to the prevailing drought, various areas, aggregating 15 square miles, were opened on permits for grazing for a part of the year.

Natural Reproduction.—Owing to the dryness of the season natural reproduction was not satisfactory. Juniper seedlings in Ziarat were mostly found to have dried. The same remark applies to the Quetta range. In places even saplings and poles were found to have dried up. Other species also suffered heavily, while new seedlings were only found in very favourable spots, and those only of certain species

Artificial Reproduction.—Walnut and ash grow slowly. It will be seen that tamarisk has done well considering the season. Robinia, as was stated last year, however, is a failure. The Forest Officer is not satisfied with his experiments with Chilgoza, and has indented for a fresh supply of seed to be tried in the Ziarat range.

The year, however, is not one to judge by, as owing to lack of water the work was greatly restricted.

Experiments with exotic pine proved a failure, and it is said that no further experiment is being made with exotics. One cannot help wondering why such were ever initiated in a division still in its infancy and showing a deficit.

Paspalum dilatatum grass seed, which was sown in the Cantonment nursery, has fairly established itself. In the Quetta plantations imported apple, pear, plum. pomegranate plants and quince cuttings were successfully put out in order to promote fruit-growing in Baluchistan.

Throughout the report, however, want of water and the dryness of the season are shown to have been a source of constant difficulty.

The following statement shows the outturn of timber and firewood as compared with previous years :—

Description of Forests.		TIMBER.			FIREWOOD.		
		1899-1900	1900-01.	1901-02.	1899-1900.	1900-01.	1901-02.
		c. ft.	c ft	c. ft.	c. ft.	c. ft	c. ft.
Reserved	...	2,031	2,255	1,178	16,288	26,088	18,039
Unclassed	...	10,678	10,898	20,979	433,784	360,924	386,492
TOTAL	...	12,709	13,153	22,157	450,072	387,012	404,531

Financial Results.—The deficit this year is Rs. 8,394, as against Rs. 12,181 of last year. This is due to a decrease in expenditure of Rs. 5,532 under "B Establishments," owing to the fact that Mr. Down, the late Deputy Conservator of Forests, retired during the year and his place was taken by Bhai Sadhu Singh, an Extra-Assistant Conservator of Forests.

General.—Bhai Sadhu Singh, in the five months that he has held charge, has found time to travel over a considerable area of the Agency, and is in correspondence with various Political Agents with a view to increasing the reserved areas. The Agent to the Governor-General notes that Bhai Sadhu Singh has shown a creditable desire to improve the financial working of the Forest Department, and it is trusted that by next year some plan will have been matured by which the drain on local forests can be reduced by the importation of timber and fuel from Sind. This experiment has already been commenced, but a report cannot yet be sent on its success.

In Zhob the season was so bad that forestry was practically at a standstill. Points referred to in last year's report are receiving attention.

The Pests and Blights of the Tea Plant*

THE second edition of Sir George Watt's volume is now issued in a form modified and enlarged by the author and Mr. H. H. Mann. While it contains a voluminous compendium of the insects and blights recorded on the tea plant, a large portion of the book is taken up by chapters on the cultivation of tea and similar matters. As a reference work for tea planters the book fills a distinct place, limited however by the ambitious nature of its scope, and should be useful to the few who have the knowledge and time to really make use of it. A large amount of information of a valuable and readable nature is to be found in the earlier chapters on cultivation, and for the planter this is probably the most important part. As an entomological book, the work is neither a useful scientific book of reference nor a really practical guide to planters. The authoritative work ends where the entomological chapters begin; no entomologist would describe a new species of *Psyche* (one wonders how the genus was determined) from a larval case alone without having the moth for reference, as is done in the case of *Psyche assamica*; and we question whether a practical entomologist would be satisfied to leave the treatment of the mosquito blight in such an unfinished condition. In this part the book lacks the authoritative weight of a specialist's knowledge, which would have prevented the authors reprinting the great mass of statements made by previous writers on the subject of mosquito blight for instance, and would have rendered a discussion of the value of parasitic fungi against insects unnecessary. Instances of this kind are numerous: the practically valuable part of the book could be reduced to small, handy, readable compass, which would at once tell the planter what was worth knowing.

---

* *The Pests and Blights of the Tea Plant,* by Sir George Watt, Kt., C.I.E., and Mr. H. H. Mann, M.S.C. 2nd Edit.

Much the same may be said of the fungus blight chapters, with the exception that the material obtained was in some cases worked on by authorities such as Dr. M. Norrie or Dr Butler. Throughout, the book has the stamp of an encyclopædic compilation of information derived more largely from reports and literature than from any practical experience, and as such it admirably fulfils its lexicographical functions. We venture to think, however, that a far more useful book could have been written had the important pests alone been considered and thoroughly worked over. It is of far more use to a planter to know how he can fight one pest than to be told that there are 17 species of bagworms on tea, and be given their names with voluminous references to the literature which he neither understands nor has a chance of consulting if he did.

Better illustrations have been introduced in the form of photographs, and this marks an advance on the previous edition. In a compilation of this kind, however, it should at least have been possible to give fuller information regarding spraying machinery and insecticides. The appendix quotes five insecticides, including the mixture Gondal Compound, and two fungicides, and there is no hint given of how to apply most of them or where to get the machines.

Whilst there are many good things in the book it cannot be said to fill a want of the planter, the man for whom it is written.

V.—SHIKAR AND TRAVEL.

Indian Pheasants and their Allies.

BY F. FINN, B. A., F. Z. S.

(Continued from page 300.)

CHAPTER VIII.

THE FOREST PARTRIDGES.

THE Partridges which remain to be dealt with are pre-eminently forest birds, never going far from cover. Most of them have very short tails, but one, the Bamboo Partridge, has the tail longer than in any other Indian species, so as rather to recall a small pheasant in appearance.

THE BAMBOO PARTRIDGE.

Bambusicola fytchii, Blanford, Fauna, Brit. Ind., Vol. IV., p. 110.

This Partridge shows no difference in plumage according to sex; the male has a spur on each shank, but this may be present in the female also. The plumage is brown above, spotted with chestnut for the most part; the face is buff, with a dark band behind the eye; the breast dull chestnut with some white spots, and the under parts below this buff, with large black spots shaped like a heart. The tail is barred brown and buff, and the pinion quills are chestnut without bars. The bill is brown, the eyes orange-hazel, and the legs grey.

This partridge is about fourteen inches long, of which the tail measures nearly five; thus it is easy to distinguish it from any other species, the Spur-fowl, which also have longish tails, showing some bare skin about the eye.

The Bamboo Partridge affects forest and high grass, and ranges through a considerable portion of the eastern hill tracts, from the Assam hills south of the Brahmaputra, through Manipur, to the Kacheri hills between Upper Burma and Yunnan. It is shy and has a loud harsh call Although the time—May and June—of breeding appears to be known, the eggs are as yet desiderata.

The various Hill Partridges (Arboricola) form an easily recognizable group of short-tailed birds with rather long spurless shanks, and particularly long, nearly straight claws. The sexes are usually alike, and they inhabit hill forests, keeping very close to cover, and occasionally perching. They are seldom if ever seen, and little is known about their breeding, except that they lay half-a-dozen or more white eggs on the ground. Their call is a low soft whistle and they are unobtrusive birds altogether; yet they are a well-represented group with us, numbering no less than six species, none of which, however, are found in Southern India or Ceylon. An interesting point about these partridges is that they possess a row of small separate bones along the upper edge of the orbit, a sort of bony eyebrow in fact. No other bird of this family possesses them, although they occur in some other groups, the Trumpeters (*Psophiidæ*) of South America and the partridge-like Tinamous (*Tinamidæ*) of the same continent. The general plan of coloration of the *Arboricola* genus is very similar, all having olive-brown backs mottled with black, and grey flanks boldly spotted with white, and usually with chestnut edgings.

THE COMMON HILL-PARTRIDGE.

Arboricola torqueola, Blanford, Fauna, Brit. Ind., Birds, Vol. IV, p. 125.

Native names:—*Peunra, Ban-titar*, Hindi, of Kumaun and Nepal; *Roli, Ram chukru*, in Chamba; *Kaindal*, Kangra; *Ko kum-but*, Lepcha.

This is the only species of *Arboricola* in which the sexes are different. The male has the head bright-chestnut above and of a paler shade of the same colour over and behind the ear coverts; the eyebrows, sides of the head, and throat are black, with white edgings at the sides, and there is a white moustache streak. The breast is grey, separated from the black throat by a white band. The skin surrounding the eye is scarlet.

In the hen the crown is brown with black streaks, the sides of the head and the throat are chestnut with black spots; the breast is brownish, and has a rusty band above it; and the white spots on the flanks tend to run up to the breast, and are larger. However, old hens lose the breast spots, and young cocks possess them. Hens and young cocks have the skin round the face purplish-red. In all, the bill is black and the legs fleshy-grey.

This partridge is a little under a foot long, with a tail of only three inches, and a shank nearly two. The wing is six inches long. Males run larger than females.

The common hill-partridge is found at moderate elevations along the Himalayas from Chamba to east of Sikkim, and also in the Naga hills and in those north of Manipur. It ranges from 6,000 to 14,000 feet, but its common range does not go above 9,000.

BLYTH'S HILL-PARTRIDGE.

Arboricola rufigularis, Blanford, Fauna, Brit. Ind., Birds, Vol. IV, p. 126.

Native names:—In Kumaun and among the Lepchas this species seems to have the same names as the last; in the Daphla hills it is called *Popku*. This species, like those which follow, appears to be a little smaller than the last.

It has the crown olive-brown with black streaks, and the eyebrows and face white, mostly speckled with black. The throat is chestnut with black spots, and below this is a band of plain chestnut, generally divided from the grey breast by a black band. The pure grey of the breast and the absence of black bars on the back will distinguish this bird from the hen of the Common Hill-Partridge.

The beak is black, the skin round the eyes dull dark-red, and the legs red.

This also is a Himalayan bird, ranging from Kumaun to the Daphla hills, but inhabiting lower elevations than the Common Hill-Partridge, since it is found from the foot of the hills to 6,000 feet only. It is also found in the Karennee and Tenasserim hills, and specimens from these localities are usually without the black band dividing the red neck from the grey breast. Four eggs of a dirty white colour were taken below Darjeeling early in July.

THE ARRAKAN HILL-PARTRIDGE.

Arboricola intermedia, Blanford, Fauna, Brit. Ind., Birds, Vol. IV, p 127.

Native names :—*Toung-kha*, Burmese.

This is hardly a distinct species, merely differing from the last in having the throat entirely black instead of being only spotted with that colour. It agrees with the eastern variety of Blyth's Hill-Partridge in having no black band across the chest.

It is found in the Arrakan hills and North Pegu, extending to North Cachar and the Naga hills, and to Eastern Manipur, where it is common. The eggs were taken in Manipur in May; they were pure white, and six in number.

THE WHITE-CHEEKED HILL-PARTRIDGE.

Arboricola atrigularis, Blanford, Fauna, Brit. Ind., Birds, Vol. IV, p. 127.

Native names :—*Peura* in Sylhet; *Duboy Dubore*, Assamese, *Sun-butai*, in Chittagong.

In this species the crown is brown running into grey in front and chestnut behind, the feathers marked with black; a double eyebrow, of grey above black, is present, and the eye is surrounded by a black patch; the cheeks are white running into buff behind; the throat is black, becoming edged below first with white and then with grey, until it merges into the grey breast; the grey flanks have no chestnut borders to the feathers in this bird.

The bill is black, and the legs orange or lobster-red; and the reddish skin of the face shows through the feathers.

The White-cheeked Hill-Partridge extends from Assam south of the Brahmaputra into the Naga, Khasi, and Garo hills, Cachar, Sylhet, Tipperah, and Chittagong. The eggs have been taken in Sylhet on hillocks, at the foot of trees in dark and gloomy places; as many as four occurring in a nest. They are white, and measure rather over an inch in length.

THE RED-BREASTED HILL-PARTRIDGE.

Arboricola mandellii, Blanford, Fauna, Brit. Ind., Birds, Vol. IV, p. 128.

In this very easily recognizable species, the head, neck, and breast are chestnut of various shades; the chin and throat being pale and uniform, separated from the darker breast by a white band bordered below by black; the sides and back of the neck are spotted with black, and the eyebrows are grey, meeting at the back of the head.

Nothing is known about the colour of the bill, feet, etc.; indeed, the species is a rare and little-studied one, which has only been obtained from the low hills of Bhootan and Sikhim; and once from the northern part of the Goalpara district. However, it is so distinct from all the rest that it ought to be easily identified if met with.

THE BROWN-BREASTED HILL-PARTRIDGE.

Arboricola brunneipectus, Blanford, Fauna, Brit. Ind., Birds, Vol. IV, p. 128.

Native names:—Appears to be called *Toung-kha*, like *A. intermedia*.

This is a very distinct form, with the face and throat buff, the latter speckled with black, the breast brownish buff, and flanks greyish buff, with the usual white spots, but no chestnut; the white-spotted feathers are tipped with black.

The bill is black, the eyelids, the skin of the throat, where this shows through the feathers, and the legs, are red, the latter varying much in intensity of colour.

This bird haunts the evergreen forests on the eastern spurs of the Pegu hills, and also inhabits the ranges east of the Sittang river as far as Tavoy, as well as the Ruby Mines District. It has not been often found, and so very little is known about it.

One partridge of this group found in our limits differs from the true Arboricolas in not having the peculiar bridge of bone over the eye; it is also distinguished by possessing a large patch of white downy feathers under the wing, which is ordinarily concealed, even when the wing is lifted, by the feathers of the side.

THE GREEN-LEGGED HILL-PARTRIDGE.

Tropicoperdix chloropus, Blanford, Fauna, Brit. Ind., Birds, Vol. IV, p. 129.

This bird bears a close general resemblance to the other hill-partridges, but the brown of the upper part is more closely mottled with black, and the sides of the body pale rusty with black blotches; the crown is dark brown, the eyebrows also brown, with white streaks, and the face and throat white speckled with blackish. Below this the front and sides of the neck are chestnut with black spots, and then the breast is coloured brown continuously with the back.

The bill is dark-red at the root and greenish at the tip; the skin round the eye purplish; and the legs pale-green.

This partridge, which agrees with the Arboricolas in habits as in appearance, is found, locally, in the evergreen forests all through Tenasserim down to Tavoy, and on the eastern slopes of the Pegu hills. Outside Indian limits it has been obtained in Cochin China.

There remain two very beautiful short-tailed forest partridges, each of which claims a genus of its own.

THE CHESTNUT WOOD-PARTRIDGE.

Caloperdix oculea, Blanford, Fauna, Brit. Ind., Birds, Vol. IV, p. 131.

In this bird the tail, though short, is longer than in the Arboricolas, the toes, and especially the claws, are shorter, and the hinder toe bears a mere rudiment of a claw. The sexes are alike in plumage, but the male has short spurs, which may be one or two on each leg.

The plumage is very characteristic, the general colour being a rich chestnut, barred with black on the flanks, where also white bars may be present; the back is black, pencilled with white above and with chestnut lower down; the wings are brown with black spots, and the tail black.

The bill is black, the eyes dark, and the legs dull-green. The length is just under eleven inches, the wing being nearly six, and the tail nearly three; the shank is nearly two inches long.

This is a forest bird, very little known, and apparently one which Europeans have never even seen in the wild state. It is found in the Malay Peninsula, and extends into the southernmost part of Tenasserim, where it inhabits dense jungle about Bankasoon. A sort of local variety of the species inhabits Sumatra.

I have ventured to call this bird the "Chestnut" Partridge, as "Ferruginous," the epithet usually imposed on it, is a rare and clumsy word.

THE RED-CRESTED OR ROOLOO PARTRIDGE.

Rollulus roulroul, Blanford, Fauna, Brit. Ind., Birds, Vol. IV, p. 111.

This lovely bird very properly occupies a genus all to itself. It has a very short tail and rather long legs, with feet of the ordinary size, and the claw of the hind toe rudimentary or altogether absent. A tuft of long hair-like feathers is found on the forehead in both sexes, which otherwise differ widely, although neither has spurs.

The male, besides the tuft of bristles, has a full and large crest of loose-textured feathers on the head, which is of a dark-red colour. The general body-plumage is steel-blue with a rich satiny gloss, changing in some lights to green; the wings are brown, and there is a white band across the forehead.

The hen has no crest, and is grass-green without gloss, with chestnut wings and slate-coloured head.

In both sexes the eyelids and feet are brilliant red, the male has the base of the bill red in addition; but in the female it is all black. This bird about equals the wood-partridges in size, being about eleven inches long; the wing measures five-and-a-half inches, and the tail two-and-a-half; the shank about one-and-a-quarter. Females are a little smaller than this.

This partridge has a wide range, being found in Borneo, Java, Sumatra, Siam, and the Malay Peninsula, where it extends into the south of Tenasserim near the Pakchan river. It is a forest bird, and gregarious in its habits, being found in small parties of half-a-dozen or more, comprising both males and females. It is described as much more lively in its movements than the Arboricolas, running about like a quail, and not scratching so much as the others The note is a soft, pleasant whistle. Nothing is known about the breeding except that the egg is buff and about an inch-and-a-half long. This beautiful and gentle little partridge would be a most charming aviary bird, but unfortunately it is not much exported, at any rate nowadays, and Mr. W. Rutledge, who imported the first into Calcutta many years ago, tells me that the late ex-King of Oudh was much pleased with them and bought them at a high price, naming them "The King's Fancy." The name "Rooloo" is that by which Mr. Rutledge calls these birds, and I presume it is the native name in some parts of the Far East.

VI.—EXTRACTS, NOTES AND QUERIES.

Indian Forests.

THERE are so many ways of thinking of the Forests of India! To the student of Hinduism the dim umbrageous alleys, lined with the lush growth of a tropical wild-wood, and tangled with great serpentine masses of flowering creepers, is the traditional retreat of the hermit and the sage. As is well known, the third of the four stages of a Brahmin's life on earth consists in becoming a Vana-prastha, an anchorite, or dweller in the forest, who, having discharged his duties as a man of the world, having married and begotten a man child to perform the sacred rites at his funeral, retires into the odorous glades, the quiet seclusion of the solemn woods, to practise, undisturbed by worldly clamour and vain ambitions, the complete round of ceremonial duties. To the Hindu, therefore, the forest has been, from time immemorial, a place of solemn and august associations, a retreat from the petty cares of life, a vast monastery of sylvan seclusion shared with the wild things that live the simple natural life of beings whose instincts are their only guide, and who yield themselves frankly to the promptings of the universal soul which fills men and animals alike. The forest, to a Hindu, is a place full of sacred awe. Nor, again, is it without romantic interest. One of the most familiar, most delightful and most universally popular of Hindu narratives is that which tells of the sojourn of Sita in the forests. Sita was, the old books tell us, the embodiment of purity, tenderness and conjugal affection. She accompanied Rama when he was driven into a woodland exile, much as the modern Forest Officer's wife wanders with her husband in forest glades and dells, safer, indeed, than Sita, whose capture by Ravana, the Demon King of Lanka, was the cause of events as thrilling as the abduction of Helen.

Then there is another view of the forests of India. To the orthodox Hindu a forest is a place of pious retirement, a sanctuary from worldly passions and worldly disappointments. To the un-Hinduised or partly Hinduised aborigine, the gloomy depths of the jungle, the home of prowling tiger and trampling elephant, of the pigs that issue in troops and destroy the ripening crops, and of bears that waylay the incautious traveller with deadly hug, are a place to be avoided by night, not because of these material excitements and dangers, but because of terrors far more tremendous; because of the weird and wandering spirits that flit from tree to tree, not the gay fauns and dryads of Western fancy, not the elves and fairies that haunted Germanic and British woods, but things horrible like the creatures of a child's nightmare, malevolent abortions of the savage mind, creatures utterly hateful and abominable. The savage woodman in India never dreams of wandering in sylvan glades.

Inter Hamadryades jaculatricemque Dianam.

The stately avenues, the woodland vistas leading in cool approaches of lengthening shade, as the evening falls, to the blue heights of the neighbouring hills, resound not only with the cheery din of jungle fowl and the cries of monkeys and the bark of the deer, but with vague sounds of terror, the voices of evil things who love the darksome shade and shun the pleasant clearances, the sunny meadows and rice fields which mark the dwellings of men. To the semi-Hinduised savage, the forest is not a place for cool and secluded meditation. It is the abode of nameless terrors, where every tree has its haunting demon, a headless monster, or, worse still, a creature which has the power of adopting the seductive shape and smile of lovely woman and so of beguiling simple and amorous man to an unimagined doom.

And then there is the forest of the *shikari*, a land of sturdy adventure, where gallant beasts and cunning may be tracked and may, with their trackers, enjoy the fierce pleasures of the chase. It is no mere theory of sportsmen that hunted animals delight in the excitement of the hunt. The whole existence of the wild folk of the woods is an alternation of hunting and being hunted. The domesticated animal toils virtuously and perhaps enjoys his vacuous existence. But the wild beast in the forest lives a life of constant excitement, suspicion, watchfulness. The deer has to run for very life, and, as it pants and strains, enjoys the exercise of the corded and tense muscles which Nature has given it as a means to safety. The Psalmist, no doubt, felt this aspect of the joyousness, the vigour of jungle life when he wrote :—

"Thou makest darkness, and it is night; wherein all the beasts of the forest do creep forth. The young lions roar after their prey, and seek their meat from God."

The denizens of the forest live in a constant state of excitement,—of *shikar*, and man joins joyously in the game. He shares its risks and more than shares its pleasures. And if any say that the risk may mean cruel and untimely death, let us reply that it is not for mortal man, whose term is ever uncertain, to speak of death as untimely; and this is at least certain, that the death of the jungle creatures is not usually painful. Dr. Livingstone has told us that, when he was mauled by a lion, his sensations were not those of mortal pain and terror, but a sudden and not unpleasing insensibility to pain, the result of what the physicians call "shock." It is right enough, then, that the *shikari* should go forth to his woodland task with a sense that he is joining in the oldest recreation known to living beings, older than organised war, the thrill of taking part in the perpetual hunt which fills every nook and corner of the forest, by night and by day, with unending and ever varied excitement.

Again, there is the forest of those who follow the many sylvan trades which belong to the out skirts of settled humanity, those who gather honey, and firewood, and lac, and rubber, and cane, and a hundred other commodities which shall minister to the convenience of more civilised communities. The Memsahib in her bungalow sits on woven cane and never enquires whence the material was procured; nay, the bicyclist whirls through London streets and never thinks of the romantic circumstance that the rubber of his tyres perhaps once grew in an Indian forest. And these and many other conveniences are collected by the humble folk who deal in the commerce of the jungle.

Finally, we have the Forest Officer, the official king of the jungle, the man who cuts firepaths and roads through the tangled wood, and builds himself rest-houses on the margin of its glades, and sits himself down therein to indite Administration Reports which, in outward aspect, are most unromantically like the Administration Reports of mere collectors of revenue, mere suppressors of crime. He may reply to this view of his writing, that he is both; that in his sylvan domain he is Collector and Magistrate. He is part of our great civilised dominion, he is trained at Nancy or Cooper's Hill; he is brimful of scientific forestry and the forest laws of civilised communities. But how much more is he! He is the guardian of the sacred hermitages of the Hindu; he walks unafraid, but intellectually conscious, of the *bhuts* and demons that people the forest shades; he is usually one of the most accomplished of Indian *shikaris*. He works hard among conditions more trying to health and vigour than those which environ most of us exiles in the East. He is modest,—as modest, alas, as his salary, which, for the officers of what is a profitable Department to the State, might well be enhanced without detriment to his usefulness. He is one of the most interesting, one of the most unique results of British rule,—a civilised sylvan deity, one whom we may place beside

Panaque, Silvanumque senem, nymphasque sorores.

Indeed, it is darkly whispered that certain jungly tribes do worship to him, and deck rustic altars with garlands in his honour. He is a son of whom Britain may well be as proud as of any of her sons who do her bidding in far lands.—*Madras Mail.*

Our Specialist-in-Chief on 'Spike.'

[Extracts from the Editorial, *Indian Planting and Gardening*, August 1st, 1903.

"In a recent issue we reviewed the steps taken by the Mysore State with a view to ascertaining the causes of 'spike' disease in Sandal wood trees . . . . . . Mr. Barber seems to have come nearest to the cause of the trouble . . . . . . Dr. Butler has utterly failed to follow up the clues which Mr. Barber has given . . . . . We now come to Mr. Muthunnah's (Conservator of Forests, Mysore) report and conclusions . . . . We cannot agree with this line of logic . . . . . Mr Muthunnah's reasoning is therefore at fault . . . . We believe 'spike' to be a contagious disease . . . . . ."]

And has it then come here to stay,
This dread and fell disease?
The thing that bears the name of 'spike,'
And effectually spikes the guns of life
Of the sweet-scented Sandal tree.
If you wish to know, if you really ask,
What hope there is for this tree so dear,
Referred you are to the lines above
By the Editor, *I. P. & G.*

You specialists are out of it,
Both Madras and India's too,
And the Mysore Forest Conservator
Adds another to the 'ignorant' crew.
For your arguments are foolish,
And you 've all completely failed
To tell us any thing about
'Spike' in the Sandal tree.
Thus, the Editor, *I. P. & G.*

For when the latter shrieked aloud
For specialists right throughout,
In trees and crops, and bugs and soils,
Manures and drains; he meant, of course,
A post above the lot to fill.
Self-appointed Specialist-in-Chief,
He'd let 'em know when they went wrong,
Would the Editor, *I. P. & G.*

So look you to it Scientists,
No matter what your lines,
Chemic, Botanic, Entomologic,
As sure as fate if you don't make
Discoveries quick and marvellous;
If you dare to point out that the 'Origin' took
The Father of Science decades three to compile,
You 'll be brought to book, by hook or by crook,
By the Editor, *I. P. & G.*

THE VAGRANT.

Resistance of the Australian Jarrah Wood to fire.

After a fire which took place some months ago in the Victoria Docks the Sub-Committee of the British Fire Prevention Committee reported as follows:—

"At the north-eastern end of the yard, and about 36 feet away from the shed, was a pile of Jarrah wood some 30 to 40 feet high, and having a frontage to the shed of about 36 feet, and to the basin of about 100 feet. Projecting in front of this pile of Jarrah wood for about 10 feet, and abutting upon it, on the shed and basin sides, were piles of deal about three quarter the height of the Jarrah stack, and these were very largely consumed by the fire, the flames from which played on to the pile of Jarrah, generating considerable heat; but though the Jarrah bore the brunt of the fire, as what wind there was blew in this direction, comparatively little damage was done to this pile and this was confined to the north and west faces, the fire failing to penetrate far into the interior. Your Sub-committee are of opinion that, but for the resistance offered to the fire by this stack of Jarrah the conflagration would have assumed much larger proportions, as in the rear and on the south side were large quantities of deals, and, had they ignited, the task of the fire brigades would have been far larger and more difficult." The report further stated that "the wooden sides of the railway trucks between these piles (deal) and the shed, were entirely consumed, only the ironwork and the decking remaining, leaving the Jarrah wood paving blocks (which were in the trucks) intact, but for charring on the face of the outside blocks directly exposed to the fire."

The Street, commenting on this fire in its issues of October and November, 1902, said: "There can be little doubt that if the timber in the mill and in the yard had consisted wholly of Australian hardwood, instead of deals and hardwood in juxtaposition, the fire would not have made much headway before being mastered by the brigades and the dock companies' floating engines. After all, an actual fire is the best fire test, even though an expensive one for the moment."

Our enterprising cousins on the other side of the Atlantic would probably take a hint of this kind and send over a few loads of a new timber they wished to place on the market and see to it that it got 'placed.'

Forestry at Ci'cester.

At a meeting of the governing body of the Royal Agricultural College, Cirencester, held on the 4th instant, the report of the Board of Agriculture Committee on British Forestry, recently presented to Parliament, was taken into consideration, and it was unanimously decided, in consequence of the recommendation of that report, to remodel and largely develop the teaching of forestry at the College in connection with the estate management branch of the curriculum In furtherance of this object it was unanimously resolved to create a new Chair, to be entitled the Chair of Estate Management and Forestry, and to appoint thereto a special Professor or Lecturer who shall be required to devote all his time to the duties of the Chair, and who shall have had good experience not only of the management of woods in this country, but also of the continental system of sylviculture followed in the State and communal forests of France and Germany *This will be the first attempt in England to deal with this important question on these lines*; and inasmuch as a large proportion of future landowners and managers who attend regular courses of College instruction pass through Cirencester, the results will be watched with much interest — *The North British Agriculturist.*

As we go to press we have received the news that Dr Schlich F R S has been appointed Honorary Professor in the Forestry Chair recently created at this college We feel sure that the Service in India will join in according their heartiest congratulations to Dr Schlich on being thus the first to fill a Forestry Chair in England whilst they will also be extended to the Governing Body of the Royal Agricultural College in appreciation of the enlightened manner in which they are dealing with a much neglected question Hon Ed

Afforestation in Ireland

Mr Thomas W. Webber, late of the Indian Forest Department, writes from Athy advocating that "the present opportunity, when ownership of land in Ireland is about being transferred by legislation, should not be lost for reserving large areas of lands, now practically waste, as a future property of the nation, and planting them with timber If peasant ownership becomes universal, every tree in Ireland will disappear. Other nations have tried the experiment of nationalising their forests with the greatest success . In Germany the forests are one acre in every four, all under State management and paying handsomely. In this country there exists but one in 25, of mixed plantations, which are mismanaged and carry but a quarter crop, and which, under present management, are a lamentable failure The advisability of establishing a British and Irish Forest Department and re-planting the forests as a national property is thus pressed upon thinking people, after the plan adopted not only in Germany and Austria, but in Republican countries like France and the United States. The amount of waste land, as given by experts, is about 20 million acres for Great Britain and six million for Ireland, of which about half is ideal forest land. All lovers of their country should press on Mr. Wyndham, who is a large-minded statesman, that the opportunity should not be lost, otherwise Ireland, now being stripped of trees, will become a bare desert. The present time is opportune, for among other reasons, that the scarcity of available timber in the world is becoming intense."—*The Standard.*

VII.—TIMBER AND PRODUCE TRADE.

Churchill and Sim's Wood Circular.

London, *3rd July* 1903.

East Indian Teak.—The deliveries in June were 800 loads as compared with 763 loads in June last year, and for the first half of 1903 they have been 5,587 loads against 6,336 loads in the corresponding half of 1902 There is no change to report in prices either here or for arrival, and business continues to be hampered by a paucity of supplies. The stock in London still dwindles and contains very little first class Burmese or Siamese wood.

Rosewood—East India.—Sizeable, prime logs are in good demand but small and poor wood is not readily sold.

Satinwood—East India.—Stocks are rather heavy, and demand being very quiet, sales are small.

Ebony—East India —Sound wood, free from knots and of good sizes, would realise fair prices.

PRICE CURRENT.

Indian teak, logs, per load ...	£10 5*s*. to £18 10*s*.
Rosewood, per ton	£8 to £11.
Satinwood, per s.ft.	6*d*. to 18*d*.
Ebony, per ton	£8 to £12.

Denny, Mott and Dickson, Limited.

Wood Market Report.

London, 1*st July* 1903.

Teak.—The landings in the docks in London during June consisted of 432 loads of logs and 254 loads of planks and scantlings, or a total of 686 loads, as against 300 loads for the corresponding month of last year. The deliveries into consumption were 572 loads of logs and 274 loads of planks and scantlings—together 846 loads, as against 727 loads in June 1902.

The dock stocks at date analyse as follows:—

4,982	loads of	logs,	as against	7 206	loads	at the same date	last year
2,988	,,	planks,	,,	3,464	,,	,,	,,
—	,,	blocks,	,,	—	,,	,,	,,
Total 7,970	loads		,,	10,670	loads ,,	,,	,,

The first six months of the year have consistently developed a gradual decrease in landed stocks, both in the United Kingdom and on the Continent. Prices have necessarily steadily advanced until they are at a figure sufficiently high to restrict business, although still not prohibitive to the main industries which use teak, such as Naval Shipbuilding and Rolling-Stock Construction. The high price for planks and conversions, however, has already seriously affected the domestic.

Business during the first half of the year has been restricted in volume owing to a generally higher import cost of wood than the industrial demand for consumption seemed to justify. The cheapness of freight has been in favour of the timber trade, but has not served to counterbalance the high f o b. prices demanded by shippers, whose hands in many of the narrower markets have been absolutely upheld by the fact of reduced forest outget, and other sound causes pointed out by us in our wood report of last January. Whilst, however, the trend in natural products is necessarily towards a higher level of value as population increases, shippers are unwise to try and force events at a time when this country is going through some reaction in trade, and its working margin of ready money has been reduced, if only temporarily, by the cost not only of the late war but also by the increasing national expenditure on Naval and Military strength as well as Educational and other social needs. That these demands have very appreciably affected the financial resources of the ordinary trader and so served to check trade briskness is a not unimportant factor in the purview of the last six months' trading.

Market Rates for Products.

Tropical Agriculturist, 1st July 1903.

Cardamoms		per	lb.	1s 6d. to 1s. 9d.
Croton seeds		„	cwt.	15s. to 22s. 6d.
Cutch		„	„	20s. to 27s. 6d.
Gum Arabic		„	„	15s. to 20s.
Do. Kino		„	lb.	3d. to 4½d.
India-rubber,	Assam	„	„	2s. to 3s. 2d.
Do.	Burma	„	„	2s. to 3s. 2d.
Myrabolams,	Madras	„	cwt.	5s. 6d. Nom.
Do.	Bombay	„	„	4s. to 7s. 6d.
Do.	Jubbulpore	„	„	4s. to 5s. 6d.
Do.	Bengal	„	„	3s. 6d. to 5s. Nom.
Nux Vomica,	Bombay	„	„	5s. 6d. to 6s.
Do.	Madras	„	„	7s. to 10s.
Oil. Lemon-grass		„	lb.	6½d.
Orchella weed		„	cwt.	10s. to 12s 6d.
Sandalwood, logs		„	ton	£15 to £30.
Do.	chips	„	„	£4 to £8.
Seedlac		„	cwt.	115s. to 129s.
Tamarinds, Bengal		„	„	8s. to 10s.
Do.	Madras	„	„	4s. 6d. to 6s.

THE

INDIAN FORESTER.

Vol. XXIX.] October. 1903. [No. 10.

Notes on Indian Trees. I - Note on Kongu (Hopea) in the Tinnevelly District.

BY P. M. LUSHINGTON.

1. *Different kinds.*—The native woodcutter distinguishes two kinds of kongu, the Vellai kongu and the Karin kongu. Of these the former is considered by far the more valuable. The distinction between them is said to be that the Vellai kongu has a smoother and lighter bark and smaller leaves. A further kongu known as Nir kongu is known in the Srivilliputtur Taluk and the wood is considered of little value.

2. *Botanical identification.*—Beddome considers that the Vellai kongu of Tinnevelly District is the *Hopea wightiana* closely allied to *Hopea parviflora.* It seems possible that both these species occur. Beddome has identified the Karin kongu as *Balanocarpus utilis,* but also states that the *Balanocarpus erosa* occurs in the Tinnevelly mountains. The chief difference between these two species appears to be the fruit. I carefully examined some of the trees and they all appear to me to have the fruit of *Balanocarpus erosa* rather than *Balanocarpus utilis.* The name Karin kongu probably covers both species. Mr C. A. Barber, who had no opportunity of examining the fruit, identified the flower as *Hopea longifolia,* which Beddome says it greatly resembles. The specimen of Nir kongu sent me was undoubtedly the *Filicium decipiens,* a tree of no particular value.

3. *Forest identification.*—To the Forester there is no necessity to go into nice botanical distinctions, and we may well follow the native classification and consider the two kinds, white kongu (including the *Hopea parviflora* and *wightiana*) and black kongu (including the *Balanocarpus utilis* and *erosa*).

4. *Difference between White and Black kongu.*—Undoubtedly the chief distinction between the two is the leaf. The white kongu has a small, rather light green leaf, with thick foliage,

somewhat resembling the beech. The black kongu has, on the other hand, a dark green, hard, big leaf, and looks very like a mango. As regards measurement, I took two fair samples of well-grown leaves which gave the following measurements:—

White kongu 4″ × 1$\frac{1}{16}$″.
Black kongu 6″ × 2″.

Both trees when young have a smooth bark, which, however, is undoubtedly much darker in the black kongu. The white kongu is generally a light brown and the black kongu distinctly dark brown. Both are greyish in places. As the tree grows older the white kongu continues lighter in colour and less rugged. The most noticeable point of distinction however seems to be the tallow-like gum which exudes from the black kongu, which is either entirely absent or very rare in the white kongu. A further difference is the fruit. This is most marked and constitutes a great difference in the sylviculture of the two trees. The white kongu is a true *dipterocarp* and has a light seed about the size of a pepper corn, with two large wings; whilst the black kongu is a heavy nut-like fruit, in a cup formed by the calyx, and is devoid of wings. It is larger and heavier in the *Balanocarpus erosa* than in *Balanocarpus utilis.*

The black kongu is always to be seen in flower at the end of April, May and the beginning of June. I have never seen the white kongu flowering, though I have looked for it at the same season; also in February and March. The distinction which the woodcutters make in the wood does not appear to be marked. Both woods show an outer wood white to yellow and heartwood light to a dark yellowish brown. I think the preference given by the woodcutter to the white kongu is due rather to the fact that more of the white kongu trees are found to be sound and, after a careful examination, I have come to the conclusion that the age of maturity is lower in the black than in the white kongu.

5. *The uses of kongu.*—Kongu is by far the most valuable wood in the Tinnevelly District, and is worth four times any other sholah or semi-sholah wood.

It is largely used for posts, beams, rafters and planks. The posts for the wire-fencing in the Palamcottah compound are white kongu. They were put up in 1902. The rafters were very largely used in the railway buildings. Beams were used for the Jubilee Bridge in 1902. Planks have been used for some years in the Tambraparni Bridge near Papanasam and have lasted well. Sleepers were cut in 1903 and sent to the South Indian Railway for trial and are of good quality.

6. *Locality, elevation, soil, etc.*—The lowest elevation at which I have found kongu is just below 1,000 feet near the

Kudivarai depôt; and the highest is on the banks of the Pi Ar, near the Sengalteri bungalow, an elevation of 2,800 feet. The lowest were the black variety and the highest the white: but between these two elevations both kinds are found very commonly growing together. It is essentially a semi-sholah tree and seems to prefer a rich soil, but I have found well-grown saplings growing out of the crevices of slab rock on the banks of the Servi Ar and Kudivarai Ar, and both species seem able to support themselves in such situations. One fact in connection with kongu has particularly struck me—it is found mainly on the hillsides bordering on large rivers, and even when a little distance away from the river it is invariably on the bank of a ravine. The close proximity of running water appears to be essential to its growth.

7. *Congeners.*—I have in several places seen kongu growing with, or close to, Vengai in the moister parts of the higher deciduous forest. More frequently it grows with *Pterospermums, Vitex altissima, Diospyros* (several species), and *Filicium decipiens.* Frequently there are patches of nearly pure kongu forest, and it is a tree which is nearly always found in large patches.

8. *Size and exploitability.*—The tree appears to grow to an enormous size and to great age. I have seen a considerable number of trees of over 15 feet girth, and one or two over 20 feet, with a bole of 60 to 80 feet.

One tree is said to have produced over 200 rafters of nearly 2 cubic feet each. I am inclined to think that many trees have been left until far beyond the age of maturity, as nearly all the large trees now standing are hollow and very unsound. I have been unable to obtain data as to the rate of growth, but as a rough guess I should estimate that it takes from 100 to 150 years to obtain a girth of 8 feet, which I consider would be the best size at which to fell the trees.

9. *Enumeration and Estimates as to the number of trees.*—I have had no time to make regular enumerations, but, owing to a note by Mr. A. B. Jackson, who considered that the supply of trees was likely to fail, I have made some careful inspections with a view to ascertain if the tree is decreasing. As a result I am convinced that the tree is largely increasing in numbers though the number of mature trees fit for felling is small.

The area chiefly subjected to test was the west bank of the Kudivarai Ar from its junction with the Servi Ar.

On the bank of the river I found three good sound trees of fair size and some fine poles of 1½ to 3 feet girth, as well as a good number of seedlings. From there I passed up the hill through a small patch of semi-sholah with a few kongu saplings, then through grass and deciduous forest (probably an old Kani clearing). and then entered into a fair sample of kongu forest Here I took an enumeration with the following result :—

Sample area —20 yards × 100 yards (under ½ acre

	Over 6′ girth.	3′—6′	Saplings up to 3′
Karin kongu...	1	2	31
Vellai kongu...	*Nil*	1	3

I then met with more grass land for a small distance, and in the next bit took another sample area.

Sample area.—20 yards × 130 yards (just over ½ acre).

	Over 6′	3′—6′	Saplings up to 3′
Karin kongu...	3	7	48
Vellai kongu...	3	5	1

Just outside this area I found the whole hillside down to the river covered with a mass of kongu saplings (some thousands in number) up to 1 foot girth with 7 mediums and 7 mature trees. All were Karin kongu.

Again I passed through a small piece of grass land and once more entered kongu forest. Here in a length of about 200 yards I met with one large Vellai kongu tree with a mass of seedlings all round it and ten beautiful mediums running up to nearly 6 feet girth. The rest of the forest is similar up to the turn of the Kudivarai Ar. So that the whole of this forest is well stocked. The belt of kongu forest I estimate to be about a quarter of a mile wide from the river bank.

I am informed that higher up the Kudivarai Ar there is a thin belt of kongu forest on either side of the river for a distance of two miles. Crossing the river I studied the forest on the north bank. Here I found some felled trees, and in quite a small area 15 to 20 mature black kongu trees (some marked for felling), the great majority of which were hollow. Here again there are patches of almost pure black kongu forest in which the large number of medium trees was particularly noticeable.

On the east side of the river I found, just at the turn, an absence of big trees but a good lot of mediums, chiefly white kongu, with a good many saplings.

All along the east side, from the turn to the Brandyodai, near the Kudivarai depôt, the forest is well stocked, especially with black kongu.

My next examination was along the south banks of the Servi Ar from its junction with the Kudivarai Ar up to the waterfall, a distance of about three miles. Here I found a considerable number of large white kongu trees (some very large), a few of which seemed to be sound In places the saplings were exceedingly numerous, and though there were a few scattered mediums, yet that class was by no means well represented. In places some splendid *Vitex altissima* and a few *Diospyros ebenum* were found growing with the kongu. There is a peculiar absence of black kongu. I am told that the growth on the north bank of the river is very similar The belt of kongu is very narrow and hardly more than a furlong broad, though the trees in places grow up the sides of the ravines more into the interior of the forest. It was from this locality that the large tree noted in paragraph 8 was said to be felled.

In this locality exploitation is difficult.

In addition to these places, I have seen very fair regeneration, and, in places, masses of saplings in the Tirukurangudi working circle, the banks of the Peyar and Tambraparni near Kannikatti, and the banks of the Kusanguli Ar (Nanguneri Taluk). In all these places there are very few mature trees and a decided absence of mediums. At Vettilayuthumedu and Ondipulaval there are a large number of mature trees (30 reported to be sound) and Forester Srinivasa Row reports that there are numerous saplings.

As a result of my inspections I am satisfied that the area of kongu forest is limited, but that wherever the tree exists there is no likelihood of its disappearance. On the contrary, though considerable time must elapse before timber in large quantity is obtainable, the kongu tree appears to be gradually spreading over a larger area, whilst in all the principal kongu forests the natural regeneration is excellent In most instances the black variety is predominant

10. *Distribution.*—The kongu appears to be confined to the Nanguneri and Ambasamudram ranges. In those ranges it is only, as far as I have been able to ascertain, to be found in the following places :—

(1) NANGUNERI TALUK.

(*a*) *Tirukurangudi working circle.*—The tree is confined to a small area along the valley of the Kombi Ar and running up some of the ravines falling into it. In coupe XI-A 40 saplings, mostly under 3 feet girth, have been marked as standards. I saw one particularly fine young tree of about 3 feet girth with a bole of 50 feet. There is one large sized tree in the same coupe which should be retained as a seed bearer. I am informed that there are also a few trees in coupe XI-B, which should all be marked as standards.

In coupe X there is one very large tree of over 20 feet girth. This has given rise to a large number of saplings up to 2 feet girth.

(*b*) *Sengalteri.*—The kongu area is small and the tree is only found on the banks of the Pi Ar. I saw one big tree and a good number of small ones in this locality. Further investigation is needed.

(*c*) *Kusanguli Ar*.—On the side of this river, close to the Singampatti boundary, I saw a considerable number of young trees. I am informed that higher up this valley, on one of the hills overlooking the river, there is a fine growth, but for the most part young trees.

In this taluk all the trees are of the white variety.

(2)—AMBASAMUDRAM TALUK.

(*a*) *Kannikatti.*—The kongu area extends from the valley of the Ullar, up the Tambraparni valley, and as far as Kannikatti south of the road. Near the Ullar there are some large trees of black kongu and there is a small plantation near the Ullar bungalow which is too dense and requires gradual opening out. On the slopes near Kannikatti most of the marketable trees have been worked out. The few large trees left must be retained as seed bearers. There is, in patches, a fine growth of young saplings. Here the trees are of the white variety. There is also a good sprinkling of trees along the valley of the Peyar with a few big trees.

The area under kongu in this neighbourhood is pretty extensive, but the growth is very scattered and the tree occurs only in patches.

(*b*) *Kodamadi.*—On the western side of the Servi Ar at the foot of Oosipothai there is a fair growth of black kongu. There are a few big trees and some fine young poles of 1½′ to 3′ girth and a large number of saplings. The kongu belt is a narrow one.

On the banks of the Servi Ar from the Oosipothai to the waterfall there are a good number of big white kongu trees, a few half grown trees and a large number of seedlings. The big trees are for the most part hollow.

(*c*) *Kudivarai.*—This area has been fully described in paragraph 9. It is decidedly the best stocked area in the district and covers about 600 acres which can be easily worked by an extension of the present cart road.

(*d*) *Vetilayuthu Medu and Ondipulaval.*—These two areas are at the two main sources of the Thalayuthu Odai. The actual area covered by kongu is not large, but I am informed that they are well stocked and contain a large number of mature trees, many of which are hollow. A large number of trees were felled in 1898, out of which there are reported to be 77 which contain timber fit to be utilized. The trees are reported to be mostly black kongu, and there are a number of saplings.

This valley could be easily opened up and other trees made available for felling, but, except for the removal of felled trees, no work should be undertaken till the opening up of the valley has enabled further investigation to be made.

(*e*) *Sivasylam.*—In the old working circle coupe I, over 170 trees were marked as standards. The growth is confined to a small area along the valley of the Kal Ar and its main affluents. The area is very inaccessible at present and requires opening out

(*f*) *Kariar.*—On both sides of the river near Sembagatota there are some trees.

11. *The sylviculture of kongu.*—The difference in the leaf and the nature of the seed must entail considerable differences in the sylviculture of the two species. The black kongu, with its large and heavier leaf, is more of a shade lover than the white variety. The difference in the seed is evidently due to the same cause. The lightness of the white kongu seed, with its attached wings, causes it to be spread over a much larger distance and to settle in places where there is plenty of light. The heavy seed of the black kongu falls directly to the ground, and, under the heavy shade of the parent tree, hundreds of young seedlings readily spring up. A mixed forest of the two kinds of kongu would be similar to the mixture of oak and beech in Europe, and in order to favour white kongu, there must be larger clearance overhead. There should be no difficulty therefore in raising pure forests of the two species, taking precautions that the white variety is not suppressed. As the white variety springs up more quickly when a clearance is made, it should get a start of the black which will be favourable to both species.

As a result it appears that a treatment of regular high forest with thinnings should be particularly applicable, and the more the two trees can be induced to grow in unison the better should be the results. This seems to be the ideal to be aimed at, but will take many years to carry out.

Hitherto the sylvicultural treatment of the two trees has not been much considered. Wherever a marketable tree has been found it has been felled, and yet the reproduction is found fairly satisfactory, because it has been useless to fell the hollow trees which for some years must have proved such useful seed bearers.

In the Tirukurangudi and Sivasylam working circles the trees left as standards, being of the white variety, should turn out useful timber trees, and the opening out of the forest would certainly have tended to increase the number of seedlings had the standards been capable of giving mature seed. The effect of this treatment should be carefully watched. In coupe X of Tirukurangudi a different treatment has been applied—an improvement felling has been made. As there is no demand for inferior trees it has been found necessary to let in light and air by ringing all the trees except those of valuable species. Owing to the recuperative powers of the sholah trees, the dying of the trees is considerably delayed, and the whole of the ringed trees will, in my opinion, not die for at least three years. This gradual letting in of the light should be highly favourable to the growth of kongu, and it is an advanced form of this operation that I intend to apply to the larger kongu forests Wherever the natural regeneration is sufficiently advanced, it will only be necessary to ring every tree that is not kongu and to cut any mature kongu tree that is not hollow Where the kongu is hollow it will be useful as a seed bearer and will do less damage by dying off naturally than by being felled. Where large trees exist but no regeneration, it will be necessary, in the case of white kongu, to ring every tree within a radius of three chains to the seed bearer; in the case of black kongu, a distance of one chain should suffice. Where there is no kongu it will be better to retain the forest in its present state, removing all marketable trees of over 6 feet girth. Of course any ringed tree which has a marketable value may be removed. In the case of kongu itself no tree should be considered mature until over 8 feet girth, unless it shows distinct signs of decay.

This system of improvement felling with a view to convert the forest into pure kongu, to be subsequently worked on the high forest system, can only be applied at present to Kudivarai. In Kodamadi and Kannikatti it will be better to allow the areas to fall within the ordinary timber working area, taking out as much as possible of the other timber which is found in conjunction with kongu and ringing all valueless trees in the same group.

In Vettilayuthumedu nothing can be done at present except the removal of timber already cut and the opening out of the valley by a road (which can easily be constructed) and the building of a small rest-house to enable a proper investigation of these forests. When this has been done, it will probably be advisable to apply the Kudivarai system to this area also.

At Sivasylam the patch of kongu is too small and inaccessible for working at present, and rest will be prescribed to enable the trees in existence to mature. At Kariar the greater part of the trees fall within the area under dispute by the Kattalamalai hukdar, so it is inadvisable to make any prescriptions at the present time.

12. *Conclusion.*—Considering how little attention has been given to the sylviculture of this valuable tree, the kongu forests are, in my opinion, in a better state than would naturally be expected. Considerable damage has however been done, especially in 1898, 1899, by reckless fellings entrusted to native subordinates and contractors. I consider that the forest is of such value, that in the kongu area all the marking and ringing operations should be under the direct supervision of the District Forest Officer, or if that is found impossible, under a really intelligent and well-trained Ranger, and not left to foresters utterly ignorant of all sylvicultural principles, as has been hitherto the case.

The Training of Forest Officers.

THE appointment of a Committee by the Secretary of State for India to report on the desirability of continuing Cooper's Hill as a College for training Engineers and Foresters for the Indian service raises the question of what should be done if the Forest Service is deprived of its present Alma Mater. As I have been closely connected with the Indian Forest Service since its first formation, and have for many years been intimately associated with the education of Forest Officers, first at Nancy and then as a visitor of Cooper's Hill College, I venture at such a critical time to offer a few remarks on the present system of training and on future requirements, hoping that some of my younger fellow workers may be induced to offer their comments and observations on what I may here adduce.

It may be safely said that no branch of the Indian Administration, not even the Civil Service itself, needs more urgently the services of educated gentlemen than does the Forest Service, controlling as it does 206,000 square miles of forest lands, or more than one-fifth of the area of our Indian Empire, and administering a revenue of nearly two crores of rupees, with a staff of upwards of 15,000 men to do its work.

Sir Dietrich Brandis, to whose self-sacrificing zeal and wise foresight the Indian Forest Service owes so much, from the very first clearly recognised the importance of employing specially trained men as Forest Officers, and in 1866 instituted the system of training young Englishmen in the Forest schools of France and Germany as officers for the Indian Forest Service. In 1869 the first batch of seven of these men were sent out to India. Under this system the English pupils were trained with and attended the same lectures as the other pupils in the schools to which they were attached, and thus benefited by the instruction of the very best Professors of Forestry on the Continent, and further had the unrivalled advantage of continually, during their training, seeing the practical working of large forest areas, administered in the best possible manner. This system was continued till 1886, and was highly successful. The Forest Officers who were trained under it and sent out to India, proved themselves to be excellent practical Foresters as well as thorough gentlemen and men of the world; and I believe I am right in saying that there is not a single instance of one of them having been dismissed the Service on any ground whatsoever. It is specially to be remarked that this system was not abolished on account either of the stamp of men sent out to India, or of their training in Europe, but on grounds of a totally different nature. Since 1887 inclusive, the Forest Officers who have gone out to India have been trained at Cooper's Hill, and it is due to Dr. Schlich and his fellow workers there that the same high standard of efficiency as had been reached by our pupils in the Continental Forest schools was maintained there; the difficulty as to the want of regularly organised forests in Great Britain for the practical instruction of the pupils having been met by sending them for the third year of the training to reside in the forests with Forest Officers in Germany.

It is to be regretted then that when we have a system of education that gives satisfactory results, we should, if Cooper's Hill is abolished, be brought face to face with another change, and have to devise another new scheme for educating our Forest Officers; but as the retention or otherwise of Cooper's Hill will no doubt chiefly depend on what is determined upon for meeting the requirements of the P. W. D. in respect to Engineers, it is well to consider carefully what courses are open to us to meet the necessities of the Forest Department in case the change is forced upon us, and in this contingency three courses seem to be open:—

1st. To revert to the system of Continental training.

2nd. To substitute one of the Universities for Cooper's Hill, and to send the pupils for their instruction in practical work to pass a third year, as at present, in the forests of Germany or France.

3rd. To utilise the Dehra Dun Forest School to train the upper as well as the subordinate staff of Forest Officers.

I will deal with the last proposal first as, though plausible, it seems to me fraught with danger to the efficiency of the Forest Service. But as it has been put forward by responsible people, the many disadvantages which would attend it should be clearly set out.

First on general educational grounds, for to send the pupils to the School at Dehra Dun for training, instead of giving them a European education, would be equivalent to sending boys to Bishop Cotton's School in the hills in India instead of to a Public School at Home. In short, they would lose the broadening of mind and general development of character which are indispensable to those who have to administer our Indian Empire.

Secondly, it would entirely fail in what we most want namely, to imbue the minds of our young officers with the principles on which large areas of forest can be managed on regular economic principles, as illustrated in the great forests of the Continent of Europe.

Thirdly, it would be unadvisable to train the upper and lower staff of Forest Officers together, as they have different functions to perform and require a totally different standard of education. Moreover, the educational Staff for such a school would be very expensive to maintain in India, and would draw too heavily on the resources of an already overworked and undermanned Department. It cannot be too strongly insisted upon in educating the upper staff of the Forest Service that broad principles, which are of universal application, are far more essential than local technicalities, which an educated mind speedily acquires on the spot. It is earnestly to be trusted that any scheme of training Forest Officers of the Imperial branch in India will never for a moment be entertained.

I will next consider the course of reverting to the old system of Continental training. If Cooper's Hill is to be abolished I frankly confess that, failing any better plan, I should be entirely satisfied to revert to the old system. It has supplied the Forest Service in the past with a body of able men, who have proved themselves in every way fitted to carry on the work of large forests—men who as a body have worked in sympathy with the native population of the forests, while they have safeguarded the interests of the State,—and in times of famine have rendered valuable services in alleviating the distress of the starving people. I do not know where better all round men can be found than those who now administer the Forest Department in its upper branches, all of whom were trained either in Germany or France. I am well aware however that any such plan would be strongly opposed by many persons who consider that men who are to hold important positions in India or our colonies should be educated at Home, and who think, wrongly, in my opinion, that a Continental training may deteriorate their character. It would also be opposed by a numerous and growing class of people, both in England and in Scotland, who are really interested in forestry, and who fear that if our Indian Forest pupils are trained abroad, all hope of establishing a Home Forest School would disappear, and with it the re-afforestation of the waste lands in our own Islands With this feeling I fully sympathise, but I am only treating here with what I think best for the Indian Forest Service.

Coming then to the other proposals, *i.e.*, of attaching our Forest pupils to one of the Universities for two years, supplemented by one year's practical work in the Forests of Germany and France, I have hardly sufficient knowledge myself to say which University would be best suited for this purpose, but as it may be assumed that half the men who go up to Oxford or Cambridge do so as much for athletics as for serious study, my inclination would be to send them to Edinburgh, where the bulk of the students are hard and conscientious workers, and where there is already a class for Forest students. In any case the teaching of forestry would have to be carried out, as at Cooper's Hill, under special Professors, who should have disciplinary control over all their work, and under whose direction the pupils should attend such other lectures in the University as might be deemed advisable. It may be urged as an objection that the time allowed would hardly admit of a degree being obtained at any University, but this must never be extended at the expense of the Continental portion of their work. In any case, either at Oxford, Cambridge, or Edinburgh, the bulk of the pupils would probably be unattached, and this would necessitate careful supervision by their own Professors to keep them up to their work. No doubt some social advantages and prestige are attached to a University education, and I do not wish in any way to underrate these.

On the whole if Cooper's Hill is abolished, and the Continental training cannot be reverted to, I think that the University course, supplemented by at least a year's practical work in the forests of Germany or France will furnish the Indian Forest Service with a body of men worthy to carry on the excellent work of those who have gone before them. I hope, however, that Cooper's Hill may still be allowed to continue its useful existence and to supply the Indian Forest Service with the high class of trained men that it has done in the past.

GEORGE F. PEARSON, *Colonel.*
Formerly Offg. Inspector-General of Forests
in India and in charge of pupils at Nancy.

What should the Madras Forests Yield.

IN 1882 Sir Dietrich Brandis estimated that the forest revenue of the Madras Presidency should amount to Rs.9,00,000, and based his proposals for establishment and other expenditure on this figure, so that while the forests yielded no net revenue, neither were they a charge on Government. Within twenty years the forest revenue has risen to Rs. 25,00,000 and the expenditure to Rs. 17,50,000; that is to say that the revenue has nearly trebled, while the expenditure has not quite doubled, and the Government now obtains a net revenue of Rs. 7,50,000 from a department which was not remunerative twenty years ago.

Will the forest revenue continue to expand in future, if so at what rate; and what should be the eventual annual yield in hard cash of the State forests?

The area of the forests under the direct control of the Department, *i.e.*, reserved forests, reserved lands and topes, amounted to 19,657 square miles on the 30th June 1902, and as the work of selection of areas for reservation is approaching completion, no great increase in area is probable, and the ultimate forest area may be put down as 20,000 square miles.

The unreserved and unoccupied area exceeds 51,000 square miles, but this includes all land not shown as occupied in the village registers; river beds, tank beds, roads, village-sites, lands liable to spasmodic cultivation at intervals of a few years, swamps, marshes, sand dunes, etc., as well as unreserved forest areas are clubbed together under this new head in the annual returns, and it is impossible to say what is the actual area of unreserved forest over which the Department exercises a limited control, and from which it derives revenue; equally impossible is it to discover how much forest revenue is derived from unreserved lands, though it undoubtedly amounts to a large sum in several districts in which the produce of fruit trees, the bark of the tangedu (*Cassia auriculata*) and other minor products are sold annually by auction, in addition to which permits are issued for certain classes of trees and the value of all trees on lands taken up for cultivation helps to swell the miscellaneous forest revenue not derived from the areas under the special charge of the Department. No calculations based on the gross forest revenue could be applied to the actual reserved area, and a statement that the yield of the State forests $= \frac{250,000}{20,000} =$ Rs. 125 per square mile would be far from correct. We must therefore turn to the forests themselves and endeavour to show what would be the value of their yield if they were properly protected and markets could be found for their annual yield. To arrive at anything like a correct figure, the forests would have to be divided into classes, the annual yield in material of each class being treated separately. The bare and burnt hills of parts of Cuddapah and Kurnool, the sal forests of Ganjam, the casuarina plantations of the East Coast, the sandal wood areas of Coimbatore and the dense forests of the heavily watered Western Ghats present such absolutely different types that any attempt to generalise must give incorrect results. Sir Dietrich Brandis, after inspecting many of the forests of the Presidency, estimated the growth in the poorest of the poor forests of Cuddapah at one-fifth ton per acre per annum; the Nellore casuarina plantations yield from 40 to 60 tons at ten years of age, or, say, four tons per acre per annum; the luxuriant growth of the Western Ghats must average quite one ton, and the great value of sandal wood places it in a class by itself, while bamboos with their rapid reproduction raise the average yield of many otherwise poor forests; but, on the other hand, petty thefts, organised thefts and fires sadly diminish the annual growth which Government can hope to sell or to store up for the improvement of its forest estate. This is concerned with the question of better protection, which will be dealt with later.

A very rough division of the State forests gives one-third unproductive, one-third productive and one-third remunerative; the actual unproductive area is probably less than one-third, but in generalising it is safer to under- than to over-estimate the sources of income. The productive area is principally deciduous forest yielding fuel and small timber, and the remunerative area includes casuarina plantations, sandal wood areas and high timber forests.

Under unproductive forests are included all the poorest forests, in which the annual growth is estimated at less than one-fourth ton per acre per annum; such areas are mostly very badly stocked and are burnt over annually; to improve them and convert them into productive forests would necessitate a long period of rigorous closure and fire-protection, aided in many instances by artificial reproduction. But absolute closure is impossible on account of the demand for pasturage for the cattle of neighbouring villages; this with the sale of thatching grass and possibly a small income from the sale of fuel is the only revenue which can be expected until these areas are re-afforested, and the average annual revenue may be put down at six pies per acre or Rs. 1,33,000 altogether.

In the productive forests the annual growth is not less than one-fourth ton per acre per annum, and taking this minimum as an average in order to err on the safe side, and further assuming that the gross value of the wood does not exceed Rs. 2 per ton (a very moderate estimate), the annual yield would amount to eight annas per acre or Rs. 21,33,000, to which must be added grazing at 6 pies per acre or Rs 1,33,000, and minor produce at, say, 1 pie per acre or Rs. 22,000; in all Rs. 22,88,000.

In the remunerative forests the produce varies considerably; teak and rosewood are worth up to Rs. 160 per ton (gross), sandal wood realises as much as Rs. 450 to Rs. 500 per ton; the value of casuarina is much lower, but the yield per acre is considerable, and in none of the forests of this class would the gross annual yield be less than Rs. 5 per acre if all the timber could be brought to market; at present this is impossible owing to want of roads, timber slides, tramways, etc., but as this estimate is based on the assumption that in due course all such necessaries will exist, Rs. 5 per acre is taken as the average yield; this gives the rather astonishing figure of Rs. 2,13,33 000. This large figure only means after all that in a fully stocked timber forest, worked on a revolution of 120 years, each acre should, on attaining maturity, contain timber worth (gross) Rs. 600; a low estimate of the crop on such an area would be 30 trees of 2 feet diameter and 40 feet bole, which would yield over 3.000 feet of timber; the above estimate therefore works out to Rs. 0-3-2 per cubic feet, which it must be admitted is very low, especially as it represents the gross value of the wood at the nearest market.

Add now Rs. 1,33,000 for grazing, for although these forests are richer than the preceding classes they are not more suitable for grazing, and Rs. 1,33,000 for minor produce, as it is in these forests that the more valuable minor products are found, and the total gross revenue for the remunerative forests amounts to Rs. 2,16,00,000.

The total forest revenue for the Presidency from State forests only would then amount to *two hundred and forty lakhs* in round figures, or almost ten times the present revenue, and if the existing ratio between revenue and expenditure were maintained, the net revenue would amount to no less than eighty lakhs.

Although the revenue producing power of forests is the lowest imaginable point of view from which a Forest Officer should regard them, it is permissible to descend to this level on behalf of the forests themselves, and as they can only be made to yield their full revenue if efficiently protected, it may be well to show what, under such circumstances, might be expected from them.

In a subsequent article the question of the establishment necessary for the efficient protection, management and regeneration of the State forests will be dealt with.

TSEROFSHI.

Forestry in America.

BY H. J.

(Continued from page 401.)

CHAPTER VII.—SYLVICULTURE.

THE whole forestry business turns upon sylviculture, and the chief obligation of the forester is to replace the crop he has harvested by as good, if not a better, crop of timber than he found.

Generally restricted to the poorer soils and conditions, he is forced to the most conservative management of the natural resources, because so long-maturing a crop cannot repay much expenditure.

The simplest method of harvesting a crop is to clear the ground by a clean felling, and then to plant or sow the new crop. In some cases the regeneration may be effected naturally by seeds falling from the trees of the old crop, and the forester will then merely direct operations so as to favour the reproduction of the more desired kinds. When left to nature, the exposure of the soil, the danger of fires, and the probability that the least desirable species will predominate in the new crop are serious drawbacks.

This method is best suited to pure crops of light-demanding species. The working is concentrated on a small area, and the transport of timber and produce is cheap. It is of course not suited to forests of protection or of ornament.

Next comes the selection method, the crudest and least intensive method, in which all ages and sizes are mixed together over the whole area, coming nearest to the conditions of nature.

This system is the best for protective areas, and suits mixed forests of shade-bearing species; its chief recommendation is the continuous soil cover, but there is great loss of production. In Germany, less than 10 per cent. of the forests are worked by the selection method and over 80 per cent. by the method of clear fellings.

To improve the conditions of regeneration, the group method has been devised, in which the mature trees are felled in groups, instead of single trees here and there all over the forest, and these groups are gradually extended.

An older method, somewhat similar to the last, is the strip method, in which the openings are made in narrow strips running through the forest, at right angles to the prevailing winds, and the strips are successively cleared towards the windward side.

This method suits species with light-winged seeds, whose young growth does not require much shelter.

For heavy-seeded kinds, the more complicated method of regeneration under shelter wood is rendered necessary. Preparatory thinnings are made a short time before the seed year is expected, and then the old crop is gradually removed by successive fellings as the young growth develops.

Beside these methods of reproduction by seed, there is another mode, namely, that of the coppice system, in which the new crop originates in shoots from the stools of the old crop. This simple method of reproduction is not applicable to conifers.

Unless there is at the same time a certain amount of reproduction by seed, the forest will deteriorate both in composition and condition and will only yield small timber.

This objection is avoided by retaining standards in the coppice, which are reproduced by seed, and shelter the underwood. The standards, however, are branchy, and will not yield first-class timber; also they injure the coppice growth by their shade.

Large-sized timber of the best quality can thus only be obtained from forests regenerated by seed, and allowed to grow to full maturity in a dense crop. To produce long clean straight cylindrical trunks, the young crop must be kept close, or even crowded, until the maximum rate of height growth has been obtained. When 20 or 30 years old, a thorough thinning must be made to secure quantitive development, and these thinnings must be repeated periodically to increase the production by giving more light as the crowns close up, and to realize such trees as are falling behind.

By judicious thinnings, the rates at which the remaining crop develops may be more than doubled, and finally a much larger total product per acre is secured, especially when the inferior material removed in the thinnings is saleable.

In Germany the thinnings yield 25 per cent. or more of the final total yield.

The preservation of the soil moisture, and the soil cover free of weeds and grass, is always an important consideration in these operations.

The entire sylvicultural requirements of the crop resolve themselves thus into one, namely, the proper management of light conditions, secured by the judicious use of the axe.

The forester has discovered that mixed crops, although requiring more skill in their management, and including species of inferior utility, give not only better results in quality and quantity, but also give better protection of soil conditions, and especially safety against many dangers, such as insects, frosts, storms, etc.

A dense crop of mixed species in vigorous development, with no dead or dying trees, or débris lying about, is very safe as a rule from insect attacks. Protection from wind is best secured by keeping the crop well thinned, and in locating the coupes so that they proceed in the direction opposite to that of the prevailing winds.

The greatest danger to forest properties however is fire. In most cases it is confined to the forest floor, merely scorching the older trees; yet sometimes the fire may run up the trees and propagate itself from top to top, often for long distances.

Young crops are readily killed, especially in coniferous forests, with their dry resinous foliage and wood, and dry soil. Up till the pole stage, the damage usually consists in the total loss of the crop, and what is even more important, the loss of the soil cover and litter, the forest's manure.

In parts of the forest which have been heavily worked, and where the amount of débris, branches, and other waste is great, the fire risk is very serious, and continues for many years, especially in coniferous woods.

Forestry is in fact throughout the United States only possible in places where the whole yield, including the inferior material and fuel, are utilizable: otherwise the risks from fire are too great, or else the cost of clearing the ground for the young crop will be too large.

That the fire danger may by proper measures be effectively reduced to a minimum, is shown by the statistics of German forest administration. In Prussia and Bavaria, the average area burnt within the last 25 years rarely exceeded ·005 per cent.; and in India, under much more difficult circumstances, not more than about 8 per cent. of the protected areas has experienced damage. Some simple preventive measures, apart from police regulations, may be mentioned here.

Woods of deciduous species, being less liable to danger, indicate the advisability of the maintenance of mixed crops: the fact that old timber is safer than young, and that, on large wind-swept areas the heat and rapidity of the fire is increased, leads to distributing the coupes and keeping thereby the younger parts of the crop in small areas surrounded by older timber. The removal of the dead and dying trees in thinnings, and the disposal of the refuse of slabs, tops, branches, and chips from conversions in the forest are obvious means of reducing the danger.

CHAPTER VIII.—FOREST ECONOMY.

In forestry, as in other technical industries, the technical art, that is, sylviculture, is distinct from the business conduct, that is, forest economy.

Beside the technical care in managing the productive forces of nature to secure the highest gross yield, there must also be exercised a business management to secure the most favourable relations of income and expenditure, that is, the highest net yield; and lastly a systematic order in working to produce this revenue is necessary.

In some Government forests, the money profits may be of comparatively little or no importance, compared with other benefits derived from the forests, but even in such cases it is still desirable to organize the working systematically so as to bring into relation results and efforts, that is, to count the cost.

The time element is the one peculiarity which distinguishes forestry from every other business. The forester cannot, like the agriculturist, harvest annually the current increment, and the forest crop is only mature and useful when the accretions of many years (from 20 to 200) have been accumulated. Therefore, in forestry, when practised as an independent industry, as in any large business establishment, it is desirable to organize and manage the business so as to secure continuously and systematically a regular annual income nearly equal or increasing year by year.

The forester's business is thus based upon the conception of the "sustained yield", and it is by means of forest regulation, or working-plans, that the realization for ever of an equal annual revenue derived from the annual production of wood crops in the most profitable form is secured.

The standard of conduct and condition which the forester aims at attaining—tries at any rate to approach, so far as is practicable—is the *normal* forest, which is an ideal forest in such condition that it is possible to harvest annually for ever the best attainable product, or to secure continuously the largest possible revenue.

In this normal forest, there must be as many equal crops, varying in age by years, as there are years in the exploitable age; that is, *normal* age-classes must be present, so that an annually equal *normal* yield may be harvested, while the reproduction is looked after and the best possible production, the normal annual increment, is secured by sylviculture.

Under these conditions, the normal stock would be present, permitting the desired annual sustained yield management.

We have seen that this normal stock, varying of course in amount according to species, site, sylvicultural system, and especially length of revolution, is found by summing the arithmetical progression represented by the accumulated increments of the age-classes, and is equal to half the accretion taking place throughout the revolution over the whole area, the other half furnishing the yield during this same lapse of years.

It is not necessary of course that the age-classes, the crops of different ages, should occupy so many separate areas; they may be all mixed up as in the selection-worked forest; in such a case, the normal condition is attained when there are enough trees in gradation from the older to the younger, allowing for losses for the younger age-class, to replace in amount the older as it is removed or grows out of its class.

In real life the actual forest will always for one reason or another be abnormal.

The normal increment may be deficient, because the area is not fully stocked, or the timber is past its prime; the age-classes too are never present in exactly the proper gradation and amount; some will be probably entirely absent, and others may be in excess, so that even if the normal stock of wood be on hand in amount, it may be abnormal in distribution.

The normal increment or annual production can only be established by sylvicultural methods, and the other two conditions (amount and distribution of the age-classes) are obtained by regulating the yield in area and amount, so that gradually the age-classes and the normal stock are established. Various methods are employed to determine the actual yield, which will gradually lead to the ultimate normal possibility.

The simplest way would be to divide the forest into as many equal areas as there are years in the revolution, and to cut one each year. But this burdens the present generation with the entire cost of securing the normal state, and probably entails a very fluctuating yield, together with a financial loss, resulting from the fact that over-mature and immature crops will be felled.

To obviate these disadvantages, the "allotment method" was invented, in which the yield is only fixed for a short rotation of ten years, and both the areas and the volumes of the present fellings are modified according to the existing state of the crops in different parts of the forest.

The most logical, though often not the most practicable, way of fixing the yield is by adding or deducting from the normal annual increment the difference between the normal stock and the actual stock, divided by the number of years in a conveniently chosen period of equalization.

In every case, the owner's interest must be the guiding principle in the management of any property, and it must be remembered that financially forestry means the foregoing of present revenue, or the incurring of present expenditure, for the sake of future revenue; it involves gauging present and future advantages, and the time element is the prominent feature of its finance calculations.

In making a working-plan, the first thing required is a topographical forest survey, followed by a quantitative survey, by which, in addition to a stock-taking, the local rates of growth and the average age of maturity will be ascertained. If normal yield tables exist, the annual yield can be at once determined by comparing the actual local conditions of growth, and the state of the crops, as described at length in the valuation survey, with these tables, which are the result of measurements of the most perfect normally stocked crops of various species, and give the average contents of such crops in ten-year periods under normal conditions per unit of area.

The next most important question to be solved is the age, or sizes, to which it is desirable to let the trees grow before felling them.

There is no natural maturity of a forest crop as we know it in agricultural crops; wood does not ripen naturally, nor do trees even die at a given period, but gradually decay. The proper felling age must therefore be generally determined by economic considerations.

Although the forester bases his calculations partly at least on the size of his crop, a simple girth or diameter limit, below which every tree is to be considered immature, would be unsound, because, without attention to systematic reproduction and cultural operations to favour the more valuable species, and to keep under the least desired kinds, the diameter restriction is of little value.

The determination of the exploitable size or age is largely a matter of financial calculation, influenced by sylvicultural and technical considerations.

For instance, the age up to which trees coppice or the periodicity of seed-years may have to be taken into account, as well as the technical value of the product and the market requirements for special materials, such as railway sleepers, etc.

From the standpoint of political economy, it was first supposed that the largest volume of produce per acre per annum ("absolute exploitability") should be the aim of forest management; but it can be shown that this age occurs quite early in the life of the tree before it has attained a useful size.

Since the current increment of a crop gradually increases in rate from its early stages up to a given age and then again sinks, there must be a time when the average accretion, the mean annual increment, attains its maximum. If, for instance, a fully-stocked acre of spruce contains at 120 years 10,200 cubic feet of wood, its average annual production is $\frac{10,200}{120}=85$ cubic feet, and if a crop aged 80 years contained 6,880 cubic feet, its average annual production was $\frac{6880}{80}=86$ cubic feet; hence from the standpoint of volume production a rotation of 80 years would be preferable.

It is, however, evident that value production is generally more important than volume production, so that if in the above instance the price averaged for 80-year old wood of all sizes was 3 cents per cubic foot, and 4 cents for the 120-year old wood, then the average value increment would be in the first case $2·58, and in the latter $3·40 per annum, so the longer rotation would be the more favourable.

But even the exploitability of the maximum value production will not satisfy any private investor, since it leaves out of consideration the expenditure necessary to secure this result.

The annual expenses should at least be deducted, and as these vary with the length of the rotation, that age should be found at which the surplus of the annual revenue over the annual expenditure is greatest, the rotation of the highest forest income. Finally, even this last age of exploitability will not be financially sound, since it takes no account of the capital invested, nor of the interest accumulating with the time.

The true financial exploitability corresponds, therefore, to the rotation which brings in the highest rate of interest on all the capital invested in soil and stock of wood,—that is, the rotation of the *highest soil rent.*

We have thus to calculate whether the saving made by lengthening a rotation will be profitable or not, and here we have to do with forest finance, a branch of forest economy which concerns itself not only with finding the present value of a single crop, and with the future value to which it is growing, but also with its value as a part of a regulated forest management, in which it is for all time to come an inherent necessary member as a producer of values.

The time element, the foremost peculiarity of forest economy, here comes most prominently to expression.

The inability of withdrawing annually the interest on the invested capital makes compound interest calculations necessary, and as this compounding has to go on for a long number of years, and the investment is—perhaps with the exception of the danger from fire,—safe, easily managed, and requiring little labour, the rate of interest at which the compounding is to be calculated is necessarily low, and should not exceed 3 or at most 3½ per cent.

The soil expectancy value is calculated from the present capital value of the intermittent revenues yielded by the final felling, and the intermediary fellings or thinnings, minus any original outlay for planting, etc., also calculated up to the end of the rotation; and from this present capital value so calculated, the capital required to furnish yearly for ever the annual charges for administration is deducted.

This calculation is, however, often difficult to make practically, owing to the uncertainty of the values to be given to the various items and of the future rate of interest, so that in practice the simpler forest rent calculation is often more satisfactory.

In selection-worked forests, instead of calculating the yield for the whole revolution, it is sufficient to base the calculation only on the existing number of mature trees, and the time required for the present stock of second class trees to grow up to the exploitable size. This method is not used by the American Bureau of Forestry, which, instead, ascertains and compares merely volume production by constructing a yield table. This method is, however, used by the Indian Forest Department, as paving the way for better methods, but caution is necessary in its application, as it is based upon the assumption, probably not often correct, that reproduction will take place, and that the younger age-classes exist in sufficient amount to take the place of the older.

A closer approach to true financial calculation could be made by basing the exploitable size on the highest net value per unit of volume in connection with the time it takes to replace it. It is evident that the value of the unit volume increases with the size of the log, yet in a decreasing ratio, so that if the time required to produce the cubic foot is put in relation, the most profitable exploitable size can be found.

A further improvement, securing a more sustained yield, requires that the number of dominant trees of the different size classes be ascertained, and compared with the number which should exist in the normal fully-stocked forest, and then the required number left of each class, or the excess removed, to bring the number to the standard.

The approach to the normal condition can, in any case, only be gradual, and may be secured in a longer or shorter time, depending on the owner's interest; in other words, the regulation of the working, primarily based on mathematical measurements of increment, yield, and values of produce, must in practice be modified by judgment, to allow for changing conditions.

Sylviculture, the replacement of the crop, is always the more important obligation, assuring continuity of yield, which can often be practised without any elaborate organization of the ideal business conduct.

Fungus Destructive to Deodar.

By B. O. COVENTRY, F.C.H.

ON 1st May 1903 at Konain, Jaunsar, U. P., I found a deodar tree blown down by the wind whose roots were absolutely rotten, with the exception of one side root which still appeared sound. The crown was still green and fresh, so the tree had only quite recently been blown down, and appeared perfectly healthy, being well developed and with a vigorous leading shoot. The tree measured 55½ feet in length and 2½ feet in girth. It was on the edge of a group of poles and had ample light. The roots were absolutely rotten throughout, with the one exception, the rotten wood being of a red-brown colour. The rottenness did not extend to the wood above ground as far as could be seen, although on one side of the stem underneath the bark to a height of six inches above ground the mycelium of a fungus was found which had destroyed the cambium tissues at this part. Just below ground underneath the bark the mycelium was thick and felt-like; elsewhere it was generally thin, like paper, or ramifying as threads under the bark, while mycelium was also present between the different layers of bark. In some parts the mycelium was of a purplish colour. A fair amount of resin had exuded from the stem where the cambium had been destroyed, but was only visible on removing the bark. There were no visible signs above ground of anything wrong with the tree, and had the tree not been blown over, exposing the rotten roots, no damage would have been suspected, and yet if the tree had not been blown down it could not have lived more than one or two years longer at most. The tree had been growing in contact with an old

FIG. 1.—Sporophores of a fungus on deodar: *a*, Bark removed showing the white mycelium; *b*, Bark partially scraped off showing white mycelium under bark flakes; *c*, sporophore (dotted line represents ground surface).

deodar stump of considerable age, which was rotten below ground, and it appeared as if the fungus had extended from this old stump to the living tree. I could not detect any signs of a sporophore, but thought that perhaps the thick felt-like portion of mycelium might be the early stages of one Not far from this spot, about twenty yards off, there was a group of about six deodar poles dead, three of which were standing; the others had been cut and removed for fuel, only their stumps remaining The roots of these trees were rotten. I noticed white hyphal threads, white mycelium in the bark and white mycelium underneath bark One of the trees measured 3ft 6in. in girth There was no apparent explanation for the death of the trees unless it could be attributed to a fungus They had plenty of light and the locality was in every way suitable as far as could be seen

On 17th May at Koti Kanasar another group of four or five dead deodar poles was seen, and at the bases of two of these sporophores were found The accompanying photographs show these sporophores On the larger tree the sporophore was a thick brown incrustation with white hymeneal layer at the base of the tree close to the ground Underneath the bark there is a sheet of thin white mycelium, like tissue-paper, clearly seen in Fig. 1 at *a*. The girth of this tree was 20 inches.



FIG 2.--Sporophores of a fungus upon deodar showing bracket-like structures above ground

On the smaller tree there was a thick rusty brown incrustation on the main root just below ground, over part of the surface of which pores (apparently hymeneal layer) were present Extending above ground, the rusty brown incrustation merged into a number of small bracket-like structures with white under surface and a rusty brown margin; the upper surface of the small bracket portions being lighter brown in colour and marked with concentric ring-like zones of growth. The roots of both these trees were rotten.

Although it is impossible to say for certain whether the fungus whose sporophores were found on the dead deodar poles was the cause of their death, yet from the fact that there appeared to be no other apparent cause, and that only shortly before a healthy living tree had been discovered with its roots attacked and destroyed by a fungus, there seem to be strong grounds for considering that these young poles were killed by the fungus. The fungus seems to be one which spreads from tree to tree attacking the roots, as in two cases groups of dead poles have been found. As far as the green tree is concerned, there is no doubt whatever that the tree was attacked when in a healthy condition, and would undoubtedly very soon have succumbed under the attack of the fungus had it not been blown down Whether the sporophores found on the dead poles belong to the same species which attacked the green tree cannot yet be stated.

I am sending this note in hopes that other Forest Officers in deodar tracts will keep a look-out and see if they can throw further light on the subject. Specimens are being sent to Dr. Butler, Cryptogamist Botanist to the Government of India, and it is to be hoped that he will be able to give further information.*

II.—CORRESPONDENCE

Botany and the Forest Officer.

By Sir W. T. Thiselton-Dyer, K.C.M.G., F.R.S.

In a sympathetic notice in the *Indian Forester* of the late distinguished Inspector-General of Forests in India, Mr. H. C. Hill, Sir Dietrich Brandis stigmatises as "absurd" "the idea which, until a short time ago, was current in England, and which to this day is held by many English botanists, that a good botanist must necessarily be a good forester." I quite agree that the idea is absurd, but as I am probably better acquainted with the English botanical world than Sir Dietrich Brandis I doubt very much whether the idea was ever current in this country or is held at the moment by many English botanists. For my part I entirely dissociate myself from it, as I know many accomplished botanists who would probably make very indifferent Forest Officers.

I am more able to agree with Sir Dietrich Brandis when he says:—"A forester, more than almost anybody else, must use his eyes and must be able on the spot to draw conclusions from

---

* A report by Dr. Butler on this subject will shortly appear in the Appendix series of this Magazine.—Hon. Ed.

'what he has observed." But the power of observation is by no means possessed by everyone. A further requisite, in which I think Sir Dietrich Brandis also agrees, is sympathy with and pleasure in Forest nature for its own sake. It appears to me that neither point is kept in view in the present mode of recruiting the Indian Forest Service.

Sir Dietrich Brandis lays great stress on sport, and unless it becomes too absorbing a pursuit it undoubtedly fulfils the conditions I have stated. It would, however, be as undesirable to insist that every Forest Officer should be a sportsman as that he should be a botanist.

But I entertain a very strong opinion that a Forest Officer will never rise to the highest level of efficiency in his work unless he has a scientific grasp of the principles which underlie it. He should be able to identify the trees which compose the forest-vegetation under his charge, and for this purpose he should have such an elementary acquaintance with botany as will enable him to use intelligently the book which Sir Dietrich Brandis has been for several years occupied at Kew in preparing for the purpose. He should further have some knowledge of the nature and conditions of vegetable life: he should grasp the idea that a tree is a living organism whose growth and development are subject to adverse or favourable conditions. He should further have some idea of the enemies and diseases by which trees are liable to be attacked and of how these attacks can be met. All this a man of ordinary intelligence can acquire if he possesses a real taste for nature without rising to the level of the professional botanist, which it would be absurd to demand of him.

There is the same fallacy underlying the view that mere administrative efficiency is sufficient for a good Forest Officer as in thinking that mere mechanical drill without resource or initiative will make a good soldier.

As I have felt it may duty to urge these views officially I should be glad to state them more publicly.

I should like to take the opportunity of expressing my regret at the untimely death of Mr. H. C. Hill, the late Inspector-General. Largely as the result of my personal persuasion he accepted a mission in 1900 to initiate a scientific forest administration in the Straits Settlements. His reports were of the highest value and will be a permanent basis for the future forest policy of that part of the Empire.

KEW, *August 25th*, 1903.

Shrinkage in Timber during Flotation.

I.

WITH reference to Mr. Tulloch's note in the *Indian Forester* for August regarding the shrinkage in timber during flotation, the following explanation, which will appear in the Punjab Annual Forest Report for the year 1902-03, will, I trust, make matters clear. There is an undoubted loss in volume in logs between the launching point and their receipt in sale depôts of about 16 per cent. How much of this is due to shrinkage of the timber and how much to wear and tear in the water it is not at present possible to say. Systematic measurements are now taken annually and reliable information should soon be forthcoming.

The measurements of logs at the launching points and of the same logs when received at the sale depôts were continued, and there are now five years' figures to help us in estimating the amount of loss incurred by a log in its transit from the forests to the sale depôts. These observations have been taken on the Jhelum, Ravi, Chenab and Sutlej rivers, and show that a loss of at least 16 per cent. undoubtedly occurs. The logs, it is to be remembered, often take two or three, or sometimes many years to reach the depôts, during which time they are frequently stranded and exposed to the sun. They have also to pass through many rough places, and the loss is probably as much due to wear and tear in the water as it is to actual shrinkage of the timber. Further observations are required to set this point at rest.

A statement was made in para 41 of last year's report that enquiries made in Bashahr tended to show that "for every 100 cubic feet cut in the forest and exported in the log, not more than 72 cubic feet are received in depôts, some 19 per cent. of the loss being attributed to shrinkage. Whilst for every 100 cubic feet cut and exported in scantling it is calculated that 48·5 cubic feet reach the sale depôts."

This statement has attracted considerable attention, and not being as clearly expressed as it should have been requires further explanation. By measurements made during the last five years it has been found that for every 100 cubic feet of log measured where it has been felled in the forest, 91 cubic feet reach the launching point, 9 cubic feet being lost on the way from the forest to the river. This is chiefly due to the loss of the bark, which gets knocked off in transit. Of the 91 cubic feet launched in the log, there will be a loss of about 16 per cent. or 14·5 cubic feet on account of shrinkage and general wear and tear in the water; and 5 or 6 per cent. on account of breakages and thefts in transit. Not more therefore than 72 cubic feet in every 100 cubic feet cut in the forest and brought out in the log reach the sale depôts.

For every 100 cubic feet of timber cut and sawn up not more than 52 cubic feet of scantlings will be obtained, *i. e.*, there is a loss in conversion of 48 per cent. Of these 52 cubic feet 5 per cent. may be lost in transit, so that not more than 49 cubic feet of scantling out of every 100 cubic feet cut in the round can be expected to reach the sale depôts.

No deduction is made for shrinkage in the case of scantlings which do not contain sapwood, as is the case with logs. These are, moreover, usually cut slightly larger than the standard sizes to allow for shrinkage, wear and tear, and the loss on this account is included in the loss by conversion.

F. BEADON BRYANT,
Conservator of Forests, Punjab.

II.

IN the August number of the *Forester* there is a letter from Mr. J. C. Tulloch on this subject, in which he quotes figures with reference to the Bashahr Division. The loss of 19 per cent. in the volume of the logs, which is termed shrinkage in the Punjab Circle Report for 1901-02, includes all breakage and general wear and tear between the time the logs are launched and the time they are received in the sale depôt. But Mr. Tulloch is not quite right in assuming that during this time the timber lies in the water. The average time occupied by a log in transit on the Sutlej River may be safely taken to be not less than one year, and for most of this period the log is either stranded on rocks in the upper part of the river or in the *chhundas* in the plains section, or is lying in one or other of the transit depôts. In all these cases the timber is seasoning, and surely this means shrinkage. I am not prepared to uphold this term as the best that could be selected to include all the forms of loss to which the timber is subject; but I think there can be no question that much of the total loss is due to true shrinkage in contents.

The figures quoted show a total loss of 28 per cent. between the forest and depôt measurements of the logs; 9 per cent. between the forest and the launching point and the 19 per cent. under discussion. The 9 per cent. is due to the removal of bark and general damage in the passage of the logs down the slides to the river bank. These calculations were based on the figures for the last twenty years, and presuppose the opening and closing transit balances in the river to be identical. To generalize in this manner is, perhaps, of less value than to take the figures for logs carefully measured before launching and re-measured in the sale depôt after identification by their marks. Figures obtained in this way, in the case of 586 logs during 1902, show a total decrease of volume in transit of 10·8 per cent.

The 51·5 per cent. of loss in the case of scantlings was intended, obviously, to show the loss between the forest measurements of logs and the contents of the resulting scantlings received in the sale depôt. Loss of scantlings in transit to this extent is not conceivable even in the worst of rivers, and for power to reduce timber to matchwood the upper part of the Sutlej is hard to beat. In the figures Mr. Tulloch gives to illustrate the loss of scantlings in Jaunsar, he does not state how he treats broken scantlings or balances known to be in transit at the commencement and close of the 13-year period he refers to—points which are of considerable importance. In Bashahr on the Sutlej the figures for the eleven years ending 1902-03 are as follows:—

	No.	c. ft,
Launched	274,435	905,591
Received whole	234,555	720,452
Ditto fragments ...	29,744	43,402
In transit on 30-6-03 ...	11,364	31,163

Very few scantlings were launched in the year immediately preceding 1892-93, and so the transit balance at the commencement of the period is assumed to be *nil*. The figures show that if each payment is taken at one half of a whole scantling, the loss is 5 per cent. in number and 12·2 per cent. in contents. The figures for the year 1902-03 with known transit balances are 2·3 per cent. in number and 10·2 per cent. in contents.

G. S. HART,
Deputy Conservator of Forests,
Bashahr Division.

A Note from the Myodwin Teak Plantations.



I AM sending you a photograph of a view taken in the 1868 teak plantations of Myodwin, Tharrawaddy Division, and also one of some ruins which are, I believe, the remnants of the bungalow occupied by Forest Officers and Sir Dietrich Brandis in the early seventies.

I have always understood that Myodwin was at that time the headquarters of the Forest Department in Burma, but 20 years ago I could only find a few houseposts left. Myodwin is now a small village some seven miles from the railway and fairly accessible, but in the old days I understand it took about three weeks to procure stores from Rangoon by cart

It would interest many besides myself if Sir Dietrich would, through your journal, give a short description of the Myodwin of his day, and explain why this apparently inaccessible jungle village was selected as a site for a headquarters station This has always puzzled us Myodwin may be translated the "city well' or the ' well of the city," but there are no remnants of any "city' to be found now

To my mind there is something very pathetic about these two views On the one hand, the ruins of a home which once echoed to the gay laughter of many of our predecessors, some of whom are gone and forgotten, on the other hand, those grand young teak trees in all the vigour of their youth putting forth an annually increasing wealth of foliage and asking only to be let alone to fulfil the destiny for which they were brought into existence by the former inhabitants of that house in the corner of which but the ruins now remain.

H S

The Assam Manual on the Powers of Forest Officers to Compound Offences.

WOULD you kindly oblige me with an opinion as to the meaning of the last clause in the paragraph quoted below.

It seems to me that officers drawing Rs. 100 or more are empowered under section 62 of the Regulation to compound. I believe certain officers of this rank in the Central Provinces do compound.

I contend that the clause has been so worded for the purpose of permitting such officers to do so. *Vide* section 62 (3) of the Regulation.

There is however a difference of opinion on this point, and an interpretation *ex cathedra* is solicited.

THE ASSAM FOREST MANUAL.

Page 42, Rule 11. The Chief Forest Officer of the Province, all Deputy Conservators, Assistant Conservators, Extra Deputy Conservators and Extra-Assistant Conservators when in charge of Divisions or Forest Districts, and all Deputy Commissioners and Subdivisional Officers shall exercise powers under sections 34, 36, 43, 44, 45, 47, 57, and 76 and also the powers referred to in clause (1) of section 68 of the Assam Forest Regulation. If the officer draws a monthly salary of Rs. 100 or more, he shall also exercise powers under section 62 of the Regulation. R. O.

[We have read the sections in the Assam Forest Manual referred to and have submitted R. O.'s question to several experts in the matter. The consensus of opinion is that the wording of the clause in question could with advantage be improved. There can be little doubt that the intention and spirit of the rule is that all Officers-in-Charge of Divisions shall have the power to compound offences, provided their monthly salary is Rs. 100 or more. It has probably occurred at times that the Province has been short-handed in Officers, with the result that a Forest Ranger has held charge of a Division. Hence the necessity for the rule. R. O.'s contention that all Officers drawing Rs. 100 and above can compound offences cannot hold water. If this were so every newly joined Assistant Conservator would have power to compound, in other words he would be empowered by Government to carry out acts which it would be out of his power to do justly, since until he had learnt the language he would be totally in the hands of subordinates, who through him would use this power to their own ends. We understand that in the Central Provinces certain Officers not in charge of divisions but drawing pay of not less than Rs. 100 per mensem are by special notification giving their names, granted power to compound, subject to the confirmation in each case of the Divisional Officer.—HON. ED.]

Cordite Rifles in the Indian Forests.

HAVING during the course of carrying out my professional duties considerable opportunities for *shikar*, I should deem it a favour if Forest Officers would obligingly give me, through the medium of the pages of the *Indian Forester*, their opinions, based on actual practical experience, of cordite rifles for heavy game. Is a ·450 cordite rifle heavy enough to stop a charging bison ? Shooting on foot in thick bamboo jungle one often has little opportunity of choosing vital spots to aim at. It is usually a snapshot As this snapshot may only be obtained at the end of a long tiring day's tracking, one naturally wishes to be armed with a weapon which will "stop" the animal if hit, whilst at the same time, as the rifle has to be carried by oneself for many miles, its weight becomes a question of maximum importance. I should be glad of advice from sporting Forest Officers on this matter.

BIG GAME.

III.—OFFICIAL PAPERS AND INTELLIGENCE.

Mr. H. D D. French

It is with great regret that we have received news of the death of Mr. H. D. French on the 2nd September from enteric fever at Lucknow, where he had recently been transferred to officiate as Conservator in charge of the Oudh Circle.

Mr. French, after leaving Marlborough, passed the competitive examination for the Forest Department in December 1882, proceeding to Nancy shortly afterwards in company with Messrs. Gradon, Mercer and Somers-Smith.

His winning manner and open-handedness soon rendered him most popular, not only among his English comrades, but also with the teaching staff and his French fellow students.

He was a good rider, a keen tennis-player and bicyclist, and thoroughly enjoyed the opportunities for outdoor life and recreation which the Nancy training afforded.

Coming out to India towards the beginning of 1886, he was posted to Bengal, where he held charge of various Divisions, remaining in the Province till May last, when he took over charge of the Oudh Circle from Mr. McKee, who proceeded on leave.

By his death the Government of India lose a valuable officer, while members of the Service, as also all who knew him, have to deplore the loss of a cheery companion and trusted friend, whose place it will not be easy to fill.

We beg to offer our profound and respectful sympathy to his widow and family.

The Government of India on the Madras Forest Administration Report of 1901-02.

IN their review of the previous year's report, the Government of India had occasion to remark on the large number of forest offences that had been reported and on their continuous increase during recent years. There has been a further increase in the past year, and the administration of the penal provisions of the Forest law calls for serious consideration. It is possible that were greater attention given to the recruitment of the protective staff, which is described as being inferior both in number and character, fewer opportunities would be afforded for the commission of offences.

It is noted with satisfaction that while 332 square miles were added to the area under special protection from fire, the area burnt was only 66 square miles in excess of that of last year; and there is no reason why a still greater measure of success should not be attained in future. In the Central Circle, for instance, in no less than 26 cases did fires cross the exterior traces, with the result that an area of 14,600 acres of valuable forest was burnt; while in the Madura Division of the Southern Circle the large number of 21 fires occurred through accident or carelessness during the burning of fire-lines. These results indicate both insufficient protective measures and a want of supervision on the part of the Forest staff, and the Government of India trust that orders will be issued to prevent similar failure in future in the protective system.

The net profits of the working of the year are the largest on record, and the Madras Government are to be congratulated on these excellent results, for which, however, the Northern and Central Circles alone appear to have been responsible. It is to be regretted that the financial position of the Southern Circle is even worse than it was in 1900-01, a surplus of Rs. 53,000 having given place to a deficit of Rs. 37,000, while the number of Divisions in which the charges have exceeded the receipts has risen from 4 to 5, out of a total of 8. In the review of last year's report it was pointed out that the Forest Administration was here not entirely satisfactory, and the suggestion there made as to the possibility of developing more profitable markets for forest produce in this Circle will no doubt receive attention.

The length of the report has been much curtailed without any diminution of its value as a record of the year's work—an improvement which the Government of India cordially recognise. They would be glad if in future it were found possible to arrange for the more punctual despatch of the report.

IV.—REVIEWS.

Annual Progress Report of Forest Administration in the United Provinces and Oudh for 1901-02.

ALTHOUGH there have been no actual additions to the forest area in the returns for the year, the total area of reserved, protected, unclassed and leased forests in the United Provinces is shown as exceeding that of the year 1900-01 by nearly 200 square miles—a substantial difference, which is attributed to an alteration in the computation by the Deputy Conservator of the unmeasured lands classed as district protected forests in Garhwal. The total area under the above mentioned forests was 18,489 square miles at the close of the year. No settlement, demarcation or survey work of special importance was undertaken during the year, but the local Government note that that important branch of administration—the proper maintenance of boundaries, appears to receive due attention in all circles. In this respect the United Provinces are certainly to be congratulated on being so well ahead of some of the other provinces. Not until the troublesome questions of settlement and demarcation have been finally dealt with can the forester really turn his attention to properly working his forests either scientifically or commercially with any real measure of success.

The Conservators appear to have had their hands considerably strengthened, whilst the right holders have been granted a useful and well considered concession, by Government allowing Conservators, at their own discretion, to make free grants to right holders whose villages have suffered from fire or other calamities. This ensures relief being extended at once to sufferers without the inevitable and needless delays which appeals and references entail.

The Province holds a very strong position in its Working-Plan record, and can show an amount of progress with which few other administrations in the country can vie. It may be said that practically the whole of the forests are under plans, of which several have already run through their first period and are under revision—a really fine record. The Pilibhit Supplementary Plan and the revised plans of the Trans-Sarda and Dehra Dun forests remained to be submitted, and a rough working scheme is to be prepared for the Bundelkhand forests.

One lakh of rupees was usefully spent on buildings and roads, and the local Government note with pleasure that good progress is being made in providing proper accommodation for subordinates, and that the improvement of the water-supply for cattle continues to receive attention. There can be little doubt that in so well housing its subordinate forest staff these Provinces set a bright example, and one that could be followed with profit in other and far more unhealthy parts of the country.

The register of breaches of forest rules shows a slight increase in the number of cases dealt with, mainly under the head of cases compounded. Owing to a prolonged dry season, the year was a bad one for fire conservancy, an expenditure of Rs. 63,751 being incurred under this head—a figure somewhat higher than during the previous year: the number of fires increased from 95 to 112, the increase being almost entirely in the School Circle, but the total area burnt, returned under the head of failures, declined from 34,088 to 27,877 acres. This class of offence, whilst the most injurious to the forest, is amongst the easiest to commit with a reasonable chance of evading detection, and the infliction of light punishments in cases when a conviction has been obtained is not likely to diminish its frequency. Incendiarism is always an extremely difficult thing to prove, as there will usually only be the evidence of a fire patrol or guard, ignorant, unlettered men, whom the most inexperienced pleader can cause to contradict themselves. Therefore, to impose light sentences, when cases have been proved, is to throw ridicule upon the whole question of fire conservancy. We note with pleasure that in one instance during the year in the case of a village where incendiarism was undoubted, the punishment inflicted was the suspension of the villagers' rights in the forest concerned.

Were this form of punishment inflicted more often so that it came to be recognised by the people as a result certain to follow acts of incendiarism in the forests adjacent to their villages, a long step would have been taken in the direction of solving this difficult problem. That valuable forest estates should, year after year, be put back through the criminal acts of an ignorant population, or the careful work of years be ruined by an act of wanton mischief is, we would think, a matter of sufficiently serious import. A private owner would not suffer such a state of affairs for a moment; and if large sums are to be spent annually in an endeavour to protect the State forests, we are unable to see why money should be thrown away owing to the inability of the lower courts to recognise the seriousness of this class of offence.

During the last few years strict attention has been paid to the Government policy as regards grazing, with the result that a much larger number of animals now pasture in the forests, either free or at reduced rates, than was formerly the case. In the Central Circle the figures show an increase of 6,660 animals at full rates, 23,595 at privileged rates, and 10,729 animals under the several settlements of rights and concessions, over those of last year. In the Oudh Circle there was a decrease of 17,974 animals, and there is a small decrease also in the School Circle, partly attributed to want of rain in the Jaunsar

Division. We note that under the new Jaunsar Working-Plan for the reserved forests 74 per cent. of the total area is open to animals of all kinds, but chiefly goats and sheep, perhaps the most dangerous animals in the forest in this respect.

On the question of the formation of fodder reserves, which has been engaging attention during the last few years, the Conservator, Central Circle, has finally come to the conclusion that (1) there are no indigenous fodder plants in the lower forests which it would be possible to cultivate, and (2) that the expense of cultivating fodder plants on a scale sufficiently large to be of value would be prohibitive. As to the question of the introduction from other countries of fodder plants with a reputation for drought-resistance, the Director of the Botanical Survey of India, in paragraph 6 of his Report for 1901-02, states that "the numerous attempts to naturalise plants of this class in India show that in tracts where in seasons of scarcity the existence of such fodder plants would be invaluable, they will not survive under normal meteorological conditions."

The total outturn of timber, fuel, and other produce amounted to 13,567,972 cubic feet, as compared with 14,523,308 in 1900-01, a decrease of 956,000 cubic feet, an increase in the Central Circle being more than counterbalanced by a decline in the Oudh Circle and in the district forests of Kumaun. Owing to an important change in the method of classification, adopted at the instance of the Inspector-General of Forests, in the Oudh Circle, the figures showing the method of extraction do not correspond to those of the previous year, but the returns, as now compiled, indicate that departmental operations are reduced to a minimum, except as regards timber in the School Circle, where the sawn timber obtained by departmental agency exceeds that removed by purchasers; and as regards fuel in the Central and School Circles, where fuel is supplied in large quantities to the troops or European settlements. The departmental work undertaken in the School Circle consists in the cutting of deodar sleepers in the Jaunsar Division in the leased forests of Tehri-Garhwal. This work has now been in progress for some years, and the extraction of the sleepers has necessitated the construction of some exceedingly interesting export works—works which form one of the show sights of the Department and well repay a visit. In the Central Circle exports of timber and bamboos were brisk, and the success of the newly adopted system of monopoly sales, combined with moderate royalty rates, was most marked. This system has been introduced to take the place of the former one of lump sum sales, and it is claimed for it that it has equalised prices and placed the timber trade on a more certain footing. As the traders are content with the new system, and the resultant revenue derived is greater, the change can only be looked upon as of a most satisfactory nature, and the Local Government remark that "great credit is due to the officers responsible for its introduction and working, the extra revenue obtained by their exertion being estimated at half a lakh of rupees," appears certainly well-merited. In the Oudh Circle a similar system was worked with success in the Kheri Division, but did not answer in Bahraich, where better results will, it is hoped, be obtained next year. The deficient outturn in this circle, which is accompanied, it may be noted by an increase in the receipts, is explained by the failure of contractors to remove timber and fuel for which they had paid.

Notwithstanding the decline of the total output, the financial results are better by a lakh of rupees than those of the previous year. The total revenue amounted to Rs.17,61,000, whilst the expenditure falls short by a few thousand rupees of ten lakhs, leaving a surplus of Rs 7,68,012 for the Provinces, as compared with Rs.6,62,804 in the year 1900-01.

The Central and Oudh Circles, in which, owing to briskness in exports, most probably due to the new system of sales introduced, the receipts increased and the expenditure either declined or did not advance substantially, contributed in fairly equal proportions to this satisfactory result, showing an improvement in the combined surplus as compared with the previous year of Rs.1,25,000; this sum, however, was reduced to Rs.1,06,000 for the Provinces by a fall of Rs 19,000 in the School Circle. The local Government notes that the Conservators point to the Naini Tal, Kumaun, and Ganges Division in the Central Circle and to the Kheri Division in Oudh as showing excellent financial results which are very creditable to the officers in charge.

We may conclude in the local Government's own words: "While the management has succeeded in obtaining for the State a substantially increased income, the Government has no reason to believe that, as a rule, there has been a want of sympathy in dealing with questions of grazing, the supply of produce to right holders, and other matters affecting intimately the interests of the agricultural community."

Progress Report of the Forest Administration in Coorg, 1901-02.

THE changes which have taken place during the year in the area of the reserved and protected forests are shown in the following statement:—

Class of Forests.	Area on 1st July 1901	Added during the year	Excluded during the year	Area on 30th June 1902.	REMARKS.
	Acres	Acres	Acres	Acres.	
Reserved Forests	1,52 407			1,52,407 (a)	(a) Consists of 1,68,636 acres of ghats only and 2,521 acres formerly paisari protected forests.
Reserved Lands (under section 4) Protected Forests	...	1 71 157	...	1,71,157	
Ghat Forests .	2 31 049		1,68,636	62,413	
Paisaris ...	1 74 755		1 74 755		
Urudves ...	3 107			3,107	
Devarakadus	15,506			15,506	
Total .	5 76 824	1 71 157	3 43,391	4,04,590	

There was no extension of reserved forests during the year, but an area of 171,157, acres was notified under section 4 of the Act for reservation Of this quantity 168,636 acres was formerly protected ghât forests; the area now standing under the latter head in the above table has consequently been reduced by that figure.

A Forest Settlement Officer has been at work since the beginning of July 1901. In all seven blocks of 2,521 acres on the plateau and three blocks of 168,636 acres of ghât forest were notified for reservation under section 4 during the year. In respect of the former, the whole settlement enquiry was completed and final orders were issued before the 30th June 1902. In respect of the latter three blocks the final draft notifications under section 19 were submitted to the Chief Commissioner by that date.

The reservation of the ghât forests and of the more valuable *paisaris* will, it is believed, be completed at an early date. The record of enquiry into *Devarakadus* and *Urudves* has been completed in two taluks and has made considerable progress in the remaining three taluks. The demarcation of *jama* cardamom *malles* and the question of allowing ryots in certain specified localities to continue the practice of cultivating by the *kumri* method are under consideration, a joint report on the subject having been submitted to the Deputy Conservator and Forest Settlement Officer.

Pending final reservation no new lines were cut during the year in connection with the new reservations. About 22 miles of ghât boundary lines were cut between Coorg and Malabar to a width of 25 feet. The total expenditure on demarcation during the year was Rs. 555.

The preparation of a working-plan for the Janikal forests was commenced during the year. As regards the sandal Plan the prevalence and spread of the "spike" disease is so great that the whole data bearing on the plan are said to have been disorganized and the preparation of the same must be postponed pending the result of the remedial measures now being put into force.

On the important question of communications and buildings the Deputy Conservator writes that with the exception of the ghât forests, still under settlement, the Division is completely provided in this respect—a most enviable state of affairs.

There is a further decrease of 28 in the number of reported cases of breaches of the Forest laws during the year, the number having thus fallen from 106 in 1899-1900 to 59. The fall is attributed to a return of prosperous seasons.

The Chief Commissioner appears to attach considerable importance to the continuance on a large scale of the work of eradicating the lantana weed.

The results of fire conservancy were extremely satisfactory, and the whole credit for this position of affairs appears to be due to the initiation by the Deputy Conservator of a system of employing the whole *kurubar* population of the forests, including the foreign settlements on the Mysore border, on a system of rewards according to results. There were in all five fires covering 170 acres against 12 fires and 1,483 acres last year. This is the best season on record. The cost of fire protection was less by Rs.326 than last season.

There is a remarkable decrease in cattle grazing on payment, an explanation of which is expected in a report shortly to be furnished by the Deputy Conservator.

The return to normal seasons and the practical absence of forest fires has resulted in favourable growing conditions, and the reproduction of teak and particularly of "honné" (*Pterocarpus marsupium*) and "beti" (*Dalbergia latifolia*) is said to be very satisfactory.

The same remark cannot, however, be applied to the sandal, the Deputy Conservator reporting that there has been no diminution in the disastrous ravages of the "spike" disease in naturally grown sandal. "As was mentioned last year, an attempt was made to check the spread of this disease at the Harangi river by the extraction of diseased individuals. It seems, however, that the disease is capable of infecting trees otherwise than through their own species. A total number of 20,000 infected trees and plants of all ages was extracted in the tract north of the river. The work was systematically taken in hand *villagewar* by parties in the charge of responsible Deputy Rangers and Foresters, and from personal and careful inspection of several localities, I am satisfied that the work was reliably carried out, but it is disappointing that on re-inspection at a later period fresh trees in considerable quantities were found to be attacked. The above area has already been twice gone over, yet the disease is constantly reappearing. Frequent observation has proved that the period from the first appearance to the death of a large tree runs from 9 to 12 months."

This spike disease still appears to be shrouded in mystery, as neither Dr Butler nor Mr Barber have been as yet able to publish reports elucidating the source of the attack. Consequently methods of counteracting it have yet to be devised.

Under the present orders of the Inspector-General of Forests an extension of 30 acres per annum of sandal planting was commenced during the year, and the existing plantations selected for maintenance were carefully weeded. The total cost of sandal cultural operations was Rs. 581, the weeding costing Rs. 470.

During the year 209 tons of rough sandal wood were brought into the depôts, which were dressed into 201 tons of good wood end chips, making, with the balance on hand of these latter from last year of 108 tons, a total of 309 tons. In addition there were also 32 tons of rough wood on hand from last year. Of this quantity 204 tons were sold during the year and 13 tons were written off as dryage. The balance in hand at the close of the year was therefore 92 tons of good wood and chips and 32 tons of rough wood. The amount realized at the annual auction for 204 tons put up for sale was Rs 90,479, *viz.* an average of Rs 443 per ton. This is the highest rate obtained to date.

A total of 301,096 cubic feet of other timber and poles was removed by Government agency and purchasers, whilst 5,330 cubic feet were given in free grants. In addition 108,020 cubic feet of poles and 132,970 bamboos and reeds by Government agency and purchasers.

The following table compares the results of the year with that of the preceding year:—

Forest year.	Division.	Revenue.	Expenditure.			Net results.
			A.—Conservancy and works.	B.—Establishments.	Total.	
1	2	3	4	5	6	7
		Rs.	Rs.	Rs	Rs.	Rs.
1900-01 ...	Coorg.	1,43,919	28,267	43,620	71,887	+72,032
1901-02 ...	,,	1,69,556	40,329	45,118	85,447	+84,109
Average for the 5 years ending 1900-01.	...	1,34,468	...	..	76,265	+58,203

The gross receipts were Rs.25,637 in excess, which is mainly due to the increase of Rs.25,700 under sandal wood The total expenditure shows an increase of Rs 12,000 under "A —Conservancy and works," which is mainly attributable to the cost of the Forest Settlement staff, *i.e.*, Rs. 11,000. Notwithstanding this latter additional expense and the large balance of sold but unpaid-for timber, the net surplus of the forest year was Rs. 84,109, which is the highest recorded.

The report we have reviewed above, whilst being short and compact, is of exceeding interest, and Mr. McCarthy is to be congratulated on his excellent management of so varied and highly interesting a division, not the least point of interest in which is the fact that it has produced one of those difficult and apparently unsolvable problems in Nature which at times crop up and defy the accumulated knowledge of Science to provide a solution or remedy. In the words of the Poet—

O Star-eyed Science! has thou wandered there,
To waft us home the message of despair?

The Fauna of British India.

The Fauna of British India, including Ceylon and Burma. Edited by W. T. Blanford, F.R.S. Hymenoptera—Vol. II.—Ants and Cuckoo-Wasps, by Lieutenant-Colonel C. T. Bingham. Taylor and Francis.

Dr. Blanford, and through him the Government of India, are to be congratulated on the steady issue of the volumes of the *Fauna.* It will be well understood that no exact regularity can be maintained, but the series of volumes already issued, which comprise the Mammals, Birds, Reptiles (including snakes), and Fish amongst the Vertebrates; the Moths, Hymenoptera Aculeata (Ants, Bees and Wasps, and a portion of the Rhynchota amongst the insects and the Arachnida are an important contribution to a knowledge of the fauna of the country. In an age when biology demands philosophical conclusions, these books play a prominent part, though they are, as a rule, purely technical. A species must be known and recognised before any accurate observation can be recorded about it, and therefore we must cheerfully labour as descriptive hodmen before that golden age arrives when the weary describer will be at rest, and remembered only as a writer of necessary muniments.

Colonel Bingham has made the Indian Hymenoptera, and more especially the Aculeata, which this second volume completes, a special study, and his book can therefore be received as authoritative. That peculiar little group the Cuckoo-Wasps are included and are illustrated by a very handsome plate, the work of Horace Knight.

It will doubtless interest Forest Officers to hear that Dr. Blanford has now entrusted Colonel Bingham with the volumes on the Indian Butterflies, and we feel confident that the work could not be in better hands, and shall look forward with great interest to the results of his labours. Colonel Bingham will be glad to receive at the British Museum (Natural History) collections and specimens of all, even the commonest, Indian butterflies, only stipulating that localities where taken, with elevation and if possible dates of collection, should be recorded against each specimen sent.

V.—SHIKAR AND TRAVEL.

The Waterfalls of the Southern Shan States.

By W. H. Craddock.

The Southern Shan States comprise a vast area of country which separates Burma proper from Siam and French Indo-China. They are made up of a number of States ruled by Chiefs with the advice of British Political Officers. Much has been written about the resources, climate and other matters relating to these States, and the Viceregal visit to the Northern

Shan States and the visit of the Shan Chiefs to the Delhi Durbar has had the effect of bringing Shan affairs of late into some prominence. With the railway from Thazi on the main Burma line to Taunggyi, the capital of the S. Shan States, within view of soon being an accomplished fact, and with the extension of the cart-road to the Salween, the opening up of the country will proceed with very rapid strides. The enormous energy represented by waterfalls will in the future without doubt form an important factor in bringing this about. The following notes on the principal waterfalls might therefore be of some interest. I should mention that all these falls are west of the Salween in tributaries of that river, with the exception of the Langa Rapids, which are in the Salween itself:—

1. *Staircase Falls* on the Nam Pang river, Kenghkam State, a few miles south of the town of Kenghkam. The staircase is some 1,200 yards long and 300 to 400 yards wide, with an approximate fall of 150 feet

EARLY MORNING ON THE LANGA RAPIDS, S. SHAN STATES.

2. *Tu-hsai Falls.*—These falls are situated in the Kenghkam State at the junction of the Nam Pang and Salween, and have a drop of some 50 feet.

3. *The Teng Falls.*—In the Kengtawng dependency of the Mongnai State. Unfortunately these falls are not easily got at and less easily photographed. My first view of them was from a hill 18 miles away as the crow flies, and even at this distance the boom was distinctly audible. The Teng river divides into three branches and falls over perpendicular cliffs 200 feet and more in height.

The clouds of spray are loaded with lime in solution, which is deposited on the foliage several hundred yards around. On going close up under the fall between 8 and 9 A M, one sees the remarkable phenomenon of a complete circular rainbow with a diameter of 12 to 15 feet, on the arc of which the spectator appears to stand. These and the Staircase Falls (No 1) are, I consider, the grandest sights in the Southern Shan States.

4. *Tam-upak Falls*—In Hsatung State at the junction of the Nam Tam-upak and Nam Pawn A fine fall of about 60 feet, but practically dry from March to May, as the bulk of the water in the stream higher up is drained off for irrigation purposes.

5 *The Langa Rapids* These rapids, of which a photograph is shown here, are situated in the Salween river, Mong Pan State. A good deal has appeared of late in the Burma papers regarding the navigability of the Salween These rapids are by far the most difficult (if not insurmountable) obstacle to the navigation of the stretch of the Salween lying in the Southern Shan States.

VI.—EXTRACTS, NOTES AND QUERIES.

The Home Timber Trade and Forestry.

PART I.

Do home timber merchants, as a whole, take sufficient interest in forestry? If the question is put bluntly to many of them they reply, if they are honest, that their interest extends only to deforestation, not to reafforestation. This is certainly a most incorrect and narrow attitude to adopt, but unfortunately it is the attitude displayed by a large proportion of the trade, although, on the other hand, a few merchants take as keen and deep an interest as it is possible for anyone to do in their position. The present unsatisfactory condition, and utter inability to withstand the invasion of foreign timber, is due to the gross negligence of adequate reafforestation in the immediate past; and we are compelled to recognise that the whole future of the home timber trade for the next century and a half is bound up in the development of British forestry during the current decade. Over 50 years ago far-seeing men did not hesitate to warn landed proprietors of the looming exhaustion of our timber supplies, in spite of the fact that the immense consumption of present times was far beyond their sphere of calculation Little heed, however, was paid to their oft-repeated admonishments, which were sometimes couched in no measured language But instead, those who took up the vocation of prophets were looked upon as mere alarmists, without proper premises for their warnings; and, as a result, the old policy of deforestation without reparation continued unchecked upon its course, and now the country is slowly awakening to the fact of denuded supplies, and huge tracts of barren and waste land without profit in their present state to either man or beast. And also, as a direct consequence of this suicidal policy of dogged destruction, one of our most ancient industries—the home timber trade—finds itself in sorry plight, in the place of that prosperous condition in which at one time it was possible to build up a comfortable fortune; and in looking upon the remnants of this important industry flickering with fitful flame instead of burning steadily and brightly, the question arises: Is not the stern reality of pressing necessity sufficient to inspire a greater interest in those fundamental elements upon which the existence of the trade primarily depends? No greater inducement to a reawakening than this is possible, and if it fails to remove the apathy the situation is indeed hopeless.

It may be thought by many that the only interest that can be shown by home timber merchants in forestry is of a passive nature. To a great extent this is true, but there are ways in which an active interest may be manifested. It must always be remembered that forestry is the basis of the home timber trade; in fact, it must be looked upon as an essential part of the trade—the source of supply—and any deterioration or negligence in this department is bound to be reflected in all the other departments. The forester is the friend of the merchant—not the opponent—and anything that benefits the former has a reciprocal effect upon the latter, and any advantage accruing from an improved system of forestry must exert a beneficial influence upon the whole trade. Any tendency, therefore, towards the increase of the timber supply, and the production of a higher standard than has hitherto been produced, and which can only be brought about by an improved and more scientific education of the forester, ought to be actively supported and encouraged by the timber merchant, as his own business must ultimately benefit to an immense degree.

In the recently-published evidence taken by the Government Commission on Forestry great stress is laid upon the importance of educating the forester. The present general imperfection and inadequacy of this education is clearly admitted on all sides. In their summarised report, published at the end of 1902, they state: "It is hardly too much to say that until within the last ten years or so owners of woodlands, with few exceptions, failed to realise that the shape, size, and quality of trees could be influenced by anything that they could do. They seemed to imagine that the character of the final product was largely a matter of accident, whereas it is mainly determined by management. They failed to recognise that cultural treatment which suits oak or ash is unsuited to pine or spruce; and so it has come to pass that British coniferous timber has been generally excluded by architects from building specifications. . . . That the yield of our woodlands can be materially improved admits of no doubt, and the evidence before us unanimously favours immediate and effective provision for bringing systematised instruction within the reach of owners, agents, foresters and woodmen. This has been on all sides emphasised as the first requisite in any project for the improvement of forestry, and consequently stands out as the cardinal point of our recommendations." The different methods suggested for establishing systematic education for all those connected with woodlands, briefly, include: For future owners and agents additional facilities for theoretical instruction and practical demonstration at our universities, as well as at agricultural colleges, and colleges with agricultural departments subsidised by the Board of Agriculture, or by the Scotch Educational Department; for foresters, the establishment of at least two large State forests for demonstrating the most perfect technical and economic developments of the art of forestry; for working foresters and woodmen, an employment with regular wages, for a certain term upon the State demonstration forests; for foresters and woodmen unable to leave their posts to go through the training in the demonstration forests, short courses in forestry, supplemented by County Councils offering scholarships or bursaries.

In the next part of this article we shall have more to say upon this education question, and also upon the problem of our waste lands, amounting, we are informed, to 21 million acres.—*Timber Trades Journal.*

Rubbers and Fibres.

THE following is the full text of Mr. Cameron's paper on "Rubbers and Fibres," read at the United Planters' Association Conference Bangalore.

MR. CHAIRMAN AND GENTLEMEN,—Three years ago I had the honour of reading you a paper on industrial exotics. Since that time considerable progress has been made in the acclimatisation of such plants, and knowing more about them, I make no apology for bringing forward the subject again to-day. The prevailing prices of coffee and tea are less hopeful than they were three years ago, and unless some unexpected reaction takes place in the supply from other countries, the outlook, especially in the former product, is not cheerful. But fortunately for the Indian planter, there is an increasing demand in the markets of Europe and America for other products which he may be able to supply; and it is concerning some of these that I venture, with your permission, to say a few words. In official correspondence with planters I am frequently asked for advice in the selection of cultures suitable to this part of India. This paper may, therefore, be of some general service as a *précis* of my views on the subject.

The vegetable products for which there is a growing demand are India-rubber, textile fibres, tans, lubricating oils and fancy woods. There are also numerous other products which it is impossible to refer to in one paper.

RUBBER-YIELDING PLANTS.

So pressing is the demand for good rubber at the present time that, while experts are exploring the world for further supplies, the chemists are actually trying to manufacture an artificial caoutchouc. If they should succeed in the latter attempt, rubber planting would, I suppose, become an unprofitable enterprise. But it is unlikely that they will succeed to copy nature exactly. I should here mention that an artificial product claiming to possess all the best properties of gutta-percha is now manufactured in Germany, and is used for insulating wires and cables. Then let us see, gentlemen, how we stand in regard to a possible rubber industry in Southern India. Of several rubber-producing plants on trial, the American trees stand out prominently in the estimation of the public. These are *Hevea braziliensis*, producing Para rubber, *Castilloa elastica*, the source of Central American or Panama rubber, and *Manihot Glaziovii*, which yields Ceara rubber; here entered in the order of merit as regards the quality and value of their respective rubbers. But the prominence of these trees is due to their extensive use and productiveness in America, where they form part of the arborescent flora of the country, and we have still to learn, to a large extent, how far they may prove remunerative to the State and planter when cultivated as exotics in this country.

This brings me to my own experiences of the three trees, and as far as their utility to Mysore is concerned, I am going to reverse the order of things by putting Ceara first and Para last. Within the past decade the Ceara tree has thriven amazingly, and has certainly come to stay in the country. It will flourish from the seaside to an elevation of at least 4,000 feet. Matured trees shed their seeds so abundantly that thousands of seedlings can be picked up wherever a few trees abound. Nor is it an unproductive tree, as it has so long been considered in this country. Recent tapping experiments in the Lal Bagh have conclusively proved that trees ranging in age from 8 to 14 years are highly charged with latex, and that the latter flows freely when tapped at the correct season and in the proper place. During the dry season, when the tree is leafless, the large root limbs should be tapped; and after the rains the operation should be transferred to the trunk, which yields its milk sap freely throughout the cold season. These experiments have also proved that, as regards the productiveness of latex, no two trees are exactly alike. Between the two extremes of a copious discharge and hardly any discharge at all, we seem to possess every degree of productiveness. This peculiarity does not appear to be due to situation, exposure, or even the quality of the soil, in whole, as two trees growing together under the same conditions of soil, etc., were found to be wholly different in the amount of latex they contained. It seems to be rather a constitutional feature that some trees contain more laticiferous vessels than others. In view to ascertaining what quantity of rubber a mature tree will yield without being injured, a specimen has been tapped twice a week for the past three months, and the coagulated latex (it is not all pure rubber, as I shall explain later) now amounts to a trifle over 3lbs The experiment is going on, as the tree shows no sign of exhaustion, either constitutionally or in the flow of latex. Early dawn is much the best time of the day for tapping, and the operation should cease about 8 A. M. The quantity collected from each of these tappings has varied from half an ounce to two and a quarter ounces.

What we have to do now is to raise nurseries of seedlings from the good trees and try to eliminate the bad ones. Being so hardy during long periods of drought, the Ceara tree would adapt itself readily to many of the scrub tracts at elevations ranging from 1,000 to 3,000 feet, with an annual rainfall of 25 to 40 inches. We know, of course, that it grows vigorously at higher elevations where the rainfall is heavy. But there seems to be a doubt (although nothing is proved) if the outturn of rubber would be as plentiful and good under the latter conditions of growth. Personally I am in favour of the maidan as the best location for a Ceara rubber industry on an extensive scale. This you will naturally think cannot be of much advantage to the planter, who is confined to the hills. But in a large concern of this kind the planter, with his matured experience and larger capital, is bound to have a share sooner or later. It is now proved beyond a doubt that the Ceara tree is wholly adapted to the climate of Southern India. It is also being proved that as it approaches maturity some varieties of the tree are highly charged with latex, and I may here state that the dry climate of the plains is all in favour of a pure rubber being easily prepared from the latter. American imports of the rubber into the United Kingdom are valued at a somewhat lower rate than similar products of Para and Castilloa. But with the improved methods of purifying the actual rubber by the extraction of hurtful ingredients, such as phosphates, resin, and albuminous matter, the best tree of the future will be the one producing the largest quantity of pure rubber or caoutchouc. The latter is suspended in the latex fluid in the form of minute globules, and needs to be separated in much the same way that cream is separated from milk. An ideal preparation of pure rubber would be to drain the latex from the tree by means of a syphon into a kind of churn where the caoutchouc is separated by centrifugal force. It follows from this that any rubber at once depreciates in value when it is allowed to coagulate with all its impurities as it is taken from the tree. This ball of rubber, for instance, which was taken from a tree a few days ago, is full of hurtful ingredients rendering the whole mass subject to the growth of fungoid disease and putrefaction, results which are greatly aggravated in a damp climate. The old American remedy to prevent disease was sun drying and smoking. But that is only partially effective and does not purify the rubber.

We now come to a brief review of *Castilloa elastica*, which has also attained the reproductive stage in the Lal Bagh In its culturable requirements this important tree seems to be intermediate between the Para and Ceara species, requiring neither the tropical humidity of the former nor the open and comparatively dry conditions of the latter. It is, in fact, a tree for the coffee zone, as, no doubt, some of you have already discovered.

Mr. C. O. Weber, an expert, who has recently visited Castilloa, a plantation on the Isthmus of Colombia, writes thus:—

"All the reliable evidence seems to show that the trees grow badly in dense forests, and produce a poor yield of rubber when grown on open ground. They appear to prosper best when growing up together with other trees, so that the trunk is always shaded, whilst the top of the tree, at least for a certain time during the day, receives the direct rays of the sun." These are the conditions which I have also found most favourable to the growth of Castilloa at Bangalore Our trees, which are about nine years old, have only been tapped very slightly in one or two places to see if the latex would run freely. It appears to be a characteristic of at least two varieties of the species that the latex does not run freely, but collects in beads and tears under the punctures. Local trees are apparently of this class. Mr. Weber further writes that in Mexico and Ecuador the latex fluid runs freely. Three distinct varieties are described by this authority, *e.g.*, *C. elastica alba*, the richest variety, producing a thick creamy milk. *C. e nigra*, yielding a thin fluid, and easily bled to death. *C. e. rubra*, affording good rubber but deficient in quantity. These names (which indicate the colours white, black and red) have reference to the colours of the bark in the different varieties, there being no botanical difference. The first named is apparently the best tree to get hold of. The seed of Castilloa ripens here in May. But as yet we have only a limited quantity—3,000 seeds were sent out to planters this season. It loses its vitality in a few weeks if not sown, and I have not observed any self-sown seedlings under the trees, as happens in the case of Ceara. But there will be no difficulty about propagation as the species increase in age and number. I only hope we possess the most productive variety. What has been said previously about centrifugalisation applies with even greater force in the preparation of this valuable rubber, which readily blends itself to such treatment. There is a large percentage of albumen in the latex, which if left for even a short period would cause fermentation in the solid product.

Although I do not say positively that Castilloa would fail on the maidan, I certainly think it will have a better chance in comparatively open spaces throughout the coffee zone. Indeed it may become a good shade tree for coffee for all we know at present.

Now we come to the last of the three American trees, *e g.*, *Hevea braziliensis* or Para Rubber. When pure, the latter is worth Rs. 4 a lb., and is admitted to hold the market at present. But under improved methods of preparation it will soon be closely run in quality, and perhaps greatly exceeded in quantity, by the rubber which I have just reviewed. Anyhow, it is not likely to be of much practical use in the drier parts of India: therefore, we are justified in turning our attention to more hopeful subjects. The Para rubber tree is essentially tropical in its requirements, and needs a humid atmosphere such as is found in the Amazon Valley—its native habitat. Ceylon has started cultivation in a small way. But the only Eastern country which is likely to compete on fairly equal terms with Amercia is the Malay Peninsula and Archipelago. Along the West Coast of India, and in moist situations under the Ghauts there may be spots where the climatic conditions are tolerably favourable. But careful experiment should be conducted before a large investment is made. At Bangalore the tree languishes and dies during the long dry season. Irrigation gives only temporary relief, as there is too little moisture in the first four months of the year.

The Assam rubber tree (true India-rubber) *Ficus elastica*, I have all along said will grow well in the coffee districts, and the reason why it is not found there in quantity is possibly due to the difficulty of rapid propagation. But in any South Indian rubber plantation this useful tree should certainly find a place. It is said to be doing well in the Straits Settlements.

Much nonsense has been written lately concerning a new rubber plant—*Landolphia Thalloni*—found on the French Congo. I have little doubt, too, but some of the writing was done to influence the rubber trade, for good or otherwise. The latex of this little shrub, which is only half a foot high, is chiefly stored in the root. But this is not an exceptional discovery, as I have shown in this paper that the roots of the Ceara rubber tree are full of milk sap. So are the roots of several species. Scientific experts who are in the best position to judge are not of opinion that this latest discovery will influence the rubber market greatly. They rather expect that many similar discoveries may be jumped upon us during the next few years. The African genus *Landolphia* promises to be a large one, and doubtless all the species contain latex. We have one or two species on trial which grow well. But as climbing plants they are not, in my opinion, very suitable for rubber farming in this country. Should we be driven to utilise climbers in preference to trees for our supply of rubber, which is improbable, the long established *Cryptostegia grandiflora*, a plant of Madagascar, offers a richer source of rubber, I believe, and it can be grown without trouble. It is known around Bangalore by the local name *Mate wuli umboo* In concluding these details of my own experience with some rubber yielding plants you will gather, gentlemen, that I favour the selection of Ceara for the plateau of Mysore and Castilloa for the moister region of the hills Para may succeed in parts of tropical West India; but of that I am uncertain.

FIBRES AND SERICULTURE.

The fibre industry is passing into the practical stage, and seems to hinge, at present, on capital outlay and a good market. Cultivation, as I told you on a former occasion, is assured in this country, where there are fibre yielding plants suitable to almost every condition of soil and climate. The plants most suitable to the tea and coffee tracts are those producing Rhea hemp, Mauritius hemp, and perhaps Manila hemp; while at the highest elevations on the Western Ghauts, in somewhat sheltered positions, of course, an unlimited supply of New Zealand flax (*Phormium tenax*) and Bon Rhea (*Villeburnea integrifolia*) could be produced.

Sericulture is also well worthy of trial in the drier districts. In connection with the latter industry the new Japanese reels recently imported by Mr. Tata promise to increase the value of local silk by at least 50 per cent. A consignment of silk thus reeled on Mr. Tata's farm, has been valued by the Home brokers at Rs. 13 per lb., and is highly praised for its excellent quality. Silk prepared by the native method is only worth Rs. 5 to Rs. 6 per lb. What we really require for our Indian industries is the best class of machinery that can be procured. Even the few products which I have named require three distinct machines or apparatus. These are, firstly, a powerful engine with decorticator, like Todd's, (costing £600), to manipulate strong leathery leaves such as afford the so-called aloe fibres, bowstring hemp and New Zealand flax. Also Death and Ellwood's scraping wheels worked by Marshall's portable engines. The latter appear to be exclusively used in Yucatan, where a single wheel can clean leaves at the rate of 20 per minute. For further information on this point, I would refer you to an interesting article which appears in the last issue of *Planting Opinion*.

Secondly, a machine after the style of Faure's, priced, I believe, at £100, to deal with the more delicate fibre of Ramie, Rhea, and possibly Manila hemp. Then we find that with proper reeling the value of silk is greatly enhanced. It is not, however, necessary that every grower of fibre should possess a machine;

The one used by the South Indian Fibre Company is carried all over the country-side, just like a threshing machine at Home. It would be the same in dealing with silk, which is not a bulky article. One central depôt for reeling should suffice for a large area. Although essentially a poor man's industry, I see no reason, especially in times of planting depression like the present, why the planter should not have a mulberry patch and try his hand at sericulture.

In Assam, the Bengal Rhea Syndicate possesses a large area of cultivation, and it is highly probable that Ramie and Rhea may do for the north of India what the aloes and hemps are expected to do for the south.

The common railway aloe, *Agave americana*, has risen to the expectations of the South Indian Fibre Company, whose best consignments have realised as much as £32 per ton of clean fibre. This only shows what a splendid opening there is in this country when Sisal and other first class fibres shall be established in quantity, and supplies assured to the brokers at Home. Another healthy sign is the increasing local demand for plants of Sisal and the Mauritius hemp. At the gardens we are booked for all that can be raised during the next two years—approximately a couple of lakhs. Fortunately our Sisal plants have commenced to pole and propagation from that source already amounts to about 18,000 plants.

There are in Mysore alone, as you well know, immense tracts of poor, but still comparatively good, land under scrub. Many of these tracts, situated near the railway, I should like to see taken up for the cultivation of fibre and Ceara rubber, of the success of which, if properly taken in hand, there can be no doubt whatever. At present the two redeeming products on these lands are grass for cattle and the tanner's shrub, *Cassia auriculata*, yielding *tangedu* bark, the staple tan of the province. High prices are offered for the best tans, evidently because natural supplies are unequal to the requirements of the time. The pinch is being felt, for instance, at Cawnpore, where there are extensive leather and boot factories. The babul tree, which furnishes the bark in that locality, is becoming exhausted, and to carry bark in bulk from distant parts of the country is too expensive. For this reason, and for its richness in tannic acid, the comparatively light pods of the Divi Divi tree command a high price and are eagerly sought for. Plantations of this useful tree should certainly be raised at elevations ranging from 1,000 to 3,500 feet, with a rainfall of 30 to 70 inches. The Divi Divi is a very hardy and long-lived tree, which becomes more productive of pods (fruit) up to at least 60 years of age. It needs an open situation with good drainage. I am now in a position to supply a large quantity of seed, should it be bespoken some months before the ripening season at the close of the hot season.—*Madras Mail.*

Working of State Forests in Russia.

THE *Journal de St. Petersbourg* of the 15th May summarises a report published by the Russian Ministry of Agriculture and Domains on the working of the State forests during 1901.

The gross revenue derived from this source is given as 57,486,900 roubles or six millions sterling, of which 54,046,029 roubles resulted from the sale of forest products, an increase of 384,258 roubles compared with the previous year.

The forest lands under the general forestry administration on 1st January 1901, covered a total area of 237,927,789 dessiatines (dessiatine = 2·7 acres), consisting of 12,520 different forests, an area which was augmented during the year by 921,960 dessiatines, principally in Asiatic Russia.

On the other hand, forests under the desmesnial forestry administration showed a total diminution of 256,614 dessiatines, the result of a revision of the forest boundaries.

The net result shows that on the 1st January 1902 the forest lands placed under the jurisdiction of the general forestry administration amounted in area to 238,593,155 dessiatines consisting of 12,562 forests

Paper Mills in British India.

THE following particulars concerning paper mills in India have been received at the Board of Trade through the India Office:—

There are eight paper mills in operation, three in the Bombay Presidency, four in Bengal and one at Lucknow. Out of the eight, two are private concerns in the Bombay Presidency. The capital invested, so far as information is obtainable, amounts to Rs. 73,20,000. Most of the white and blue foolscap and much of the blotting paper, notepaper and envelopes used in the Government offices is now obtained from the Indian mills. The total quantity of paper made in 1902 was nearly 47 million lbs., and its reported value Rs. 64,38,319. The mills employ 4,865 persons. The capital employed has been trebled in 20 years, since 1883, and the production and number of persons employed have increased about six-fold. But in recent years there has been a depression in the paper making industry in Bengal, owing to the importation in large quantities of cheap paper made from wood pulp, which is of more attractive appearance, if less durable, than paper made from grass, gunnies, and rags in the Bengal mills.

The following table shows the progress of paper mills in India during the last five years :—

	Number of mills at work	Capital employed (as far as known)	Daily average number of persons employed.	Production.	
				Quantity.	Value.
		Rs		lbs.	Rs.
1898	8	62,72,000	4,187	42,181,590	61,06,459
1899	8	67,72,000	4,436	44,428,440	62,40,905
1900	8	70,22,000	4,871	45,940,591	62,51,748
1901	9	73,20,000	4,978	46,713,125	65,83,724
1902	8	73,20,000	4,865	46,654,833	64,36,319

VII.—TIMBER AND PRODUCE TRADE.

Churchill and Sim's Wood Circular.

Dated 5th August 1903.

East Indian Teak.—The deliveries during July have been only 975 loads as compared with 1,653 loads in July last year, making the deliveries for the past seven months 6,562 loads against 7,989 loads for the same period of 1902. The market in London has shown some slight weakness during the month, the extreme prices current being difficult to get for anything but first-class wood, and of that there is little. There is still no prospect of any rapid return to anything like a normal supply ahead.

Rosewood—East India.—Sizeable and really good logs are in demand but inferior wood is not wanted.

Satinwood—East India.—Sizeable wood, sound and round, would realise good prices, but inferior pieces are very unsaleable.

Ebony—East India.—For really good logs there is a fair demand.

PRICE CURRENT.

Indian teak, logs, per load ...	£10 to £18 10s.
" " planks " ...	£13 to £20.
Rosewood, per ton	£8 to £11.
Satinwood, per s.ft.	6d. to 18d.
Ebony, per ton	£8 to £11.

Denny, Mott and Dickson, Limited.

WOOD MARKET REPORT

1st *August* 1903.

TEAK.—The landings in the docks in London during July consisted of 1,357 loads of logs and 984 loads of planks and scantlings, or a total of 2,341 loads, as against 287 loads for the corresponding month of last year. The deliveries into consumption were 759 loads of logs and 234 loads of planks and scantlings—together 993 loads, as against 1,541 loads for July 1902.

The dock stocks at date analyse as follows:—

	5,580	loads of logs,	as against	6,030	loads	at the same	date	last year.
	3,738	„ planks,	„	3,386		„	„	„
	—	„ blocks,	„	—		„	„	„
Total	9,318	loads	„	9,416	loads	„	„	„

The above figures show a wholesome increase in the supply both of logs and planks. The demand for planks is increasingly restricted through the high price necessarily demanded by holders here. There is, however, a fair demand for logs owing rather to naval than to commercial shipbuilding requirements. The increasing importance of the South African and American demand for teak continues to conduce to making the Indian shippers masters of the position, and although the high level of price is strangling the teak trade in Europe, it is idle to expect shippers not to put their wood on the best market. There is, however, increasing signs that this market will no longer respond to higher values for planks, which, as explained in previous reports, are now being displaced by other woods for domestic construction, and even in rolling stock construction the substitution of steel for teak frames has been greatly stimulated by the increased cost of teak planks.

Business during July has presented little feature of note. The want of animation has been accentuated by the commencement of the holiday season; and the f. o. b. values all round continue to be on so high a level that the chief aim of importers is to keep their forward stock commitments as small as may be compatible with the maintenance of their ordinary business.

Market Rates for Products.

Tropical Agriculturist, 1st *August* 1903.

Cardamoms ...	... per lb.	1s. 6d. to 1s. 7d.
Croton seeds ...	... ,, cwt.	15s. to 22s. 6d.
Cutch ...	... ,, ,,	20s. to 27s. 6d.
Gum Arabic ...	... ,, ,,	15s. to 20s.
Do. Kino ...	... ,, lb.	4d. to 5d.
India-rubber, Assam	... ,, ,,	2s. to 3s. 2d.
Do. Burma	... ,, ,,	2s. to 3s. 4d.
Myrabolams, Madras	... ,, cwt.	5s. to 6s. nom.
Do. Bombay	... ,, ,,	4s. to 7s. 6d.
Do. Jubbulpore	... ,, ,,	4s. to 5s. 6d.
Do. Bengal	... ,, ,,	3s. 6d. to 5s. nom.
Nux Vomica ...	... ,, ,,	7s. to 10s.
Oil. Lemon-grass ...	... ,, lb.	6½d.
Orchella weed, Ceylon	... ,, cwt.	10s. to 12s 6d.
Sandalwood, logs ...	... ,, ton	£15 to £30.
Do. chips ...	... ,, ,,	£4 to £8.
Seedlac ...	... ,, cwt.	115s. to 122s. 6d.
Tamarinds, Calcutta	... ,, ,,	8s. to 10s.
Do. Madras ...	... ,, ,,	4s. 6d. to 6s.

THE

INDIAN FORESTER.

Vol. XXIX.] November, 1903. [No. 11.

On Certain Important Forest Questions.

BY J. S. GAMBLE, F.R.S., C.I.E.

THE August number of the *Forester* has just come, and I hasten, as an old editor of the Magazine, to offer you and your colleagues my congratulations on the interesting papers I have found in it.

Two of them, in particular, seem to require some remarks, and I hope you will allow me to give my opinion on certain of the questions raised in them To some of the others I may refer separately, but the two papers referred to—the two first in the number—refer to questions of the highest importance to the welfare of the Department, and I think it best to send you what I have to say as quickly as possible.

The second paper contains Colonel Pearson's interesting reminiscences, which, I feel sure, all your readers will hope he will continue. Among old pioneers of the Department were several whose names and work might get lost sight of if nothing is done to recall them to memory. The "Highlands of Central India" was, and is still, a classic work on Indian jungle life and Indian sport: it also contains much information about the beginnings of forest work in the Central Provinces, but its author was too modest to say much about himself. Colonel Pearson has therefore done well to tell us something about Captain Forsyth, and I hope that he may be induced to tell us more. I have been greatly pleased to find that he has recalled to notice Major Douglas, for he was the first Divisional Officer I served under, in the Tharrawaddy Division in Burma, and I had already known him because when I was at Nancy he came there when on furlough and spent some time with us both in the lecture-room and on tour in the forest. He was one of the best of chiefs and most lovable of men, and the picture of him which I still possess I value highly. He was "a fish out of water" in Burma: accustomed to Hindustani peoples and Central Indian jungle tribes, he did not take very kindly to Burma ways. He was far more interested in such work as he had been doing in the Central Provinces and Berar—the selection and demarcation of reserves, their opening out by roads and paths, their protection from fire, and the supply of material to villagers—than in the timber works of Burma—the operations of girdling and extraction and the collection of a large revenue. His move to Burma affected his health and energy, and when, too late, he was transferred to the Punjab, it was only to die without having the chance of becoming a Conservator. I hope Colonel Pearson will tell us more about him and of other similar pioneers of Indian Forest Administration. And here, Mr. Editor, may I suggest to you the compilation, say, for those officers who served in the Department during the 19th century, of a list, with brief biographical notes on those who are no more.

I am glad that he noticed the great services which the late Sir Richard Temple rendered to the establishment of forest conservancy, and as one who on several occasions accompanied Sir Richard on his tours in the Darjeeling hills, I can say that Lower Bengal forestry at any rate had no better friend, unless perhaps it was Sir Richard's predecessor Sir George Campbell, or his successor Sir Ashley Eden, for all three took the greatest interest in the welfare of the Department, and all three I am sure held strongly the opinion that its officers should be scientific men.

The point in Colonel Pearson's most interesting paper which has most particularly drawn my attention is where he says: "The use of the term 'Conservator' was also deliberately adopted by Government, as indicating more strictly the first duty of the Forest Department. Then, as now, there was a disposition in some quarters to insist on its being a revenue-producing department, an idea which, if carried out, would necessarily end in forest destruction." This is a most important remark and one which cannot too strongly be kept in mind, for, if I mistake not, the tendency of the policy followed by some of Colonel Pearson's successors has been to make the Department in the first place a "revenue" one and to some extent to relegate conservancy and improvement to the background, especially in some Provinces and most notably in Burma. In my opinion, and I believe I am not alone in the opinion, making the collection of a large surplus revenue the chief aim of a Forest Department is a dangerous policy in several ways, and especially as it may so very easily lead to over-cutting, to the neglect of works of improvement, to a falling off in the quality of the staff and in the interest taken in their work by both officers and subordinates, and to the gradual replacement of forest conservancy by forest "destruction" or at any rate "deterioration." In a recent paper read before the Royal Colonial Institute

I said: "I believe it to be a wrong policy to gauge the work of such a department and of its individual officers, as is only too often done, by the amount of their financial surplus. It is for the Government to decide what, and how much, produce is to be given free, but the consequent reduction of revenue ought not to be made the reason for the reduction of staff, a curtailment of work and a consequent loss of efficiency. Forest conservancy has a higher aim than that of merely giving so much revenue, and it is a mistake to encourage officers to risk over-cutting their forests in order to please the financial authorities. We have sometimes been made to understand that if we require a better staff and more expenditure on important works of administration and improvement, we must first show that they will pay, and for my part I believe this principle to be wrong."

Having drawn attention to Colonel Pearson's opinions and explained my full concurrence in them, I should like to turn to the first paper in your August number, in which another former Inspector-General of Forests, Sir D. Brandis, adds to an appreciation of the services of the late Inspecter-General Mr. Hill, whose recent sad death I and all his friends have been so sorry for, a few remarks all of which I am not quite sure Mr. Hill himself would have fully approved. Sir D. Brandis says: "The forests of Lower Burma had, since 1856, been worked on a well-considered plan, and had ever since that time yielded a steadily increasing annual crop of teak timber and of revenue. Now, since the annexation of Upper Burma, the net annual revenue produced by the Burma forests equals the net forest revenue of all other Provinces taken together. It stands to reason that service in Burma must be regarded as a necessary preparation for employment in the highest appointments." Here we have an indication of an opinion which seems to differ considerably from that of Colonel Pearson. I believe I am right in thinking that, at the present time, forest management in Burma is too much subordinated to the production of revenue. The selection, demarcation and settlement of permanent reserves, a work which elsewhere is completed or nearly so, is still very much behindhand in Burma. Fire protection, as we know from the correspondence that has gone on in the *Indian Forester* for several years, is in a backward condition, many officers expressing openly their disbelief in its utility. Of roads, not merely for export but for inspection and forest protection, there are practically none; houses for the staff have hardly been started; and the only works of importance that have been carried out, if I am not misinformed by the reports I have read, are the clearing of streams to improve them as waterways for timber floating, a very important work no doubt, but all the more useful if supplemented by good roads rendering access to the forests easy and simple. I see too, from your pages, that no good plans of campaign have been organised to deal with the critical period which will come when the bamboos flower. Excellent work in taungya plantation has been done; but what works have been done in those reserves where taungyas are not cut and where the constant extraction of only teak *must* be impoverishing the capital of the forest and encouraging less valuable species? In a recent number of the French forest magazine, the *Revue des Eaux et Forêts*, was published an extract from a report by the French Consul at Rangoon dealing with the teak trade. He says: "The remarkable decrease in the export trade in teak wood, and especially to England, is attributed to the small amount arriving in Rangoon and also to a notable falling off in the quality of the wood, timber suited to European requirements arriving in less and less amount each year. The total imports of teak wood into Europe during 1901-02 fell nearly 40 per cent, while the consumption only decreased 15 per cent. England seems to be losing its monopoly." How far the Consul's statements are accurate I have no means of ascertaining, but it rather looks as if, in the desire for revenue, the quantity cut for some years back has been greater than it ought to have been, so that the reaction is now beginning to be felt. I cannot say that I regret it, but I think that if the Burma officers could have their energies diverted for a time from the necessities of making large surpluses and could devote them to the consolidation and improvement of the estate, it would be a good thing in the end and give the new stock a little time to grow. I expect that in most Provinces the story is the same, in a greater or less degree, though I think that, of late years, there has been an improvement elsewhere than in Burma, and most of all in those presidencies where forest matters are not so directly governed by the Inspector-General's advice as they are in the north and where service in Burma is not "a necessary preparation for higher and more responsible positions." *

That arrangement of sending officers to Burma to qualify for promotion is, to my mind, a mistake. The opinion of a really good officer will always be of value, whether he has actually served in the locality or not, and just as a good officer was wasted when my old chief Major Douglas was transferred to Burma, so work in two Provinces may be retarded by sending a man from one which he knows thoroughly to another of which he knows very little. Then, too, there is the certainty that if not eventually given the promotion he has been sent to qualify for, he will ever after have a grievance. I think that I am just in saying that it is not to Burma that an officer would go to see the best systems of demarcation and settlement, the best fire protection, the best working-plans, the best communications, the best system of housing the subordinate staff, the best planting work, and the best arrangements for the extraction of timber. To really qualify, an embryo Inspector-General should see something of all Provinces, and that is manifestly impossible.

---

* Whilst printing our correspondent's article *in extenso* we would wish to disassociate ourselves from some of the opinions expressed therein, for which the writer is solely responsible. We trust that those Officers who have been, we feel sure through inadvertence, to some extent unfairly criticised, and those Provinces in which the progress of Forestry, owing to an evidently imperfect knowledge of the true state of affairs at the present time, has been adversely commented upon will find defenders. We shall thus be able to satisfy our distinguished correspondent, whose evidently keen and laudable interest in the welfare of the Service he so worthily adorned we all applaud, that his fears on the score of the quality and quantity of our progress since he left us are groundless.—HON. ED.

I should now like to say something on the "Botany" question. Apparently our old Inspector-General has persuaded himself that "shikar"* is the real special subject that Forest Officers should study. I may be wrong, but I do not think that this was always his opinion. There are plenty of officers who would be glad, I expect, if the Government took the same view, though it is hardly likely to, and nowadays few Forest Officers can get any time for shikar, for there are too many reports to be written and every moment available for out-of-doors has to be devoted to inspection, which usually means the companionship of quite a large following and the consequent absence of any chance of game. Those officers who do much shikar generally take, I think, an occasional holiday for the purpose, and a good thing too; but shikar and inspection are, I maintain, incompatible, for either you see the game and fail to remark what is doing among the trees or you see the trees and the game gets away. Sir Dietrich says that "many English botanists" hold the opinion that a good botanist must necessarily be a good Forester. I should like to know on what grounds he makes that statement, for though I have myself a considerable acquaintance among English botanists, I know of none who have, or were likely to have, said any such thing.

What some botanist may have said is that, *cæteris paribus*, the officer that is at home in the forests knows the trees that he has to deal with or can easily find out about them, knows their value economically and sylviculturally and so on, is likely to be a better man than one who does not. Sir George King, as an instance, said in his address to Section K at the meeting of the British Association at Dover in 1899: "To most people who give even casual attention to the matter, it appears fitting that the possession of a knowledge and liking for Botany should form a strong characteristic of officers whose main duties are to be in the forests."

---

[*] The writer would seem to have misread the article in question. Sir Dietrich says (on p 312): "Both love of sport and devotion to Botany and Entomology are most useful *helps, but they are not Forestry.*" The italics are ours.—Hon. Ed.

I well remember the secret feeling of despair which I had when, in 1872, I was sent to work in a region of many trees very little known. There were no "Forest Floras," no "Flora of British India," no lists with native and scientific names, and except one or two kinds nobody knew which trees had good timbers which worthless ones, what kinds were useful for building, which for fuel, what for valuable minor products and so on.

I found some small acquaintance with Botany and some capacity of studying such books as there were a great help, and it always beats me to imagine how men who really love the study of sylviculture can get on without rather more personal knowledge of the trees concerned than is given by a mere knowledge of the name and often not even of that. If he is to be really useful a Forest Officer has not only to know his trees, to understand their value and their physiology and how to make the most of their products, but he has to be also more or less a zoologist, a geologist, etc. It will be a bad day for the Department when it gets to be supposed that an officer need know none of these things, when he loses the prestige of being a scientific man and appears openly as only an official timber merchant with a dash of the policeman. Then there will be no need for Forest Officers, Burma-trained or otherwise, as Inspector-General or even as Conservator; a few junior Civilians will do as well; forest schools to teach useless subjects will be unnecessary, and the fabric of which most of us, and I feel sure, more than any, Sir D. Brandis himself, are proud, will crumble away. No! I say it emphatically if the Indian Forest Department is to preserve its prestige, it must be a scientific department and its officers must be capable of advising on all subjects connected with trees and forests and their treatment.

To think that the old Forester who, as he himself tells us, had the chief work in starting the Department, can imagine that the solution of "the problems of sylviculture and of forest management in a practical manner" can be effected without a good acquaintance with the individual species which make up the forest is a strange thing, and for my part I hope that the authorities will not take his opinion too seriously. The fact is, I expect, that he and others have a wrong idea in their minds in talking about "Botanists" or "Entomologists" or what not. They imagine such people to be those who think of and do nothing else; they have in their mind's eye the man with the collecting tin, only interested in the search for rare plants, or the man with the butterfly net and collecting tubes, or him with a hammer and chisel and a bag of rocks; but those are not the kind of persons that we necessarily want or that we need think of. The botanist or other "ist" that I should think of would be the one who keeps up his Forest School teaching in after times, who if he met with a tree he does not know can successfully use a "Flora" and with it find out what use it is and how it is to be treated, who understands well the main principles of plant physiology, who, if he comes across an insect doing damage knows how to go to work to find out what it is, and so ascertain what is known of the means of preventing its damages* and so on. A few men who are specialists are doubtless useful in the staff of a Forest Service, but it is not specialists that are required, but that all officers should know sufficient to be able to use their powers of observation with advantage, and to the benefit of their work. An officer who cares only for new plants, a new insect, a rare mineral or a pretty photograph *is not likely to be in the first rank as a sylviculturist*, *any* more than the one who is only interested in shikar or in polo or in lawn tennis or in billiards; *but in a general way they* are all useful things, and so far as the present mania for reports and correspondence allows, every officer should, I think, have a private study in addition to his work, if only as something to fall back upon when at last his pension time arrives and he takes his place among the unemployed at Home. The private interests make life in India much more endurable, and when these interests are of a kind to be useful in the officer's own work, it is all the better. I can, myself, call to mind the names of many of my contemporaries who had useful hobbies, and I can also call to mind many who were good all round with a sufficient knowledge of most of the necessary subjects and capability of using that knowledge. Careless writing, like that of Sir D. Brandis, is only harmful and dangerous, and, as I have before remarked, I only hope that the authorities at the India Office and at the Supreme Government in India will not attach too much importance to it, and indeed, I may add that I hope that it will not make the young men now in training at Cooper's Hill or Dehra Dun think that they can dispense with the study of scientific subjects which they are expected to pass in, and on a knowledge of which their careers in India will so largely depend. Shikar is an excellent amusement and is often a necessity, as the poorest shot knows well, for there may easily be cases where his dinner depends on his success; but it is not the only pursuit, or even the best pursuit, which will induce a man to "make the forest his home" and learn to understand it, to observe all that is going on, to devise improvements in administration, and when he leaves it finally to feel that it is in a better condition in every respect than when he assumed its charge. Every officer in the

---

* Mr. Gamble neglects to inform us how the Forest Officer is to attain this enviable position in the total absence of Indian works on this subject. He himself tells us that he felt a feeling akin to despair in [illegible] when he went to work in a region full of unknown trees. To the work of specialists, amongst whom he holds a place in the foremost rank, the Department owes the excellent "Floras" now in existence, and to the work of entomological specialists, and these will have to be found in the ranks of the Service itself, will the Department have to look if it is to be placed in a similar position with regard to a working knowledge of its insect foes.—Hon. Ed.

Service is called upon at some time or another to prepare working-plans. He has to begin with a description of the locality and bring in his knowledge of meteorology, geology and the composition and value of different soils. He has to go on to describe the forest growth and the idiosyncracies of the different species composing the forest as regards light, heat, climate and soil. He has to study the field agriculture of the surrounding district and the mutual relations between it and the forest. He has to describe and. if possible, map the boundaries, outer and inner, and apply to the subject his knowledge of surveying and geography. He has to study the legal position of the area and has often difficult questions to deal with in special systems of revenue settlement peculiar to the place. He has to describe carefully and carefully classify the forest crop on the various parts of his area, study its component kinds and their sylvicultural requirements, notice the various kinds of produce that it yields, capable of utilization for timber, fuel, minor wood industries, extracts for tanning, dyeing, medicine and other purposes; report on the injuries to which the crop is liable: fire, frost, climbers and parasites, grazing, insects, fungi and what not, with the best way to meet them. Then he has to describe the roads and rivers and other works of engineering met with or required, the markets for produce, and their positions and wants and the methods of extraction of material.

And when he has gone into all these questions, requiring not perhaps high special scientific knowledge, but a sound training in some substantial part, at any rate, of many subjects of both pure and applied science, he has to prepare his plan of working which is to last for many years and provide for the yearly utilization on the interest on the capital stock and the progressive improvement of the capital. Can it be said that all this (my description of subjects is taken from the Government authorized text-book on the "Preparation of Forest Working Plans for India") can be done by a practical man without regular training and without a proper knowledge of Botany and allied sciences? I feel sure that most impartial people will say no! As a final remark, I may suggest to such of your readers as are still sceptical, the study of the article "Forestry in America," by H. J., the commencement of which appears in your August number at page 323. If that does not convince him that Forestry, itself, I maintain, a scientific subject, cannot do without the aid of Botany and other allied sciences, I do not know what will. Indian Forestry, as Colonel Pearson says, must be something more than the mere collection of revenue if it is to maintain the position it has in India and the prestige it enjoys outside Indian limits.

The Training of Forest Officers.

OUR readers will have perused with interest an article on the training of Forest Officers from the pen of Colonel Pearson—an article which the Service will be proud of, since it proves the keen interest which its senior retired officers maintain in its efficiency, prosperity and well-being. We are happy to think that as long as those who have so brilliantly distinguished themselves whilst serving on the active rolls continue to evince, this keenness in our welfare we are not likely to deteriorate. There can be little doubt that the expression of their opinions on this important question of professional education, both by those on the retired and those on the active lists, would be of considerable value at this juncture, seeing that the Service is practically face to face with another threatened change in the training of its recruits. Colonel Pearson invites discussion, and his article affords plenty of food for serious thought and grounds for argument both for and against his propositions.

We have already advocated in the pages of this Magazine what we consider the ideal plan, the plan which we, as a Service and as the only trained Foresters in the Empire, know to be the true solution of the difficulty which may shortly have to be faced, our suggestion being the formation of an Imperial Forestry College and the training in England of English Foresters for service both at Home and throughout our dependencies This is an urgent need of the Empire. We have suggested that, in the event of the Royal Indian Engineering College being closed as an Indian P. W. D. training ground, Cooper's Hill, owing to its many advantages for the purpose in view, should become the headquarters of the Forestry College.

But whilst thus advocating the question of the maintenance of and the imperialization of the College, whether for the teaching of Forestry or—for the suggestion appears to be an equally sound one—for the training of both Forest and Engineering students for service in the Empire as a whole, as we have recently seen proposed in the columns of the *Pioneer*, it will be well that we should not lose sight of the other ways of dealing with the question—that we should not, in fact, place all our money upon the one horse, only to find that it gets 'left' and remains behind in company with the starting machine and its operator. We would wish therefore to consider here Colonel Pearson's proposition or suggestion of a return to the old system of training, a return to the Forest colleges of the Continent. This question, as in the case of the others, should, we think, be looked at in all its bearings and be thrashed out on its merits. We are aware that many of our best scientists have in the days of their youth studied in the lecture halls and worked in the laboratories of the great German specialists. We know that to-day many English students go to these German science schools for that thorough grounding in their subject which the supineness of our own nation in such matters precludes their obtaining at Home. And we ask, "Are they not justified in so going?" Whilst, the hallmark "Made in Germany" is often synonymous in the commercial world with the cheap and nasty, that same hallmark in the scientific world has long been acknowledged as being very much the reverse. And though made in Germany the Englishman does not remain there. Owing to some constitutional deficiencies he apparently usually requires more to eat than his German confrère, and therefore has to seek out spots in his own Empire where his pay will be more commensurate with his grosser appetite. It follows that the man himself and the Empire both benefit. It may be granted that this is not as it should be; but until we, as a nation, place the telescope at our seeing eye the true position of affairs will not be perceived. We are here concerned with facing realities, not the might be's. We think therefore that this question of a return to the Continent should not be approached in a spirit of carping criticism, but rather that it should be discussed in all its bearings in as judicial a frame of mind as any of the other proposals *sur le tapis*, since our first thought must be the well-being of the Service, and that well-being is entirely dependent and wrapped up in the kind of men recruited and the thoroughness of their Home training. That we all admit.

We are, however, of opinion that a return to a Continental college, should it become necessary, would require a modification of the old arrangements. The students during their stay at the college should, whilst getting the best of the Continental training, at the same time in some way be shown how the principles they are being taught bear upon Indian Forestry, be taught something about Indian trees, how to apply to Indian conditions what they have learnt in the European schools, etc., and that information would be required to be given at first hand week by week in the lecture-room as well as in the forest. As in the old days, there should be a Chief, of the rank of a retired Inspector-General, who would still be required to exercise a general supervision over the students' work, to perhaps accompany them on some of their more important tours, and to be the responsible officer to represent the India Office with the Continental college authorities; but we venture to think that something more than this Chief in necessary. With a couple of dozen students, which the numbers of the three years would total up to, it would be quite impossible for the Chief to cope with the necessary lectures, nor indeed would it be compatible with his position as the representative of the India Office that he should undertake such duties.

For the special Indian lectures at least two men would be required, and we would suggest that such men could be best found in, and taken from, the ranks of active members in the Service itself. Keen men and good men would be required to fill such posts, as on them would almost entirely depend the efficiency of the recruits coming out; but there would be no difficulty in obtaining them. In fact we surmise that the difficulty would rather be the other way, when it became only too apparent that the numbers to select from were only too numerous. These two officers would remain in residence at the college and should be made entirely responsible for the discipline of the students and for the manner in which they worked, etc. The details of fixing the hours of the Indian lectures would be a matter of simple arrangement with the college authorities. Under some such plan the senior officer in residence would hold much the same position as regards authority and discipline as is held by Dr. Schlich at Cooper's Hill, the Chief occupying one analogous to that of the President of Cooper's Hill. The introduction of this scheme would have several advantages. The men deputed would themselves greatly benefit by such a deputation and through them the Department. The fact of there being such posts available would form an additional incentive to the hard and keen workers, men who now look in vain for any stray plums on the Forest Tree,—that Tree of the many branches immortalised by a former Inspector-General. For although the Department knows how to grow trees, it certainly does not seem to be able to make this particular one bear much fruit, or is it that the foliage is so thick and dense in the lower portions that the twigs wither, die and drop off in their efforts to push up higher and see whether it does produce an odd plum or two? But the great advantage would, we think, lie in the fact that the Forest students would have as their Indian lecturers men straight from Departmental work and absolutely *au courant* with the changes that were taking place. The dictum *Tempora mutantur nos et mutamur in illis* is very true, even in the unchanging East, and perhaps nowhere more so than in the Forest Service in India. One has only to compare the progress made in the last decade with that of a decade before to become aware of this almost self-evident fact. As this progress is likely to be equally rapid in the future, we consider that the two lecturers on the Indian portion of the curriculum should be kept equally progressive.

We feel sure that in thus writing we shall not be considered to be in any way reflecting upon the present training of the Departmental recruits. We have already considered that subject and we would wish to see the present college and method of teaching put on an even wider basis. We are here dealing with the subject from one of the other points of view. In the event of the students going to a Continential college, the teaching posts available would only be taken by more junior men, and these could only be successfully looked for in the active service lists. We feel sure that our meaning will be clearly understood and that with us all *Salus populi suprema lex*, the Service taking the place of *populi*.

With regard to the selection of the officers to be deputed, we would suggest that the senior should have from 18—20 years' service, in fact be a budding Conservator, whilst the second should be sufficiently his junior to avoid there being any question as to the authority of the senior, *i.e.*, he might be chosen from 15-year service men. The officers so selected would be seconded, and their deputation might be for a period of three years corresponding to the length of time passed at the college by the students. This would reduce to a minimum the chances of a man getting stale and would bring in a succession of men fresh from actual work in the field.

We throw this out as a suggestion. Others will perhaps have better ones to make, and we trust they will give the Service the benefit of their ideas upon the subject There is one point upon which, we think, too much stress cannot be laid and upon which in all probability most agree. The Forester to be really efficiently trained requires special courses of lectures in the various branches he has to study, and these he cannot obtain except at a Forest College *proprement dit*.

Notes on Indian Trees, II—Notes on Hopea odorata.

BY D. H. ALLEN, *Forest Ranger.*

Hopea odorata, Roxb. Vern. *Thingan*, Burma.

A LARGE evergreen tree sometimes attaining a girth of over 12 feet.

Bark dark brown with deep longitudinal furrows, about half inch thick; the younger shoots are of a greyish colour. The leaves in some specimens are oblong, inclined to be lanceolate, in others ovate; young leaves puberous, becoming glabrous as they get old.

The flowers are small, white and very fragrant, growing on very short stems The fruit, a nut, is attached to a calyx with two long and three short lobes. This description agrees with that given in Kurz "Forest Flora."

The flowers appear in March and continue till April. The fruit appears in May and June.

It grows mixed with other species in the tropical forests of Lower Burma and is also found in the Pyinmana district. In Mergui and Tavoy it is plentiful. It grows up to an elevation of about 1,000 ft.

The colour of the timber varies from yellow to brown. The timber is hard, heavy, close and even-grained. It is said by the timber traders of Mergui that trees with narrow leaves have harder and better timber than the trees with rather broader leaves. The specimens of the former kind are said to grow chiefly in valleys and small hills, the latter on low-lying land and along the edges of the larger streams. The wood is very durable. It is used in Mergui chiefly for boat building; boats built of thingan are said to last longer than boats built from any other timber found in Mergui. Although attacked by *Teredo navalis* it is less susceptible to their attacks than the other timbers known here, except perhaps *Fagræa fragrans.*

While on the subject of boat building it may be of interest to mention the way the people here preserve their boats from the attacks of *Teredo navalis.* Once every month or so the boats are taken out of the water and raised off the ground by placing two logs or anything else that may be suitable under the two ends of the boat. A lighted torch made of split bamboo is then held and moved about under the boat till all the water that the wood has absorbed evaporates; this burning operation lasts about two hours; the boat is then well smeared with earth oil and allowed to stand for about six hours.

Thingan boats treated in this way are said to last for 25 years.

Thingan is also very good for house building, the timber in houses fifty years old showing no signs of decay. In Mergui it is seldom used for this purpose because a duty of Rs. 15 per ton is charged on it, and many cheaper timbers being available the people prefer to use these. The timber is also used for roof shingles, cartwheels and furniture. It makes almost as good shingles as teak. The Burma Railway has been supplied with a large quantity. The tree yields a yellow resin, which is sometimes used in varnish. Burmans use it in painting pictures. It is ground into a fine powder when dry and mixed with the paint; it is said that pictures painted with paint in which thingan resin has been mixed keep their colour much longer than they would otherwise. It is also mixed with ink for the same reason. The resin is also used for caulking boats; for this purpose it is said to be better than Pwenyet, the product of the dammer bee. It is not largely used for any of the above mentioned purposes, as the systematic tapping of thingan trees is not allowed.

The local price of round timber is Rs. 40 per ton; sawn timber is sold at Rs. 60. From 300 to 500 logs could be exported annually from here if the timber could be worked out.

It is, however, very hard to get contractors to work out timber in these parts, elephants being very scarce and the use of buffaloes for dragging being unknown.

Forestry in America.

By H J.

(*Concluded from page* 450)

In chapter IX. Dr. Fernow devotes nearly fifty pages to the "Principles and Methods of Forest Policy."

After summarising the principal contents of the previous chapters, the necessity for, and the justification of, the State's interference in forest matters are laid down. The providential functions of the State, as guarding the interests of the future, are performed by direct control, that is, by ownership, and management by its own agents; by restrictive measures, exercising police functions; and thirdly by education.

The first College of Forestry was instituted by the State of New York, 1898, and is administered by Cornell University. Among the most efficient means of education are *experiment stations:* the State alone can afford to conduct extensive investigations that must be continued for scores of years under systematic organization, and such experiment stations are obviously best utilized when worked in connection with educational institutions. A still more far-reaching influence, also of an educational character, is properly exercised by the State in securing and publishing *statistical information.*

These statistics would refer first of all to the use made of the soil.

All culturable soil should be devoted to systematic food production and the absolute forest soils to systematic wood production: certain forests too exercise a potent influence on cultural conditions, so that topographical location and its relation to the hydrography of the country are important to know.

To get an idea of the amount and value, present and future, of our forest resources we must know the composition, consistence, constitution and condition of the forests, and especially the conditions and stages of development of the young crop. The commercial side too is important, though a statistical investigation of market conditions or of the requirements of wood-consuming industries offers no great difficulty. Lastly, the methods of forest management as well as the condition of the resource call for statistical inquiry.

The Federal Government of the United States has lately inaugurated through the Forestry Bureau a system for the encouragement of organized forestry, which consists in giving private owners specific advice as to the management of their forests; the Government bearing the greater part of the expense of these working-plans.

A discussion of the principles of the State's taxation of forest properties, of export duties, and of the State's responsibility with regard to protection against forest fires and other injuries, and finally, a discussion of the right of the State to interfere in the management or mismanagement of private forest properties closes the chapter.

Chapter X is devoted to the forest policies of foreign nations, and shows an intimate acquaintance, both professional and administrative, with the forest policies of all the principal forest growing countries.

The past history and the present state of forestry of the following countries is given at some length, though in a condensed but interesting form:—France, India, the British Colonies, Russia, Austria, Italy, Switzerland, Sweden and Norway, and lastly Germany, to which country thirty pages descriptive of German forests and their management are devoted.

Chapter XI relates to the forest conditions of the United States. The actual area under forest is given roughly as 500 million acres, but this area has for the most part already been worked over and the marketable timber of the better kinds extracted The productive forest area is about 26 per cent. of the whole country.

The Federal Government started forest reservation so lately as 1891, and has now reserved some 60 million acres, which however includes a good deal of scrub jungle, grazing land and desert, and even so only amounts to a little over one per cent. of the public domain.

The State of New York owns near 1¼ million acres with the avowed purpose of increasing the acreage of State forests, but the majority of the States have not yet begun to acquire State forests In 1880, there were 200 million acres in the hands of private owners, mostly agriculturists, but much of this area has since passed into the hands of wood-working companies.

Of late years a tendency has developed in the timber trade, as in other industries, to consolidate forest properties, and to form trusts, which now own some millions of acres of forest land. Such trusts, controlling large areas under uniform and continuous policy, may prove, next to Governments, the best agencies for practising forestry properly organised for continuous business.

Of the 500 species of tree growth in the American forests not more than 100 are useful. The most important are the conifers, commercially called "soft-woods" to distinguish them from the broad-leaved species or "hard-woods."

In order of importance the chief kinds are:—White pine, Spruce and Fir, Hemlock, Long leaf pine, Short leaf and Loblolly pine. Among the hard-woods, the oaks are the most important, followed by the ashes, hickories, maples, the tulip tree, chestnut and other kinds.

The principal supplies of timber are in the white pine forests of the Lake States, and the yellow pine forests of the Gulf and South Atlantic States.

The Atlantic forest is principally composed of deciduous species, with a small mixture of conifers.

The burning question in connection with the protection and working of the United States forests is the forest fires, which are most destructive. The standing timber, the young growth, the accumulated leaf-mould, the fertility of the soil, are all destroyed: the timber supplies have thus been decimated, and the protective function of the forest cover on the mountain slopes very considerably injured, producing denudation, droughts and uneven seasons.

The last chapter of Dr Fernow's book gives a history of the forestry movement in the United States.

The first official recognition of the necessity of a forest policy was in 1876, when the agency out of which grew the Division of Foresty, now designated as Bureau of Forestry, was established in the United States Department of Agriculture. This bureau prepares working-plans for private owners, and two million acres have thus been dealt with.

In April 1882 the American Forestry Association was formed, and it has become the centre of all private efforts to advance the forestry movement. It publishes a monthly journal, now called *Forestry and Irrigation*, and is quite unaided by Government.

New York was the first State (even before Federal Government), to inaugurate the policy of forest reservation, as well as to make the first effective forest fire law (1885), and further took the first steps to provide technical education in forestry by establishing in 1898 the New York State College of Forestry, to be administered by Cornell University, together with a demonstration area of 30,000 acres in the Adirondacks.

Pennsylvania, next to New York, has most progressed in forestry, and Michigan comes third. The most complete forest fire law is that of Minnesota, 1895, but the reduction of forest fires appears now to depend chiefly on education and development of morals, which must come in time.

The Division of Forestry in the United States Department of Agriculture has now, for the last 25 years, been the official centre of the forestry movement, and together with the American Forestry Asscoiation has largely moulded public opinion.

The principal result of the influence of these two agencies towards a federal policy was the inauguration of forest reservation;

In 1891, an Act was passed by Congress by virtue of which in 1894 seventeen forests with a total area of 17¼ million acres were reserved within the three years following.

These reservations were established usually upon the petition of citizens in the respective States and after due examination, the Forestry Association acting as intermediary.

In 1897, thirteen more forests, with an area of nearly 21½ million acres, were reserved, but owing to a want of proper forest administration this wholesale reservation met with a great deal of opposition, especially in the Western States, who, however, have later learned to appreciate the wisdom of these reservations, especially in the irrigation districts.

The administration of these reserves is still of the crudest kind, and forestry practice is as yet hardly attempted. The Forestry Division of the Department of Agriculture, elevated to a bureau in 1901, occupies only an advisory position, and is still without administrative functions, though it ought of course to be in charge of the public reserved forests.

Are there any lessons to be drawn from this sketch of forestry in America?

The Indian Forest Service is the largest forestry establishment in the world, and has been in existence much longer than the Forest Department of the United States. Have we progressed as we should have done, and advanced our professional knowledge, or are we paralysed by officialism, or sunk in indifference?

It must certainly strike one as curious that, while in America, where forestry is only just starting, there should be numerous research bureaux and systematic agencies for collecting and publishing statistical information on forest matters, there should not be in the whole of India one single forest experiment station.

Generations of Forest Officers come and go, but very little definite reliable knowledge is accumulated regarding the rates of growth of our principal species, the classification of the soil and climate conditions of the chief forest countries, the age of maturity of our timber trees in different localities, the best methods of ensuring natural reproduction in the more difficult types of forest, and the normal rates of production per acre per annum in our best-stocked forests. Even the life-history of the sal tree appears to be only imperfectly understood, and in one corner of the Continent it is openly declared by some that fire-protection in forests is generally a mistake.

Surely these reflections suggest that at any rate at Dehra Dun if not at all other provincial centres, there ought to be systematic and continuous experiments made in all these subjects.

No doubt the Department is always undermanned, and the Government vastly prefers its officers to be engaged in revenue work than in technical research, since the latter yields no immediate return; but we must feel that we have duties to our own profession as well, and a share to take (in our own quarter of the world) in those experiments and researches which are year by year being made in France, Germany and America.

To the Forest Research Bureau we require an office attached for the collection of statistics and data of all kinds regarding the Indian forests and the principal species they contain.

At present, a large proportion of all the knowledge and experience gained is generally lost again. Much information no doubt is buried in working-plans, which are most often not accessible except to officers in the circle to which they apply. Personal observations and the results of desultory experiments may often be embodied in stray reports or sometimes in the *Indian Forester*, but even so these records are not generally available nor easy to find afterwards.

What we want is a central office, where data of every description would be collected from reports, working-plans, and memoranda of all kinds, and the results of all sample plots, enumeration surveys, yield tables, etc., catalogued and compiled so as to be permanently on record and easily available to everyone. A collection of photographs of forest crops, drawings and models of engineering works, would also be useful.

At present very insufficient record is often kept of our sample plots for rates of growth, for results of thinnings, etc. The same applies to plantations. In order to profit by experience, there should always be a large-scale map kept, and the annual results of all sowings and plantings placed on permanent record in full detail; nor is it sufficient to state simply success or failure, as it is the suspected *reasons* for the failure that it is important to record. The means of communicating ideas between different divisions, circles and provinces, too, are at present insufficient. Why should the most successful methods of planting deodar in Jaunsar, for example, be unknown and unheard of in the Punjab? May not the Central Provinces too have something to learn from Burma regarding the working of teak? Compare the New York *Forestry and Irrigation* with our own *Indian Forester*.

It was not long ago suggested in the *Forester* that a special officer should be detailed to undertake the collection of all data relating to the commercial side of our work, and to this might well be added the collection of samples of forest produce and specimens of economic products.

As time goes on, if we are to hold our own in the profession we shall certainly require more specialists, and the time has already come when we ought to have a separate working-plans branch, under a Conservator who would also be Superintendent of Working-plans.

Notes on the Forest Nursery and Plantations in the Panch Mahals.

BY R. S. PEARSON, I.F.S.

I VENTURE to write the following notes on plantations, partly with the hope that they may be of interest to some of the readers of the *Indian Forester*, and also hoping that some brother officer, with more experience, may pull me up where I have gone wrong and give me the benefit of his advice on this subject.

The nursery in question is situated in the compound of the forest bungalow at Godhra, and for the purpose of supervision the site could not have been better chosen.

The bed area is 1 acre 9 gunters, containing 280 beds, $1\frac{2}{3}$ yards wide and 12 yards long.

The water is obtained from a common "koss" well some 40 feet deep, and is raised into a tank 22 feet above ground level. From this tank runs an iron pipe into the centre of the nursery, which is tapped by a hose carrying the water to all points of the garden.

The whole plantation and nursery are comparatively new, and the outturn of seedlings, chiefly teak, has varied between 20,000 and 30,000 at a yearly cost of roughly Rs.800, including upkeep of nursery and transplantation in the forest.

In 1901 the question was raised as to the advisability of maintaining this nursery, as the cost was heavy compared to the outturn. It was, however, pointed out that the possibility of the nursery was never reached and that three times the number of plants could be produced at practically the same cost. I was therefore allowed a further trial before the nursery was condemned as a failure. The result was not as good as expected, partly owing to inexperience and partly to a slice of bad luck. Roughly, 100,000 plants were transplanted from the seed beds and doing well in July 1902. Then came a four weeks' break in the rains. After the first week orders were given to water the plants, and on the 2nd day the canvas hose split, though a comparatively new one, and not till 14 days later was a new one obtained. The result was disastrous, as 50,000 plants died, and at the end of the year only 45,000 seedlings were transplanted out into the forest. Had the well been nearer the nursery, wholesale irrigation might have been carried out, which would have saved the situation.

This year there are about 75,000 plants transplanted and about 20.000 still remain in the seed-beds to be dealt with. The rain has been good, but cockchafer grubs have appeared and have done some damage. The beds have been dug up with three-pronged hand forks and the grubs collected, which has to a great extent stopped the damage.

As regards the method employed to quicken the germination of teak seed; it is put into pits 10 feet square and 2 feet deep. It is then flooded with water and left in the pits for 3 or 4 days, and then taken out and dried in layers of about 1 inch thick on the paths. This process is repeated 3 or 4 times, till the outer shell is soft and the seed on the point of germinating It is then sown in the seed-beds at the commencement of the rains. About 25 per cent of the teak seed germinates in the first year, and it is only in the second year that the seed-beds really produce seedlings in large numbers. I hope some forester will put me on the right line and tell me of a better method of making teak seed germinate in the first year, as two years of germination means two sets of seed-beds and consequently loss of land.

The teak seedlings are transplanted from the seed-beds in August when they have three pairs of leaves. If transplanted earlier they often die; and, on the other hand, if transplanted later the taproot not infrequently gets damaged while being lifted, with the result that the plants wither before being able to catch on to the soil.

Khair (*Acacia Catechu*, Willd.) and ain (*Terminalia tomentosa*, W. & A) are also grown in the nursery. The germination of both is easy to effect, the only precaution taken being to sow the ain seed on a bed of mixed leaves and straw. This practise saves many of the seeds from rotting from excessive moisture and does not retard the germination Ain is always transplanted, and khair is either sown straight into the beds or transplanted. I prefer the former method for khair, as in transplanting seedlings they not infrequently die, especially if small

The beds are watered every 8 to 10 days during the dry season, and at the end of the year, after the break of the monsoon, the one-year-old seedlings are planted out in the forest. The Panch Mahals forests consist chiefly of 30 years' coppice-with-standards The work is therefore confined to planting up blanks which contain not unnaturally poor soil. The last two years' plantations have been, however, fairly successful, as in the largest plantation made in 1902 only 15 per cent of blanks had to be filled up this year and the old plants are healthy and have firmly established themselves.

The cost of making the poles came to Re. 1 per 1,000 and 12 annas for planting the same number of seedlings.

One of the largest plantations being within 4 miles of the forest bungalow, I had ample opportunity of frequently visiting it during the rains, and I came to the conclusion that the failures were due, to a great extent, to the transplants being small and not vigorous when they were sent out to the forest, and this was especially the case with khair. I examined the roots of plants that had failed, but could find no trace of insect or fungus having damaged them.

The reason for weak plants having been produced in the nursery was that the soil had been impoverished by taking out successive crops of seedlings and never improving the soil. This year the nursery has been well manured before transplanting operations commenced. A mistake was, however, made with this manuring business, as the heaps of manure were left lying for some time on the paths, while the beds were being prepared, and they acted as collecting grounds for the cockchafer grubs.

In the plantations made this year, the soil in the blanks being extremely poor, 15,000 seedlings were planted with a handful of manure each, at a total cost of Rs. 4. If any benefit is derived from this addition of manure the result will be seen next year, when the manured and non-manured plants standing side by side are compared.

My idea of manuring the small seedlings was to help them in establishing themselves during the first year, after which they get their roots down and can better take care of themselves. The question of plantations in dry regions, such as the Deccan and the Panch Mahals, has been much discussed at various times. Some foresters have condemned such works, while others believe that good results can be obtained at a reasonable cost. Personally I feel sure fair results are obtainable even on very middling soil, with a limited rainfall, provided that strict supervision is exercised by the superior officer, especially during the critical times of transplanting in the nursery and out into the forest, and also the difficulty of making a plantation a success will become less with years of experience and careful observation.

"Double-barrelled" Bamboos.

By C. E. Muriel, I.F.S.

Some two months ago (July) I noticed some cut bamboos (*Dendrocalamus strictus*) 10 miles north of Pyinmana with double hollows at their upper ends, and since then I have investigated further specimens.

The lower portions of the culms are of the ordinary type of *Dendrocalamus strictus* found growing in fairly moist forest, but in some cases a partition is formed longitudinally some 15 to 20 feet from the ground.

The partition appears to commence as a filament growing longitudinally between the nodes, sometimes straight and in other instances developing spirally. This is succeeded by a straight partition across the bamboo, which thickens in the higher internodes until the upper portion of the bamboo becomes quite solid.

There is nothing in the external appearance of the bamboo to indicate the double hollow.

The sketches accompanying this note may help to explain the appearance of the partition.



1.



1b.



1a

Specimens of bamboos with partitions are not infrequent in forest some 10 or 12 miles north of Pyinmana, and could be obtained for any person interested in them.

I have sent some specimens to Mr. Gamble (to whom I had written when I first found the double-barrelled bamboo, and who tells me that he had never seen an instance of such growth* during his long experience in India), to the Director of the Imperial Forest School, Dehra Dun, and to the Director of the Burma Forest School.

---

* In the absence of Major Prain, I.M.S., on tour we submitted Mr. Muriel's sketches to Captain Gage, I. M. S., at the Royal Botanic Gardens Captain Gage informs us that he has never heard of the occurrence of the double-barrelled bamboo and that there are no specimens of it in their Collections.—Hon. Ed.

II.—CORRESPONDENCE.

Cooper's Hill as a Training College for the Imperial Forest Service.

YOUR editorial article on the subject of "Cooper's Hill as a Training College for the Imperial Forest Service" will, it is hoped, draw the attention of the general public to the fact—perhaps not so widely appreciated as it should be—that the Royal Indian Engineering College not only trains Engineers in the Public Works and Telegraph Departments, but also Foresters for the Imperial Forest Service of India and that at the present moment more than half the members of the Imperial Forest Service have been trained at Cooper's Hill.

If the committee of enquiry appointed by the Secretary of State for India to decide the fate of Cooper's Hill recommend that the Royal Indian Engineering College is to be closed, then the question of how recruits are to be obtained for the Imperial Forest Service of India in the future will have to be decided.

The policy of grafting a School of Forestry on to the existing Engineering College is a standing proof of the wisdom of the founders of the British School of Forestry, as in India—and the same statement will, it is believed, be found true in the less developed parts of the British Empire—the Forest Officer has to be his own engineer, surveyor and architect, and a thorough practical knowledge of the elementary portions of the Cooper's Hill Engineering Course are second in importance only to the principal study of Forestry in all its branches. And what is the use of being able to maintain or even constitute forests if the Forest Officer is unable to make roads, lay out tramways and sledge roads, utilize floating streams in order to bring the timber in the cheapest way possible to the market?

In Europe and highly civilized countries this knowledge of engineering and surveying is not so necessary, as the services of professional men can be obtained; but in the as yet undeveloped parts of the British Empire such a knowledge is most necessary to the Forest Officer.

The British School of Forestry has now been in existence at Cooper's Hill for eighteen years, and may consequently be said to have passed out of the experimental stage and to have established traditions of its own.

Dr. William Schlich, F.R.S., the founder of the school, brought with him all the best teachings of German forestry which his long and varied service in many parts of India have enabled him to apply specially to the varying conditions—so different to what exist on the Continent of Europe—met with in the different parts of India. While Mr. Fisher, who has been associated with Cooper's Hill for so many years, represents the French School of Forestry, and has also had the benefit of having served for many years in the Indian Forest Service.

The British School of Forestry has thus from the commencement of its existence been founded on the best traditions of the two famous Schools of Forestry on the Continent, the German and the French; and has thus been enabled to assimilate those principles of each school which are most applicable to Indian conditions. That the present Forestry Course at Cooper's Hill is well suited to the requirements of the Indian Service is sufficiently proved by the work which has been done by Cooper's Hill Foresters in India.

In a Service where there are so many hard workers it would be invidious to particularize, but a glance at the list of officers in the Imperial Service will show the number of Cooper's Hill trained men who are engaged on the preparation of working-plans—the most scientific part of a Forest Officer's profession—or who are in charge of important divisions; while the history of the Imperial Forest School, Dehra Dun, has been intimately connected with Cooper's Hill men in the rôle of Instructors and additional lecturers ever since 1890.

Such a record amply justifies the continuance and expansion of the British School of Forestry, especially as its influence is spreading beyond the confines of India through Forest Officers who have been deputed on foreign service to many parts of the British Empire.

It may not be out of place to mention here that forest management in India is infinitely more difficult than in Europe, on account of the vastly greater number of valuable trees which it is necessary to study sylviculturally, the enormous area of the Government forest estates and the many variations of climate, locality and soil which must needs exist in so large a dependency.

The climatic and local conditions on the Continent of Europe are much more like those of Great Britain than they are in India or other more remote parts of the British Empire, in tropical and semi-tropical climates, and when all is said and done, whether trained entirely on the Continent of Europe or in Great Britain (with tours and special practical work on the Continent) a Forest Officer on arrival in India is in the same position, *i.e.*, of being placed (in virtue of his special training) in a favourable position to begin to learn—to learn how to apply practically the principles that he has learnt theoretically. And his success or otherwise as a Forest Officer will depend upon the assiduity and persistence with which he applies himself to that task.

Sufficient has been said to prove the necessity of continuing the British School of Forestry and of enlarging it so as to meet the demands not only of India, but of all parts of the British Empire.

It is ridiculous to say that it is not possible to teach the fundamental principles underlying forestry in Great Britain. The results obtained at Cooper's Hill *ipse facto* disprove such a statement.

If further proof were needed look at the United States of America. The States have taken an interest in forestry much more recently than Great Britain has, and should *primâ facie* know less about the *technique* of a profession so essentially based on successful practice. America trains her own foresters now and professes to be in a position to teach forestry to the whole world.

If America can train her own sons in forestry without the aid of Continental Europe, much more so can Great Britain, with her large practical experience and with Europe near at hand as an example of the degree of perfection to which scientific forestry can be brought. Or are we to confess that the British nation is so effete and worn out that it cannot train its own sons in a profession which has become a matter of great importance to her material welfare and will become more and more so year by year.

The requirements of the civilized world as regards wood are yearly increasing, while the existing natural stocks are annually decreasing owing to lack of systematic management. It follows that the market value of wood must increase and that the necessity for maintaining and developing the world's supply of timber will become more and more urgent.

This in itself is a sufficient justification for the maintenance and development of the British School of Forestry in the highly efficient state to which it has been brought by Dr. Schlich and the professors associated with him in his great work.

There can be no doubt that if it is considered expedient to close Cooper's Hill as an engineering college that the establishment of an Imperial Forestry College at Cooper's Hill, carried on on the same lines as at present, would be the best solution of the problem of recruitment for the Indian and possibly Imperial and Colonial Forest Services.

The commission appointed by the late Mr. Hanbury, Minister for Agriculture, to consider the question of the afforestation of the British Isles on a large scale suggested the transfer of the Cooper's Hill Forestry College to a University, preferably Cambridge.

The wisdom of this suggested change is open to question. If Cooper's Hill is to be abolished, it would, I think, be better to move the British Forestry College either to Edinburgh

University or Owen's College, Manchester. Both of these institutions are well known for hard work and frugality. Edinburgh has always encouraged the study of Botany and Natural Science, whereas Manchester, though of much more recent origin, has already earned a great reputation in the educational world of Great Britain as a means of applying science practically to the requirements of modern commerce and manufacture.

This is specially important to an Indian Forest Officer who, the Government of India recognize, must attend to the commercial as well as the scientific side of his profession, in order that the forest resources of the Empire may be fully utilized. In Europe the uses of the products of the forests are well known and one and all find a market. In India and the Colonies, however, it is very different, and the Forest Officer has to make known or develop the resources of the forests and to bring them forcibly to the notice of the commercial world and to induce them to start industries, some of which were well established in Europe before scientific forestry was seriously considered.

The system of education at either Oxford or Cambridge is too academic and theoretical to be a good training for a Forest Officer whose subsequent profession is of an essentially practical nature. The aim of a University student is to get a degree pure and simple, whereas a Forestry student must fit himself to be an eminently practical worker. These two aims are diametrically opposite.

The discipline at these universities—a most important consideration—is not so strict as at Cooper's Hill, and it would be impossible to keep such a thorough control over the students there as is done at Cooper's Hill Much less hard work would be done at a university than is done under the present régime at Cooper's Hill, with the consequence that the results obtained would not be so good.

The temptations not to work would be much greater also at such a university, where so many men spend 3 or 4 years, not with a view to qualifying themselves for a profession, but more with the view of giving a finish to their education and indulging in sport.

The *esprit de corps*, which is a marked characteristic of Cooper's Hill men, and which makes them willing and conscientious hard-working servants of Government, would be absent among university trained men, who would probably hardly know each other, and Government, not its servants, would be the loser in consequence.

By all means let the British School of Forestry continue to flourish and its scope be enlarged, but for efficieny's sake let it be constantly associated with a school of engineering, strict discipline and *bon camaraderie*. All of which will tend to develop the class of Forest Officer required to manage, husband and exploit economically the vast timber resources of the British Empire.

PORT BLAIR,
THE ANDAMANS;
3rd September 1903.

C. GILBERT ROGERS,
Deputy Conservator of Forests.

The Flowering of Bambusa polymorpha

"WATHON'S" letter in the June number of the *Indian Forester* requested a discussion on the subject of the operations to be undertaken when the *Bambusa polymorpha* flowers to promote teak reproduction I would accordingly venture to give a few views on the subject.

We wish to take advantage of the general flowering of this bamboo over large areas to help in the natural reproduction of teak, and where such natural reproduction is deficient, to introduce teak seedlings in patches scattered over large areas, and as we are unlikely to have unlimited funds at our disposal for this work in order that large areas may be undertaken, our operations must be done as cheaply as is consistent with efficiency,

The selection and method of treatment of the patches into which teak is to be introduced will require very careful consideration. Let us first consider what happens in the case of deserted taungyas cut in Kyathaung forest. Whether these taungyas have originally been cut in old taungya sites or in virgin forests, the year after they have been abandoned they get covered with a dense growth consisting chiefly of weeds and rank grasses with few or no bamboos. After 3 or 4 years the bamboo has again established itself on these areas, unless in cases where the taungya has been cut on both sides of a fairly high spur or ridge, when as a rule the bamboo, while re-establishing itself on the slopes, is unable, at any rate for a good many years, to re-establish itself along the top of the ridge, and in its place on the high ground we get a growth of coarse grass.

Taking the above into consideration, it would appear that whether we cut down the bamboos or not before the bamboo seed ripens on the areas that we wish to operate on, we are certain to find that heavy weeding operations are necessary during the year following the introduction of the teak seed and probably for several years later in addition to whatever weeding is necessary during the year of introduction. In fact if this method were adopted for the treatment of our areas, the cost would probably be as much per acre as is the cost of our present taungya plantations, and even if the cost were not considered prohibitive for extensive operations, it is doubtful if the trained staff could adequately supervise the subsequent weeding operations over scattered areas.

Let us now for further consideration divide the forest in which *Bambusa polymorpha* is the prevailing bamboo into three classes as follows :—

(*a*) Forest as a rule not very moist and where teak is plentiful.

(*b*) Forest somewhat moister than in class (*a*), teak fairly plentiful.

(*c*) Moist forest, teak scarce or absent.

Class (*a* practically never escapes being burnt over by the annual jungle fires ; class (*b*) suffers somewhat less from these fires, being moister ; and in class (*c*) large areas often escape altogether being burnt over.

Natural regeneration of teak is, as a rule, good in class (*a*) although the seedlings suffer considerably from fire. In class (*b*) the natural regeneration of teak is usually fair only ; the forest, being less open and the soil richer than in class (*a*), teak does not seem to spring up so well from seed as in the former class. In class (*c*) where teak occurs natural regeneration is usually poor or absent altogether, and the introduction of teak into forest of this class is, I presume, what should receive our chief attention when the Kyathaung flowers.

As regards the operations to be undertaken to promote or introduce teak into the forests at the time of the flowering of the bamboo, I would suggest the following :—Operations to be undertaken only in fire-protected areas or in areas that can be brought permanently under fire protection, commencing with the year in which the bamboo flowers.

In class (*a*) if there is a fair crop of seedlings on the ground, except strict fire-protection no further measures should be necessary. The seedlings should from the first dominate the young bamboos and weeds that spring up when the Kyathaung stems die ; but great care must be taken, if necessary with additional interior fire lines, to prevent fire getting into the area.

In class (*b*) if teak seedlings are on the ground a similar treatment should suffice with the addition that to admit more light a number of the inferior species mixed with the teak should be girdled or otherwise killed.

Class (c) will require most careful attention. In this class of forest there is, so far as my experience goes, as a rule, a fairly dense leaf canopy, and a good many of the trees continue in leaf the whole year round. The soil is usually rich - generally a good sandy loam—and if teak were ever indigenous it was driven out; and in my opinion if teak is introduced it will be driven out unless we are prepared to take continued measures for its protection. Teak, so far as I have seen, when found in this class of forest, occurs in patches generally on the higher ground (which might possibly point to it being the remnant of the older type of forest) and its regeneration is poor. Even where enough light is admitted to the soil for the growth of teak seedlings, these will rarely spring up.

As we will have to take continued measures for the protection of teak when established in forest of this description by killing species that encroach upon it, it would seem preferable to seek to introduce it into a few large areas rather than into numerous small patches, as it is difficult to manage adequate inspection of scattered patches with a limited controlling establishment, and the advantage of scattered patches is doubtful unless they can receive sufficient attention Accordingly, as in such forest there is little danger of our exterminating other species and gaining an unmixed teak forest, I would select for treatment areas, say, half a mile upwards in length and 80 to 100 yards broad running along the tops of spurs and ridges.

To introduce teak into such selected areas—as cutting the bamboo would involve heavy expenditure and as a considerable outlay on weeding is certain to be necessary later—instead of cutting the bamboo I would towards the close of the hot weather (having carefully fire-protected the area during the hot season) when all the bamboo seed has fallen, burn the whole area together with adjoining areas unless these are rich in teak. This ground fire should kill off a large proportion of the bamboo seed, and having burnt the area I would dibble in teak seed in lines 9 feet apart. Teak nurseries should be established on the areas undertaken and transplants put in when necessary during the first year. Also before burning the area a large proportion of the inferior species should be girdled, or if necessary felled to admit more light. During the following year the young teak will require assistance from the growth of bamboos and weeds, and I would weed them in lines, say, 6 feet wide, leaving a line of weeds 3 feet wide between each weeded line. One weeding only during the first year following the operations and none during subsequent years might suffice, as usually the greater proportion of the teak dominate the surrounding weeds after the first weeding of their second year.

Forests of class (*a*) and class (*b*) in which there was no teak might be treated similarly to the above; but in my opinion if teak is present and there is no natural regeneration it should be sufficient to break the ground slightly here and there in the vicinity of teak seed-bearers to promote the germination of the seed which falls from them without having recourse to fire, but subsequent operations to free the teak seedlings from the surrounding bamboo growth will probably be necessary. In teak areas when natural regeneration is absent, experiments should be started at once to see whether breaking the soil near seed-bearers is sufficient to promote the germination of the seed. After the dead bamboo stems fall, the danger from fire for about the following two years will be very serious, and to guard against this in the areas operated on we shall have to make our fire protection a little more elaborate with numerous interior fire lines dividing up the areas treated.

Operations conducted somewhat as suggested above should cost little as compared with the cost of our present taungya plantations, and if we succeed in establishing teak on the higher ground in moist Kyathaung forest, in after years when the teak so established begins to produce seed, with seed-bearers on the higher ground, by here and there judiciously killing inferior species on the lower ground to admit light, and if necessary breaking the soil in patches, it should be possible at a very small expenditure to extend the growth of teak over a yearly increasing area, and furthermore it should be possible to regulate the percentage of teak as compared with the other species in the resulting mixed forest; but this will be work for a later generation of foresters.

18th September 1903. "KWE-TU-WET-TU."

Our neglected Commercial Side.

So striking an instance of the necessity of some such bureau as that advocated in an article published under the above title in the June issue of the *Indian Forester* has come to my notice that I forward this note without apology.

Some months back, at the instance of the Conservator of the Circle, I initiated enquiries regarding the exploitation of and the trade in sabai grass (*Ischæmum angustifolium*, locally known to the Uriyas as "Babuli"). I was compelled to trouble 2 or 3 Forest Officers of another presidency where this grass yields a considerable revenue, and all most courteously furnished me with valuable information. I further had a quantity of grass collected as an experiment and the grass was sent to a paper mill. The venture resulted in a dead loss, but supplied useful data for further guidance. Within 15 days of completing the transaction, happening to look through some back volumes of the *Indian Forester* (the property of another officer), I came across an article on

"Bhabar grass and the trade in it" in Vol XIX (September 1893). This article over the signature of Mr. J. S Gamble is a *résumé* of some reports submitted by several Divisional Forest Officers and among them one from this very district.

On referring back to old records I now ascertained that not only was a detailed enquiry made and data obtained, but also an experimental supply similar to my unsuccessful attempt of this year was carried out, without any greater success, so far back as 1886.

So in 1903 we are exactly where we were seventeen years ago!

CHATRAPUR, GANJAM DISTRICT. C. E. C. FISCHER.

Corrigenda to Mr. Mercer's Tables showing cubic contents of logs.

I SHOULD be very glad if you would insert the accompanying corrigenda slips * (English and Urdu) as an advertisement in the *Forester* for 2 or 3 months, and also this letter, once at least, in explanation of the same.

Copies of the slips have been distributed to all who have received copies of the books as far as is known, but it is just possible that some books may not have been traced or may have changed hands.

The tables were printed in two editions, but there is nothing to show to which edition any particular copy belongs. All copies should therefore be examined and corrected where necessary.

Spare copies of the slips can be obtained from the Deputy Conservator of Forests, Garhwal Division, Naini Tal.

F. A. LEETE,
Deputy Conservator of Forests,
Garhwal Division.

NAINI TAL:
Dated 9th September 1903.

III.—OFFICIAL PAPERS AND INTELLIGENCE.

The Treatment of Hardwickia Binata.

I SEND the enclosed for favour of publication, in the hope that its perusal will provoke criticism and discussion and thereby lead to a solution of the puzzle which the treatment of the forests of *Hardwickia binata* certainly is to Foresters who have had the good or bad fortune to work them.

---

* See advertisement sheets.—HON ED.

Gamble (*Manual of Indian Timbers*, pp. 276-7) says: "Its reproduction is good; it gives a profusion of seed, and the seedlings spring up quickly, but, like those of teak, sal and other Indian trees, are killed to the ground-level year after year in the season of hot winds, until finally the roots get far down into moist strata and the shoots are strong and big enough to grow into trees. The saplings, however, never seem to grow thickly, but prefer to be separated for some distance, even when there are no, or few, other species of tree in the interval. It *coppices well.*" The italics are mine and I should like Madras Foresters, who have actually worked the tree as coppice, to corroborate the statement thus italicised. As regards reproduction by seed, I wish anjan seedlings were like those of sal, for then we should have absolutely no difficulty in working our anjan forests here in Berar. It is a very very far cry indeed from sal, which reproduces itself without any trouble on the part of the forester, to anjan.

CAMP CHIKALDA, BERAR;
22nd August 1903.

E. E. FERNANDEZ,
Conservator of Forests, Berar.

Letter No. 352 *(Camp), dated the* 19*th August* 1903, *from E. E. Fernandez, Esq., Conservator of Forests, Berar, to the Divisional Forest Officer, Buldana.*

I have the honour to address you in reply to your letter No. C/46, dated the 11th May last, on the subject of the manner of exploiting anjan.

2. While on tour with you and Rai Bahadur Mansukh Rai in Geru-Matargaon Reserve in December 1901, I pointed out to you (i) that experience in the Nimar Division of the Central Provinces had proved that anjan does not lend itself to the coppice treatment proper; (ii) that pollarding had been adopted with apparent success for the production of firewood in that division in those localities in which that tree, as in Berar, does not attain a large size, and (iii) that we have still to discover by experiment how to utilise in an effective manner the periodical gregarious seedlings of the species.

3. Again, in my letter to the Inspector-General of Forests, No. 230 (Camp), dated the 3rd January 1902, which was published in the Proceedings of that officer, I wrote as follows:—

"*Anjan forest.*—This is here a most unsatisfactory type. The species is incapable of attaining the dimensions of sawyers' timber, and can at most furnish house-posts. But the worst point about it is that there has been *absolutely* no reproduction for at least 20 years. After each seeding numbers of seedlings come up, but all disappear before the end of the ensuing hot weather. The tree will moreover not coppice. The treatment of the type is hence for the present a puzzle, and only tentative methods can be adopted until we hit upon the right one."

4. Lastly, when with you in January last, I informed you that in view of our absolute ignorance regarding the proper treatment of the species, I had decided to include all anjan areas in the category of "unworkable" in the working-plan now under preparation for your division, the object of such inclusion being to leave us a completely free hand to put to the test every practicable method of treatment without the delays (fatal to the success of such experiments) that would be inevitable in the event of our having to refer each time to higher authority in respect of each change contemplated

5. It is obvious that during this experimental stage we ought not to work on any extended scale, if we do not wish to run the risk of permanently injuring the forest or at least of throwing back considerable areas for a long series of years in the event of the tentative methods proving to be altogether unsuitable. For this reason I am strongly opposed to your proposal to work through entire coupes at a time.

6. You wish to begin at once pollarding on this scale. In regard to pollarding there are two principal points to be established by experiment, *viz* :—

(i) The maximum girth up to which a tree if polled will produce strong *erect* shoots, not merely a bunch of thin *weeping* shoots like those which come up on stools cut close to the ground.

(ii) The maximum height down to which a tree may be polled while still being capable of throwing up such erect shoots. It is obvious that the lower we can cut the trees, the better will be the yield of wood and the better the class of forests that will result.

7. Until we gain more or less certain knowledge in regard to these two points, we must content ourselves with experimenting in a few, well-distributed sample plots, representing different gradients and every class of soil and subsoil. Four-acre plots will be large enough for the purpose. In each sample plot the polling will be effected at various definite heights, from a minimum of 1½ feet rising by 6 inches at a time, to a maximum of 3½ feet. It would not be possible to cut higher than this without very great inconvenience and waste of time. You will be careful to see that the stems cut at one and the same height represent in more or less equal proportion all girth classes commencing at a minimum of 18 inches (the lowest marketable girth for firewood) and rising by 4 inches at a time to the thickest individuals standing in the plot. To secure this equality you should, before proceeding to

fell, girth all the anjan trees in the plot 16 inches and upwards in circumference at 1½ feet from the ground, and at once record the results in a bound register in the manner shown below :—

Characteristic number of girth-class.	Girth measured at 1½ feet from the ground.		Enumeration.	Total number of stems in each class	Number polled at				
					1½	2	2½	3	3½
	Not less than	And under			Feet from the ground.				
	Inches.	Inches							
I	16	20	𝍸 𝍸 𝍸 𝍸 //	22	5	5	4	4	4
II	20	24	𝍸 𝍸 𝍸 𝍸 𝍸 ////	29	6	6	6	6	5
III	24	28	𝍸 𝍸 𝍸 𝍸 𝍸 𝍸 ///	33	7	7	7	6	6
IV	28	32	𝍸 𝍸 𝍸 𝍸 𝍸 𝍸 𝍸 /	36	8	7	7	7	7
V	32	36	𝍸 𝍸 𝍸 𝍸 𝍸 //	27	5	5	5	6	6
VI	36	40	𝍸 𝍸 𝍸 ///	18	3	3	4	4	4
VII	40	44	𝍸 𝍸 ////	14	2	3	3	3	3
VIII	44	48	𝍸 //	7	1	1	1	2	2
			Total ...	186	37	37	37	38	37

Having ascertained the number of stems in each girth-class, it will be easy to effect an equal distribution, as shown in the last five columns above. As each tree is measured, the characteristic number of its girth-class, together with its serial number, should be at once marked on it, with white zinc paint, between 1 and 1½ feet from the ground. In one and the same plot these numbers should, for easy recognition, be painted on one and the same side of the stems, say, all on the east or, if on a slope, on the lower side of the slope. They should be repainted as often as they *begin* to be illegible. With the stems numbered thus, all subsequent proceedings will be rendered easy and systematic.

The statement prescribed above will constitute the first entry for the plot to which it relates, all subsequent measurements, countings and other observations being recorded below it in chronological sequence.

8. In November each year each sample plot will be carefully examined and the results observed recorded as just directed above under the following heads :—

A. Year of observation.

B. In respect of all the stumps of each girth-class polled at one and the same height complete data as under :—

(*a*) Number of stumps not bearing any rigid erect shoot at all.

(*b*) Number of stumps bearing only one such shoot and for the entire class the minimum, mean and maximum distances of this shoot from the top of the stump, together with the minimum, mean and maximum lengths and girths (at 6 inches from its insertion on the stump) of the shoot.

(*c*) Number of stumps bearing two such shoots and for the entire class the minimum, mean and maximum distances of the shoots from the top of the stump, together with their minimum, mean and maximum lengths and girths (at 6 inches from their insertion).

(*d*) Number of stumps bearing three such shoots and, as above, for the entire class the minimum, mean and maximum distances of these shoots from the top of the stump, together with their minimum, mean and maximum lengths and girths.

(*e*) The same information for stumps bearing more than three such shoots.

In the course of perhaps less than five years the information thus recorded will enable us to decide with certainty at what height the trees should be polled in order to give the best results.

9. This valuable knowledge will at once receive its practical application in the event of our failure to discover a method of securing with absolute certainty a complete new generation by means of seed alone. Indeed, in view of the fact that anjan seedlings take a great many years to reach the stage at which rapid upward development begins, it is for consideration whether we may not have to adopt pollarding as a practical working system and have recourse to reproduction by seed only as a means, first of filling up the, at present, rather open crops, and, then of keeping up a constant fresh supply of good material for future pollarding. The local demand in the case of anjan is exclusively for house posts and for firewood. Pollarding will produce stems quite thick enough for the former purpose, and a pollarded forest will return a very much larger yield of firewood than a seedling forest. Again, we cannot forget the fact that at its best anjan in Berar will never furnish large timber.

10. The beech in Europe, like the anjan in India, will not coppice after a certain early age. The result is that in many parts of France and on the Swiss side of the Jura Mountains it is subjected to a peculiar system of pollarding technically known in French as *furetage*. It will be best described by supposing that we have, to begin with, a crop raised entirely from seed and hence composed of trees consisting each of a single stem. In order to get it coppice, this crop must be cut young. At this initial stage the trees may, of course, be felled close to the ground as in ordinary coppice, and it is obviously advisable

to do so, save for very urgent reasons to the contrary. But now comes the difference. Many, if not most, of the stools will throw up more than one shoot, and the majority of these, beech enduring heavy shade well, will survive until the next felling. As the object of *furetage* is to create and maintain a forest composed of individuals consisting each of a clump of several stems starting from as near the ground as possible, all the subsequent fellings must perforce leave the original stool or stump untouched, the shoots to be removed being cut sufficiently high above their base so that the stump left may be able to throw up fresh shoots. The necessity of doing as little damage as possible to the stems to be left standing (see immediately following sentence) also obliges the woodman to cut well above their point of insertion those he has to remove

The felling rotation is short (8—12 years), and at each exploitation only those stems are removed which have attained the minimum exploitable girth, so that contrary to what takes place in the coppice method, the crop is never clear-felled Thus from the second exploitation onwards the forest consists of clumps of shoots of various ages and sizes standing on one and the same original stock.

11. There is no reason why *furetage*, applied consistently with the cultural necessities of anjan in Berar and the requirements of the local demand, should not prove to be not only entirely suited for our forests of that species, but even the only possible method of working them. The system of complete "rest," combined with the exclusion of fire and grazing, has now been tried for the past 30 years without any result whatsoever as regards reproduction, and this policy of expectant passivity must now give place to cultural activity. On the zeal and intelligence with which you carry out the experiments ordered in paragraphs 7 and 8 above will depend how soon we shall be able to organise our anjan forests on an effective working basis and at length obtain some utility from them beyond that of occasional grazing grounds. If, as the outcome of our experiments, *furetage* is adopted, even their value as grazing grounds will be considerably enhanced, for in forests so treated, as the rotations are necessarily short and the forest is never clear-felled, the greater portion of the area can remain open to cattle. As Boppe says in his excellent work on sylviculture, "In the Cevennes, in Savoy and in Switzerland, in fine everywhere, the system of *furetays* has been evolved wherever it was found necessary to reconcile pasturage with regeneration by coppice." If we adopt a rotation of ten years, the most promising shoots left standing for three rotations will be large enough to furnish ordinary house-posts, and if thicker pieces were required, the strongest shoots still in full vigour of growth could be maintained up to the

6th, 7th or even higher rotation. Anjan not developed directly from seed becomes fully fertile long before its 20th year, so that under *furetage* effective seed-bearers would, contrary to what happens in clear-felled coppice, be *never* wanting anywhere.

12. As regards the third point stated in paragraph 2 above, I cannot do better than send you the annexed copy of my letter No. 347 (Camp), dated the 16th instant, to the address of the Conservator of Forests, Central Circle, Madras, and in connection with paragraph 5 thereof to ask you to undertake the following experiments:—

I. You will select and permanently mark off three 1-acre plots, one on level ground, the second on a gentle slope and the third on a fairly steep slope. In and around each plot there should be a sufficiency of fertile anjan trees to sow its entire area when a gregarious seeding takes place. In each plot you will, in a year of gregarious seeding just before the seed begins to be shed, have square patches dug up on the square pattern 20 feet from centre to centre either way. The soil in each plot will be loosened to a depth of 1 foot and completely freed from grass and grass roots. One-third of the patches will be 8′ × 8′, one-third 10′ × 10′ and the remaining third 12′ × 12′. In the immediately ensuing rainy season every patch will be weeded once in the last week of July. Half of them will be weeded a second time in the last week of August. At the first weeding the respective total numbers of seedlings in the patches of the three different sizes will be counted and registered. The counting will be repeated on 1st November, 1st February and 1st May during the first year, and on 1st July and 15th January in the subsequent four years. The data collected during these five years will probably give us all the information we require. At the last counting the height of the seedlings should be measured and the minimum, mean and maximum heights recorded.

II. In the third year following the appearance of the seedlings a certain number of them, not less than 100, will be transplanted in different ways between the lines of patches and the results observed during the subsequent two years recorded in full detail in respect of each method of planting adopted.

III. As some anjan trees are to be met with every year in fruit, where small groups of such trees are found you will have a few patches 10′ × 10′ similar to those described under (I) above prepared in the midst of, and around, the groups and carry on observations as prescribed under that experiment. There will be three such experimental groups, one on level ground, another on an easy slope and the third on a fairly (not too) steep slope.

13. It is hoped that the result of the experiments prescribed in the immediately preceding paragraph will be to show us how to turn to the best account both the annual sporadic seeding and the periodic gregarious fructifications of anjan.

14. I need hardly add that unless the experiments ordered in this letter are carried out systematically and in the proper scientific spirit of enquiry, they will be worse than useless, as they must inevitably lead to the formation of erroneous and even dangerous judgments. I say nothing of the time and labour that would be thus wasted. It does not, however, follow that the instructions conveyed in this letter are not liable to be modified during the course of the experiments, for circumstances that cannot now be foreseen and progressive acquaintance with the conditions of the problems to be solved will most certainly call for altered, if not entirely new, lines on which the investigation should be conducted. In no case, however, ought you to adopt any change of method or subject without previous reference to, and the full concurrence of, this office.

Letter No. 347 (*Camp*), *dated the* 16*th August* 1903, *from E. E. Fernandez, Esq., Conservator of Forests, Berar, to the Conservator of Forests, Central Circle, Madras.*

I owe you humble apologies for having so long delayed to reply to your letter No 554, dated the 15th April last, in which you ask me to give you my experience with regard to the sylviculture of the *Hardwickia binata* in the Central Provinces. The reason for the delay is that we are ourselves engaged at present in trying to resolve in a practical manner the question of the sylviculture of this tree here in Berar, and are no further advanced now than we were when we took it up 20 months ago on my starting enquiries preliminary to the preparation of a working-plan for the forests of the Buldana Division. On that occasion I wrote as follows to the Inspector-General of Forests on the subject:—

"*Anjan forest*—This is here a most unsatisfactory type. The species is incapable of attaining the dimensions of sawyers' timber and can at the most furnish small house-posts. But the worst point about it here is that there has been absolutely no reproduction for at least 20 years (I should have more correctly said 30 years), although there has been abundant seeding every 3—5 years. After each seeding numbers of seedlings come up, but all disappear before the end of the ensuing hot weather. The tree will moreover not coppice. The treatment of the type is hence for the present a puzzle, and only tentative methods can be adopted until we have hit upon the right one."

2. In the Central Provinces there are, so far as I could judge, two distinct subtypes of anjan forest according as the underlying rock is sandstone or trap.

8. On sandstone the tree attains to magnificent proportions, reaching a height of 80—100 feet, with a clean cylindrical bole of 40—60 feet and a diameter of 7—12 feet. Such is the case in Punasa and Chandgarh in the Nimar district. In the former forest, when I saw it for the first time, nearly 30 years ago, seedling reproduction had been making excellent progress, for in most places (save, of course, where the soil and situation excluded the species altogether) the seedlings were numerous enough to produce a fairly dense forest if all of them grew up to the dimensions of trees. Up to the reservation of Punasa, only a few years previously, every attempt, as Colonel Keatinge, who had ruled over British Nimar as Political Agent, has left on record, had been made to get rid of the forest and replace it by field crops, but the forest reappeared almost as fast as it was destroyed. To one acquainted like yourself with the system of cultivation followed in those days by the semi-savage tribes of the Nerbudda valley, it is superfluous to say that the ground was never completely cleared of forest, numerous trees of seed-bearing age were left scattered all round and over the fields. The seed fell from these trees on the newly broken land, now at last also freed to a great extent of grass, and the resulting seedlings came up under the most favourable condition for survival. The subsequent cultivation of the soil, limited to a mere scratching of the surface, left an appreciable proportion of the seedlings uninjured to continue their development, and as the field was abandoned as soon as the soil showed the first signs of exhaustion, the young plants were left in complete possession of the ground. In this connection I cannot do better than quote from my letter to the Inspector-General of Forests already cited :—

"As already explained above, we have still to devise a means of saving a sufficient proportion of the myriads of seedlings that make their appearance at each periodic fructification of the species. There is no doubt whatsoever that the death of the seedlings is due to their inability to force their long slender taproot down deep enough through the matting of grass roots occupying the soil everywhere to a depth of 1—2 feet. Experimental sowings made by me in Nimar showed that the anjan seedling develops in its first three months, if not impeded in its growth, a taproot more than 6 feet long in order to reach the permanently moist layers of the soil and thus obtain sufficient moisture to continue its vegetation throughout the trying period succeeding the cessation of the rains, and to start back into full vegetative activity during the height of the ensuing hot weather. In the Punasa forests in 1874, when I took over charge of them, I found the most perfect new reproduction wherever there had recently been field cultivation. In this year the tree seeded with its usual profusion and in the ensuing rains the ground everywhere was so covered with its seedlings that it was impossible to put one's foot down anywhere without stepping on one or more of them. In October the seedlings began rapidly to wither, and by the middle of the hot weather there was scarcely a single one alive, the inability of the taproots to penetrate through the dense mass of grass roots was the cause of their death. Hence the only thing that will save a sufficient proportion of the future crops of seedlings that are bound to appear after the several successive fructifications will be to do something whereby they may be able to get their taproots down into the permanently moist layers of the soil. The experiments that will be prescribed in the plan will have this end for their objective."

During the 7 years that I was able to continue my observations before I was transferred to the United Provinces the seedlings of pre-reservation days continued to strengthen themselves and develop, but no new contingent of seedlings survived to swell their numbers, and in my inexperience and under the influence of the erroneous idea, unfortunately still very generally prevalent, that the exclusion of fires and cattle was the one panacea for all our forest ills, I attributed the death of the new seedlings exclusively to the annual conflagrations lighted by incendiaries, who thought that they would by such means compel us to abandon conservation We are now wiser, for we have learnt that more than 20 years of successful fire prevention have given us no better results. The seedlings are as usual produced in countless numbers after every periodic gregarious seeding, but, being unable to push their taproots down deep enough, they all perish in their very first year.

4. On trap the anjan is a very small tree and has quite a different habit of growth. Moreover, besides the periodic gregarious seedings, a few trees here and there, scattered or in small groups, are to be met with every year in fruit during the interval. Nevertheless reproduction is no more successful here than in the sub-type growing on sandstone. Indeed, the chances of survival on the class of trap affected by the anjan are less favourable than on sandstone, which always offers numerous deep fissures for the downward development of the taproot of the seedlings.

5. I feel certain that my diagnosis of the reason of the failure of anjan to reproduce itself from seed is absolutely correct, and that the only remedy for it is to devise some practical and therefore necessarily cheap method of keeping down the grass at numerous points not too far apart from one another in anticipation of a gregarious seeding. I would encourage as much as possible grazing while waiting for this event, and then in the immediately following dry season prepare properly distanced patches at least 10′ × 10′ in size for the reception of the seed. If necessary, I would supplement the naturally fallen seed by sowing with the hand. The patches should be weeded once to keep the soil in them sufficiently free for the rapid downward

extension of the taproots of the seedlings. As anjan bears transplanting well, I would utilise superfluous seedlings from the patches from their third year onwards (younger seedlings would not be robust enough) to fill up the intervals between the patches. An ideal method would, of course, be to grow agricultural crops on the ground up to, and including, the seed year, but it would be impossible to find a sufficient number of persons complacent enough to take up the cultivation on the condition of clearing out at the end of the rainy season immediately following upon the fall of the seed. Grazing must, of course, be absolutely excluded until the young crop is tall enough to be safe from injury.

6. Before deciding to write this letter I asked our old friend, Mr. T. B. Fry, now in charge of the Central Forest Circle, Bombay Presidency, to give me the benefit of his long experience of the anjan in that Province. A copy of his reply is annexed. At the same time I would ask you kindly to favour me with your own experiences and views.

Letter No. 1558, dated the 11th August 1903, from T. B. Fry, Esq., Conservator of Forests Central Circle, Bombay Presidency, to the Conservator of Forests, Berar.

In reply to your letter No. 312 of 3rd intstant, I have the honour to say that our experience regarding the natural reproduction of anjan appears to be much the same as that which you have described as taking place in Berar. The tree seeds more or less irregularly every year and abundantly every third or fourth year, but in spite of this one never finds a dense growth of saplings. Throughout Khandesh and Nasik, where the tree is fairly abundant in parts, I have almost invariably noticed that the trees are dotted about singly 20, 30 or more feet apart. In our case fire and grazing may have had something to do with this, especially in Khandesh. If we could protect seedlings from these two dangers, I believe that many more of them would survive, though possibly the open nature of the forests in which the anjan grows may have something to do with the great mortality among the seedlings. Perhaps they cannot stand the fierce hot weather to which they are exposed, and something might be gained by introducing nurses.

REVIEW.

Progress Report of Forest Administration in Assam, 1901-02.

THE area of reserved forest in the Province at the close of the year was 3,707 square miles, 98 square miles having been added (99 added, 1 excluded) to the area shown in last year's report. In the. unclassed forests 976 square miles were added and 350 excluded, owing to relinquishment, leasing and correction of areas, the total area on the 30th June 1902 being 17,865 square miles.

Under the forest settlement operations 99 square miles were notified as reserves, whilst 131 square miles was in course of settlement at the close of the year. It is satisfactory to note that rights of villages in the Barail reserved forest in the Cachar Division were disposed of at a cost of Rs.1,385.

The expenditure on demarcation work and maintenance of boundary lines amounted to Rs.2 838 as compared with 2,619 in 1900-01, the cost per mile being Rs. 0-2-9 greater during the year under review. 1,143 miles of line were cleared and 4,602 boundary mounds repaired from the same spot.

During the year the revision of the Goalpara sal forest plan was commenced, but very little progress would appear to have been made with the work, said to be due to a scarcity in the labour supply. One wonders how many coolies are required for preparing an Assam working-plan! The Dambu working-plan also came up for revision, the 15 years for which it was sanctioned coming to an end at the close of the year. In this period only 2,820 trees were exploited out of 8,000 mature trees, and the officiating Conservator states that a revision of the plan is therefore not called for until there is a rise in the demand, and he says that the introduction of some scheme of extraction by means of portable tramways or slides to make transport easier seems necessary. One would have thought that this would have been one of the first things to be considered at the time of the preparation of the working-plans 15 years ago. To draw up schemes for the future working of a forest in which the number of trees to be extracted during the period is laid down and to omit to include full detailed plans of the methods by which these trees are to be taken out of the forest, with full and carefully worked-out data as to the cost of these extraction works and their nature, whether roads, tramways, slides, etc , is to produce a plan of little assistance to the officer whose duty it is to carry it out and one hardly worth the paper it is written on. A plan shows the number of trees, etc., which should be extracted and consequently the amount of revenue to be obtained from the area It must also clearly show the amount which will be required to be spent annually to enable this extraction to be made.

We gather that the question of export works would appear to be receiving serious attention, an expenditure of Rs.10,142 having been incurred on 2½ miles of a portable tramway line for use in the Goalpara, to which another mile was to be added during 1902-03 The expenditure on buildings decreased from Rs. 17,960 in 1900-01 to Rs. 10,456 in 1901-02. The reason for this large decrease does not appear from the report. We consider any cheeseparing economy in this branch of expenditure to be a very false policy, since the proper housing of the establishment is intimately connected with its health, and a sickly staff must necessarily mean poor work.

The table showing the breaches of forest law shows a decrease of 19 cases taken into court for the year under review, the fire cases decreasing by nine. Two important cases resulted in satisfactory convictions. In the one unauthorised fellings resulted in the offender being fined Rs 200, in the second the obliteration of Government forest marks on a log and the possession of an unregistered mark were met by fines of Rs. 500 and Rs. 250 respectively—both most satisfactory cases in which to have obtained convictions, though perhaps a sojourn in jail in addition to the fine would have better met the desserts of the first offender, since there are more places in India than Assam where such offences are common and they are invariably exceedingly difficult to bring home to the offenders. So profitable is this form of robbery and so small the risk of detection that a fine of Rs. 500 can easily be paid out of the large gains, whereas a sudden lengthy sojourn in jail disconnects "business" arrangements and may not improbably lead to further discoveries and convictions.

Fire protection during the year was very successful, only a small portion of the area protected suffering. The reason is attributed to the commendable exertions of the protective staff and to a favourable fire season.

Grazing in the reserve forests does not appear to require much anxious consideration in Assam, since 73 per cent. of the total area was entirely closed throughout the year, whilst of the balance 915 square miles were closed only to browsers for the whole year and 63 square miles for part of the year, leaving an area of 21 square miles only unrestrictedly open. The whole of the unclassed State forests were, however, open to grazing.

Creeper growth would seem to be becoming a serious menace to the sal trees in Goalpara, and we certainly agree with the officiating Conservator that in good sal forest expenditure must be faced in order to keep down this curse of semi-tropical forest areas.

Kokowa bamboo in the Nowgong and Tarai bamboo in the Garo Hills flowered during the year.

The expenditure incurred on plantations was Rs. 6,554. 4,252 rubber trees were experimentally tapped during the year; they yielded 1,240℔ of clean rubber and 814℔ mat (inferior) rubber. The expenditure incurred on the tapping operations was Rs. 671. The rubber remained unsold at the close of the year owing to a fall in the market price.

The Charduar caoutchouc plantation was extended by 217 acres at a cost of Rs. 6,349. Experimental tapping was again carried on in the plantation, 4,193 trees being tapped, their average age being 22 years. 1,071 rubber trees in the nurseries in compartments 2 and 3 of an average age of 22 years were also tapped. The result was a yield of 6,740lb of rubber, which remained unsold.

A rough system of selection felling is said to prevail in the reserve forests throughout the circle, under which no tree of under 4½ feet girth may be felled. 13,210 trees of all kinds were removed, of which 6,819 were sal, as against 11,250 and 7,386 respectively in 1900-01. In the unclassed forests 11,550 trees of all kinds were removed as compared with 27,477 in 1900-01, the decrease coming under the trees removed under trade licenses. The receipts from grazing show an increase of 17,012 as compared with 13,925.

There was a decrease of more than a million cubic feet of timber as compared with the previous year, and this is attributed entirely to the fluctuating demand for *gurkati* timber in the Garo Hills. This demand appears to drop by a third every other year.

The departmental operations undertaken show that 73,906 cubic feet of timber, 11,586 cubic feet of fuel and 18,172 cubic feet of minor produce were extracted as compared with 50,742, 4,651 and 12,913 cubic feet respectively in 1900-01. No sleeper operations were undertaken.

Purchasers removed 4,693,420 cubic feet as compared with 5,541,481 of the preceding year.

The number of tea boxes sold amounted to 412,887 as compared with 386,076, the royalty realised being Rs. 22,362 as against Rs. 20,938.

The value of minor produce decreased by Rs. 63,000, chiefly due to the smaller revenue derived from rubber owing to the low prevailing market rates. It is proposed to send that collected departmentally to England in the hopes of realizing a better price for it.

The financial results are as follows:—

	Rs.
Receipts	4,83,908
Expenditure	3,25,507
Surplus ...	1,58,401

A decrease of Rs. 62,036, which has already been explained above. Some new rules were introduced during the year for the regulation of the extraction of produce from the Garo and Jaintia Hill tracts.

V.—SHIKAR AND TRAVEL.

The Indian Pheasants and their Allies.

By F. Finn., B. A., F. Z. S.

(*Continued from page* 420.)

Chapter IX.

QUAILS.

The partridges being now disposed of, we come to the quails, under which heading, as I said in the introduction, are included all the smallest members of the pheasant family, having the closed wing under five inches in length. The term, like "teal" among the ducks, is somewhat conventional, for just as some small ducks, such as the whistlers, are called "teal," though their relationship to the proper teal is obviously small, so some of the "quails" are evidently tiny partridges rather than close allies of the typical quails. Whatever their real relationships may be, the ten little game birds which are popularly known as quails are separable as follows :—

The *Mountain quail* by having the tail well-developed, nearly as long as the closed wing; other quails having very short tails.

The *Stout-billed bush quails* (2 species) by their thick, short bills, and short but well-formed tails about half as long as the wing.

The *Slight-billed bush quails* (4 species) by having ordinary bills and well-formed tails about two-thirds as long as the wing.

The *Typical quails* (3 species) by having no noticeable tail at all, the tail feathers being not only less than half as long as the wing, but so soft that they are not easily distinguished from the ordinary plumage of the rump.

It should be noted that the so-called Button quails or Bustard quails do not belong to the pheasant family at all, but form a curious little group of their own, the Hemipodes, which will be dealt with at the close of this series. They have the same soft tails as the typical quails, but differ from them and from all other *Phasionidæ* in having no hind-toe,* no web at the base of the toes, and only a single row of scales down the front of the shank. The head has also a quite different expression from that of ordinary quails, the bill being longer and the eyes yellowish white.

---

* The Australian Plain Wanderer (*Pedionomus torquatus*) has a hind toe and some Australian Hemipodes have short stout bills, but the above characters will diagnose all Indian species.

The typical or soft-tailed quails fall into two sections, one containing the common Japanese and Rain quails, with the sexes not very different and about a dozen feathers in the tail, and the other the little painted quail, in which the male and female are extremely unlike and there are only eight tail feathers. The plumage in these quails is marked conspicuously with light streaks above, and there is no spur in either sex, though this does not prevent the males from fighting furiously. They live always on the ground, and are more or less migratory.

THE COMMON QUAIL.

Octurnix communis, Blanford, Faun. Brit. Ind., Birds, Vol. IV., p 114. Native names:—*Bater*, *Baru bater*, *Gagus bater*. Hind.; *Butairo*, in Sind; *Butri*, Bengali; *Gundri*, Uriya; *Soipol*, Manipuri; *Botah Surrai*, Assamese; *Bur-ganja*, *Gur-ganj*, Poona and elsewhere; *Burli*, in Belgaum; *Gogari-Yellachi*, Telugu; *Peria-ka-deh*, Tamil; *Sipale haki*, Canarese.

Both sexes of this species are much alike, the plumage being a mixture of black, brown, and buff, streaked with cream colour; there is a conspicuous cream streak down the crown and eyebrow stripes of the same colour. Below, the plumage is buff, darkening into reddish brown on the flanks, which are spotted with blackish, and boldly marked with whitish streaks. The pinion quills are brown, with buff bars on the outer web. The bill and eyes are dark and the feet flesh coloured.

The male has the breast without spots, and the throat dirty white with a dull black mark shaped somewhat like an anchor, the shank running down the centre of the throat and the arms curving up on each side. The female has the throat plain whitish, but the breast is spotted with black. Although there is a good deal of variation in tint in this quail, Indian specimens are on the whole true to colour, though some males occur with a rusty ground colour on the throat; in Europe this, and even the marking, is more variable: and this part of the plumage may be entirely dark or rusty brown. This quail is about eight inches long, with the wing, which is longer in proportion than in any other bird in the family, four to four-and-a-half inches; the shank is about an inch long. The hens run longer than the cocks, though the difference is not striking. The weight is between three and four ounces.

This is the most widely-spread and thoroughly migratory species of the present family; it is found over most of Europe, Asia, and Africa, breeding in the northern parts of its range and moving southwards in winter. Great numbers are caught on migration and many must perish at sea; I remember, ten years ago, I saw one poor little thing try to board a ship I was on in the Red Sea, and, striking the side, fall into the water. Another, less utterly exhausted, was caught on board and ultimately reached the London Zoological Gardens Most of our Empire is visited by this bird in winter, but it is most abundant in Northern India, rare in Burma, and absent from Ceylon and Tenasserim Some come by sea on to our Western coasts—Sind, Cutch, and Guzerat—but most cross the Himalayas from Central Asia, and these arrive earlier

Their distribution with us varies with the season they encounter on reaching India If there is plenty of food in the north, most of them stay there, but in years when the crops are deficient there, they move southward to a greater extent; moreover, in some years a great many more birds arrive than in others. In the Calcutta bazaar during the seven years I have watched it, quails only came into the ordinary bird-sellers'* hands one winter, about two years ago if I remember aright; then the men had plenty of them, and they were reported as being unusually common in Bengal Ordinarily only one man in the Calcutta bazaar has quails, and he gets the birds from up-country and keeps and feeds them for months being a resident and considerable dealer, unlike the men who only come in the winter to sell birds more or less locally captured.

The quails come in across the sea from the west before the end of August, and about a fortnight later the main body from the north arrive At the end of February they begin to draw northwards again, and if the south of India has not come up to their expectations the north will be full of them in March Some will linger in the south for a time as others had done in the north, but in any case hardly any will stay behind permanently and breed with us

They migrate at night as a rule, though stray specimens may be seen, at sea at any rate, by day Mr Hume describes how on one moonlight night in April a few miles from Mussoorie, a huge cloud of them, 'many hundred yards in length and fifty yards I suppose in breadth' passed over him quite low down. That the quail is more or less nocturnal I have little doubt. A specimen which I kept years ago in my rooms at Oxford was quite as active by night as by day whereas ordinary birds will go to roost in a room quite irrespective of the artificial light of lamps or gas. For the same reason quails are very unsuitable inmates for a mixed aviary, unless they have a wing cut, as they will get restless at night and fly up against the roof, to the detriment not only of their own personal appearance, but also of the peace and happiness of the other inmates of the place.

A special place for quails, where these birds may be kept for food, should, however, it is said, be kept dark to prevent their fighting. The floor of a "quailery" should be well supplied with sand, and fresh turf, white ants occasionally, and a constant supply of water in a small trough should be provided in addition to their ordinary food of millet. Thus treated they will keep fat and healthy, and, as many people know, be of the greatest use in the hot weather As they are even better to eat when properly fattened than when killed wild, it is not only humane but politic to treat them as well as possible, as is the case with all other animals in a state of captivity or domestication.

---

*Quail were very plentiful round Calcutta in December-January, 1899-1900, good bags being made in a couple of hours' shooting The birds were also plentiful in the Dun (N India, in the autumn of 1900 and spring of 1902 —Hon. Ed.

The natural food of this quail is millet and other grain when it can get it, and at other times grass-seed and small insects chiefly; it feeds chiefly in the morning and evening, resting in the middle of the day. Here and there a few pairs remain and breed with us, even in the east as far as Purneah and south in the Deccan. These, however, are not of a resident strain or race, such as exists in some other countries which quail also visit as migrants, but birds which by some accident, such as one or both of the pair having been wounded by shot, have been unable or unwilling to depart with the rest of their kind.

Though the male has the reputation of associating with several females where the species is numerous, he appears to pair with one only in India; the nest is a mere hollow in the ground, usually with more or less of a lining of grass. In India ten eggs appear to the largest clutch, though up to fourteen may be laid in Europe.

These eggs are a little over an inch long, and are speckled with brown on a buff ground, the markings varying a good deal. They may be found in March and April. In the latter month this bird was observed to be breeding abundantly about Nowshera in 1872, which was an exceptionally backward year, so that the quail had evidently decided in many cases to make the best of things where they were and not go north, since they should have all been out of India a month later in the ordinary way.

The cock quail is a pugnacious little wretch, and is often kept by natives for fighting, as he used to be also by the ancient Greeks. The latter used, besides setting the birds at each other, to indulge in an even more feeble sport, which consisted in putting one's bird in a ring when the other player tapped it on the head with his finger, and won the game if the bird ran out of the circle.

In Calcutta I have now and then seen in the quail cages a bird of a lurid red ochre hue, evidently stained with some dye: and I am told on good authority that the said dye is nothing more or less than the saliva of a *pan* chewer, smeared on the luckless bird to stimulate its courage; certainly such an application would infuriate a white mouse, I should think! Presumably the bird which, after this doctoring, permits itself to be defeated is frugally sold as an edible; but after this I rather draw the line at red quails in that capacity. In China the unhappy quail is said to be brought to an enhanced state of irritability by baths of hot tea.

The note of this quail is unmistakable, being a distinct tri-syllable, the first note being the longest; many attempts have been made to render it in words, such as "Wet my feet." This is only uttered by the male, but some small chirping notes are emitted by both sexes.

Their haunts are in crops and the stubble of these, grass, bush jungle, any low cover in short, and they afford more good shooting than any other bird of this family in India. Their flight is low, straight and swift, and one has been seen to escape from a harrier by sheer speed, but then a harrier is not a very swift hawk. They are often very unwilling to rise, and I have even heard of one being trodden upon, which is what one might call falling a victim to a policy of *laissez-faire*.

VI.—EXTRACTS, NOTES AND QUERIES.

The Home Timber Trade and Forestry.

PART II.

In the first part of this article we confined ourselves to a brief notice of the close relations existing between the forester and the timber merchant, and pointed out some of the recommendations of the recent Government Commission on Foresrtry for improving the education of owners, agents, foresters and woodmen so that a better and more efficient system of forestry may be introduced into this country. The necessity for this is apparent to everyone who depends for his living, or a part thereof, upon our home timber productions. The present deplorable condition of British forestry has been too often emphasised recently to need further comment here, except to say that it was the increasing outcry against the continued existence of this condition for an indefinite period which was directly accountable for the appointment of the commission by the late Mr. Hanbury, whose untimely decease is deeply regretted by everyone interested in the land problem.

The establishment of a high standard of theoretical and practical education in woodcraft must be looked upon as the primary step towards improved forestry; but, at the same time, before any considerable sums of public money are expended in this direction, we desire to know the exact form it is contemplated that this new educational system would take. Special lectures upon tree growth from chemical, botanical, geological and agricultural points of view would doubtless be beneficial scientifically. A practical knowledge for growing trees to perfection in masses is very useful. But in growing trees with public money the commercial aspect demands the highest consideration. It would not be wisdom to enter into hazardous experiments with untested varieties of trees at the outset. We do not altogether anticipate this would be the case, but we feel compelled to utter a word of warning, as we have noticed during the last few years that there is an increasing tendency amongst arboriculturists to experiment in growing trees of foreign extraction but which turn out to be entirely unsuited to our climate, and it is just possible that they might look upon proffered Government assistance as a favourable opportunity for carrying out these experiments upon an extensive scale, and would bring pressure to bear for the purpose. We have already a great variety of timber-producing trees which, from generations of experience, are known to be capable of perfect development and are adapted to the British soil and climate, and on the strength of this proven knowledge the whole structure of the home timber trade is built up. We would not throw cold water upon any experiments for increasing by valuable additions those varieties constituting our standard commercial timber trees, but this must be a secondary rather than a primary matter. In any serious State-aided attempt to improve our forestry it must be essentially upon an economic basis, and it is necessary to proceed along lines possessing the greatest possiblities of success with the least risks of failure, and it can only be done in this case by taking advantage of practical knowledge resulting from long experience, and absolutely confining the first steps to perfecting our present varieties of home-grown timber trees; and there is plenty of scope in this direction alone to occupy the most ardent forester for many years to come.

Although the Government commission are deserving of praise for recommending increased facilities for thoroughly educating all persons in any way connected with forestry, they appear to shirk the main issues. Education, after all, is merely preliminary, and if State aid is to stop short there we are afraid it will do more harm than good It will create an intolerable position for the newly-educated and ambitious forester, instead of leaving him in a state of blissful and contented ignorance. In the majority of instances he will find his hands tied by the limited resources of the owner, who may not be in the position, or even have the inclination, to lay out money to improve his woodlands; and after much expense to himself, and considerable cost to the country, the poor forester, with all his certificates and diplomas, will be compelled to hide his light under a bushel, and revert to his pre-educated existence—a sadder and a wiser man. It would be the greatest possible mistake to stop short as soon as the course of technical instruction was completed. In the event of anything being done, it should be incumbent upon the State to provide positions in which those foresters who had successfully passed through their studies could advantageously utilise their knowledge so as to warrant the expenditure of public money for educational purposes. Any attempt to solve the problem of British forestry cannot be satisfactory unless it is carried out in a wholehearted manner. No amount of mere tinkering will assist the matter one iota. but would give rise to much dissatisfaction amongst the public, who would look upon it as a useless expenditure, unless some really permanent and profitable object was to be attained, and any adverse attitude would probably end in a retrogressive movement, causing any effectual solution to be postponed indefinitely.

Any extensive improvement of British forestry can only be accomplished by forestry becoming a great State industry. To any one who has given serious thought to the question this is a foregone conclusion, as no individual efforts on the part of private persons can ever succeed in giving the country a reliable supply of timber in large enough proportions. It is the aim of those persons who have the question most at heart to place the country in a position independent of foreign competition as far as coniferous timbers and those hardwoods which can be grown to perfection in our climate are concerned, and the only way in which this can be done is for forestry to be conducted on commercial lines absolutely controlled by the State, with the exception of those woodlands already in cultivation by private owners, which, by the way, if improved, would act as a welcome supplement, although their present unsystematic condition renders them scarcely worth consideration. The astounding fact that there are 21 million acres of waste land in the British Isles is a standing disgrace, reflecting adversely upon all our national, political and social economic systems. The future historian as he turns to this fact will be amazed at the immense and paradoxical folly of our times. Our overcrowded towns glutted with a superfluity of both skilled and unskilled labour, our depopulated rural districts deserted for the towns and arid wastes and barren plains of far-off countries, will present to him a mysterious and inscrutable problem, particularly as we have within our reach a natural mine of wealth totally unexploited not only capable of giving employment to a great new rural population, but with untold commercial possibilities.—*Timber Trades Journal.*

The Lumberman and the Forester.*

BY GIFFORD PINCHOT,

Forester, U. S. Department of Agriculture.

IT is only a few days since President Roosevelt, speaking to the Society of American Foresters, a body of professional foresters, said that in the final analysis the success of forestry must depend upon the attitude of the lumbermen toward it. [*Vide* p. 301 of this volume.—HON. ED.] That view is accepted and believed by no one more completely than by the foresters, and it is, first of all, for that reason that I am glad of this opportunity to say a word to you. I realize that the great majority of the timber lands of the United States will pass through your hands first or last, and that upon your attitude toward them will depend the final result, not only to you in your business, but to the nation at large in the perpetuation of its forests.

One of the recent tendencies in the lumber business has been to reduce waste in every possible direction You have taken this up first of all in the mill; it has gone from the mill to the woods and the methods of logging, and in many parts of the country has already begun to affect methods of cutting This tendency to avoid waste, to make better use of natural resources, is not confined to the lumber trade by any means. It is characteristic now of all the industries of the United States, and is the logical outcome of the economic situation, just as, in my belief, the interest of the lumbermen in forestry must necessarily be the logical outcome of the economic conditions under which the lumber business is placed You have naturally and logically moved forward step by step in this progress of eliminating waste, making more out of the material with which you have to work. It is perfectly logical and natural, therefore, that the next step for you to consider is the use of your standing timber, not merely for itself alone, but also in relation to the value of the land to you later on. That is the whole essence of forestry. As President Roosevelt has phrased it, "The principal idea in forestry is the preservation of forests by wise use," and the conception upon which the whole matter is based is simply the question of whether or not you intended to get a second crop.

The old idea that the forester was the enemy of the lumberman, and, above all, the enemy of cutting timber disappeared long ago from the minds of foresters, or rather friends of forestry—for no true forester ever held it—and is rapidly disappearing from your minds and those of other lumbermen. And that is perhaps the happiest aspect of the whole situation, for the perpetuation alike of your industry and of forestry depends upon your attitude toward this single question: Do you or do you not intend to get a second crop?

---

* Address delivered before Convention of National Lumber Manufacturers' Association, Washington, D. C., April 20, 1903.

I am very far from wanting to discuss with you the supplies of standing timber or the prospect of a timber famine—questions with which you are more familiar than I am; but it is perfectly obvious that the supplies of certain kinds of timber are rapidly disappearing, that the lumber trade is falling back year by year on poorer material and longer hauls, and that the question of its continuance is already demanding an answer

This is purely a business proposition which I want to lay before you, to be considered, accepted, or rejected on a business basis. Forestry deals with the forest in some ways with which you have but an indirect interest. I am not talking now about the effect of forests on the flow of streams, on winds, or on the general prosperity—matters of vital importance in their place; but the question I want to bring to you is simply this: Is it worth your while, from a commercial point of view, to consider the forest as a part of your plant, and from that point of view should you cut off your timber and let the land go back for taxes?

Let us take an illustration. Suppose any one of you has a tract of timber land in Arkansas, for example—for we have some good figures for that State. You find that under certain conditions, which make practically no difference in the cost of getting out your logs—and it is the business of the Bureau of Forestry to ascertain what those conditions are—you can get a second crop of the same amount off that land in forty years. It will be a man's tendency, as it was mine when I began this work, to think of forty years as a very long time, a period beyond ordinary calculation, hardly worth while to figure on. Nevertheless, if I interpret the economic tendency of the country at all rightly, men look farther ahead now than they once did, and it is very well worth their while to do so We will say that in forty years you can get a second crop on that land equal to the first. We take the stumpage at its present value, with taxes as they now stand, and we estimate the expense of protection against fire and theft. We find in this particular case that the returns on the capital invested for those forty years is 6 per cent. net. That is calculated on the basis of the present value of stumpage. We all know that the value of stumpage will increase largely in forty years. The matter becomes, then, simply a question of whether or not it is worth your while to take the incidental risks and hold your land for forty years rather than to put your money into something else. But it is not a question of whether you will put the money back into your land after taking the timber off of it, but whether you will take the timber off in such a way that when you have cut over the land it will be in condition to go on producing timber without further expense. Either the timber land is part of the manufacturing plant, or it is not, and that is the whole difference.

If you are the owner of a mill, as of course you all are, you must necessarily consider, if you want to keep that mill in permanent operation, how much land you need to grow timber to supply you with your daily cut. Then you have a complete plant which is like a machine shop, turning out material for its own needs. From the point of view of the forester, where a business question is as clear cut as that, it becomes as foolish to destroy the productive capacity of your land as it would be for the owner of a machine shop, when he had an order for a shaft or a cog wheel, to take that shaft or cog wheel out of his own machinery and sell it rather than make his machines produce it. As I have said, and repeat, this is purely a business question.

The Bureau of Forestry offers certain assistance to lumbermen in preparing the basis upon which such questions can be most intelligently decided. What it does is simply to put a certain amount of trained skill at your command. You pay the expense and we prepare for you the necessary figures. The way we do it is to send a man to the spot, who finds out what there is on the ground, with special reference to the smaller sizes—how fast each diameter class of trees grows, how much will be left of certain sizes after cutting out others, and how much will be standing to the acre after a definite number of years. We put the thing purely and entirely on a business basis.

These methods of forestry are not at present as fully applicable everywhere in the United States as they will be later on, and it is as far from me as possible to want to urge any man to adopt the methods of forestry unless they are going to pay. The arrangement we make with timber owners is never that they shall be compelled to apply the plans we submit, but always that they shall apply them or not as they find it wisest to do. I would be exceedingly sorry if any man should take up a proposition in forestry and apply it if he was not confident it would turn out well, because this is not a question of a few days or merely for present conditions.

What I have been describing to you is, of course, only one of the ways in which the Bureau of Forestry is attempting to serve the lumber interests of the United States. Another is a very extensive series of timber tests which we are just taking up to learn the comparative merits of different timbers for different purposes: and there are many others, some dealing directly with the lumber interests and some indirectly. But the essence of what I have to say to you to-day is simply that this matter of practical forestry is presented to you as a business proposition to be accepted or rejected as a business proposition, and that my interest in it and the object of my presence here is simply to [illegible] you whether it is worth your while to consider your forests as a part of your plant or whether it is better worth your while to abandon them after they have been cut.

I shall be very glad, indeed, if I can answer any questions which may come up now or later on, and I shall be especially glad if I or any other member of the Bureau of Forestry can be of use to you, individually or collectively, in any possible direction. There has been too long a feeling that the foresters were trying to force the lumbermen to do something or other against the lumbermen's will. I think it is time for the lumbermen to give the Bureau of Forestry a chance to do some things which they would like to have it do.

VII—TIMBER AND PRODUCE TRADE

Churchill and Sim's Wood Circular.

4th September 1903.

East Indian Teak.—The deliveries for the first eight months of this year amount to [illegible],603 loads as compared with 8,890 loads in the same period of 1902; while for August last they are 1,041 loads against 901 loads in August a year ago. The London market has been dull during the month, prices being at a level from which they must come down some time or other if there is to be a return of free supply and consumption; and although there is no prospect of this ahead at present, the trade remains hampered and nervous. In the meantime the forward demands which arise cannot be quoted for, even for next year's supply.

Rosewood—East India.—Well grown wood, of large dimensions, would find ready buyers at full figures, but small and inferior logs are not wanted

Satinwood—East India.—The demand remains inactive and sales are not easily effected, while the stock on hand is more than sufficient.

Ebony—East India—Most of the wood in stock is inferior and consequently very unsaleable.

PRICE CURRENT.

Indian teak, logs,	per load ...	£10 to £18
" " planks	" ...	£12 10s. to £20.
Rosewood, per ton	... ...	£8 to £11.
Satinwood, per s.ft.	... ...	6*d*. to 18*d*.
Ebony, per ton	... ...	£8 to £11.

Denny, Mott and Dickson, Limited.

WOOD MARKET REPORT.

1st September 1903.

Teak.—The landings in the docks in London during August consisted of 655 loads of logs and 258 loads of planks and scantlings, or a total of 913 loads, as against 820 loads for the corresponding month of last year. The deliveries into consumption were 496 loads of logs and 389 loads of planks and scantlings—together 885 loads, as against 972 loads for August 1902.

The dock stocks at date analyse as follows:—

	5,739 loads of logs,	as against	5,424 loads	at the same date last year.
	3,607 " planks,	"	3,240	" " "
	— " blocks,	"	—	" " "
Total	9,346 loads	"	8,661 loads	" " "

The market has developed no new feature. The Indian shippers continue to look to America and South Africa rather than to Europe for the marketing of the small supplies remaining on hand at the shipping ports. The chief question of interest for European importers is, when the present autumn's outget from the forests is likely to reach Rangoon, Moulmein and Siam in sufficient quantity to judge of the quality and volume of such outget. Shippers do not seem to contemplate that the result is likely to affect their present independence of the European market; but, naturally, contracts are of a hand-to-mouth character with importers here, and consumers, at the present level of prices, continue to be reluctant to buy anything more than they imperatively need. This market is, therefore, likely to be a dragging one for the remainder of the year—the more especially as the efforts to substitute Oregon and pitch pine for many purposes where teak used to be specified are meeting with some measure of success.

Business during August has shown some little revival in a few directions, but this has been due rather to the approaching close of the season in respect to some imports, than to any strengthening in the demands for consumption.

Market Rates for Products.

Tropical Agriculturist, 1st *September* 1903.

Cardamoms	...	... per lb.	1s. 6*d*. to 1s 7*d*.
Croton seeds	...	... " cwt.	15s to 22s. 6*d*.
Cutch	...	... " "	20s to 27s. 6*d*.
Gum Arabic	...	... " "	15s. to 20s.
Do. Kino	...	... " lb.	4*d*. to 5*d*.
India-rubber, Assam		... " "	2s to 3s. 2*d*.
Do. Burma		... " "	2s. to 3s. 4*d*.
Myrabolams, Madras		... " cwt.	5s. to 6s.
Do. Bombay		... " "	4s. to 7s. 6*d*.
Do. Jubbulpore		... " "	4s to 5s. 6*d*.
Do. Bengal		... " "	3s. 6*d* to 5s.
Nux Vomica	...	... " "	7s. to 10s.
Oil. Lemon-grass	...	... " lb.	6½*d*.
Orchella weed, Ceylon		... " cwt.	10s. to 12s 6*d*.
Sandalwood, logs	...	... " ton	£15 to £30.
Do. chips	...	... " "	£4 to £8.
Seedlac	...	... " cwt.	115s. to 122s. 6*d*.
Tamarinds, Calcutta		... " "	8s. to 10s.
Do. Madras	...	... " "	4s. 6*d*. to 6s.

THE

INDIAN FORESTER.

Vol. XXIX.] December, 1903. [No. 12.

Notice to Subscribers.

Mr. E. P. Stebbing, Honorary Editor, having proceeded on six months' furlough to Europe, Mr. R. McIntosh has undertaken to act temporarily as Honorary Editor until Mr. Stebbing's return. All contributions should be addressed to R. McIntosh, Honorary Editor, Dehra Dun, United Provinces.

The Commercial Value of Mhowra (*Bassia latifolia*, Roxb.) Seeds.

By G. M Ryan, F.L.S., I.F.S.

It might interest Forest Officers in the Bombay Presidency, and also other parts of India, to hear, in case information on the subject has not already reached them, that a brisk demand has just set in in the Bombay market for Mhowra seeds. A certain demand for this minor product has existed, it is true, during the past few years for various purposes, as the export returns quoted later on show; but the present demand appears to be quite distinct from the previously existing one, brought about apparently by a discovery in Europe of a new use for the oil from the seeds; and the supply, judging by information obtained in the Bombay market, appears to be unequal to the demand.

A gentleman in one of the leading firms in Bombay, under date 2nd October 1903, referring to Mhowra seeds, says: "We bought only yesterday at Rs. 5-8 per cwt., but this was an unusual price; you may take Rs. 4-8 per cwt delivered free railway station in Bombay as a reliable rate. Prices of Mhowra seed fluctuate a great deal, but I have never seen them below Rs. 4-4 per cwt."

Another large firm received an order from England on the 3rd instant for Mhowra seeds at £8 2s. 6*d*. per ton, but have been unable so far to execute it. Such being the state of things, it seems incumbent on me, with a knowledge of the facts, to make them known, and it is felt that by doing so through the medium of the *Indian Forester* some benefit might accrue to the State thereby. An eye ought certainly to be kept on the Mhowra seed collections wherever the tree is found in any quantity, and if timely arrangements are made for the Departmental disposal of the produce some additional revenue may possibly be realized in certain localities from this produce. The market value of Mhowra seeds is higher than for myrabolams, and if it is considered desirable in the interests of the State to dispose of the latter minor product annually, why not so with Mhowra seeds?

It might be urged that the collection of seeds will interfere with the local requirements of the people, for almost everywhere oil is expressed from them for domestic purposes; but if the right to collect the seeds is farmed out, or a duty levied on the amount exported from a district, there need be no apprehensions on this score. It might be thought, also, that the collection of seeds will restrict the collection of the flowers—a product which is also an important article of minor produce; but fortunately no apprehensions need be felt on this account also, for it is only the fleshy corolla of the flower which is gathered, the calyx and pistil and ovary being undisturbed. In some parts of India the produce is evidently being collected to a tolerably large extent, judging by the export returns, but no record exists in the Forest Administration Reports of any revenue being realized by the State from it. *

DISTRIBUTION.

So far as the Northern Circle is concerned, I am aware that a large quantity of Mhowra is to be found in the Panch Mahals, for during the severe famine of 1899, when there on famine duty, its majestic form in places was prominently brought to my notice, and doubtless in the other districts of Guzerat, even where no forests exist, such as Broach and Khaira, the tree will be found in fairly large quantities also In the Mandvi Taluka of Surat it is abundant.† In Khandesh the tree is fairly common on the Satpuras and Satmalas.

Sir Dietrich Brandis, in his work *Forest Flora of North-West and Central India*, says: "It is cultivated, propagating itself by self-sown seedlings, and protected in most parts of India. In the Panjab it is grown in the Sub-Himalayan tract and the outer valleys as far as the Ravi, but not commonly in the plains; abundant in all parts of Central India from Guzerat to Behar. There seems no doubt that the tree is indigenous in the forests of the Satpura Range of Western India above Ghat and perhaps also of Eastern Kamaon."

---

* In the Central Provinces Mahua and Achar are shown in Form No. [illegible] as having been exploited in 1900-01. Mahua is possibly *Bassia latifolia* but what Achar is I do not know.

† It *was* abundant 20 years ago, and the number of trees may have been reduced since, but about this I have no information at present.

Mr. Talbot in his book *The Trees, Shrub, and Woody Climbers of the Bombay Presidency*, says: "It is common in the dry forests throughout the Presidency, also in the Konkan and North Kanara forests, but nowhere abundant in them." In Thana it grows to advantage in the drier parts of the districts, away from the seacoast, the best specimens being found perhaps in Murbad and the Mokhada Petta—a tract of broken hilly country about 2,000 feet, which forms the western projection of the Ghats. The tree, which is familiarly known as Moho by the natives all over the district, is scattered in all the forests, though it is smaller in size in the Bassein seacoast taluka than further inland. It is never seen lopped for *tahal* for *rab*,* or cut for any other purpose. Hence it is invariably a much larger and more imposing tree than many others, both inside and outside the forests. It attains a height of about 30 to 40 feet and a girth of about 5 feet, and possesses a dark coloured bark, and seems to be of a light demanding habit It is a fertile cause of forest fires all over Thana, for in order to facilitate collection of the corollas the area under the crown of a Mhowra is cleared of all growth, and the lazily disposed effect this by burning the patch underneath, and the fire in most cases spreads into the forest. In spite of notices and orders cautioning the wild tribes against carelessness in this respect the evil continues. The only effective check against this is arresting the offenders and having them prosecuted, and this is commencing to have successful results, judging by the latest returns for fires from this cause in Central Thana.

ECONOMIC USES.

Leaves.—During the famine in the Panch Mahals in 1899-00 the leaves were extensively collected and used as fodder for cattle in that district, especially in the vicinity of large towns. In the Thana District they are used as wrappers for small parcels by small shopkeepers and as dinner plates.

Flowers—The flowers are of a very pale yellow, and appear in March after the leaves have fallen. The corollas shortly afterwards get detached from the calyx and begin to fall to the ground; after this the new flush of leaves, which are ruddy or a dull pink and brown appear. It is during the cool hours of the evening, during the night and early morning, up to about 9 a.m., that the constant dripping of the corollas from the trees takes place, and they are extensively collected by the people. In the Mokhada Petta the wild tribes barter the flowers in the Kasara Bazaar on the G. I. P. Railway below the Thull Ghat, for onions and salt. Marwaris obtain the flowers in this manner from the Thakurs and Kolis and export them to the distilleries at Uran across the harbour in Bombay.* Three to four baskets of flowers are bartered for one basket of onions and a little salt. The dried flowers are also sold for one anna per basket to contractors' agents. In parts of Wada the people, who are permitted under the Abkari rules to store 2 seers (i.e. 4℔) of flowers for household purposes per head, sell their surplus stock to Abkari agents, who come round to make purchases, for ¼ anna per paili of 4℔. Locally the flowers are extensively collected and eaten after preparation in the following manner. They are spread out and dried in the sun for 3 days, after which they are pounded into flour and mixed with similarly prepared kurasni (*Verbesina sativa*) seeds, salt and bread and eaten. The dried flowers are also mixed with the powdered young roots of the Ranshekit (*Moringa concanensis*) in parts of the Wada Taluka and boiled, and the decoction is drunk in colds and chills; cattle are also stallfed on the flowers for augmenting their milk supply and calving and for swollen throat complaints. The spinners and weavers in Bhiwndy eat the dried flowers also with bread.

---

* *Tahal* is the term used for the branchwood which is cut for burning to provide wood ash manure, and *rab* is the manured plot on which the rice seedlings are raised for transplantation.

Bears, it is believed, are fond of the flowers, and I remember an incident occurring in the Khandesh Satpuras many years ago, when my camp was some miles away from a post office, which rather supports this statement. The post never arrived one afternoon, and on the following day when it did arrive, the Bhil who brought it informed me that the failure to bring it the previous day was due to his being obstructed by a bear who sat in the path along which he had to go and prevented him passing. His explanation was that the bear having eaten the Mhowra flowers became intoxicated and wished to attack him. At the time I was rather inclined to discredit the story and have never since received any corroboration of it.

In order to remove the temptation for the illicit distillation of Mhowra spirit in villages, an edict went forth that the tree was to be cut down wherever it existed in Thana, and this has resulted in a large diminution during the past 18 or 20 years in the number of trees in the Thana district. In the coupes the tree is never reserved as a standard on this account, and also because of it being a source of forest fires, as already explained.

Seeds.—The seeds, which are commonly known in the vernacular as *Moholi*, are ready for collection usually by about the end of May or beginning of June.

As in the case of myrabolams, called Hirda† in the Bombay Presidency, the crop varies in quantity from year to year. Oil from the Mhowra seeds is extracted locally all over the district and eaten with vegetables.

---

* In 1884 Government undertook the collection of flowers in Thana departmentally for export, and many hundreds of maunds were collected, but in that very year France, to which country the flowers chiefly went, levied an import duty on them, so that the exports were curtailed and the venture proved a great loss.

† *Terminalia Chebula*, Retz.

Existing sources of supply of exported Mhowra seeds.—The following are the principal sources of supply of Mhowra seed received at Bombay. It has not been possible to get out the figures for each of these stations, as for some years now the railways have included Mhowra seed under the heading "Other Seeds":—

BY G. I. P. RAILWAY.

Central Provinces and Berar.

Hurda.
Itarsi.
Stations on the Nagpur Branch.
Stations on the Wardha Coal State Railway.

N.-W. Provinces

Jhansi.
Hamirpur Road.
Karwi.
Atarra.
Banda.
Mahoba.
Mau-Rampur.

Southern Mahratta Railway.

Harlapur.

East Indian Railway, *via* Jabalpur.
Oudh and Rohilkhand Railway, *via* Cawnpore.
Bengal & North-Western Railway *via* Nagpur.
Hyderabad Godavery Valley Railway, *via* Manmar.

BY B. B. & C. I. RAILWAY.

Tapti Valley Railway.

Amalner.
Fort Songhad.
Bardoli.
Nandarbar.
Dondaiche.

Godra-Rutlam Railway.

Dakor.
Thasra.
Sevalia.
Godra.
Sunth Road.
Piplad.

Gaekwar's Dabhoi Railway.

Bodeli.
S. Bahadarpur.

Ahmedabad-Prantij Railway.

Taled.
Idar Ahmednagar.

Rajpipla State Railway.

Nandod.

BY SEA.

British ports within the Presidency.

Firms engaged in the trade.—The following firms in Bombay which deal in myrabolams would probably purchase Mhowra seeds:—

Messrs. Volkart Brothers
Messrs. Ralli Brothers
Messrs. Owen and Okell
Messrs. C. Macdonald & Co.
Messrs. Bagdle & Co.
Messrs. Killick, Nixon & Co.
Messrs. N. Futtehally & Co.

Amount of seed available for export in Thâna.—Without interfering with the local demands and the amount of seed needed for sowing and planting[*] if necessary, the quantity of seed available for export would probably be not less than 400 khandies or say 2,000 cwt.

Cost of collection—It pays contractors to purchase the myrabolam crop in Thana and export it at their own cost, and this is done when the present price of the crop is worth Rs 3-4-0 per cwt delivered Bombay. The Mhowra crop being worth Rs. 4-4-0, it can be easily understood how much more lucrative the transaction would be. Doubtless the value of the produce would fall as the supply increased, but even allowing for this, a profit equivalent to that in myrabolams at any rate will probably result. It is unnecessary to enter into further details so far as cost of collection of seed is concerned under the circumstances, especially when the crop is to be farmed out. In case however contractors are reluctant to enter on this new business, it may be necessary to undertake Departmental work at first, and for this reason the following rates, as obtaining in Thana, and other particulars are given for information :—

PRICE OF SEEDS IN BOMBAY :—

	Per cwt Rs. a p.	Per cwt. Rs. a p.
		4 4 0
Cost of collection	1 8 0	
Cost of gunny bags	0 8 0	
Freight at 2-9 per maund for 50 miles .	0 4 0	
Loss by dryage and wastage, etc, 20% ..	0 8 0	
Establishment 25%	0 11 0	3 7 0
Rs.	3 7 0	
	..	0 13 0

Profit say :—

13 annas per cwt. for 2,000 cwt.

13 as. × 5,500 cwts. Rs. 1,635.

Exports from India—Very full and interesting particulars about the Mhowra tree, its distribution and the economic uses of its flowers and seeds may be found by a reference to the *Dictionary of Economic Products.* In that volume, page 414, wherein figures showing the external trade of Mhowra are given the export returns of flowers only is quoted. It would appear that at the time the note was written[†] (*viz.* 1883-84) an export trade only in flowers existed and that the trade was mainly with France.[‡]

---

[*] Quite recently some Mhowra seed was collected in Thana for Mr. J. P. Watson, a Bombay merchant, for despatch to South Africa, where he intended to try and grow it on the veldt.

[†] There may be a subsequent note, but I am not able to trace it.

[‡] Mhowra seeds are exported to Hamburg and Antwerp.

Now this trade has almost entirely ceased, judging by the recent returns, for only once during the last two or three years have Mhowra flowers been exported from India, and the quantity was only 93 cwt.

The export trade in Mhowra seeds has been as follows since 1897-98 for Bombay and the whole of India :—

	Bombay Cwts	All India. Cwts
1897 98	not given	253,746
1898-99	148,450	189 389
1899 00	358 083	367,092
1900 01	31,958	31 958
1901-02	597,009	612,649
1902 03	252 668	

For the sake of comparison the exports of myrabolams for all India are as follows :—

	Cwts
1897-98	726 060
1898 99	905 916
1899-00	1,019,285
1900-01	945 648
1901-02	1,085,174

Cotton seeds used to be exported from India in small quantities for a number of years, but now, as is well known, the demand has risen very considerably for this product for the manufacture, more particularly, of margarine, it is said; so that the exports have reached enormous proportions. Let us hope that a similar good demand is setting in for Mhowra seeds (at present at any rate a very good demand exists) and in these days of a declining revenue in myrabolams it behoves us to look around for further sources of profit.

Conclusion.—I am indebted to the courtesy of Mr. Noel Paton, secretary of the Bombay Chamber of Commerce, for the statistical information given above about the Mhowra seed exports. He is a gentleman most interested in the development of new industries, and will be at all times willing, I am sure, to supply Forest or other officers with all the information they might at any time need about the value, etc., of various commercial products.

What should Madras Forests yield?

II.

In the previous article an attempt was made to show roughly the value of the yield of the Madras forests if they were properly protected and markets could be found for their annual yield.

To deal first with the question of markets; the unproductive forests will only be open to the production of revenue under compulsion, to meet the demands of neighbouring villages. So far as this class is concerned, the market question presents no difficulty.

The remunerative forests yield principally timber, and as we are constantly hearing about the diminution in the world's supply of timber and the coming timber famine, it may be presumed that the export trade will absorb surplus over internal demand.

The productive forests will, at ¼ ton per acre, yield 10,66,666 tons fuel and small timber annually, and the market for this large quantity must be found in the Presidency itself and within a comparatively small number of miles of the sources of production. In exceptional cases it pays to transport fuel a considerable distance (*e.g.*, casuarina fuel from Nellore can be sent to Madras, a distance of 80 miles, by canal, and sold at a profit), but as a rule fuel will not stand cartage exceeding 12 to 15 miles, while small timber eats its own price if transported by cart for more than thirty miles.

On the other hand, the denudation of unreserved lands is making rapid strides, and the population is becoming more and more dependent on the Government reserves for its fuel and small timber; the large towns, such as Madras, Madura, Trichinopoly and Salem, will before long be entirely dependent on Government forests for fuel for domestic consumption, and the demand for agricultural implements, materials for cart building, fuel for jaggree and indigo boiling, for lime kilns, brick kilns, etc., in every village must be met more and more from the same source. The railways still burn wood fuel, and are likely to continue to do so as long as it can be supplied at prices which compare favourably with those of coal, and as they can dispose of 40,000 tons annually, only 166,666 tons are left to be accounted for by domestic consumption, agricultural requirements and local industries. A very rough calculation will show that if all these local requirements are to be met from the produce of Government forests, not only will there be no lack of markets, but the total quantity available will not equal the demand. At one pound per head per diem every six persons need one ton of wood per annum, and if there were not other sources of supply there would be a dearth of fuel in the land. As the State forests are practically the only protected wooded areas (except private casuarina plantations), it is evident that as years pass the demand for fuel will fall more and more heavily on them, and in order to meet this demand more rigorous protection is required now, so as to improve the stock and increase the annual yield. And this brings up the question of protection. Before the days of Dehra Dun Rangers, the Forest Department was a happy hunting ground for subordinates of all classes; the only bit of leaven in the district loaf was the District Forest Officer, who was unable to check the predations of his subordinates scattered over an area of several thousand square miles; these were of course exceptions, and happy was the D. F. O. who had at least one trustworthy Ranger under him. Some were merely lazy and did as little work as they could, and as some ranges were over a hundred miles in length, neglect of work at any one spot was always accounted for by the Ranger's absence at the other end of his enormous charge. Others were absolutely dishonest, and joined the department with the sole object of enriching themselves, an object easy of attainment when every man's hand was against the forest, and even the local magistrates sympathised with the people who were not allowed to help themselves to forest produce when, where and how they liked, as their forefathers had done before them.

With such an example set by the Rangers it cannot be wondered at that the forest guards followed suit, and the post of forest guard was so much sought after that it was not uncommon for a man to resign a post in some other department on a salary of Rs.10, Rs 12 or even Rs 15, in order to obtain a forest guard's post on Rs.6 or Rs.7. The reverse of the shield must also be taken into consideration; District Forest Officers had such enormous areas to travel over that they could not supervise and inspect Rangers' work sufficiently often or thoroughly; Rangers on small pay and with no recognised official position in the taluk could not obtain assistance from village officers in sending messages to guards, etc; the village officers, being frequently engaged in trade in stolen timber or fuel, threw every possible obstacle in the way of Rangers, who, ignorant and untrained, in charge of areas which even a trained Ranger would find it impossible to thoroughly control, meeting with opposition at every turn and almost sure of punishment for neglect at each of the D. F. O.'s inspections, made hay while they had the chance. The guards' beats extended over as much as 50 square miles of forest, frequently comprising two or three blocks ten miles away from each other; the guards could not protect such large and disjointed areas, and did not try; it was much simpler to go the round of the villages and collect eight annas per plough, one goat per hundred, etc, for not seeing them in the reserves, and these annual payments were so considerable that if dismissal closed a guard's career after two or three years' service, it could be taken smiling, putta lands and growing herds acquired during service more than counterbalancing the loss of prospective pension.

The advent of the trained Dehra Dun man has raised the moral status of the Ranger class, and though there are still black sheep in the flock, and occasionally even a Dehra man turns out badly, the improvement, as compared with past years, is most marked, and is bearing fruit in improved protection and increased revenue. To the credit of Dehra be it said that the training there has changed many a youth from a listless, helpless, indifferent subordinate, to a keen, capable and energetic Ranger, who does his best and does not spare himself in trying to manage an area large enough to keep four men like him fully employed, and in spite of being hampered in his field work by the old class of guard and in his office work by incompetent clerks. Protection of the forest against man and fire is still far, very far, from perfect, and must remain so until each guard has a beat of a size which he can protect and each Ranger has an area so limited that he can make sure that every one of his guards actually does protect his beat.

To arrive at some idea of the establishment required, it is necessary to begin at the smallest unit, the guard's beat. What area can a guard efficiently protect ? This depends on the nature of the forest, the formation of the ground, the facilities for patrolling, the vicinity of villages and the location of the guard's house. It is evident that in a high forest in the plains, opened up by roads and inspection paths, a guard can cover a larger area than in a scrub forest full of thorny growth on a rocky hillside, in which neither roads nor paths have been opened. It is evident also that a guard living in his forest can protect a larger area than one living in a village two miles from the boundary of his forest. Conditions vary so enormously that no hard and fast limit can ever be laid down, but there is no doubt that in the present unopened (by roads, paths, etc ,) condition of the State forests a much larger number of guards is required than will be the case some years hence, when guards have been provided with suitable accommodation *in* the forests, and when export and inspection roads and paths have been driven through the forests in every direction. Another element has also to be taken into consideration, namely, that the population of the country has not yet accepted the fact that the State forests are absolutely the property of the State, and that theft of trees from a State forest is as much an offence as theft of crops from a neighbour's field ; until this is realised, the protective establishment must be exceptionally strong.

In the French forests, with a law-respecting population, with forests thoroughly opened up by roads and paths, with guards' houses in the forests, the average size of a guard's beat is 2½ square miles, and though it may be argued that in the interior of such vast forests as the Nallamalais, which cover 2,000 square miles, such small beats will never be necessary, it must be remembered that, on the other hand, there are numerous small forests of about 1,000 acres in extent, for each of which a guard will be required, and that in many larger blocks, owing to the proximity of villages, beats will have to be below the average in extent. If then in France, with developed forests and law-abiding people, one guard is required for every 2½ square miles of forest, the same average area cannot be deemed excessive in Madras, with undeveloped forests and a law-resisting population (23,749 forest offences were reported during 1901-02).

At this rate 8,000 guards would be required for the whole Presidency.

Next comes the range, the most important unit in the chain of forest control. A Ranger should be able to visit each guard's beat at least once a month; he has also to attend court to prosecute forest cases, to attend to special works in the forests, and to devote a certain time to writing reports and posting returns, etc. Allowing 4½ days for Sundays, 1 day for occasional holidays, 4½ days for office work, 2 days for attending court, 3 days for devoting to special works, a ranger would have 15 days a month for beat inspection, and though in a compact range he might cover two beats in a day, in a range composed of scattered blocks he might find it hard to manage even one beat daily. Fifteen beats would give an average of 24,000 acres or 37½ square miles per Ranger, and 533 Rangers would be required for the Presidency.

Next comes the question of the controlling staff, consisting of Imperial and Provincial officers, who would each have charge of a division, the size of which would depend on the number of ranges a Divisional Officer could control, and whose accounts could conveniently be consolidated in one office. Each range should be visited twice a year at least, some time would have to be spent in headquarters, and some time devoted to special works, such as laying out roads, constructing slides, etc., in the forests. With a centrally situated headquarters, a Divisional Officer might manage 12 ranges, but with ranges scattered over a large extent of country 8 would keep him fully employed. Assuming the average as 10, 53 Divisional Officers would be required, each having 375 square miles of forest under him.

An increase would also be required in the number of Conservators, each of whom should visit each of his divisional charges once a year; nine such charges would fully occupy a Conservator's time, and six Conservators would be required.

A Department of the size sketched above would require a head, and it would be necessary to have an Inspector-General over the Conservators, holding a position similar to that of the present Inspector-General under the Government of India.

The above suggestions may seem as wild and impossible as the calculations of revenue in the former article, but the material to yield that revenue exists or can be called into being by efficient protection, and it is surely worth considering what protection is necessary in order to realise the full value of the State forests and at the same time build up and maintain forests which will be of infinite value in many ways to the country. Naturally the increase in establishment will have to be made gradually, but with a net revenue of Rs. 7,50,000 annually, the time has come when a commencement can be made.

The present establishment costs, in pay alone, and excluding office establishments and temporary establishments charged to works, Rs. 5,48,200, or 22 per cent. of the gross revenue; the establishment of the future as sketched above would cost Rs.16,45,600, or less than 7 per cent. of the estimated revenue; in other words, in order to bring the establishment up to the strength required for the efficient protection and exploitation of the State forests, an increase of Rs. 11,00,000 of establishment is required, which would ultimately result in an increase of Rs 2,15,00,000 of revenue. Is this wild and impossible? Let the Rs 7,50,000 net revenue be devoted for the next seven years, half to increased establishment and half to opening out the forests, protecting them against fire and working them systematically, and then let results speak for themselves.

TSEROPHI.

Fire-protection in the Teak Forests of Lower Burma.

IN the March number of the *Indian Forester* Mr. Gleadow did me the honour of making a few comments on a letter I wrote on this subject.

He assumed that fire-protection is oppressive, and on this account makes use of the strong expression "pernicious" with reference to my letter Our teak forests in Lower Burma were, however, for the most part waste lands and not required by the neighbouring population, but by fire-protecting them the neighbouring population benefits directly by the large sums of money which this work involves.

He blames me for not specifying more precise localities than those mentioned in the heading of my letter; but, writing for fire-protection, somewhat illogically thinks it unnecessary to be bound by any localities at all, and brings forward statistics collected in N. Europe for use in India.

There is a hackneyed platitude to the effect that "the conditions of locality" differ, but that forest principles are the same throughout the world, and therefore it is necessary to avoid the prejudice in favour of fire-protection, which is caused by the act that by keeping fire out of the forests of Europe or India a considerable loss is known to be avoided, and to deal with the question in Burma on its merits, in accordance with sylvicultural principles.

Through the kindness of the former Editor of the *Indian Forester* I was able to obtain a very interesting but entirely inconclusive discussion on this subject.

The passage which struck me most was: "In forestry, in our view, it is the mature opinion of experienced professional men that is of more value than statistics."

I quote this because it shows the foundations on which our scheme of fire-protection is based, namely, on the mere opinions of Forest Officers, and not on statistics or general information collected through experiments conducted by them.

The opinions of Forest Officers, however, are not unanimous in favour of fire-protection, and even if they were, Mr. Glea low's manner of deciding an important question in Forestry appears to me to be opposed to fundamental forest principles.

A scientist is usually very cautious and does not advance theories, or advise others to act on them, merely on the strength of his reputation, but seeks to establish them by proof (usually obtained by a series of experiments).

Similarly in scientific forestry, in those countries where there is a staff of trained men, Forest Officers are invariably cautious, not only on account of their reputations, but also because in carrying out sylvicultural operations a large sum of money is always involved.

Before applying any method or theory to the forest on a large scale great care is taken to eliminate all possible errors of judgment, and numerous experiments are first carried out on a small scale to test the proposed method and to clear up all doubtful points and contingencies which might possibly arise. It is, in short, considered essential that the value of a proposed measure should be *proved* before it is carried out on a large scale. The typical instance usually given of unscientific forestry is that of thinnings in England.

Our colleagues there, who are doubtless also shrewd and able men, are almost unanimous in making thinnings too heavy, and by neglecting to obtain sufficient information, make an error of judgment. In this instance it would be possible to obtain information and ready-made statistics from the very similar localities on the Continent, whereas for fire-protecion in Lower Burma it would be necessary for us to collect information ourselves in the usual manner. Otherwise the parallel is, I think, complete.

Although there are numerous doubtful points in connection with fire-protection on which Forest Officers disagree, yet as far as I can find out, not a single experiment has been carried out nor any effort made to collect accurate and convincing proof, and therefore I maintain that we are similarly incurring the possibility of an error of judgment.

As regards the effect of fire or fire-protection on the soil, it is well known that fire does not cause any loss of inorganic matter, but it has been proved from experiments carried out in Europe that fire, by destroying the soil covering, caused a loss of organic compounds. The question arises, therefore, whether teak suffers by this loss.

There is, I believe, no known instance of the growth of teak having been improved by this loss being averted, but it has been repeatedly noticed that a teak seedling thrives best on a well-burnt patch where this loss is greatest. This seems to show that teak either does not suffer by this loss, or that it can obtain nitrogen and other organic compounds in some other manner.

Moreover, the effects of fire-protection are not the same as the avoidance of the loss caused by fire. For example, the leaves which fall annually do not accumulate and form humus in a fire-protected area, but when not destroyed by fire are eaten by termites.

To compare these two modes of destruction. When destroyed by fire there is no loss of mineral matter, and there is the advantage that an extra quantity of mineral matter is often automatically supplied in places where teak seedlings are likely to spring up, such as in gaps caused by windfall trees, and, on the other hand, the loss of inorganic compounds is only of doubtful importance.

When destroyed by termites the leaves are gradually digested and pass through the bodies of several termites and the residue is probably deposited near the nest or used in its construction. It is possible, I think, that the earthlike material of which their mounds are composed is really the unrecognisable remains of digested leaves, as also the cellulose matter found in the interior.

It seems to me therefore probable that the loss of organic compounds and of that due to the nonformation of humus is the same in both cases, but that the loss of mineral matter is greater in the latter case, owing to its being deposited in isolated spots instead of being returned evenly to the soil.

As regards the effect of fire-protection on insect life, it has been clearly shown in the columns of the *Indian Forester* that there is doubt on this subject. It was pointed out that it is essential that we should first know the full life-history of the principal insects which damage teak. We shall then know in which stage of their metamorphosis they pass through the fire season and what effect the fires have on them. This desirable position of affairs has not yet been reached, and it was pointed out that even the life-history of *Hyblæa puera*, which is doing increasing damage, is not yet fully known.

The extent of the damage done by fire is a question on which there is considerable difference of opinion.

There is a general belief that fire is responsible for a great number of our hollow trees It is held that when a teak seedling is burnt back by fire, the seeds of decay are admitted into the roots. The base of the taproot becomes swollen, and from it coppice shoots are sent out until one is sufficiently strong to resist fire.

It is laid down that trees grown from coppice tend to become hollow for obvious and intelligible reasons, which do not apply in this case, as the taproot is discarded at an early date in favour of laterally branching roots, and with it the few germs of decay disappear.

Old age, suppression, etc., appear to me to sufficiently account for the hollow trees we find, and I entirely fail to understand how the burning back of a teak seedling can possibly cause hollowness.

As regards general damage, the greatest is found in localities which are not typical of teak forests, such as on steep hillsides, where not only is the growth poor owing to the shallowness of the soil, but also leaves falling downhill collect against the trees, and being annually burnt over, cause large wounds on the upper side of the trees. In typical forests teak is always found associated with a dense growth of bamboos. These bamboos keep down the undergrowth of grasses, etc, so that there is little inflammable matter except the annual fall of leaves, and the fire is therefore very slight.

It is quite a common occurrence to find stumps of teak trees which have been cut a long time ago, and although decaying, still practically untouched by fire.

It is not unusual to find statistical information of the power of teak to resist fire, in the shape of badly girdled trees bearing hammer marks some 20 years previous, and proving that a tree of which the vitality is nearly extinguished can resist fire for a long period, and the logical conclusion is that even a moderately healthy tree can offer a greater resistance. Attention is often drawn to the fact that one or more inverted V-shaped patches are often found at the base of many teak trees where the bark and sapwood have been burnt. In a seedling the sap is drawn up equally round the stem, but in a mature tree the sap is drawn up from laterally branching roots and then distributed. The presumption is, therefore, that there are inverted V-shaped patches at the base of each tree between the points at which the roots meet the stem where very little sap flows, and the bark and sapwood being practically dead, are specially susceptible to fire, but if burnt the growth of the tree is not affected, and in fact is only so when the sapwood and bark are so burnt that the upward passage of the sap from the roots is interrupted and the root rendered useless.

In the case of these inverted V-shaped wounds the marketable value of the timber is in the majority of cases unaffected, only the sapwood and bark being destroyed and not the heartwood, which apparently possesses some matter which renders it more incombustible than the heartwood of other species of tree.

There are great differences of opinion between experienced Forest Officers, but as far as I am aware no attempt to obtain accurate information has been made. Not even the simple precaution has been taken of keeping a number of trees on a few typical areas under observation, and noticing the extent to which they suffer from fire, or whether slight wounds develop into large ones or gradually heal up. It is, however, probable that the damage is considerably over-estimated as it is so striking.

Similarly, during the war in South Africa, I remember a war correspondent remarking that there was a tendency to over-estimate the loss caused by fighting, and that had it not been for the carefully prepared returns, very inaccurate impressions would have been received of the comparative loss due to the fighting on the one hand and of disease on the other.

I have never seen or heard the expression "loss caused by fire-protection," but there can be, I think, little doubt that loss is caused, and that it is usually under-estimated, as it is not of a kind which strikes the eye. When Forest Officers undergo training they are familiarized with artificial forests, and there is, therefore, a natural tendency to forget that in Burma, with its innumerable species, its quick growth, and abundant rainfall, the struggle for existence is very keen. As Darwin says: "Nothing is easier than to admit in words the truth of the universal struggle for life, or more difficult, at least I have found it so, than constantly to bear this conclusion in mind."

Teak is invariably admitted to resist fire better than most other species, and I will further quote the same author as, in his *Origin of Species*, he shows how damage occurs "Each species, even where it most abounds, is constantly suffering enormous destruction at some period of its life, from enemies or from competitors for the same place and food; and if these enemies or competitors be in the least degree favoured by any slight change, they will increase in numbers; and as each area is already fully stocked with inhabitants, the *other species must decrease.*" The matter is theoretically quite clear: if by fire most species suffer more than teak, the converse holds good that by fire-protection they will gain more than teak and will oust it, and in practice the truth of this is admitted by the majority of Forest Officers when they state that in fire-protected areas natural regeneration of teak suffers.

I noticed a good illustration of the effect of fire-protection in S. Tharrawaddy.

Teak is often found associated with Kyathaung (*B. polymorpha*) and a little Tinwa (*Cephalostachyum pergracile*), but in the fire-protected parts a dense undergrowth of Tinwa seedlings has sprung up, so dense as to kill or prevent the appearance of teak seedlings, even when the additional help has been given of opening up the canopy by improvement fellings. In the areas not protected teak seedlings are numerous.

The amount of seed of Tinwa is the same in both cases, but in the latter case much of it is burnt by fire, and the seedlings which do appear are constantly burnt back, and where the shade is moderately dense and the vigour weakened thereby, the seedlings are often killed outright.

Teak does not bear a great quantity of seed, and the seed is not fitted with any contrivances to be widely distributed, and therefore it competes at a disadvantage with more favoured species, except that the seed and the tree throughout their lives are admirably adapted to withstand fire, and, therefore, by fire-protection we are taking away the principal means by which teak scores over its rivals.

It is well known that dahs and axes cannot make headway against the luxuriant vegetation of a typical dense teak and bamboo forest, except at a cost which is prohibitive on a large scale, and even if fire caused some damage to teak it has counterbalancing advantages, in that it destroys much useless seeds and plants and overmature trees, and is in reality comparable to an improvement felling. Its usefulness in this manner can be readily realised by sowing teak seed in protected and unprotected areas in every place where it is thought a teak seedling would have a chance of springing up.

The fact that by not spending vast sums of money on fire-protection we should enable more seedlings to spring up is of vital importance, in consideration of the fact that the outturn of the future depends on the natural regeneration of the present.

One of the first effects of fire-protection is that the shade is increased owing to the survival of useless species and their increased germination. This shade is not increased immediately, and when first an area is protected teak enjoys the advantages of both fire and fire-protection.

It is generally agreed that in unprotected areas about ten years elapse before a teak seedling establishes itself against fire, but that when established, the growth is not further affected by fire. On the other hand, teak is well known to be very sensitive to shade, as witness the difference in growth between one grown under shade and one grown in a plantation, and therefore fire-protection, by increasing the shade, causes considerable loss of increment, and it is not improbable that many seedlings are eventually killed.

An examination of the stump of nearly every teak tree shows that at some time or another the tree has been badly suppressed and within an ace of being killed by shade.

Is it not probable, therefore, that fire-protection, by increasing the shade, would in many cases have been the last straw, or that the loss which will ensue by successfully protecting our forests for a long period of time will be considerably greater than that caused by fire?

It has been acknowledged in previous Forest Administration Reports that natural regeneration of teak suffers under fire-protection, and it has been suggested that this state of affairs should be remedied.

It was suggested that after periods of fire-protection reserves should be from time to time burnt over, and at the same time that natural regeneration of teak should be further stimulated by improvement fellings, etc.

It may, however, I think, be urged that if during the period of fire-protection teak benefits, other species will benefit to a still greater extent, and, in spite of an occasional fire, will still continue to oust the teak.

The light manner in which fire-protection has been taken up and the little attention given to a study of its effects is due, I believe, to the very general belief that a protected area can be at any moment restored to its former conditions by ceasing to protect. This belief, however, does not appear to me to be well founded.

Unlike Europe, where it is abnormal for a fire to occur in a forest, in Burma the forests have been burnt over from time immemorial. As fire affects some species more than others, it is obvious that it must have been an important factor in determining the proportion of the different species one with another, and therefore fire-protection upsets the normal balance.

There are doubtless many species whose numbers are kept down by fire, which spring up in great abundance when fire is excluded, in course of time establish themselves against fire, and are unaffected when it ceases temporarily to be excluded. Thus in the example of the effects of fire-protection I gave previously, dense masses of bamboo seedlings have sprung up during a period of fire-protection, and these now are of sufficient size in many cases to resist fire, and many localities have in this manner become almost unproductive of teak.

There are many localities equally suited to evergreen or teak forest. There has lately been some correspondence in the columns of the *Indian Forester* on the subject of encroachments of evergreen forests, and this Sir D Brandis attributes to the fact that an area must have escaped fire for a year or two. Consequently I think there is reason to expect that under fire-protection encroachments will become numerous and areas rendered unproductive of teak.

I maintain therefore that it cannot be taken for granted that after disturbing the normal balance by fire-protection, the former productiveness of an area as regards teak can be restored by readmitting fire.

There is a further consideration, that even at present fire-protection absorbs the greater part of the working season, and as every teak forest in Burma is to be protected during the next five years, the work will be nearly doubled. We do next to nothing to stimulate natural regeneration of teak now; is it likely that fire-protection in the future will leave us any time to administer its antidote?

Our object in a teak forest is to increase the revenue from teak, and fire-protection must be considered merely as a means to this end.

To increase the revenue it is necessary to increase the quantity of teak.

Fire cannot be said to prevent teak from becoming more numerous, and I have in fact endeavoured to show the contrary; but the competition with other species does. One teak tree alone would suffice in a very short time to stock the whole of Burma were it not for this competition, and therefore the most natural way to increase the future revenue would be to devote our energies towards lessening this struggle for existence instead of at present increasing it. I am inclined to the opinion that the damage done by fire is only, in the majority of cases, secondary, and that it is only when the vigour of a teak tree is affected by causes, such as old age, creepers, suppression, etc., that fire causes serious damage.

If this is the case, the damage can be reduced to a minimum by preventing the *primary* cause of damage. In the future we shall extract trees at maturity, and already we cut creepers, but as far as I am aware no attempt has been made to free trees from suppression. Teak trees are seldom so close that a neighbouring tree cannot be felled without damaging them, or if so close a dense unreserved tree would probably do more damage by remaining than in being felled. When felled it is only the small branches which burn strongly, the larger branches and bole merely smouldering away and causing no damage. There would be also the further advantage that in falling these trees would form gaps, and being burnt, would form suitable germinating beds for teak seedlings. In this and other ways, without incurring the evil effects of fire-protection, the damage from fire would be reduced to a minimum, and we could devote our energies and our money to lessening the struggle for existence and to increase the proportion of teak by direct means.

We all love our teak trees, and are distressed when we see an occasional one blackened by fire, but forestry is not a subject in which sentiment can be indulged.

A large amount of intelligence is not required to suggest fire-protection as a means to prevent the damage from fire, but in forestry it is customary to find out definitely what benefit will be gained and what will be the effect of any proposed measure, and whether the expense is justified.

Some Forest Officers, I understand, who have been sufficiently fortunate in convincing themselves concerning the value of fire-protection, take up a pharisaical attitude about this question, and when any doubt is expressed talk about heresy. I maintain however that since its commencement there always has been doubt, and that, on the principle that forestry is not a suitable subject for speculation, it is unorthodox to carry it out on such a large scale. Instead of attempting to stifle doubt, it would, I think, be preferable to prepare to meet it with reliable and carefully collected information.

At present Forest Officers differ in opinion very considerably.

Our motto is merely to "hope for better things;" but no harm would, I think, be done by definitely ascertaining that we actually are improving our forests by the vast sums of money we spend on fire-protection.

H. C. WALKER.

Charles Broilliard.

BY J. W. O.

MOST of our readers will have noted with regret the recent retirement of M. Charles Broilliard from the editorship of the *Revue des Eaux et Forêts.* The following are some extracts from an account of his work in the Forest Department of France, by F. Fankhauser, which appeared in the April number of the *Schweizerische Zeitschrift für Forstwesen.*

Charles Broilliard was born on the 4th July 1831 at Morey, a small town in Haute-Saône. The cliffs behind Broilliard's home command an uninterrupted view over the borderland between hill and plain, from the domes of the Vosges to the snowclad peaks of the Swiss Alps, and it may well be that the peculiar charm of this richly wooded country early awakened Broilliard's love of nature, and influenced in great measure his choice of the forest service as a profession.

Broilliard entered the Forest School at Nancy in the year 1851. After completion of the school course and the subsequent year of practical work he began his forest career in the summer of 1854 at Briancon in charge of a highland forest division extending ever 23,000 hectares. His 2½ years' tenure of this post was spent in making himself thoroughly familiar with the management of the larch and Scotch pine forests of the higher Alps; at the end of 1856 he was transferred to the Upper Doubs Valley, the region of the spruce and silver fir, for the study of which he had ample opportunity during the next 2 years. From 1859 to 1862 we find him engaged on the management of the oak and beech forests in the Vosges at the source of the Saône. In all these forests he originated working-plans of considerable importance, and thereby acquired the fullest knowledge of the requirements of the different species.

It was in the last named division that the skill of the practical young forest officer first came to the notice of Parade, the then Director of the French Forest School, who transferred him to Nancy, where he was appointed lecturer on forest working-plans, holding at the same time charge of the Forêt de Haye.

At Nancy Broilliard laboured fully 18 years. Notwithstanding the exacting duties of the professorship, he managed to find time to solve numerous special problems connected with forest management and to make himself acquainted with all the more important forests of France.

In 1881 he relinquished the Chair of Forest Working-Plans and was appointed conservator, first at Macon, and three years later at Dijon, which latter post he held until his retirement in 1891. During these 10 years he was enabled to put his theories into practice and also carried out most of his studies of the forests of foreign countries. From 1892 onwards his whole time was given up to the *Revue des Eaux et Forêts*.

Such briefly has been the life of Broilliard, but the work accomplished by his versatile genius cannot be described in so few words. His writings and teaching have established his reputation as one of the most distinguished masters of forest science, and he has long been the recognized head of the French School. Brilliant as he is as a theorist he proved himself no less efficient in outdoor work, and his pre-eminent qualifications marked him out for a ruling position. Broilliard unites rare talent with extraordinary knowledge. His thoroughly scientific education, constantly kept up to date by an attentive study of new forest literature, was supplemented by the great accumulation of knowledge he had acquired as a close observer of nature, by travel and by long experience as a practical worker. Few persons have been gifted with Broilliard's faculty of at once grasping the true facts and conditions and of forming a correct judgment in regard to them. With all his learning he was however by no means a mere theorist. His theories were formed not in the study but in the forest, and for this reason his teaching has always been welcomed by the practical worker, and his clear and terse writings, remarkable not the less for the elegance of his language, bear the unmistakable stamp of originality and freshness.

His first work, and one which marked a distinct epoch in forest science, was the *Cours d'aménagement*, a summary of his lectures on working-plans, which appeared in 1878. This was shortly followed by *Le traitement des bois en France*, an important work written with special regard to the needs of the owners of private forests. Broilliard is further the author of the numerous articles in various forest periodicals, especially in the *Revue des Eaux et Forêts*, dealing with all the forest questions of the day, which have exercised a great and beneficial influence on the development of Forestry in France. To Broilliard belongs the credit of having been the first in France to recognize the necessity of treating and utilizing forests in accordance with the requirements of each separate standard and of subordinating to this all considerations in regard to continuity of yield and regularity of age classes. His writings in regard to the selection-and-coppice standard systems are among the most important published on these subjects. No one has advocated more strenuously and with greater success the raising of the felling rotation of coppice woods and the provision of an increased proportion of valuable oak timber as standards. But above all we have to thank him for the development of the French doctrine of regarding thinnings in the light of a gradual freeing the crowns of the principal individuals combined with the maintenance of an undergrowth for the purpose of protecting the soil. Few however have understood so fully as Broilliard the actual life of the forest, the claims of each individual species in it, and the high importance of even the least of these as a part of the whole.

Much more could be written in praise of Broilliard's work and yet leave much untold. May he in the evening of his life enjoy many happy days of well earned repose.

Chir (Pinus longifolia) "Twig-borer."

BY B. O. COVENTRY, F.C.H.

DURING the hill tour with the Forest School students in Jaunsar, April 1901, Mr. F. Gleadow drew my attention to a malformity of the newly-formed shoots of the young chir pines in a forest between Khatian and Thadiar. The malformed shoots (usually leading shoots) were bent down, brown and dry, with a "fox-brush" like appearance. On examining them they were found to be hollow and full of dry resin and brown excreta of a lepidopterous larva; but no insect could be discovered In 1902 the same conditions were observed, but again no insect could be found, and it was presumed that the season was evidently too late to catch the culprit at work.

This year, May 1903, whilst aligning a road, with the junior class students, at Koti Kanasar, our work took us down into the chir pine zone, and here again the same malformity of the new shoots on the young chir pines was observed. On this occasion however I was successful in finding the culprit, namely, a lepidopterous larva, as was at first suspected. The first larva was discovered underneath the bark of the stem of the previous year's growth and not in the current year's shoot. It appears that the larva, after having tunnelled down the current year's shoot, which gradually dries and bends over as the damage extends, comes outside and tunnels into an older stem, in which it tunnels up and down irregularly underneath the thin bark, feeding on the soft tissues between the bark and the hard central core of wood. In this latter position the larva is difficult to detect, as the stem is covered with long green needles, and shows no apparent signs of being attacked; but a closer observation will show that there are small openings on the surface of the bark from which resin and excreta have exuded The larvæ however were not easy to find, for although I carefully searched a fairly large number of attacked plants, I only succeeded in finding half a dozen larvæ, three of which were in current year's shoots, which had only been partly destroyed, as in the case illustrated in the accompanying photograph,* the other three being in the older portion of the stem under the bark. The probabilities therefore are that the larvæ, when mature, leave the plant and pupate in the ground.

It appears probable that the eggs are laid on the terminal buds or young shoots, that the young larvæ live in the current year's shoots, first of all in those which are very young, then attacking those which are more advanced, and finally attacking the older stem; eventually, when mature, leaving the plant and pupating in the ground: a larva found on 14th May pupated on the 28th May and the moth emerged on the 22nd June.

The larva is, when full grown, about 1 inch long, bright pink in colour, with a brown head, smooth and shining, but becomes a dirty greenish colour just before pupating It is thicker at the centre of the body, tapering to both extremities, and is furnished with a few short stiff hairs.

It is very sensitive when touched, wriggling away with great activity. The pupa is red-brown in colour, being paler on the ventral surface and with a dark line down the dorsal surface, the last segment being dark with a few bristle-like hairs. It is slightly over ½ inch in length.

The moth measures 1⅛ inch across the expanded wings. The fore wings are of a purple-grey colour with brown markings. The hind wings are hyaline with a brown tinge. Both fore and hind wings have a fringe of ciliæ.

---

[*] We regret to say that it has been found impossible to satisfactorily reproduce this photograph.

The moth appears to resemble, as far as I can judge, the description of *Phycita abietella* given on page 108 of Stebbing's No. 1 "Departmental Notes on Insects which affect Forestry." If it should turn out to be the same insect, the above will be an interesting addition to its life-history. The insect is being sent to Mr. Stebbing for identification.*

The accompanying photographs show a malformed shoot; which is partially destroyed. The upper portion marked *a* has been tunnelled down and has bent over and become dry and brown, the needles being malformed. The larva has tunnelled as far as the dotted line and is working downwards. After reaching the base *d* of the terminal shoot *a* it will probably come outside and tunnel into the previous year's shoot *e*.

I have not yet had sufficient opportunity of ascertaining the extent of the damage caused by this insect. The destruction of the leading shoot does not, as far as I have at present seen, lead to any permanent injury by causing the tree to fork, as is the case with the "Tun twig-borer". The destroyed leader becomes replaced by one of the shoots which would ordinarily have been a side branch. The destruction of the cambium and sapwood, in the older portion of the stem lower down, appears likely to result in serious damage by causing the whole of the plant above to die, but I have not yet been able to determine if this takes place or not, and it is to be hoped that those who have chir forests close at hand will try and obtain further information.

II.—CORRESPONDENCE.

On certain Important Forest Questions.

ANYTHING from the pen of Mr. Gamble always commands attention, but it is with somewhat mixed feelings that I have perused his article in your November's issue, nor am I able to agree with some of his remarks on what he aptly terms the dangerous policy of making the collection of a large surplus revenue the chief aim of the Forest Department. There is little doubt that this has at times been the aim of some Conservators in the past, but I am glad to think that everything now points to the existence of a more enlightened policy, and that a judicious expenditure of money on forest improvement is now recognized as one of the essentials of sound administration. Mr. Gamble appears to be under the impression that in those provinces where forest matters are more directly governed by the advice of the Inspector-General, the consolidation and improvement of the forest estate are not showing the progress visible elsewhere. This, to my mind, while casting an unmerited censure on the policy of the Government of India in so far as it may be based on the advice of the Inspector-General, is written under mistake of fact. It must be borne in mind that the administration of any particular province is not in the hands of the Inspector-General, that he has nothing to do with the preparation of the budgets and is in no way responsible for the surplus obtained on the working of the year. Where, however, the Inspector-General is permitted a voice in the proposed expenditure on improvements is in the recommendations he may forward to local administrations regarding working-plan prescriptions and suggestions. Now, sir, I have a fairly intimate acquaintance with several score of working-plans, and I may say that in no single instance, as far as my memory serves me, has the Inspector-General ever suggested the policy of increasing the surplus at the expense of useful improvements. On the other hand, I have more than once come across a remark to the effect that considerations of sylviculture and improvement have been subordinated to financial results. When surpluses have been obtained at the expense of improvements, this is in no way due to the advice of the Inspector-General, but rather to a misconception on the part of local administrations and their forest agents as to the true meaning of the term "Commercial Department" and still more to administration officers not utilizing the funds allotted to them, and allowing such monies to lapse, sometimes with the object of saving a larger surplus, more often because they have not the time to superintend improvements with which they are in full sympathy, but the execution of which they are not prepared to entrust to their subordinates. There is little doubt that in earlier days it was often held advisable to show as large a surplus as possible in order to justify the existence and extension of the Department, just as a commercial company in its infancy is often inclined to show as large a profit as possible in order to establish its position and raise its credit. This was the first stage. We have now reached the second, where the company, with position firmly established and credit assured, is powerful enough and is prepared to sink money in improvements with a view to its future welfare, but is forced to restrict expenditure with this object within such limits as can be efficiently controlled. I know as a fact that the late Mr. Hill considered that insufficient money was being laid out on permanent improvements, and used to say that the percentage of net to gross revenue had no business to be higher in India than on the continent of Europe, where settlement, demarcation, communications, etc., are more or less completed. This view, I am in a position to say, is also held by his successors and by the senior officers of the Department. Where then Mr. Gamble implies that the advice given by the Inspector-General is in some measure responsible for unduly large surpluses obtained at the expense of improvement, I consider that he goes too far and that facts will not bear him out.

---

* The insect arrived in a damaged condition. It is larger than *P. abietella* and belongs to a different genus. It proves to be new to the Indian Museum collections.—HON. ED.

Where there has been restricted progress in consolidation and improvement, it would be nearer the mark to say that this has been rather due to the large areas that individual officers have to administer, rendering it impossible for them to find time to devote to improvements that under more favourable conditions they would be only too willing to initiate and carry out. It is difficult to realize that the tracts under the control of the Forest Department aggregate one-fifth of British India, and that the Imperial Forest Service, which is chiefly responsible for the management of this vast area, consists of a small band of less than 200 officers, who have to endeavour to supervise everything in person as they are loth to rely upon their subordinates, who are not infrequently deficient both in quantity and quality. When once this has been realized, what to me is astonishing is the progress that has been made in extension and improvements during late years. It may safely be said that were it possible to limit the size of separate forest charges to what could be efficiently controlled by Imperial officers, not only would expenditure on well considered improvement increase by leaps and bounds, but that no one would welcome such progress more than the senior officers of the Department from the Inspector-General downwards.

Cordite Rifles in Indian Forests.

IN answer to "BIG GAME'S" letter in your number for October, the following *pros* and *cons*, based on practical experience, will probably assist "BIG GAME" in coming to a conclusion on the questions he raises.

As "BIG GAME" mentions bison particularly and does not mention any other sort of game, I have confined my remarks to this particular species of heavy game.

Before proceeding to deal with the question of powders, bullets and rifles it is necessary to discuss briefly a few of the habits of the bison in order to determine what is required of a bullet in order to deal with a charging bison.

The cases on record in which an unwounded bison has charged are exceedingly rare; so much so, in fact, that the probabilities of a charge need not be taken into account. On the chance therefore of receiving a charge there is no necessity to continuously carry a heavy rifle during a stalk, and as will be afterwards shown, this is also unnecessary in order to bring the stalk to a successful finish. Turning now to wounded bison. A wounded bison will usually try to escape, but he will sometimes round and charge, and the possibilities of his doing so must be taken into account.

In the cases which have been recorded of a bison charging mention has seldom been made as to his mode of attack, and whether he came on with his head up or down. In the single instance in which I have been charged by a bison, the bison held his head up until within a few feet of me; he then lowered it to strike, but as this is the only instance in which I have seen a bison charge, I cannot say whether this is their invariable mode of attack or not. However, it does not matter very materially whether they do or not. There is no exception to the rule however that a charging bison must be coming head on and either uphill, on level ground or downhill, and almost invariably from a short distance.

The shot at a charging bison is therefore a hurried one, and the only shots that will kill him outright are—

(1) a shot in the brain;

(2) a shot in the neck or back from above, so as to break his neck or back;

(3) A shot in the neck so as to break it from below. (A heart or chest shot will seldom stop a charging beast).

These are the shots that will kill him. Now any rifle that the sportsman is carrying after bison with a hard bullet will reach these spots, from a Mannlicher up to a ·577. The matter in the first instance is therefore chiefly a matter of aim, but other considerations must be taken into account.

Firstly, a smokeless powder in one barrel at least will leave the sportsman free to put in a second shot, whereas black powder will leave the sportsman in darkness for a few seconds, and I do not hold with the theory that the bang and smoke of black powder will turn an animal.

Now as regards the bullet; it is essential that the bullet must be of a penetrating nature, and this of course can be sufficiently well obtained in small and big rifles, but the chances of a big bullet touching one of the vital spots is greater, and even the mere fact of it passing close to the vital spot will suffice in some cases; whereas with a small bullet this is seldom the case. So much for the deadly shots at a charging bison. Of other shots which will save the sportsman there are two.

Firstly, a shot breaking the foreleg will bring the bison over, or at any rate so disable him that an active man who keeps his head can easily escape. Here again, however, the arguments given above as regards powder and bullets hold good.

Secondly, there is a shot which misses a deadly spot but gets him either in the chest, shoulder, neck or face, and a shot fired at a charging bison is as likely to hit one of these places as it is to break his neck, back or reach his brain. What I mean to say is, that it is very likely the deadly spot will be missed.

Now in this case again smokeless powder is preferable to black for the reasons already shown. But, on the other hand, a heavy bullet is absolutely essential, as the sportsman must either floor or turn the bison from sheer shock.

There are two ways of producing this shock. Either by a fairly large bullet, such as a ·450 driven at great velocity by a nitro powder, or a heavier bullet driven at a less velocity by black powder or a nitro powder; Sir Sam Baker states a bullet from the "Baby" catching an animal fairly never failed to stop it. The "Baby" was a 4 bore, and, speaking from memory, I think it weighed 22 lbs. and carried 16 drams of powder.

But since Sir Sam Baker's day rifles and powders have been greatly altered, so that high velocity without a blinding smoke can be obtained, and thus making the use of a second barrel possible.

Moreover, it is not every man who could shoot with the "Baby," and for these reasons a modern big game rifle has two barrels, neither of which can carry so heavy a ball as the single barrelled rifles of past generations. Now of modern rifles there are three sorts in use which will do the required work, namely, the 8-bore, the ·577 and cordite ·450 express, but the former, namely, the 8-bore, only shoots black powder, which has its drawbacks as already shown, and as in fact the 8-bore is no improvement on the old type of black powder rifles, it need not be taken into account. Personally, if I was charged by a bison I would prefer to have the "Baby" in my hands than a double 8-bore.

The question really resolves itself into the ·577 or ·450 cordite express—which?

The consideration of smoke does not apply, as the ·577 can be used with a smokeless powder, which gives as high a velocity as that obtained from black powder. The question is therefore narrowed to whether a ·450 bullet, driven 2,200 feet a second, or a ·577, driven at 1,600 feet a second, is best. This matter is one over which sportsmen differ greatly, and is one on which a verdict has still to be obtained. Probably there is not much to choose between the two, but as already shown above, there is a certain advantage in the heavier bullet, and as the penetration of the ·577 has proved itself sufficient, I consider the excessive penetration of the ·450 unnecessary. An illustration of how the energy produced by a bullet driven at a great velocity can be wasted is the following. Imagine a smaller bullet driven at 2,400 feet a second and a heavier bullet driven at 1,600 feet a second, and the weights of the two bullets so arranged that the striking energy is equal in both. Now imagine each bullet hitting a charging bison and catching him say in the shoulder. The smaller bullet would pass on through the shoulder and into the body, and thus, as the striking energy of the bullet is distributed over the course it takes, some of the energy only is expended in the shoulder.

Now the larger bullet would penetrate and remain in the shoulder, thus expending all its energy in the one limb. It will be seen therefore that the striking force of the heavier bullet is more concentrated than that of the smaller, and this, in my opinion, is one of the reasons why the shock produced by the heavier bullet is the greater.

Personal experience has led me to prefer the heavier bullet to the smaller, even at the cost of a certain amount of velocity.

To recapitulate briefly the above remarks therefore: firstly, "BIG GAME" in following up wounded bison would do well to carry a rifle loaded with smokeless powder in at least one barrel.

Secondly, the rifle should be the heaviest "BIG GAME" can manipulate, by which I mean that the powder charge must give sufficient peneration, and after that the heavier the bullet the better.

I have now dealt fully with the question of wounded and charging bison, and I propose to conclude by adding a few remarks on rifles to use on unwounded bison, as in this case circumstances are altered, and the remarks which hold good for charging bison do not apply to unwounded bison. To begin with, in tracking up bison, although better, it is not necessary to continually carry a rifle in one's hand, as the bison can usually be heard before being seen, or at any rate unmistakable signs on the track show that the quarry is at hand. Rather therefore than tire oneself out, and this is likely to happen, as tracking bison is hard work, it is preferable to have the rifle carried and only take it on approaching. Now one of the points about a shot at bison is that it is nearly always a close shot. Many are shot under 50 yards and hardly any over 100; exceedingly accurate shooting is therefore possible.

Now the vital spots are the brain, neck, back; the neck and the back of course must be broken; then the heart and both lungs. It is necessary to wound both lungs; an animal will go a long way with one lung hit, whereas if both are penerated he will choke almost at once. To these I add the forelegs, as if a bison's foreleg be broken above the knee he will certainly be bagged; the shot however is not one that commends itself.

Now firing at any of these spots, except the brain and leg, the spots are more or less concealed, and in all instances, except the lungs the mark is a fairly small one. Accurate shooting is therefore necessary. It is of course an axiom in shooting, although one that is often forgotten, that the larger the game the more accurate the shooting must be in order to bag and not merely wound.

Personally, if I wish to make an accurate shot I prefer a small bore rifle, the Mauser for preference, and with this weapon at 50 yards I can make tolerably certain of hitting a 4-inch bull, whereas with a ·577 I am more likely to miss it than not. Of course there may be many men who have attained extreme accuracy with heavy rifles, but certainly the majority of men will shoot infinitely better with a small bore rifle. For the first shot under the following circumstances therefore I would advise "Big Game" to use the rifle which has sufficient penetration and with which he can make the most accurate shooting; if a large bore rifle of course so much the better.

The conditions in which this rifle is to be used are those which conduce to an accurate shot. These conditions are:—

1. The sportsman must be steady, by which I mean he must not be blown or excited.

2. The vital spot must clearly be seen.

(I take for granted the sportsman knows how to reach the vital spots.)

3. The bison must be standing quite still.

Under these circumstances a tolerable shot who does not get excited—but this frequently happens—will be almost certain of hitting a vital spot, and whether it is hit with a Mauser or a ·577 makes no difference. I should recommend him to fire either just at the base of the neck or for both lungs if this is possible.

Whenever the above conditions are not found, namely, if the sportsman is blown or is excited, or the bison is moving and it is impossible to be certain of hitting a vital spot, then accuracy and the small bore rifle must give place to the heavy rifle producing shock. In fact we return to the conditions already described under a charging bison, in which there is a probability of the vital spot being missed and the same arguments which applied in that case apply in this, and therefore the same rifle is recommended in this case as was recommended to meet a charging bison.

The above remarks are based on experience with bison in the Central Provinces only, to which part of India only they are meant to apply; in the main they probably hold good however for other parts as well.

Solid Lead.

Ripening of Cones of Pinus Longifolia.

I.

I have read Mr. Birbal's letter several times but cannot understand exactly what he means. Apparently his meaning is (though I may be mistaken) that in the spring the young cones appear at the extremity of last year's shoot, and that the new shoot then grows out from below the young cones.

This seems to be a curious method of growth, and is quite different from what occurs here, which is as follows: Last year's shoot terminates in a bud. In March or April this bud expands and develops into a shoot, which bears at or near its extremity the young cones. When the shoot has expanded to its full length, it is found to be terminated by a bud, round which the young cones are situated. (The male cones are situated on and around the lower portion of the year's shoot and drop off soon after they have shed their pollen. (Male and female cones do not of course occur on the same shoot.)

Mr. Birbal does not attempt to prove his statement that 'the cones only take 12—15 months to ripen. If this is the case how does he explain the fact that in spring cones of three different years are found on the trees? (I exclude the cones which have already shed their seed.) These cones are as follows: (1) the young cones at the extremity of the shoot; (2) the half ripe cones at the base of the current year's shoot. These are still green and soft except the tips of the scales, which are brown and woody. (3) the large ripe cones at the base of last year's shoot. At this time of year (September) only two kinds of unripe cones are found on the trees, *viz.*, *(a)* this year's cones at the ends of the shoots and surrounding the terminal buds. These are now brown externally, but are green within. Next spring when they enlarge they will have the appearance of (2) above. (*b*) The cones at the base of the current year's shoot. These have nearly reached their full size, but are still green except the tips of the scales They have become fairly hard. I have sent to the Forest School a branch which bears cones (*a*) and (*b*). All the Rangers in this district and some zamindars whom I have questioned state that the cones require two years to ripen.

Sirdar Bishen Singh, Extra-Assistant Conservator of Forests, has also proved the fact experimentally by attaching a piece of wire to the young cones.

Consequently there seems no doubt about the matter so far as the Punjab is concerned. It may be the case that at Dehra Dun the cones ripen in 12—15 months but it appears hardly likely.

E. B. COVENTRY,
Deputy Conservator of Forests.

II.

I see a letter in the last *Forester* from Birbal, Curator, with some queries about chil seed and its ripening. I enclose a copy of a table sent to me by yourself in 1886 showing the results of my observations made in that year, or rather printed in that year, for I began to make notes a year or so previous. I am quite sure of my facts, at any rate for the Chamba Valley.

J. C. MCDONELL.

TABLE SHOWING PERIODS OF RIPENING SEEDS OF CONIFERS IN THE HIMALAYAS.

Species.	First appearance of male flower.	First appearance of cone.	Pollen shower.	Cone scales closing.	Ripening of seed.	Time between first appearance of cone and falling of seed.	Remarks.
Cedrus Deodara, Deodar.	26th June	16th August	1st October	24th October	1st October	14 months	Male flower and young cone never found on the same tree. Cones erect. Empty cones non-persistent. Scales fall off separately when seed is ripe.
Abies Smithiana, Toe, Rai (Spruce)	15th April	20th April	4th May	14th May	November	7 months.	Empty cones persistent. Cone pendulous and falls complete, scales not detached.
Abies Webbiana, Rai, Morinda (Silver Fir).	15th April	20th April	4th May	14th May	November	7 months.	Cones erect and break to pieces when seed is ripe.
Pinus excelsa, Kail (Blue Pine).	16th April	26th April	3rd May	5th June	November	19 months.	The same tree may have (1) male flower, (2) young cone, (3) ripening cone, (4) empty cones persistent. Cone erect when young, pendulous when mature, and falls complete; scales not detached.
Pinus longifolia, Chil (Chir).	15th Feb.	25th Feb.	1st March	15th March	1st July	29 months.	Young cones not only found on same tree as male flower but even on same leaf-bud or stem. One tree may have 4 years' cones on it at one and the same time and also the male flower. Cones pendulous. Empty cones long persistent Scales not detached when falling. The dates vary with elevation. The above are for the higher elevations.

6th May 1886.

J. C. McD.

Jaunsar Working Plan.

As an old Jaunsari I have read with great interest Mr. Clutterbuck's working-plan for the Jaunsar Division, United Provinces. May it have every success and may the old division flourish and improve under its provisions.

There is one point in the plan which I should like to see more fully discussed. Para 122, on which the possibility is based, says: There are no data as to the percentage of trees which pass from one class to another. The following are estimated figures, but care has been taken to keep them low so as not to vitiate the result:—

95 per cent class I survive for 40 years.
80 per cent. class II become I.
75 per cent. class III become II.
60 per cent. class IV become III.
33⅓ per cent. class V become IV.

Taking these as given, the following are calculated from them:—

60 per cent. class III become I.
36 per cent. class IV „ I.
12 per cent. class V „ I.
45 per cent. class IV become II.
20 per cent. class V become III.
15 per cent. class V „ II.

It would be useful to know how these figures were estimated, as most of them seem to be too high. In these mountainous forests, with so much precipitous ground, such variable depth of soil and so many different aspects, it would seem that the ordinary formulæ of text-books need considerable adaptation before they can be safely employed. Is it not possible that, owing chiefly to the above causes, a much larger proportion of the different classes fail to reach the next class, within the average time, than is commonly supposed. Believing this to be the case, when I prepared a working-plan for the Naini Tal sub-division, in the portions where enumerations were made 15 years previously, a general fresh counting was not made, but the stock in four compartments was re-enumerated, the exact number of trees felled during the past 15 years being known. The result was as follows as regards Chir (*Pinus longifolia*), all decimal points below ·5 being omitted for simplicity's sake.

						Compartments.		
Percentage of	II	class chir	entering	I	class in 15 years	9	9&10	7—10
Do.	III	do.	do.	II	do.	11	10	11
Do.	IV	do.	do.	III	do.	17	19	18
						15	22	20·5

The different countings thus give very similar results and point to the very fair accuracy of this method of estimating the stock. The only great difference is in the percentage of IV class trees becoming III class ones, and this was only to be expected, it being but natural that the number of suppressed trees in the IV class should vary considerably with the density of the young pole forest. These countings show the actual changes which have taken place in the growth of nearly 10,000 chir trees stocking 370 acres.

Taking the percentages of trees passing from one class to the other as determined above for a period of 32 years, the average time it takes in Naini Tal (according to ring-counting) for a IV class tree of the lowest dimension to reach the III class:—

43 per cent. of II class chir becomes I within the average time.
56 do. III do II do. do.
25 do. III do. I do. do.

Might I venture to suggest that half-a-dozen carefully selected compartments at different aspects, etc., which were enumerated in 1888, and where the number of trees felled since is accurately known, be re-enumerated. We should then be in a position to judge whether the figures adopted in para 122 are sufficiently near the mark or not.

N HEARLE.

Wild Beasts and Magic.

WHEN reading Col. Pearson's most interesting reminiscences in the August issue of the *Indian Forester*, it struck me as strange and noteworthy that a very similar belief to that quoted by the author of the article with regard to a man-eating panther was current last February in connection with a man-eating tiger, among the Uriyas in this district.

In this case the man-eater is said to be a tigress, and it is a woman who is believed to have been transformed by means of powerful "mantras". The woman-tigress's husband forgot (perchance by no accident) the reversing "mantra," whereupon the wife incontinently eat him and is still at large, having since devoured some ten or twelve human beings.

C. E. C. FISCHER.

Chatrapur, Ganjam District.

N. B.—"Mantra" is a charm or invocation, *e g*, "abracadabra."

III.—OFFICIAL PAPERS AND INTELLIGENCE.

Mr. F. B Dickinson.

It is with the greatest regret that we have received news of the death of Mr. F. B. Dickinson, Conservator of Forests, Central Circle, U. P., at Almora on the 12th October, at the comparatively early age of 52.

Mr. Dickinson received his professional training at Nancy, coming out to India in 1872, and has, since the death of Mr. Hill, been the sole representative of his year in the Bengal Presidency. On his arrival in India he was posted to the C. P., and after gaining an intimate knowledge of the forests of those provinces and of Berar and Coorg, he was confirmed as Conservator in Burma in 1894.

His health gave way completely under the malign influences of the Burma climate, and although he went on long furlough to recruit, he never entirely recovered. On his return from furlough in 1899 he was appointed to the charge of the Central Circle, U. P., where he remained until his death.

There was, we venture to think, no one in the Department more universally and deservedly popular: it is difficult to believe that he had a single enemy, while his unfailing courtesy, cheeriness and good nature gained for him hosts of friends wherever he went. As a forest officer his loss is unquestionable, and it will be difficult to replace him, as his long and varied experience, combined with ripe judgment and tact, rendered his services specially valuable.

His many personal friends, as well as those who have been brought into contact with him in their official capacity, will mourn his premature death, which adds another name to the long roll of Englishmen who, by sacrificing their health to their high sense of duty in the fever laden portions of the Empire, have worthily upheld the traditions of their race.

Mr. Dickinson's death is all the more sad as he contemplated quitting the country for good within the next 18 months.

VI.—EXTRACTS, NOTES AND QUERIES.

The Home Timber Trade and Forestry.

III.

TAKING home-grown and foreign timber together, we annually consume nearly £30,000,000 worth, of which £25,000,000 stands for our imports. If of this £30,000,000 we could circulate £25,000,000 within our own shores instead of expending it abroad, it needs no statistician to appreciate the enormous addition to our internal wealth. But, at the same time, it merely represents the nucleus of a much larger sum which would be put in circulation by the establishment of industries dependent upon wood supply, but now mainly carried on abroad. It would not, of course, require the whole of the 21 million acres of waste land to produce our timber supply, as it would be imperative that any State development of forestry should be carried out upon the most perfect scientific system, and 7 million acres, in addition to our present woodlands, would be quite sufficient for the purpose, if we base our calculations upon the statistics of our present consumption. In their report the commission infer that State forests are the only practical key to the situation, in spite of the fact that they shrink from recommending their establishment They say: "The great area of waste land in these islands, which might be afforested, and with regard to which such valuable evidence has been led, thus becomes a matter of grave national concern. No individual effort is likely to cope with such extensive afforestation, not only because British forestry, as now practised, is inefficient, but because of the capital required, the time which it remains sunk before producing income, and the lack of all security on private estates for continuous good management from the time that the forest is formed until matured timber is placed upon the market. We do not feel justified in urging the Government to embark forthwith upon any general scheme of State forests under present circumstances." What are these circumstances? Surely 21 million acres of waste land, representing a huge capital lying dead and buried, is a sufficient recommendation in itself. If not, the absolute ruin of British forestry as it at present exists would count as a mere feather in the balance. Against this extent of waste land we can only show 3 million acres under woodland, and to put the question plainly, we would ask: Is the Government doing its duty to the country by practically neglecting so great an opportunity? Is not the fact that our landowners are utterly incapable, as a whole, of properly utilising their land of grave enough importance to the community at large to demand Government interference? There is a law empowering sanitary authorities to condemn habitations unfit for human occupation. There is also a section of the same law compelling builders to adhere to the bye-laws of their district, and enforcing the destruction of any new work not in conformity.

It would be a good thing, from a public point of view, if some law was in operation to compel landowners to cultivate the whole of their land where possible One of the fundamental principles of the National Constitution is that the whole of the land is nominally the property of the State, and landowners are tenants at will of the Crown. It, therefore, becomes the duty of the State, or nation, to prevent its property from falling into ruin, and as we are essentially first and foremost a commercial nation, it is only sound policy to profitably utilise the whole of our assets. It is a statement beyond dispute that any State system of forestry conducted strictly upon scientific and economic lines is bound to be a commercial success Belgium is an admirable instance of the flourishing condition of State forests In that country the forests cover 1,750,000 acres, and yield an annual return of £4,000,000, leaving a good margin of profit after all management expenses are defrayed.

The greatest question that would face the Government is the acquirement of the land. In his admirable article on "The Sad Plight of British Forestry," contributed to the *Nineteenth Century* for October, 1901, Sir Herbert Maxwell says: "Suppose that Parliament could be persuaded to vote a sum of £10,000 a year for the purchase and planting of suitable land There are tens of thousands of acres now offered for sale in Scotland, producing an annual rent of not more than 2*s.* an acre as sheep pasture, of indifferent or no merit as grouse ground, but very suitable for growing timber. Thirty years' purchase—a liberal price as times go—would secure 1,000 acres for £3,000. Upon this basis it would take only £21,000,000 to purchase the 7 million acres required for present supply, or a cost of £700,000 per annum for 30 years. The cost of planting, including drainage, would not exceed £6 per acre. The planting would probably not all be done at once, but could be extended over, say, 12 years, or at the rate of £3,500,000 per annum, representing a total cost of £42,000,000. The cost of management and up-keep should not exceed 5*s.* per acre per annum, or £52,000,000 for 30 years in round figures, making a total cost as under :—

Cost of 7 million acres	21,000,000
„ planting and draining	42,000,000
„ upkeep including management expenses for 30 years	52,500,000
	115,500,000

For at least the first 10 years no return would be forthcoming, so a certain amount would have to be considered for interest, so that we will say that £120,000,000 at the outside will cover the whole cost of establishing a system of State forestry in the British Isles, averaging only £4,000,000 per annum for 30 years. These figures represent the liabilities, and against them we have now to consider the assets.

It depends entirely upon the variety of timber and the soil upon which it is planted, as well as somewhat upon the situation, as to how soon it arrives at sufficient maturity to place upon the market. It may be anything from 40 up to 100 years, but from experts' opinion we are pretty safe in considering that each acre will yield an average of 75ft. cube of timber in thinnings for every year from the date of its planting until the crop become matured. Valuing these 75ft. per acre per annum at 6*d* per foot we have an asset in 30 years of at least—

1,300,000,000 feet at 6*d*	32,500,000
A saving on sowing part of the 7,000,000 acres instead of planting	5,000,000
	37,500,000

and deducting this from the £120,000,000 above, we have a net expenditure to the nation of £82,500,000 during the first 30 years, or an actual cost of £2,750,000 per annum. And with what result? The establishment of a gigantic State industry yielding at least £15,000,000 per annum clear profit assured to the Treasury eventually when the whole of the system is fully developed; the repopulation of our rural districts with a healthy and contented race of people; the security of our timber supply beyond question of doubt, unassailable by foreign competition; and, what is by no means of small consequence, the conferring of an immense boon upon British agriculture, for it must always be remembered that the sheltering influence of woodlands in exposed districts must always increase the productiveness of both pasture and arable land in the vicinity.

In conclusion, if this question is to be removed from its academic surroundings into a sphere of practical possibilities, it must receive the attention not only of landowners, foresters, and the timber trade, but of the nation generally. Now that the Government has seen fit to introduce the Irish Land Purchase Bill, surely it is high time some scheme was formulated for bringing into active cultivation the waste lands right throughout the whole of the British Isles, and nothing better can be devised, as far as a part of them are concerned, than the institution of an efficient system of State afforestation.—*Timber Trade Journal.*

The Preservation, Seasoning and Strengthening of Timber.

MR. W. POWELL read a paper on this subject before the Engineering Section of the British Association at Southport on Wednesday (September 16th, 1903). He said that he proposed to show how some kinds of timber at present valueless might become exceedingly useful; how timber used for structural purposes might be so strengthened as to bear a much greater load or strain; how our streets might be cheaply paved with sanitary wood blocks which would neither absorb surface water nor give out disagreeable effluvia; how the ravages of dry rot might be combated; and how all this might be done simply and at comparatively small cost. Seasoning timber, either by natural or artificial means, tended to impair its strength by reducing its specific gravity, and this was especially the case in timber rapidly dried by artificial means. He had found that by boiling timber in a thin saccharine solution until most of the air in the timber was exhausted, and then by leaving the wood in the syrup to cool, a certain amount of the sugar was absorbed by the timber, in some cases so much as to cause the timber to sink. After the wood had become sufficiently saturated it was put into a drying stove and the moisture driven off at a fairly high temperature until the wood was thoroughly dry seasoned, as the term goes, and it was then ready for immediate use. This process differed from others mainly in the fact that before drying was attempted the interstices of the timber were filled in with a viscid, glutinous solution, which took the place of the natural sap and air which the wood had been forced to part with. So, when the moisture was driven off by stoving, the sugar which remained in the wood acted like a strong binder, and held the fibres together, just as cement or mortar bound the stones or bricks in a wall. He was informed by Dr. Herman von Schrenk, the head of the Forest Products Branch of the United States Forestry Department, that there were thousands of square miles of land in the States covered with timber which at present was of little or no commercial value; and the same might also be said of Canada and most other timber-producing countries. These useless trees might aptly be called the weeds of the timber garden. Most of them were too weak, too sappy, too porous, and were so liable to rapid decay as to be not worth cutting down. In some respects they were similar to our English poplar, and, like it, grew very quickly. This class of timber was especially amenable to the process he had described, and the results were somewhat astounding. Poplar absorbed over two and a half times its own weight of the solution, and when thoroughly dried was 75 per cent. heavier than in its natural state. If this could be effected with our English poplar there was every reason to believe the same results might be obtained with the soft woods of America and other countries, and so a fresh source of supply of timber most suitable for railway sleepers, paving blocks, planks for piers, stations, etc., might be opened up. Everyone was aware of the power of wood pavements to emit stifling effluvia, especially on a hot, close summer night. The excreta absorbed by the block, and thus evaporated, made it a perpetual source not only of discomfort, but possibly of ill-health. If the good qualities of soft wood could be retained, while making it not only harder and tougher, but, above all, less absorbent, then one of the great difficulties of the municipal engineer would have been solved. While the weight of pine was not much increased by the process, its effects on the strength of the wood was remarkable. Experiments showed that the tensile strength of pitch pine was increased from 14 to 32 per cent., of white pine from 29 to 39 per cent., of yellow pine from 56 to 107 per cent. Tests as to the effect of the process on the flammability of wood, especially of such wood as the pines, showed that it was to make the wood less inflammable, by reason of its greater compactness and solidity. Beech came next to poplar in its greediness for syrup, and its weight was increased by treatment by about 50 per cent. It became a very firm, tough timber, nearly as tough as oak or teak, without having their brittleness. As to the cost of the process, sugar was a very cheap raw material, being only about the same price, weight for weight, as the lower-priced woods, and if the by-products of sugar manufacture were used the cost would be almost nominal. The amount of labour involved in the process is comparatively small, and the plant was simple.—*Timber Trades Journal.*

THE RELATIONS OF FORESTRY TO ZOOLOGY.—It has been pointed out recently by H. A. Surface, professor of Zoology at Pennsylvania State College, that there is a direct and important connection between forestry and zoology, and he gives several examples of how this connection exists. Aside from the clearing of forest growths, which naturally drives the denizens of the woods from the cleared localities, he finds that the effect of forest destruction on streams is a far-reaching one. Clear streams, flowing perpetually through wooded country, are the natural haunt of the trout: but if the country in which these streams rise or have their courses is destructively cut over, the streams themselves become intermittent, muddy, and in some cases only a succession of warm and slime-covered pools in midsummer. As such they are fit only for the lurking places of the mud-sucker and the carp. In the larger streams and rivers, which, under natural conditions, are the homes of the desirable game fishes, the black bass and pickerel, which pass the winter in deep pools in a state of partial hibernation or quietude, the changes are even more to be deplored when the watershed is deforested. Floods arising from the destruction of the trees bring down immense quantities of silt, "washings," sand, etc., and deposit them in the deep pools where the current runs slower, so that the quiescent fish are covered over and destroyed. Another disastrous result comes from the washing of the fishes out of their places of winter abode, dashing them against rocks and ice and in some cases leaving them stranded to gasp out their lives after the water subsides.

The setting aside of forest reserves will not only keep the forest and the beauty of the landscape, but will restore game and

song birds to their original haunts, protect the wild animals, and preserve the most desirable fishes—the trout, bass, and pickerel.

[We have often pointed out the desirability of protecting and encouraging insectivorous birds in this country. Copses and hedgerows are essential to such for nesting purposes, and both the forester and agriculturist should bear this in mind From a scientific point of view it is equally desirable to protect animals, and more especially those species whom contact with man tends to decimate and reduce to extinction. The formation of large closed reserves is the one practical remedy to safeguard them from much to be deplored extinction.—HON. ED.]

FORESTRY IN SARAWAK.—The country of Sarawak, Island of Borneo, is best known to the rest of the world through the exploits of the first Rajah Brooke, an Englishman who, unaided and alone, took a Malayan province in the throes of internal war, and by his force and foresight made an independent nation of it, and giving at the same time the best example of European government of Asiatics. The present Rajah, nephew of the great Rajah Brooke, is following the policy of his predecessor in taking an interest in everything that concerns the welfare of his people, from the most trivial to the most serious. Among other things, he has taken an interest in forest preservation, as explained in the subjoined report reprinted from the *Outlook*:—

"A meeting of the council was convened this day. His Highness the Rajah informed the members he had what he considered an important matter to lay before them in reference to the future supply of timber for building purposes. At present large quantities of different kinds of woods are being felled immediately in the vicinity of the principal town, for export; and a trade had sprung up which threatened to despoil the forests of all the best and most useful woods necessary to the inhabitants of a growing town. At this end of the state, where so much wood is now being worked for export, the country is comparatively narrow, being only a few miles in depth to the boundary with Netherlands territory; and in this narrow strip of land large quantities of valuable timber have been destroyed by generations of Dyak farming. What there is left should be preserved as far as possible for local use, for were these woods, even the commonest of them, once worked out, the inhabitants of this town and the neighbourhood would be put to the greatest inconvenience.

"His Highness now proposed that all woods in the forests lying between Tanjong Datu and the right bank of the Sadong River shall be preserved for the use of the inhabitants, and that after six months from the present date the exportation of timber from any port within the above-mentioned limits shall be prohibited.

"This was carried unanimously."

DR. SCHLICH, F.R.S., AND FORESTRY AT CIRENCESTER.—In connection with the note upon this subject in the September number of the Magazine, Dr. Schlich has asked us to point out that the appointment of Honorary Professor in the Forestry Chair at the College does not necessitate his taking up residence there or entail the delivering of lectures. He will act as adviser on Forestry matters and perhaps deliver an annual address.

EUCALYPTS FOR FUEL.—Californians are devoting considerable attention to the growing of Eucalyptus trees for fuel purposes. The remarkably rapid growth makes certain species specially adapted for firewood. Their advantages are, besides maturing quickly, ability to thrive in thick stands and to reproduce abundant timber in coppice growth. Near El Toro, California, 3,600 acres will be planted with this exotic, for fuel purposes alone. Experiments demonstrate that under favourable conditions 20 tons of dry wood a year may be perennially cut from well-managed groves at a cost much less than that of coal.

PROPOSED SCHOOL OF FORESTRY FOR WALES.—At the quarterly meeting of the Pembrokeshire County Council, held in the Shire Hall, Haverfordwest, on Tuesday, August 4th, Dr. Griffiths in the chair, it was proposed and seconded that the following councillors represent that Council at the conference of the whole of the County Councils in the Principality, and that the place of meeting be the Shire Hall, Haverfordwest, in October next:—Sir Charles Phillips, Bart., Messrs. W. H. Waters, Edward Robinson, and F. Egerton Allen. The Clerk was also instructed to notify the fact to the respective County Councils.

JARRAH SLEEPERS.—The growing popularity of jarrah sleepers on Indian railways is indicated by an order just placed with the Bengal-Nagpur Railway for 30,000. The East Indian Railway are ordering the new timber in lakhs, and we hear the Calcutta Port Commissioners are contemplating a large purchase for their lines. This last mentioned conversion to the new cult is probably due to the fact that the present Port Trust Engineers are old railway men. The E. B. S. R. are showing signs of conversion also to the adoption of the Australian timber.

JAPANESE WOOD PULP TRADE.—The Japanese wood pulp trade, which has only figured in the Customs returns since 1898, is, according to H. M. Consul at Yokohama, growing largely, with the result that the demand may advance for some years yet, but the material is in the country, and only proper methods of working and transport are needed to obtain a local supply. As an instance it may be mentioned that one company sent the capital, which as recently as 1900 imported from abroad, has now set up a mill in the wooded districts and manufactures its own pulp, both chemical and mechanical. The chief foreign supplies come from Germany and Norway. Canada only supplied 313 tons in 1902– figures which should be capable of great expansion if attention was given to the matter.

VII.—TIMBER AND PRODUCE TRADE.

Churchill and Sim's Wood Circular.

2nd October 1903.

EAST INDIAN TEAK.—The deliveries for the first nine months of the year amount to 8,382 loads against 9,980 loads in the same period of 1902, and for September 779 loads against 1,000 last year. There has been a slightly better feeling noticeable during the month, and more enquiry, though this is not at present reflected in the deliveries from the docks. There is no forward business to report on account of the continued inability of shippers to quote for cargoes suitable for European demands.

ROSEWOOD—EAST INDIA.—There is a fair demand for good wood, from medium to large sizes, but small and inferior logs are not readily sold.

SATINWOOD—EAST INDIA.—Sales have been small, as the demand is dull and stocks too heavy

EBONY—EAST INDIA.—Only prime wood, of good sizes, is asked for.

PRICE CURRENT.

Indian teak, logs,	per load	...	£10 to £18.
„ „ planks	„	...	£12 10s. to £20.
Rosewood, per ton	...	...	£7 to £11.
Satinwood, per s.ft.	...	...	6d. to 18d.
Ebony, per ton	...	...	£8 to £11

Denny, Mott and Dickson, Limited.

WOOD MARKET REPORT,

LONDON, 1*st October* 1903.

TEAK.—The landings in the docks in London during September consisted of 1,148 loads of logs and 214 loads of planks and scantlings, or a total of 1,362 loads, as against 851 loads for the corresponding month of last year. The deliveries into consumption were 645 loads of logs and 202 loads of planks and scantlings—together 847 loads, as against 952 loads for September 1902.

The dock stocks at date analyse as follows:—

6,242	loads of logs,	as against	5,308	loads at the same date last year.
3,619	,, planks,	,,	3,225	,, ,, ,,
—	,, blocks,	,,	—	,, ,, ,,
Total 9,861	loads	,,	8,533	loads ,, ,, ,,

This market has been sluggish during the last month, but prices continue to harden for logs—notwithstanding the fact that whilst 6,082 loads of logs have been landed during the first nine months of the year, only 5,234 loads have actually gone into consumption. The consumption of planks and other conversions has also been discouraged by the high c.i.f. cost, as of 3,862 loads landed during the nine months, only 2,872 loads have gone into consumption. These figures serve to show that when production is restricted, consumers learn to cut down their requirements by substituting other material rather than pay abnormally high prices to encourage fuller shipment.

Dearer money on the top of the high import cost of nearly all descriptions of timber has served to check any increase in the restricted volume of business. Important failures at the outports will tend to affect unfavourably the financial confidence which has for the last few years characterised the timber trade.

Market Rates for Products.

Tropical Agriculturist, 1st *October* 1903.

Cardamoms ...	... per	lb.	1s. 6d. to 1s. 7d.
Croton seeds ...	... ,,	cwt.	15s. to 21s.
Cutch ...	... ,,	,,	22s. 6d. to 30s.
Gum Arabic ...	... ,,	,,	15s. to 20s.
Do. Kino ...	... ,,	lb.	4d. to 5d.
India-rubber, Assam	... ,,	,,	2s. to 3s. 7d.
Do. Burma	... ,,	,,	2s. to 3s. 5d.
Myrabolams, Madras	... ,,	cwt.	5s. to 6s.
Do. Bombay	... ,,	,,	4s. to 7s. 6d.
Do. Bengal	... ,,	,,	3s. 6d. to 5s.
Nux Vomica ...	... ,,	,,	7s. to 10s.
Oil, Lemon-grass ...	... ,,	lb.	6d. to 6½d.
Orchella weed, Ceylon	... ,,	cwt.	10s. to 12s. 6d.
Sandalwood, logs ...	... ,,	ton	£15 to £30.
Do. chips ...	... ,,	,,	£4 to £8.
Seedlac ...	... ,,	cwt.	117s. 6d. to 135s.
Tamarinds, Calcutta	... ,,	,,	8s. to 10s.
Do. Madras ...	... ,,	,,	4s. 6d. to 6s.

REPORT

ON

"SPIKE" DISEASE AMONG SANDALWOOD TREES

BY

DR E J BUTLER, M.B, F L S,

CRYPTOGAMIC BOTANIST TO THE GOVERNMENT OF INDIA.

Dated the 27th February, 1903

Previous references

The first detailed reference to this disease appear in a Memorandum by Mr. McCarthy, Deputy Conservator of Forests in Coorg, on "The future supply and culture of Sandal in Coorg," in December 1899 Mr. Barber, Government Botanist, Madras, visited Coorg for the purpose of studying the disease shortly prior to my arrival. His report, however, was not available at the time, and I remained in ignorance of his work until my own was completed.

Area and period of affection

2. The disease affects a portion of the Sandal area of Coorg and a smaller portion of Mysore. It would appear to be of recent origin, since it is hard to believe that so remarkable a disease could have escaped attention.

External characters of the disease

3. The external characters of the disease are well described in the reports of Mr. McCarthy and Mr. Barber. There is, therefore, no need to dwell at any length on them here. A short account must, however, be given of its very peculiar symptoms in order to understand the course of the disease. From a certain moment all the new leaves produced, sometimes on a few isolated branches only, sometimes over half the tree, sometimes even over the

whole, take on new characters, becoming narrow, pointed, stiff and crowded together. From this moment the affected shoot never ceases its growth, differing markedly from the normal tree which lies dormant for a considerable period each year. The newly formed internodes are considerably shortened. As growth continues each new leaf is smaller, narrower, and more pointed than its predecessor, and as the older leaves fall off, the apical portion of each shoot is clothed with a tuft of leaves the size of which forms an indication of the stage to which the disease has progressed. Finally, to quote Mr. McCarthy's words, "the new shoots present the appearance of fine spikes, bearing four rows of fine bristles."

This forced growth, which I take to be the dominant character of the disease, is further indicated by the bursting out of old buds on diseased shoots below the diseased portion; by excessive branching; and by the occurrence of "phyllody" or the transformation of the normal petals, sepals, etc., into small foliage leaves, in the inflorescence. None of the last three symptoms are constant, but all are sufficiently common to be distinctly associated with the disease. Where the bursting out of old buds is well marked on a shoot far advanced in the disease, it can be clearly seen that the buds break out into spiked shoots at the same stage of the disease as that to which the apical growing portion has arrived. So that when the main shoot bears nothing but a tuft of fine bristles at its apex, the new lateral shoots, often formed a considerable distance lower down, come out also with tiny bristle-like leaves in place of the ordinary foliage. And this rule by which all new-formed shoots on a diseased branch show the same degree of spike, is general for the whole diseased area of the tree, or for the whole tree where the disease has from the first affected all parts. It can point to nothing else but to a profound disturbance in the nutrition of the tree.

.Phyllody appears to occur only where the inflorescence is already partially formed before the first development of spike on the inflorescence-bearing branch. Branches already attacked never bear any inflorescence at all. Phyllody is, as Mr. Barber points out, usually an evidence of increased nutrition or of the stimulation of a parasite. Since all the other evidence points to increased nutrition, and since, as will presently be seen, no parasite could be found, it is probable that the phyllody is to be taken as due merely to excessive nutrition in the early stages of the disease The absence of flowers, which in Sandal, as in many other plants, normally appear at the termination of vegetative activity, is similarly an evidence of increased nutrition resulting in a prolongation of vegetative growth beyond the normal. The alternative explanation, that the prolongation of vegetative growth results from the failure from some other cause to form flowers, need not be taken into account, since there is abundant evidence from the internal examination of the tissues of an increased nutrition, and since this increased nutrition is quite sufficient by itself to account for the phenomenon in question Later on, when the tree becomes exhausted from the continuous vegetative activity, flower production would involve too great a drain on its resources to be possible.

Thus the two salient and constant external features of the disease are an increased vegetative activity, and a failure to form flowers; both evidences of a forced and possibly abnormal nutrition

Condition of the tissues

4. A detailed microscopical examination was made of the tissues from leaf to root and checked by a series of preparations kindly lent to me by Mr Barber. The first fact noted was the absence of any trace of parasitic action sufficient to account for the disease, in any part of the diseased trees. A few fungus-hyphæ were found on epidermis and cortex, a few bacteria in the tissues, and some probably saprophytic organisms on the roots; but these were similarly found in healthy trees, and were in any case totally inadequate to produce such marked symptoms of disease.

At first sight the tissues appeared normal, and nothing resembling a degenerative change was observed. Certain departures from the normal, however, occur, and must be carefully considered as they form the only clue to the nature of the disease. The most prominent is that all the parenchymatous tissues of a diseased tree are loaded with starch, which is present in enormously greater quantities than in a healthy tree. With this great increase of starch certain structural alterations are noticeable. The leaf is thickened in substance while much diminished in surface area, this hypertrophy being due not so much to an increase in the number of layers of cells as to their elongation at right angles to the surface of the leaf. This is especially towards the upper surface of the leaf where the sub-epidermal cells are about twice as long as those of the healthy leaf; thus a well marked palisade tissue is formed, which is absent in the healthy leaf. All the cells of the internal tissue of the leaf, or mesophyllum, are loaded with starch; and as the enormous quantity of starch in the storage cells of the plant shows, the function of carbon assimilation is progressing with quite abnormal vigour. I think the cellular hypertrophy of the leaf is probably an effort to deal with this excessive starch-formation, and to compensate for the diminished surface area presented by the diseased leaves. That a compensatory effort is being made by the plant in this case is supported by an examination of the epidermis, which shows that the stomata, or openings by which air, bearing carbon-dioxide for the nutrition of the plant, enters, are very greatly increased in number in a given area as compared with a healthy leaf. It is probable that, at least in the early stages of the disease, the amount of carbon-dioxide, which enters the plant, is, in spite of the diminished leaf area, at least equal to that of the normal tree, and the hypertrophy of the leaf-cells, in view of their diminished number, may be an effort to deal with this. The only alteration in the internal structure of the stem is a somewhat diminished and irregular formation of vascular tissue in advanced cases, which is not visible in the early stages of the disease.

The roots are perfectly healthy, with the exception, noted by Mr. Barber, of the root-ends and "haustoria."

The chief internal evidences of the disease are then an excessive production of starch, together with certain structural alterations in the tissues.

Meaning of the modifications.

5. It has recently been shown that a certain train of modifications in the structure of a plant occurs when the plant is forced to take in excessive quantities of carbon-dioxide by exposure to an atmosphere unduly charged with this gas. These are, shortly, as follows :—

1. The elongation of the internodes is checked ; but the period of growth, *i e.*, of vegetative activity, is lengthened.
2. The growth in surface of the leaves is early arrested.

3. The absolute number of stomata in a given area of leaf surface is considerably increased, though the proportion of stomata to epidermal cells is about the same as in normal leaves, all the cells being diminished in size

In other words, the number of stomata on the leaf is increased, as though to compensate for the diminution in size.

4. The structure of the leaves is not materially altered.

5. The xylem, or inner portion of the vascular ring, of the stem, is less perfectly developed.

6. Starch is accumulated in the leaves and parenchymatous tissues.

7. No alteration can be detected in the roots.

This group of modifications shows so striking a resemblance to those above described, as characterising Spike disease in sandal, that they are worthy of careful consideration

The main features common to both are the forced carbon-assimilation resulting in an accumulation of starch in the plant ; the increased production of leaves, shown in the shortening of the internodes ; and the prolongation of vegetative activity. Since, in the experiments just mentioned, forced carbon-assimilation was the obvious result of the increased supply of carbon-dioxide, it is at least likely that the remaining train of modifications resulted directly from this. Hence it is evidently possible that the whole of the alterations observed in Spike disease are directly due to intensified carbon-assimilation, or are the result of overloading the plant with starch. The only prominent modification present in spike, not observed in these experiments, is the leaf hypertrophy, and this may be due to some factor not present in the plants experimented with. It, therefore, appears to me probable that the intensified carbon-assimilation is the modification to which attention should be directed, and that most of the other alterations are consequences of this.

We have, unfortunately, as yet nothing to guide us as to the cause of the intensified carbon assimilation in spiked sandal. It would be absurd to suppose it due to unusual quantities of carbon-dioxide in the atmosphere. The effects of such a condition would have been rapidly visible on the human population of the country affected. The cause must, therefore, be sought in the plant itself. For some reason or other the tree, or some isolated branches of it, suddenly proceeds to manufacture starch out of all proportion to the demand for this food by the tissues. As a result of this, growth is forced, the tree gets no rest, and dies of exhaustion, the result of starch-poisoning.

Possible causes of intensified carbon-assimilation.

6. In the plant itself a disease of the stomata, or of the starch-forming cells, or the circulation of some substance in the sap, might each account for the forced production of starch. The stomata are certainly much altered, lying flush with the surface of the leaf, instead of forming a depression in the epidermis as in the healthy plant. But I can find apparent cause for this, and the condition is probably secondary to the leaf-hypertrophy. The starch-forming cells are apparently healthy. The existence of a poison in the sap can only be determined by a series of infection experiments carefully conducted over a number of years. I fail to see how the mere destruction of the root-ends could possibly result in an increased formation of starch, for that starch is formed in excessive quantity, and not merely stored up because

not consumed in normal amount as fast as it is formed, is evident from the fact that growth is actually increased, and that, therefore, more starch than usual must be actually consumed. But the destruction of rootlets may well be an early evidence of the action of some poison circulating in the plant. That this poison, if present, actually enters through the root-ends, we have nothing to show, since no organism has as yet been found in the roots that would be likely to be a source of disease. The fact that in addition to the free rootlets, the organs of attachment to other roots, or "haustoria", through which a portion of the food of the sandal tree is absorbed, are also dead in spiked trees, tells against a local disease of the rootlets alone. The existence of a poison circulating in the sap seems, therefore, to be the most probable explanation of the suddenly intensified starch manufacture.

Association with Lantana.

7. We come now to the association of the Lantana invasion of Coorg with the appearance of the disease, first called attention to by Mr. McCarthy. In a search for any recent change in the conditions of sandal-growing, this is the one striking new factor. It might be thought an easy matter to exonerate Lantana from any share in the disease. But this is not so easy as it looks. For several days I sought round Fraserpet to find a spiked tree isolated from Lantana, but without success. When we remember the great distances to which the roots of sandal extend, probably at least fifty yards, and the general nature of the Lantana invasion, this failure may be understood. Still the near future must settle this, for spike disease is progressive, and the area covered by Lantana restricted. If the disease continues to spread into Mysore, as it appears to be doing, and extends beyond the Lantana country, then it obviously cannot be traced to this source. If, on the other hand, spike disease remains confined to the Lantana country, and its originally rapid spread is checked, then there is grave reason to suspect the Lantana and a definite, though not very hopeful, objective to which to direct our preventive measures.

A definite communicable disease.

8. That the condition is a definite disease and communicable, the study of the plantations around Fraserpet, and in parti-

cular of the "River," plantation clearly shows. In this plantation a fire destroyed the outer fringe of sandal. Fire, as Mr. McCarthy mentions, is a predisposing cause to this, as to some other, diseases. The outer trees which had survived the fire took spike, while those inside remained healthy. I may mention in parenthesis that these outer trees grew out of Lantana, while those inside were isolated. But the disease from that time has slowly progressed in a centripetal direction, until now, after some years, the plantation is practically destroyed. The slow and steady nature of this progression seems to point to underground communication, and since Mr. Barber has shown that sandal roots form connections with other sandal roots, a channel through which the virus might pass from tree to tree is here evident. In opposition to this slow infection, probably occurring from tree to tree, there is the first invasion of the disease which was rapid. It is as if a first wave of the disease passed rapidly through the air, and that those trees which escaped this first attack were afterwards slowly killed out by underground spreading, a mode of extension which is always gradual. The whole country round Fraserpet shows evidences of this secondary and gradual spread in a centrifugal direction from trees which succumbed to the first attack.

Course of the disease.

9. It is probable that death follows the first appearance of the disease much more rapidly than was at first suspected. Thus a tree which was observed during Mr. Barber's visit to be showing the earliest signs of spike, was, at the time of my arrival at Fraserpet six weeks later, far developed in the disease Instead of years, we must probably speak of months in estimating the rate of progress. No case of recovery has as yet been reported.

Treatment.

10. The all-important question of treatment is naturally a difficult one where the cause of disease is unknown. Still it is far from being insoluble. One of the most serious diseases with which American fruit-growers have to contend is that known as "Peach yellows". For more than twenty years this disease has ravaged the Eastern States, and its nature remains to this day as obscure as in the beginning. The best energies of the United States

Department of Agriculture have been directed towards ascertaining its origin, but without success. One after another all the more usual causes of disease, fungi, insects, bacteria, etc., have been excluded, yet there is full evidence of the infectious nature of the disease. And the treatment is on the whole fairly successful, so that the disease is under reasonable control. "Peach yellows" bears several remarkable resemblances to spike disease, and one of the explanations offered of it is the presence of an infectious fluid in the sap. The success in checking this disease holds out a fair hope for the eventual controlling of spike.

The first thing to be done is clearly to endeavour to confine the disease to the area at present infected. The not uncommon escape of isolated trees gives an indication which might usefully be followed up. A belt of country around the diseased districts ought, in my opinion, to be cleared entirely of sandal trees. This belt, judging from the known length to which roots extend, should be not less than 100 yards wide. The taking out of every tree in such a belt all round the infected area ought not to be very difficult when we take into account the scattered way in which sandal grows, a tree here and a tree there. The local forest officer will be the best judge of that, and I am in correspondence with him on the subject. It would seem to me that the Mysore Government should be asked to co-operate in the work, as it is certainly useless to endeavour to eradicate the disease in Coorg if, across the Cauvery in Mysore, spiked trees are allowed to remain to be possible sources of infection. Diseased trees are at present being removed in large quantities in Coorg for the yearly sales, and this practice might well be followed in Mysore, for the evidence of communication from tree to tree cannot now be ignored, although the fact is not yet scientifically proved. So far as microscopical examination can show, the disease causes no deterioration in the quality of the wood. The disease must soon lessen its intensity in districts such as the vicinity of Fraserpet, from the very fact that there will shortly be little sandal left for attack. To endeavour to eradicate all spiked trees in such acutely infected areas, impossible up to the present, may then become practicable as more and more is cut down or destroyed by the disease, and the new generation may be preserved; for it is an important fact that young trees do not usually suffer. In freshly infected areas I would strongly advocate the total extirpation of a tree the moment it shows signs of spike, and the burning on the spot ofall the *debris* from rough-dressing the wood. In "Peach yellows" the living tissues have been proved to be highly infectious, and in its mode of spreading and many of its symptoms, this disease is closely allied. Hence the danger of disseminating infectious matter during the removal of the tree must be borne in mind.

Experimental work.

11. These recommendations, which are only too scanty, are all that I think it is justifiable to suggest in the absence of experimental work. I may add that excision of diseased branches in early stages does not seem to have any effect in checking the extension to other parts of the tree.

Further work must be guided entirely by the results ot experiments, which I hope to be able to commence with Mr. McCarthy's aid immediately. These experiments cannot be carried through in a short time, but must extend over several seasons before any trustworthy results can be arrived at. One great difficulty in the way is that the work can only be carried on in already infected areas, since there would otherwise be a risk of spreading the disease to new districts. It will be hard to find suitable healthy trees for inoculation under such conditions that the danger of infection from outside is inconsiderable. The experiments will be directed chiefly to determine the mode of spread of the disease; its period of incubation; the nature of the virus; and the influence of the "nurse" plant, *i.e.*, the plant from whose roots the sandal draws a portion of its nourishment, on the development of the disease. Their results will be communicated at a subsequent date.

Summary.

12. It will be evident from what I have said above that I consider spike in sandal to be a nutritional disease, characterised by a forced carbon-assimilation and a consequent train of

modifications in the form of the tree. No parasite origin can be assigned. The cause of the forced carbon-assimilation is unknown, but is probably not local. It may be due to the circulation of a poison in the sap. The disease shows marked similarities to "Peach yellows," and, like it, there is reason to believe it is communicable. Treatment at present must be chiefly directed to confining the disease to its present limits. Experimental work is necessary before further recommendations can be given.

G. I. C. P. O.—No. 3185 R. & A.—12-8-1908—650—S. M. W.

A NOTE

ON

THE SANDAL WOOD BORING INSECTS OF MADRAS,

BY

E. P. STEBBING, F.L.S., F.E.S.,
OFFICIATING SUPERINTENDENT, INDIAN MUSEUM

References have been made at various times to the damage done to the sandal-wood tree in Madras by wood-boring insects. In 1891 a considerable loss was experienced in Mysore owing to their depredations. As is well known, the wood of this tree is particularly valuable, and when it is understood that the least blemish in it (and the old gallery of a wood-boring insect is considered a very serious one) reduces its value from 1st class[1] (R850 per maund) to 3rd (R750) or 4th (R700) or lower, it becomes readily apparent that it is of the first importance to know something about the life histories of these boring insects with a view to ascertaining what measures are feasible to counteract their attacks.

The insect, which up to the present has been quoted as chiefly responsible for these depredations, is the caterpillar of the moth *Zeuzera coffeæ* Nietner, a species which also infests the coffee.[2] Careful observations on the ground have shown me that this belief is erroneous. Such specimens of infected trees as have been sent to the Indian Museum for identification of the pest have been naturally small and consisted probably entirely of branch wood or small sapling tops. These are the parts of the trees which caterpillars of the *Zeuzera* prefer. It is, however, the heart wood of the main stem and the larger branches which has a commercial value, and this is attacked by two quite different classes of borers. One is a beetle grub belonging to the Family *Cerambycidæ* which contains some of the largest wood-boring insect grubs known to exist. I can find no account of these having ever been reported as damaging the sandal and yet they are undoubtedly the main cause of the loss experienced. The second, which was taken from the heart wood, belongs to yet another class of borers. It is the larva of a species of *Sirex* or wood wasp, a destructive boring family belonging to the Order *Hymenoptera.* I cannot say at present whether this is plentiful or otherwise in the sandal districts, but that it should have been found in the wood at all is of sufficiently startling import.

---

[1] First class wood must be free from cracks and holes; 2nd class wood must have no holes, etc.

[2] Indian Museum Notes, Volume III, 1. 1.

The following are my observations on these borers made in the North Coimbatore forests. I was unable to inspect the Mysore and Coorg sandal-wood areas owing to want of time.

1. STROMATIUM ? SP.

The Longicorn Borer.

Although the identification of insects in their larval or grub stage is by no means easy and very often impossible, I am of opinion that the one commonly found boring in sandal-wood stems may prove to be that of a species of *Stromatium,* a genus belonging to the *Cerambycidæ* family of beetles. A member of the genus, *Stromatium barbatum,* was reported some years ago as attacking young teak saplings in the Kulsi Plantation in Assam.

Throughout the sandal-wood areas of the North Coimbatore forests this cerambycoid grub was by far the most aggressive pest of the tree. The following is a description of the grub :—

Larva.—White with a pinkish tinge, thickish, tapering slightly behind. Mouth parts black; thoracic segments (the segments following the head) yellowish. Length 1 inch to 1¼ inches.

Life History.—Grubs differing in size but from ⅔rds to nearly and quite full grown were found in galleries in the stem of the trees in the first week of August. No small larvæ were found. From their total size, and the length of the galleries bored, and from the fact that no young larvæ were found in the stems examined, I should think it improbable that they spend over a year in this stage and the period may be a few months only. Neither the pupal nor beetle stages of the pest have been yet obtained.

Method of Attack.—The larvæ are to be found either in the main stem or in the side branches. An examination of these latter shows that the grub has often started in the branch and then bored down it to the main stem and then down the latter. This is not invariably the case, as at times the larval gallery is entirely confined to the main stem. From this it is evident that the eggs are laid by the beetle on the bark of either a branch, somewhere close to the main stem, or on the main stem itself. These observations are the result of an examination of a number of trees and saplings, some of which were entirely cut up for inspection purposes. The tunnels are tightly packed with the digested wood particles which are passed out by the larva as it proceeds down the stem. The galleries are chiefly confined to the heart wood of the tree, both in the branch and main stem, and the grub always bores downwards. Before changing to the pupal state the larva enlarges the gallery slightly and fills the extreme end with particles of wood refuse and chips. It then turns round in the free space and changes into a pupa. The beetle on maturing bores its way out of the tree by a horizontal hole driven directly through the heart wood, sap wood and bark to the outside. The position of this exit gallery, with reference to the larval gallery inside, makes it evident that the larva turns round in the pupating chamber before changing to the resting stage. Whilst boring its gallery the larva may eat out one or two off-set tunnels to the outside. These are always at right angles to the main gallery and are for aëration purposes only. When the larval gallery is confined to the main stem there will usually be only one of these. If the gallery has started in a branch there will often be two.. The insect would appear to confine itself to saplings and young poles. Between Dhimbum and Kollegal a number of trees and saplings were found to be attacked. The following is a description of a badly infested one which, together with others, was cut up *in toto*. It is quoted as indicative of what this borer is capable of.

The tree had a diameter of 2¼ inches at the base and a bole of 15 feet to the point where the crown commenced. This bole had been attacked in several places, the last gallery running down to within 8 feet of the base of the tree. Both new and old galleries were visible upon splitting up the stem. These were as follows beginning at the lowest one :—

1st. New Gallery.—Contained a living grub just about to pupate in the heart of the stem. Gallery about 18 inches[1] in length bored downwards and confined to the stem only. Gallery slightly winding.

2nd. Old Gallery.—The eggs were probably laid upon the bark of a side branch. The gallery commenced in this. The young larva on hatching out had bored straight to the heart of the branch and then down its centre till it reached the main stem down the heart wood of which it carried its tunnel. Length of gallery in main stem 7 inches. The larva had pupated at the end of the gallery, the extreme end of it being packed with wood chips. The rest of the gallery, with the exception of the pupal chamber, was blocked with a dark red hard mass (the heart wood is reddish) consisting of chewed wood. A large hole starting at one side near the upper end of the pupal chamber was bored horizontally through the wood to the outside. This exit hole was very visible on the outside of the stem.

---

[1] This gallery was unusually long for one confined to the bole.

3rd. Old Gallery.—This one also commenced in a side branch, the larva working down the branch into the main stem, and then down the centre of this latter finishing up close to where No. 2 joined the main stem. It did not connect with this latter. Length about 1 foot. An air hole had been bored to outside. Exit hole of beetle bored in the same way as in No. 2.

4th. New Gallery.—Contained a living larva which was about to pupate. It had enlarged the end of its gallery for this purpose. About 3 inches of the gallery was free of the compressed wood excreta. Length of gallery 11½ inches. Was confined to centre of the stem and contained one air-hole bored to outside about half-way down. In this case the eggs must have been laid by the mother beetle either on the outside of the bark in a crevice or in the softer layer of tissue below.

5th. Old Gallery.—This gallery started at the point where the main stem branched into two or three forks, *i.e.*, where the crown commenced. It began about 1½ inches up one of the forks and then came down the main stem, its total length being from 15 inches to 16 inches. One air-hole present. This gallery ended near where No. 4 commenced.

6th. New Gallery—A tunnel containing a living larva which ran down one of the forks and ended very near where No. 5 joined the main stem. The grub inside was not more than a half to two-thirds grown and the gallery appeared to be still in course of construction. The larva was apparently on its way to the main stem.

From the above we see that there were no less than five tunnels in the main stem (two of which contained living grubs) and one unfinished one in a fork of the crown near where it joined the bole, giving a total of nearly 5′ 6″ of tunnels in a length of 12 feet of bole. The tree was alive, but badly stag-headed. It was growing near Osahatti in the Sandal-wood coupe No. 7.

Result of Attacks.—Only living trees are attacked by this pest, and it would appear to confine itself to saplings and young poles. The sandal is not necessarily killed by the action of the boring grubs; in fact, unless these latter are numerous, the tree is probably but little inconvenienced, and the cambium-layer soon covers over the old air- and exit- holes made by the pest. In such cases there is no evidence externally that the tree has been attacked. When it is felled and converted, however, the heart wood is found to contain the old galleries, made by the boring grubs which infested the tree when young, and the value of the wood is thereby greatly lessened, however fine in quality it may be. At other times, on the other hand, the tree shows externally plenty of evidence of old attacks. The air-holes and exit-holes are plainly visible, and if the sandal is from any cause sickly and unable to cover these over, they begin, under the action of the sun and rain, to "weather," become greatly enlarged, and even at times coalesce.

When the latter takes place, the tree will be found to have its centre exposed on one side,—perhaps for a distance of several feet—and a considerable amount of heart wood will have rotted away under the "weathering" action.

The plantation at Bailur was visited and inspected. The poor character of the growth here was due to other causes, but it was apparent that a number of the trees had been attacked some years previously by a cerambyx borer, not improbably the *Stromatium*. About 4,000 badly shaped or dying and dead trees had been cut out the year previous to my visit (1901), or it is not unlikely that the evidence of the pests' work would have been even greater.

Summarising the above we see that this pest may—

(1) Kill saplings (probably not often).

(2) Bore up the heart wood of young living trees. That subsequently the vitality of these

latter is sufficient to grow over the air- and exit-holes, thus hiding all trace of the attacks which are only discovered when the wood is converted for sale.

(3) The exit- and air- holes may "weather" to such an extent that they coalesce, and thus 50 per cent. or more of the heart wood of the tree may be destroyed.

During a visit I paid to the Sandal Koti at Bangalore I was able to inspect the damage done to the wood by these insects. Unfortunately I arrived a week too late to be present at the actual sorting of the year's outturn, which was stored in the godown. Had I been present at this, it would have enabled me to inspect many hundreds of logs, and I should have been able to form some conclusion as to the insect's abundance or otherwise in Mysore. I was shown the various classes of wood, and the system of classification was described to me. Wood with holes and galleries in it, even though its quality may be otherwise absolutely 1st class, is relegated to the 3rd or 4th classes, and therefore it is quite possible to calculate the actual monetary loss resulting from the work of this longicorn. My inspection showed it to be sufficiently high to render the full working out of its life history a study of the first importance.

Note.—In a tree with a diameter of six inches at the base, I found another kind of longicorn larva which is not a *Stromatium*. The tree, a large one standing in the Odayarpalaiam compartment of the Doddasanpige Forest, had a dead 5-foot top. Below this in the green wood I cut out a longicorn grub, about 1¼ inches long, white, but with much larger thoracic segments than has a *Stromatium* larva. A second one was found lower down in the bole. I have not been able as yet to ascertain anything more about this grub. It would not appear to be so numerous as the *Stromatium* since I only found these instances of it. The heart wood of this tree, a particularly fine one, was greatly reduced in value by the numerous old and new galleries it contained.

2. ZEUZERA COFFEAE, NIETNER.

The Red Borer.

References.—Nietn. Edin. New. Phil. Journ. XV, 1862, p. 36; C. & S. no. 1588;
Moore, Lep. Ceyl. ii, pl. 148, figs. 1, 1 *a*, *b* (larva). Steb. Injur. Ins. Ind. For., p. 104, fig. 168.
Zeuzera oblita, Swinh. Trans. Ent. Soc. 1890, p. 198.
Zeuzera roricyanea, Walk. Journ. Linn. Soc. vi, p. 177 (1862).

Classification.—Order, *Lepidoptera*. Sub-Order, *Heterocera*. Family, *Cossidæ*.

This is the well-known red borer of the Madras coffee districts and has always been supposed to be the chief sandal-wood borer. I give the following description of the larva made from fresh living specimens. Large, stout, flesh-coloured to darkish red. Segment following head swollen, and hood-like, yellowish, with three black blotches, placed triangularly upon it. Mouth parts black. Posterior half of 10th segment and whole of 11th and 12th segments dark yellowish-green to very dark olive with longish scattered light-coloured hairs on them. Last 2 segments smaller than the others and taper bluntly, being bent over almost vertically downwards. A few scattered tubercles and hairs on the other segments. Larva is lighter coloured below. Length 1¾ to 2 inches.

Life History.—This has been already described in *Injurious Insects*. I need not recapitulate here. It may, however, be mentioned that the moth appears on the wing in February, and the eggs are probably laid somewhere about this time.

Result of attacks.—The eggs are laid upon the bark of the branches or upon that of young saplings, and the boring caterpillar confines itself to these parts. It requires soft woody tissue for its food, and does not bore into the hard heart wood of older trees, as is the case with the *Stromatium*. It is a serious pest to young saplings, as these are either killed outright under its operations, or are so weakened as to be thrown down by the wind. In boring this caterpillar hollows out a large portion of the interior of the branch and keeps the tunnel quite free from wood particles and excreta. It is thus unlike the longicorn borer which is tightly packed with the two latter. The difference between the work of the two grubs is most marked.

The red borer attacks and kills young saplings. If the trees get safely through this period of their lives, they will not be much harmed by it subsequently, as it will confine itself to attacking the branches only.

The white *Stromatium* borer probably only kills the tree when present in numbers. It, however, invariably bores in the heart wood and thus spoils its quality and reduces its value. In addition to the actual amount of injury these borers are capable of doing *per se* to the sandal, further damage may arise from the fact that the external holes form convenient methods of entrance to the interior of the tree for fungous spores, and consequently serious fungoid attacks may follow the insect ones.

3. SIREX ? sp.

The Wood Wasp Borer.

Classification.—Order, Coleoptera. Family, *Siricidæ.*

I have before alluded to the difficulty which the identification of grubs usually presents. Perhaps the two easiest families of insects to identify in this stage of their existence are the *Cerambycidæ* and *Siricidæ*.

It is to this latter family that the third of the sandalwood borers under consideration belongs. The following is the description of the larva :—

A thick, flattish, pale, whitish-yellow grub, convex above and flat beneath. Head small, orange yellow; mandibles black; rest of mouth parts brown. Thoracic segments enlarged, the anterior one being hood-like dorsally with a narrow neck of same circumference as head where it joins on to this latter. Thoracic legs well marked and 3-jointed. There are no abdominal legs, but slight protuberances. Abdominal segments nine in number, widening out posteriorly to the seventh, which is the broadest; the two terminal ones taper posteriorly, the last ending in a brown spike which is black at its extreme tip; round its base is a circle of minute brown spiklets. Head, prothorax, and last two segments of abdomen shining above. The segments of latter are bulged out at the side, giving the grub a crinkled edging on either side. Length just under ¾ inch. Width across seventh segment $\frac{2}{16}$ inch. (Grub probably not full size.)

Life History.—I know at present little about this insect. No member of the family has ever previously been recorded as attacking the sandal tree. The larva was found in the heart wood of a tree in the first week of August, and was not, I think, full size. Unfortunately the wood in which it was found had been so chopped about that its gallery could not be satisfactorily traced in its entirety. It is not unlikely to be irregular in direction. Sirex larvæ usually only bore into dying or dead wood, but require this to be in a sound condition. The female does not usually need bark to lay her eggs in, but drills a hole in the wood itself and oviposits. These habits render this pest one to be feared and make the working out of its life history imperative since it is capable of committing damage to the sandal-wood after it has been cut and barked, and when no further attack is to be feared from the other above-described borers. We require to know how long it spends in this larval stage, and how long in the pupal and adult or fly stage. The adult will probably be a fly not unlike the one shown in Pl. VII, fig. 1, *e*, of the *Departmental Notes on Insects that affect Forestry*, No. 2. Also whether it attacks the trees when they are still quite green or only when the wood has already begun to dry.

Distribution.—All these three borers exist in the sandal-wood areas in North Coimbatore. The Deputy Conservator of Forests at Bangalore, to whom I explained, with diagrams, the nature of the damage done, told me that he thought two of them were present throughout Mysore.[1] He could not tell me anything about the Sirex one. From an examination of the sandal billets in the Sandal Koti at Bangalore I think that there can be little doubt that the Deputy Conservator is correct.

I have at present no information as to whether the borers exist in Coorg.

Protection and Remedies.—The question of methods of protection against these internal boring pests is difficult, and the drastic one of cutting out and burning all infested trees is often the only one that can be recommended. The matter is rendered more difficult in this case owing to the scattered way in which the sandal grows. In the case of the red borer undoubtedly the most effective check will be to cut out all infested saplings. The operations of this caterpillar are easily recognisable from the outside owing to the fact that it keeps its burrow quite free of all wood particles, excreta, etc., and therefore small heaps of sawdust-like excrement are to be found at the foot of the tree beneath the entrance-hole and air-holes. There will also usually be exudations of sap trickling down the bark from these holes. When these exudations are seen to be fresh and wet, and when the sawdust at the foot is fresh, the borer will be found inside. Such infested trees need not be cut down at once, as other moths may lay their eggs in them (it is often noticeable that for some reason or other a particular tree or trees are more favoured in this way). A careful watch must, however, be kept over them and when the boring inside appears to have ceased, the tree should be cut down, chopped up, and the borers or their pupæ killed. This should be done carefully. If a number of young plants are cut out for borers, they should be stacked and burnt in one heap and not cut up at all. Every part should, however, be thoroughly burned. This remedy should be vigorously put into force when bad attacks similar to that of 1891 in Mysore have to be coped with.

---

[1] Since this note went to press, I have received from the Conservator of Forests, Mysore, a full-grown larva taken from a young sandal stem at the end of April of this year.

With regard to the *Stromatium* borer, we require to know a good deal more about its life history and above all the period at which it lays its eggs and how long they take to develop and hatch out the young grubs. If the beetles all issue at approximately the same time and lay their eggs on the bark within a period of a fortnight or so, it would be quite possible to make an attempt to check the pest in localities where it is seen to be bad by scraping down the bark of the trees with a blunt instrument. This would get rid of the eggs and save the tree. I recognise that there would be difficulty in doing this owing to the fact that the sandal usually grows in the midst of thorny scrub bushes. In the case of severe attacks, however, it would be quite feasible and the value of the tree would justify the expense. It is therefore of great importance that the periods of emergence of the beetle and egg-laying should be ascertained.

Trees infested are not so easily recognisable as in the case of the red borer, as the longicorn packs up its tunnel with wood excreta as it progresses forward and does not eject these. It will be remembered, however, that it also bores air-holes to the outside, and these can be recognised in the same way as those of the red borer. Further, we have seen that a tree infested in previous years is liable to be attacked again in a succeeding year. So it would be well to remove those in which air-holes and fresh exit-holes are present.

We require to know a good deal more about the Sirex borer before suggestions can be made as to the best means to combat it.

A study of the predaceous and parasitic insects which prey upon these larvæ should also prove most useful.

Points in the life histories requiring further observations.

I. The *Stromatium* borer—

1. Exactly where and when the beetles emerge and egg lay.
2. The period occupied in egg-laying. This period may coincide with that during which the beetles are to be found upon the wing.
3. The period passed in the egg stage.
4. The period spent by the grub boring in the wood. Is this less than a year?
5. Length of time passed in the pupal stage. Since I found grubs full fed and about to pupate in the first half of August, one of three things may occur:—
   (*a*) The pupal stage may be a short one, and the beetles may emerge in September or October and lay their eggs upon the bark at once, and the cold weather may be passed through in this stage, the grubs hatching

out in February or March, probably the former, or

(b) The insect may remain in the pupal stage throughout the cold weather, or

(c) The beetle may become fully developed before the cold weather, but remain in the pupal chamber throughout the cold weather, emerging about February.

6. Length of time spent in the beetle stage.

7. What predaceous and parasitic insects prey upon this borer?

II. The Red borer—

1. The length of time spent in the larval stage. Is it under or over a year? I found some apparently about half-grown larvæ in the first week in August. These were brought to me as the sandal pest.

2. The period of emergence of the moth. Mr. Green has stated that in Ceylon the moth does not appear to issue at any one particular period of the year.

A moth was bred out in the Indian Museum, Calcutta, on the 9th February.[1]

3. What predaceous and parasitic insects prey upon this borer?

III. The Wood wasp or Sirex borer.

Most of the questions asked under head I, for the *Stromatium* borer above, apply to this one. It is specially important to know when the eggs are laid, exactly how the larvæ bore, how long they spend in this stage, and when the mature insect emerges.

---

[1] These moths may lay the eggs which give rise to the caterpillars of which a specimen was recently received in the Museum. This was full-grown at the end of April. It would therefore appear probable that moths may be found towards the end of May or in June. The August larvæ found last year would then be those of a second generation hatching from eggs laid by the June months.

G. I. C. P. O.—No. 391 R. & A.—6-6-1903.—675.—W. S. DB.

A NOTE

ON

THE CASUARINA INSECT PESTS OF MADRAS,

BY

E. P. STEBBING, F.L.S., F.E.S.,
OFFICIATING SUPERINTENDENT, INDIAN MUSEUM.

For some years past reports have been received from officers in charge of the Casuarina Plantations created along the Eastern sea board of Madras that the trees, both in nurseries and in the plantations, suffered from the attacks of insect pests. At first these reports appeared to be conflicting, since by some it was stated that the roots were the part of the tree affected, whilst others described attacks to the bark and wood of the stems and branches. From the various grubs sent me on several occasions it soon became apparent that several different kinds of insects were responsible for the damage done, those most often sent being the caterpillar of a moth and the grubs of two different families of beetles. In spite of several attempts it was not, however, until the present year that perfect insects were procured thus enabling me to identify the pests.

The insect which would appear to be at present the best known and to cause the greatest damage is the caterpillar of one of the wood-boring families of moths, the insect being a species of *Arbela*. This has been reported from Chatrapur, Godavari, Cuddalore, Nellore (South Arcot), and North Arcot

Next in importance are some Longicorn beetle borers (*Stromatium sp*. and *Lamia*(?) *sp*.) which are injurious in North Arcot, Godavari, and Cuddalore.

Of some importance would appear to be the larvæ of the well-known rhinoceros beetle (*Oryctes rhinoceros*), the date-palm borer, whilst a bostrichid beetle (*Apate jesuita*) apparently riddles the wood in Nellore.

During a tour in the first-half of July (1903) I was able to pay my first visit to a Casuarina plantation. I inspected three plantations near Chatrapur in Ganjam and personally investigated, in company with Mr. C. E. C. Fischer, the attacks of the *Arbela* caterpillar. Two other insects were discovered to be doing damage to the tree. One, a Psychid caterpillar belonging to a species of *Clania* moth, not previously reported, was very fairly plentiful and was defoliating the trees; the other, a Fulgorid, was collected upon the green branches where it was engaged in sucking up their sap. Two coccids were also present, one a *Monophlebus*, the other an *Icerya* or closely allied genus. Of these nine insects, the first, the *Arbela* caterpillar, is the best known to officers in charge of plantations, and it will consequently be first dealt with in this note.

1. ARBELA TETRAONIS Moore.

The Casuarina Bark-eating Caterpillar.

References.—Moore, P. Z. S. 1879, p. 411, pl. 34, fig. 3; C. & S. No. 1605 Hmpsn., Faun. Br. Ind. Moths. I. 315, No. 675.

Classification.—Order, *Lepidoptera*. Sub-order, *Heterocera*. Family, *Arbelidæ*

This is the insect whose caterpillar forms the well-known winding covered-way galleries on the outside of the bark on the stem and branches of the trees.

Larva.—Head black with a few longish yellowish-white hairs on it. Following three segments, which each bear a pair of long legs, yellowish, this colour merging into pink on the third. These three segments are swollen and larger than the head. The following segments are flesh coloured except the last which is yellowish. Five pairs of short sucker legs are present, one pair each on the sixth to ninth and a pair on the last segment. A few long scattered whitish hairs on each of the segments. These nine segments are narrower than the first three and taper off slightly behind so that the twelfth segment has only about half the diameter of the fourth. Length one and a half inch. Width of thoracic segments $\frac{3}{16}$ inch.

Pupa.—Yellowish-brown, except in front where it is very dark-brown to black. Shining, circular in section and of uniform thickness throughout except for a slight swelling at the anterior (head) end which is furnished with two small spiny spikes. The wing covers are very short and reddish brown. The last five abdominal segments have transverse circular rows of fine teeth on them, the first three segments bearing a double row on each placed close together, the last two having but a single encircling girdle situated near the centre of the segment. The last segment is blunt at the end and furnished with small knobs and spines. Length 1 inch; breadth $\frac{3}{16}$ inch.

Moth.—♂. Fore wings greyish, thickly irrorated with dull brown spots which tend to form transverse bands; three large velvety brown patches, one centrally, placed a little below costa, a second near the base of wing, and the third (the largest) a little beyond it. Hind wings grey, irrorated with a few ashy-coloured patches. Head and thorax covered with long silky-brown hairs. Body greyish. Expanse of wings = $1\frac{3}{4}$″.

Life-History.—The appearance of the moth on the wing is evidently variable. In the Godavari district moths have been reported as issuing during March, whereas in Ganjam a specimen was bred out by Mr. C. E. C. Fischer as late as the 3rd July. In Cuddalore, on the other hand, nearly mature pupæ were taken on the 1st June. From these data it appears that the moth is to be found on the wing between March and the beginning of July. I could find none at Chatrapur towards the middle of this latter month (in 1903) though numbers of the year's empty pupal cases were visible upon the trees. It is probable that the moths lay eggs at once since the members of this family have no mouth and take no food in this stage of their existence. The eggs have not yet been found, but they are evidently laid upon the bark of the trees. We do not know as yet when they hatch out. In Chatrapur, which gets the South-West Monsoon, it would probably not be until September or October, but further south down the coast where the rain comes in October or November, they may hatch out earlier. The present recorded months in which caterpillars have been obtained are January and March in Chatrapur (with pupa in June and a moth on 3rd July); December in North Arcot (with pupa in June); the same month in Godavari (with pupa and moth in March); full grown caterpillars and almost mature pupæ on the 1st June in Cuddalore, and what appear to be nearly mature caterpillars in June in Nellore. We have yet to ascertain the length of time passed by the caterpillar in the larval stage. It spends most of this stage of its existence feeding upon the bark which it eats off the tree in patches which are at times several inches wide. It does not move about the bark of the tree in the open but constructs for itself a kind of covered way, resembling a glorified termite (white ant) gallery, consisting of particles of its excrement bound together with a kind of close woven felted silk. Externally the appearance is simply that of a mass of excrementous particles. These covered ways curl round and up or down the tree and are very conspicuous, being about ⅓ to ½ inch in breadth and from 9 inches to as much as 18 inches in length. They are reddish brown to, in parts, black in colour and form raised galleries on the surface of the stem. Sometimes the gallery completely encircles the stem, the tree being then ringed; at others it is taken in a spiral manner up or down the tree. At times two or more covered ways join together, but they are more usually, except in very badly infested trees, separate. The bark beneath the gallery is always eaten, either only the upper green living tissues being consumed or the whole being removed down to the sapwood. Occasionally, as mentioned above, the bark is seen to be eaten off the tree in irregular-shaped patches on either side of the covered way. This may be done by the young larvæ living and feeding gregariously together before they construct covered ways for themselves, or the caterpillar may leave the covered way at night and eat off the bark in its vicinity. These galleries or covered ways have a more or less uniform width throughout their entire length, and from their appearance the larva would seem to add to them at the sides so that the internal chamber remains uniform in width throughout its length. When full fed the larva bores straight into the wood of the tree, generally retiring to the middle of its covered way before commencing to bore in. From the observations I have been able to make on attacked trees, I have little doubt that the caterpillar only enters the wood to pupate and does all its feeding upon the bark. The tunnel in the wood is always straight and does not ramify as it would do if the grub were feeding in the wood. There is generally a raised lump on the covered way, the result of the addition of the wood excrement thrown out, marking the place where the caterpillar has gone into the wood. When it has reached or nearly reached the centre it enlarges its gallery and changes to the pupal state. We do not yet know the time spent in this latter stage. In my description of the pupa I have shown that it is furnished with circular rows of spines and by means of these, when the moth is ready to emerge, it wriggles and forces itself along the tunnel and pushes itself through the mass of excrement which forms the covered way, from which it remains protruding about a quarter of its length. After the moth has left the pupal case, the empty skin of the latter may be seen projecting from the covered way. Therefore when this latter is visible, it may be taken that the insect which formed the particular covered way under inspection has left it.

Results of attack.—This insect appears to be fairly wide-spread throughout the Casuarina plantations, and it has been reported to commit considerable damage in some. Information is still far from perfect, but damage is undoubtedly committed in Ganjam, North Arcot, Godaveri, Cuddalore, and Nellore.

In feeding upon the bark the insect in its younger stages only consumes the more tender and greener portions of the outer thin bark, but as it grows older it eats right down to the sapwood and even into it, either in a continuous ring or in small irregular patches. Thus the trees are often seen to have holes and pits through the bark reaching to the wood beneath. These "weather" and at times coalesce. In the plantations I visited I noticed that some trees were much more severely infested than others and in these the action of the caterpillars had almost ringed the trees. There can be little doubt that when thus badly attacked the trees die. Both young and old trees are equally subject to attack and the larva feeds equally upon the thicker bark at the base of the tree and the thinner near the top. The covered ways are perhaps shorter in the lower portion of the tree.

Towards the end of 1900 the District Forest Officer of North Arcot reported that these caterpillars had nearly ruined the Anunundi Plantation. The plantations appear to be infested in patches. In the Ogastinowgam Plantation near Chatrapur in Ganjam where the insect would seem to have only recently appeared, the attack was confined to one patch of the area, the rest being entirely free. A private plantation, about a couple of miles away, was unattacked, whereas the Chatrapur Plantation, about 4 miles from the Ogastinowgam one and a mile or so from the private one, was badly infested in parts. The attack doubtless spreads outwards from these infested areas and in course of time infects the whole plantation.

Summing up therefore we see that the damage is done entirely by the caterpillar and that, as far as present observations have shown, this latter feeds entirely on the bark, only entering the wood of the tree to change to the chrysalis state.

Protection.—My inspection at Chatrapur enabled me to suggest a remedy to Mr. Fischer. We have seen that larvæ are to be found between December and June, and that during this period or portions of it they are to be found in covered ways on the bark of the trees, only leaving these to bore down into the wood to change into the chrysalis state. I would suggest that the larvæ be searched for and killed during the period they are feeding upon the trees. The covered ways are very visible and each fresh one should be carefully pulled to pieces and the larva taken out and killed. Boys in charge of a watcher could be put on for this purpose. The watcher would first count the number of covered ways upon a tree and then send up the boy to take out the caterpillars, and the number of these latter should tally with the number of covered ways counted and the boy be paid accordingly. The covered ways should be pulled off the bark only after the caterpillar has been taken out. In the cases where they coalesce, the operation should be done carefully, so as to make certain of taking all the caterpillars. If any of these latter escape, they will soon construct a fresh covered way and continue their depredations. A kerosene tin with some kerosene mixed with water at the bottom will form a convenient receptacle in which to throw the caterpillars. This work should be started as soon as the new covered ways are seen to be making their appearance on the tree, and if done carefully and systematically throughout the plantations, I see no reason why it should not be possible to stamp out this pest or reduce its numbers to such proportions as will no longer endanger the plantations.

Points in the life-history requiring further observation.

1. Where the eggs are laid and how? Are they laid singly or in patches? How many are laid by one moth?
2. When do the caterpillars first hatch out from the eggs? Does this period vary on different parts of the coast?
3. When hatched out, do the young caterpillars live for a time gregariously on the bark before separating and living alone in the covered ways, or are these covered ways constructed at once? I am of opinion that the former is probably the case.

4. Length of time spent in the larval state.
5. Length of time spent in the pupal state.
6. The exact times of appearance of the moths in the different plantations.

The following longicorn wood-borers have been reported as boring into the wood of the stem and roots of the tree.

2. STROMATIUM sp. prox. BARBATUM.

Reference.—Provisionally determined as *Stromatium* sp. prox. *barbatum*.
Classification.—Order, *Coleoptera*. Family, *Cerambycidæ*.

This is the beetle whose whitish grubs have been reported as committing, in company with the *Arbela*, serious damage to the plantations in North Arcot.

Beetle.—♀. A somewhat elongate, narrow, lightly-built beetle of usual longicorn shape, dark brown with a purplish tinge often merging into a lighter shade towards the tips of the elytra. Antennæ and legs yellow. Former not as long as body. No sculpture on thorax or elytra; both pitted and covered with a fine yellow pubescence. Abdomen yellow beneath. Length seven-eighths inch (varies—may be smaller).

♂.—Smaller than ♀. Antennæ longer than body. Body narrower and slimmer than in ♀; elytra more lightly coloured on upper half.

Length five-eighths inch. Greatly resembles *Stromatium barbatum*, the Kulsi Teak borer.

Life-History—Grubs of this insect have been found in the trees in December, boring and feeding in the cambium layer and sapwood of the tree. In June beetles, said to be the adults of these larvæ, were obtained from the trees. We do not yet know how long these grubs spend feeding in the tree in this stage. It is, however, almost certainly the greater part of a year and may be longer. The pupal stage is probably short.

The damage is done by the grubs destroying the bast layer of thē tree. When they are numerous the tree is practically ringed beneath the bark and dies.

Results of attack.—In December 1900 the Divisional Forest Officer, Mr. C. D. Thornton, reported that grubs, identified as longicorn ones, "had nearly ruined the Casuarina trees in the Anunundi Plantation .... The grub is found in the cambium layer, under the bark of old trees, on which it feeds."

At my request for more specimens the beetles here described were obtained and sent me in June (1903), by the District Forest Officer, North Arcot. At present we have no further information about this insect. This insect has a strong resemblance to the Kulsi Teak Borer, *S. barbatum* which riddles young teak in Assam.[1]

3. LAMIA (?) sp.

Reference.—Provisionally determined as *Lamia* (?) *sp.*

Classification.—Order, *Coleoptera.* Family, *Cerambycidæ.*

This is the beetle whose thick white grubs have been reported as boring into the wood of the roots of the tree at Cuddalore.

Larva.—A thick whitish-yellow grub with blackish-brown head and black mouth parts (mandibles) followed by a largely developed segment which is slightly darker yellow than the following ones. These latter taper slightly to the tenth which is half the size of the prothoracic segment. Last two segments smaller, ending in a blunt point. Length $1\frac{1}{10}$th inches. Breadth across the big segment behind the head (prothoracic segment) $\frac{5}{16}$th inch.

Beetle.—♀. Black, moderately shining. Abdomen very dark red beneath. A short thick beetle with a vertical head. Prothorax sculptured and spined above and at sides, widest in middle. Joined on to the elytra (wing covers) by a short neck. Elytra wider than hind portion of prothorax, parallel to near apex where the outer edges turn inwards, the elytra thus terminating in a blunt point. Elytra entirely cover the base of body. They are corrugated and spined at their basal portions and pitted strongly for the rest of their length.

---

[1] *Vide* Author's Inj. Ins. Ind. For. pp. 73-76.

First joint of antenna is swollen and well marked. Length thirteen-sixteenths inch.

Life-History.—We know little at present about the life-history of this insect. The grubs attack and live in the cambium layer and sapwood of the roots of the tree and are said never to be found in the stem. Grubs were found in this position on the 1st June and one mature beetle was obtained from the Talaukoda Plantations near Cuddalore. We have no records as to the amount of damage this beetle commits. Since it lives in the cambium layer of the roots it is likely to prove a very serious pest when present in any numbers in a plantation.

Protection and remedies.—Until more is known about the life-histories of these two beetles, it is difficult to prescribe remedies against them. Badly infested trees should, however, be cut out whilst the insect is still in the grub stage and the bark stripped off so as to expose the cambium and sapwood of the tree to the sun. In this position the grubs and pupæ will soon be killed off and will never reach the beetle stage. This must be done whilst the insect is still in its larval stage. If left too late the beetles will begin to emerge and many will escape and lay eggs in adjacent trees.

The same applies to trees whose roots are attacked. The earth should be removed round the larger of these latter, since it is in these that the grubs will be found, and the bark be then stripped off.

Points in the life-histories requiring further observation.

1. Where the eggs are laid by the beetles.
2. When do the young larvæ hatch out ?
3. Length of time spent by the larvæ feeding in the cambium layer and sapwood.
4. Length of time spent in the pupa stage.
5. When does the beetle emerge ? Is it only towards the end of May and beginning of June or do beetles appear at other periods in the year ?

6. Does the *Lamia* sp. grub also attack the stem of the tree?

4. ORYCTES RHINOCEROS Linn.

The Rhinoceros or Date-palm beetle.

Reference.—Linn. Syst. Nat., ed 10, 1758, 346; ed. 12, 1767, 544.

Classification.—Order, *Coleoptera*. Family, *Scarabaeidæ*.

This is the common date and cocoanut palm-borer of Southern India. Its grubs have been reported as feeding upon the roots of young seedlings and trees.

Larva.—A large stout curved grub. Head flat, purplish-brown. Mandibles brownish to black, large and stout; antennæ 5-jointed, basal joint enlarged. On first three segments behind head are three pairs of light-brown, stout, long, 3-jointed legs. Body yellowish-white, last two segments blackish. The head is smaller in transverse diameter than the rest of the body. Body is very thick, corrugated, curved, and swollen out so as to be almost bag-shaped behind. On each side of the third to tenth segments is a large dark-brown spiracle. Body above and below is thickly covered with brown spiky hairs, except on last segment where they are small and scattered.

Length, taken round curve, 4 inches. Breadth ¾ inch.

Beetle.—Black, shining, massive, and large with a prominent horn, which curves backwards, on its head from which it gets its name of rhinoceros beetle. The elytra are very convex above, the insect being flat beneath. Shanks (tibiæ) of legs armed with spikes, the front ones having each three spikes on their outer edges. A large roughly heart-shaped depression on front portion of thorax. A series of broad striæ and punctures on elytra. Dark rufous beneath with hair of same colour in parts. The beetle is easily recognisable by its form, by its antennæ ending in a series of terminal plates, by its spiked tibiæ and 5-jointed tarsi and great size. Length 1¾ inches. Breadth across elytra ¾ths inch.

Life-History.—This beetle is to be found on the wing during the greater part of the year. It may hibernate, either as a larva or pupa or perhaps beetle, from November to about March. I have obtained living beetles towards the end of March and in the beginning of November. The adult insect spends some time in this state and apparently can do with little food in this stage of its existence as I have kept beetles for over two weeks without food of any kind.

The insect appears to lay its eggs in dead and decaying palm trees or in masses of palm and other refuse situated in or near palm topes. The grubs on hatching out feed in the decaying trees or in adjacent refuse heaps, and evidently also consume the roots of seedling plants. Mr. C. B. Dawson, District Forest Officer, Kistna, reports that the large grubs feed upon young Casuarina seedlings being attracted to them owing to the moisture in the sand in which they are planted. These young seedlings are watered whilst in the nurseries and thus the moist layer of sand filled with the young roots would quickly attract grubs of this kind. It is, I think, improbable that the beetles lay their eggs in the nurseries. The young larvæ on hatching out would require something softer and of a more decaying nature as food at first and would only attack rootlets when their mandibles were stronger and more fully developed.

We do not yet know how long the larva spends in this stage of its existence. It will certainly be several months, since the full-grown grub is of very large size, and it may be considerably over a year. This latter would seem the most probable (unless the insect has several generations in the year which is unlikely) as from the fact that beetles are to be found almost, if not quite, continuously from March to November, it is evident that the generations overlap, *i.e.*, that at any period it is possible to find eggs, grubs, pupæ, and beetles. This of course adds immensely to the insect's capabilities of doing damage. The time spent in the egg and pupal stages is still unknown.

Result of attacks.—Young seedlings attacked by the grubs at first show signs of wilting and then die off. Only seedlings and very young saplings are attacked.

Protection and remedies.—The following are remedies which have been already recommended to Mr. Dawson for trial:—

1. Employ boys or women to carefully remove the soil round seedlings which are seen to be wilting and take out and kill the fat grubs found at the roots. This should be done when seedlings are seen to be dying off in any considerable number even at the expense of killing adjacent young plants by thus disturbing their root system. The grubs will go from one plant to another, and one grub may thus destroy a number of seedlings.

2. If feasible, a simple and effective plan is to flood the plantation for a few hours so as to drown all the grubs in the soil. Those that come up to the surface should be collected and killed.

3. Remove all diseased and dead and decaying date and cocoanut palms in the vicinity of nurseries and young plantations. Also, and this is an important point, all refuse heaps of rotting vegetation, etc. If, for the preparation of the nursery, special soil pits of manure, litter, and leaves are prepared, they should be carefully inspected for these grubs as the beetles will be certain to lay in such a place. I came across an instance of this in a Calcutta garden quite recently (end of June). The heap of rich soil and humus used for manuring the flower beds contained numbers of the larvæ of this insect which were spreading from here into the beds of young seedlings whose roots they were devouring. There were palm trees close by.

Points in the life-history requiring further observation.

1. Length of time spent in the grub stage.
2. Length of time spent in the pupal stage.
3. Length of time spent in the beetle stage.

5 APATE JESUITA Fabr.

References.—Lesne. Ent. Soc. F. Vols. LXV, LXVI.
Bostrichus jesuita. Steb. Inj. Ins. Ind. For. p. 42.

Classification.—Order, *Coleoptera.* Family, *Bostrichidæ.*

This insect has been reported as tunnelling into Casuarina in Nellore.

Beetle.—Black with parallel sides and a uniform breadth throughout of three-sixteenths inch, perhaps a little less anteriorly and a little more posteriorly. Body more than twice length of prothorax; latter rounded and pitted above; elytra with longitudinal ridges running down their dorsal surfaces with punctures between; elytra deflexed at their apices. Abdomen red beneath. Legs black, short. Antennæ with a club. Length $\frac{11}{16}$ths inch.

Life-History.—This beetle is a wood-borer and bores into the wood of the tree for egg-laying purposes.

It was reported as boring into the trees in June, and therefore the eggs of one of the generations of the year are laid in that month. Nothing further appears to be known about its life-history.

In all probability the beetle does not attack the tree until it is either felled or has from some cause become sickly. The damage is done to the timber, and if the insect is numerous and the wood is required for planks, it would probably cause a considerable loss.

The length of time spent in the larval and pupal stages and the number of generations in the year have yet to be ascertained.

The following pests were obtained by the writer during a tour made to Waltair and Chatrapur (Ganjam) in the first-half of July 1903.

6. CLANIA sp. prox. CRAMERI.

The Casuarina Bag-Worm.

Reference.—Provisionally named *Clania* sp. prox. *crameri.*

Classification.—Order, *Lepidoptera.* Sub-Order, *Heterocera.* Family, *Psychidæ.*

I obtained the caterpillar (which lives in a small case made of leaf-bearing twigs) fairly plentifully in Waltair and Chatrapur.

Larva.—Full grown. The portion of the caterpillar seen outside the case when it is feeding or walking has a mottled appearance. It is shining, hairless, yellow to yellowish-white with black spots and markings. Head large and prominent. Front legs black and yellow, long and stout. The front segments of the body are fairly large and thick, those behind (seen when the grub is taken out of the case) smaller. The case is formed of small pieces of the needle-like leaves placed side by side so as to form a cylindrical bag open at both ends. The head of the case is lined with a greyish thick silken bag which protrudes. It can be closed by the larva when the latter retires into the case. The case inside is lined with a shining layer of white silk.

Just after leaving the egg.—The little grub is very small and has no case. The head is black, shining, large. Mouth parts brown. The segment immediately following black with a white edging. The next two segments yellow with narrow black to brown transverse bands dorsally, this band being divided in the middle on the third segment. These three segments are each furnished with a pair of legs. Rest of segments orange yellow and are held curved up over the back. All the abdominal legs are present but are not functional and are never placed upon the ground, the minute caterpillar walking on the front ones, these being well developed and large even at this stage. The segments are covered with large scattered yellowish hairs. There is a patch of brown dorsally on the last segment. Length = $\frac{1}{16}$th inch. The first case is acquired about 20 hours after leaving the egg and consists of a tiny conical roll formed of a fine flake of epidermis from the young shoot of the tree.

Pupa.—The pupa is reddish black anteriorly, the abdominal segments being a red brown and nine in number. The anterior portion of pupa is thickened, the body tapering to more or less of a point. The wing cases are short. A row of spiny protuberances run down the back of the pupa: by means of these it is enabled to pull itself forward and so escape from the bag case of the larva. Length nine-sixteenths inch.

Moth.—♂. Smallish, greyish brown with bipectinate antennæ in the male. Wings and body light brown. Fore wing with some of veins streaked with black. Hind wing greyer, the veins being streaked with brown. Thorax and abdomen covered with long hair, the under surface of the latter being ashy in colour with a narrow central dirty-white band. Expanse of wings one inch.

♀.—The female never leaves the case. She is wingless and canary-yellow in colour consisting of a simple sac-like body resembling a miniature Queen "white ant". Her body swells up after fertilization and shows five distinct segments. At the end of the anterior one is a small orange-coloured process resembling in shape a cock's comb with four divisions to the crest. Below this latter are two short brown processes thickened out and ridged at base. Beneath this on the under-side is a triangular-shaped black patch reaching down to the end of the first segment, the apex of the triangle being at the posterior end. The posterior segment ends in a bifurcated copulatory organ. There is no trace of wings or legs. Body tapers slightly to each end. Length $\frac{3}{4}$th inch. Width across thickest part $\frac{3}{16}$ths inch.

Life-History.—The writer noticed the larva of this insect defoliating Casuarina trees in Waltair at the beginning of July 1903.

On visiting the plantations at Chatrapur (Ganjam) he found the insect to be very fairly numerous. It escapes general notice as all that is usually apparent to the observer is the greyish case hanging to the branches of the trees. This, as the caterpillar the case contains is not seen actively feeding, is not associated with any defoliation the trees may have undergone. Some of the larvæ found near the middle of the month were full grown, others had pupated, whilst one moth issued in the box they were kept in on the 13th. Others were bred out in the Museum on the 18th, 25th; August 4th, 12th, 13th, 14th, 19th, 20th and 24th respectively. The pupal stage would appear to last from 10 to 14 days, but further observations are required on this point. Female moths were obtained at the Museum through August.

Before pupating the caterpillar attaches its case to the branch or twig of the tree and then closes up the silken bag-like mouth. It then turns round in the case so as to hang head downwards and becomes canary-yellow in colour losing entirely its mottled appearance: its head and first segments also shrink greatly in size. When the male moth is ready to emerge, the pupa forces itself downwards through what was formerly the bottom or posterior part of the case until it projects about two-thirds of its length. The moth then bursts the upper end of the pupal case and emerges.

The female moth remains in the case and the male pairs with her in this position. A very large number of eggs are laid. From countings made of young larvæ which issued in the Museum I find the number of these latter issuing from eggs laid within the bag by one female to be between 550 and 600. The eggs hatch within a week of laying. The young larvæ on issuing from the egg are naked, *i.e.*, they have no bag. They are very active on leaving the old case and spread out over the tree walking with great rapidity. In this defenceless state they must be very subject to attacks of all kinds of predacious foes and also be liable to be drowned off by heavy rain storms. Within 20 hours they make their first covering or bag, this being formed of a small piece of the epidermis of the bark of a twig. This is added to as they grow larger. Larvæ, a week old, had a double coil of this epidermis forming their case. The first larvæ issued in the Museum cages on the 6th August: others on the fifteenth and twentieth, these all being those of probably the second generation of the year.

The larva is a heavy feeder and eats the needle-like leaves of the Casuarina from top downwards to the base, or it may bite through the needle (leaf) half-way down, the upper portion falling to the ground, whilst it consumes the lower, a most wasteful method of feeding.

Results of attack.—This insect when numerous would be capable of entirely defoliating a plantation and consequently its life-history requires careful study. Unless the defoliation is very heavy, the insects' attacks will probably remain unnoticed and since the larva is very quickly alarmed (when it immediately retires within its case), even if the defoliation is noticed, it would not ordinarily be placed to the credit of the apparently small dead bundles of sticks hanging from the branches. From the large number of eggs laid by the females, which are more abundant than the males as can be readily distinguished by the fact that their cases are larger, it is evident that in a dry, warm, favourable season the mortality amongst the young larvæ would be much less, and this would undoubtedly lead to very severe, if not total, defoliation in the plantations. It is not improbable that the death of trees attacked by the wood-boring *Arbela* caterpillar described in this note is accelerated by defoliation due to the larvæ of this *Psychid*, and it is of importance that its life-history should be worked out, so that we may know how many generations it passes through in the year, *i.e.*, how many times in the year the trees run the danger of being defoliated.

Protection and remedies.—Undoubtedly the best method of reducing the attacks of this pest is by the collection of the larval cases. Owing to the thin light foliage of the tree these cases, once they have been pointed out as the source of damage, are easily recognisable and very easily seen in the plantations. Their careful collection in years of serious infestation would well repay the expenditure incurred and would practically stamp out the pest. The periods at which this collection should be undertaken depend upon the number of generations passed through in the year. For the June-July generations of larvæ the best time would appear to be the latter half of June.

Points in the life-history requiring further observation.

1. When the eggs of the first generation, *i.e.*, that producing the June-July caterpillars, are laid.
2. How long the eggs of the first generation take to hatch after they have been laid.
3. Time spent in the larval stage.
4. The number of generations in the year. This is extremely important as it is necessary to know how many times in the year the trees may be subject to this defoliation. Are there more than two?
5. In which stage are the cold weather months passed through and where? This is very important as if cases containing any stage of the insect—egg, larval or pupal—are to be found upon the trees at this period, this would be the best time to collect and destroy the cases.

7. FULGORID.

Classification.—Order, *Hemiptera.* Family, *Fulgoridæ.*

The writer discovered this insect, which is a small black shining "hopper", clustered on the green branches of the tree at the beginning of July. It was found fairly plentifully both at Waltair and Chatrapur (Ganjam). The insect was in all stages of development from minute little green specks to larger shining black insects $\frac{1}{16}$th inch in length but still wingless, to full fledged winged insects of a greyish black appearance and $\frac{1}{3}$rd inch in length. The insects feed entirely by suction, and from youngest to oldest had their beaks, of which their mouth parts consist, embedded in the bark of the branches from which they were engaged in sucking out the sap.

At present nothing more appears to be known about this pest, which has not previously been reported. Observations are required as to when it first makes its appearance in the year and as to how long it is to be found in this manner in all stages of its life-history upon the trees. There is no doubt that it might develop into a serious pest in nurseries and young plantations and owing to its small size and inconspicuousness it would probably escape notice for some time.

8. ICERYA ? sp.

Classification.—Order, *Hemiptera*. Family, *Coccidæ*.

This note would not be complete without a short mention of another insect the writer discovered on the trees in Waltair and Chatrapur. This is a member of the family Coccidæ, which contains so many pests to trees and plants. The insect is white, and in its older stages has a mass of white fluffy substance on its dorsal posterior surface rendering it fairly conspicuous upon the branches upon which it lives by sucking out the sap.

9. MONOPHLEBUS sp.

Classification.—Order, *Hemiptera*. Family, *Coccidæ*.

The genus *Monophlebus* may be said to be the forest genus of Coccids since all the species at present known confine their attacks to woody plants. Both at Waltair, at Chatrapur, and at the Botanical Gardens, Calcutta, a species of *Monophlebus* has been obtained on the Casuarina. It feeds by sucking out the sap of the green shoots going down to the more woody branches as it gets older. It was quite small at the beginning of July but had grown considerably by the third week in August. Only the female has been as yet secured, so it is impossible to say what the species is. The male will be a small two-winged black fly. The female is an oval white fleshy scale, convex above and flat beneath, with three pairs of short black legs and a pair of black antennæ.

G. I. C. P O.—No. 1100 R. & A.—1-9-1903.—650.—W. S. L'R.

A
DEODAR DISEASE
IN
JAUNSAR.

BY

E J. BUTLER, M.B.,

CRYPTOGAMIC BOTANIST TO THE GOVERNMENT OF INDIA

In June 1902, I was sent by Mr. J. W. Oliver, I.F.S., specimens of a nearly dead young deodar from the Jaunsar forests, showing the stump with a number of roots attached, and a section from the middle of the stem. Mr. Oliver wrote that the trees were dying from what appeared to be a definite disease. His description was as follows. "One young tree generally dies first and then the disease spreads to other trees near it. It mostly attacks trees six to fifteen feet high. The first symptom is an exudation of resin at different points along the stem, then the needles turn yellow and fall off. It seems to take about two years to die completely." With the specimens were sent some sporophores of a fungus found by Mr. Oliver on the stem of a young deodar and said by him to be present on numbers of apparently healthy trees, as well as on some which showed the resin flux which is the first symptom of the disease. The fungus was probably a species of *Stereum*, but there was nothing to lead one to suppose that it was connected with the disease.

However the stump sent showed definite signs of having been killed by a parasitic fungus. Even in the absence of sporophores and without any experiments to demonstrate the cause of death, it is not impossible to decide, from the structure of the diseased wood and from microscopic examination, that death has resulted from the action of a parasitic fungus, especially in the case of coniferous trees. The rot produced by the action of parasitic fungi before the death of the tree is, as Hartig has shown, characteristic of the particular fungus at work, in many cases, and different from rotting due to physiological causes and from that which occurs *post-mortem*. The principal diagnostic features are the presence of mycelial strands and sheets visible to the naked eye, as in trees attacked by *Polyporus sulphureus;* of peculiar white spots or streaks in the wood, as in *Stereum frustulosum* (*Telephora perdix*) and *Fomes annosus;* and of certain definite tissue changes visible under the microscope. Even where the parasite is one and the same, however, the symptoms produced by it vary according to the host plant. Thus *Trametes pini* produces changes which are quite different in the larch from those which the same fungus produces in the spruce. Unfortunately the forest diseases of India have not been investigated in the way that those of Europe have and the symptoms of fungus diseases of indigenous forest trees are not known. It is, therefore, not possible in the absence of fully developed sporophores to do more than state that the tree has been attacked before death by a parasitic fungus.

Further specimens received this year from the same district from Mr. B. Coventry, I.F.S., filled up the gap. They bore some particularly fine sporophores of *Fomes annosus* Fries, a fungus better known perhaps by Hartig's name of *Trametes radiciperda.* This fungus had been suspected by Mr. Oliver and myself last year, and Mr. Gamble in his "Manual of Indian Timbers." mentions it as one of the fungoid pests of the deodar.

Mr. Coventry's specimens corresponded exactly in the structure of the wood and the arrangement of the fungus mycelium, to those examined by me last year, and the mycelium could be traced without any difficulty to the fruiting organ. There can be little doubt, therefore, bearing in mind the virulent parasitism of this fungus, considered by Hartig to be the most dangerous enemy of coniferous trees in Northern Europe, that it is the active agent in the disease in question. A curious fact in its biology is that it is mentioned by von Schrenk in quite a secondary place amongst the coniferous diseases of the new England States.

Fomes annosus, of which a good account will be found in Hartig's works and in Ward's "Timber and some of its Diseases," attacks *Pinus, Picea, Abies, Juniperus, Thuja*, and also the beech and some other dicotyledonous trees. Its destructive effects are most marked on the conifers. The form on *Cedrus Deodara* only will be here described and will be found to differ somewhat from the others.

Young trees are particularly mentioned by both Mr. Oliver and Mr. Coventry as suffering most, though in the pines in Europe trees of all ages are attacked. The underground portion is probably the first infected. Mr. Oliver's account of the centrifugal spread points to this, and it is in harmony with what has been observed elsewhere. The lateral roots become rotten, and are marked by characteristic white sheets and bands of mycelium between and under the bark scales. The bark cracks down to the cambium and may be lifted off in crusts separated from each other by sheets of mycelium. These sheets are delicate, but here and there they form thicker layers. In the European conifers small sporophores are derived from cushions of mycelium similarly developed and form the most characteristic peculiarity of the fungus. These underground sporophores were not found on any of the specimens examined by me. The latter were, however, few, and it is quite possible that a careful search amongst the roots of dead trees would bring them to light. Aggregations of mycelium representing, perhaps, the beginning of the formation of fruiting organs were found here and there on the bark of the roots. The root destruction is very complete. In one of Mr. Coventry's trees a single lateral root alone was found alive, which he concludes must have provided the whole root-nourishment of the tree. Of course a tree in this condition will not stand long. The first storm is pretty certain to bring it down.

It is probable that the root destruction may proceed far before the above-ground parts show the resin flux and fading of the needles noticed by Mr. Oliver.

The roots are not the only part affected. Broad bands of mycelium invade the collar, entering, so far as could be seen, in most cases, from lateral roots. These bands show an ascending growth, forcing their way along the cambial layer in feathery strands of delicate snow-white tissue (fig. 2). Since these destroy the cambium completely round the stump their effects must be disastrous, but in addition the wood is directly attacked and destroyed by fine hyphæ extending through its elements. In the roots the invasion of the wood is marked by violet brown streaks, which on section are seen to be due to browning of the wood parenchyma. Though under the microscope a commencement of similar browning of the cells of the wood parenchyma of the collar can be seen, their effect was not visible to the naked eye in any of the stems examined. Hence the red rot produced by this fungus in pine and spruce wood was not evident in deodar. Except for the white areas to be mentioned presently, no other discolouration was observed in the diseased wood

The density of the wood is greatly diminished. Floated in water only about one-third of a block, which was advanced enough in the disease to show distinct white areas, was submerged; whereas in a block of fresh healthy deodar the upper surface was nearly flush with the water; Its toughness is also somewhat decreased, and splinters can be torn off without much effort. Its value as a timber must therefore be already considerably lessened before the disease shows itself fully.

One of the most characteristic features of the disease is the production in the wood of numerous white areas, usually somewhat elongated in the direction of the axis of the stem (fig. 3). At a later stage they become excavated into holes or cracks, but this is often obscured by the presence of a fringe of loose white fibres. The latter result from the action of the fungus in dissolving out the lignin elements from the wood cells, leaving only pure cellulose, and in destroying the middle lamellæ between adjacent cells so as to isolate them from the rest of the tissue.

The hyphæ which penetrate the wood are extremely fine. Their effects on the tissues as disclosed by the microscope are as follows. The cells of the wood parenchyma and those of the medullary rays become browned. This action is most marked in the roots, which show violet-brown streaks on section. The interior of the cell becomes filled with a brown cloudy substance, probably resulting from the decomposition of the protoplasm since cells poor in protoplasm are not discoloured. Starch is unaltered till a late stage and may be seen immersed in the brown substance (fig. 4 a). In the stem, where the brown discolouration of the starch-bearing cells is much less visible, they may be seen, still loaded with starch, lying free amongst the fringe of isolated fibres and tracheæ which border the white areas. In and through all the elements scattered fine hyaline hyphæ pass, often so slender as to be made out with difficulty. Brown ones such as occur in the same disease in other conifers were not found. These bore their way freely from cell to cell, dissolving out sharply defined holes in the walls for their passage, which persist after the fungus filaments by which they were produced have themselves disappeared (fig. 4). In some places the wall may be seen to be perforated like a sieve by these holes.

The wood fibres and tracheæ are altered in a remarkable manner, apparently resulting from the selective action of ferments produced by the fungus on certain elements of the walls (fig. 4). The lignin elements (hadromal of Czapek) are removed. Pectose is probably also early dissolved. The white areas of diseased wood are formed of dissociated cells composed of practically pure cellulose and giving the blue reaction of the latter with iodine and sulphuric acid. The walls are marked with fine spiral striation, superposed walls giving a network from the crossing of the two spirals. The middle lamella, which consists largely of pectose, is dissolved so that the individual elements fall apart; they are eventually decomposed leaving small hollows in the wood, lined with a white fluff of loose fibres. Before dissolution the wall cracks in large spiral cracks which, following the course of the striation mentioned above, are apparently always in a right ascending spiral (fig. 4 *c*). Longitudinal cracking does not occur. The spiral cracks are often seen, as an optical effect, crossing other cracks, chiefly, I think, of the opposite wall of the cell, in flattered elements, so as to produce an appearance of crossed cracks exactly like that figured by Hartig in wood attacked by *Polyporus Schweinitzii*. It is easy to see that these cracks owe their direction to the fine spiral streaking made evident by the lignin extraction and which must represent a fine spiral thickening of the lamellæ of the wall, the streaks being the lines where the edges of two lamellæ are approximated. Rupturing takes place naturally along these lines of least resistance.

The fruiting organ (sporophore) (fig. 1) arises from cushions of mycelium which force their way to the surface at the lower part of the trunk. These first appear as small rounded chocolate-brown nodules, which increase in number and run together forming a brown incrustation on the stem, broken by numerous irregular ledges and tubercles. On the under surfaces of some of these a white hymenial layer is developed. In the specimen figured in fig. 1, many small porous areas were found on the brown incrustation (*a a*) which composed the greater part of the sporophore. On this portion, however, all were old and of the same brown colour as the rest, with the pores partially filled up by a new hyphal growth from below, except one small white one apparently still active. At the time when it was obtained the main active portions of the spore-bearing organ were developed on a series of imbricated bracket-like protrusions (*b b*) from the upper part of the organ, where the trunk had curved away from the plane of the incrustation. These brackets measured 2½ to 4 inches in breadth and projected about 1½ to 2 inches from the stem.

The hymenial layer is white and covers the undersurface of the bracket partially with a thin white layer, leaving a band of brown sterile tissue round the edges.

The pores are irregularly rounded or elongated, and are in stratified layers, the new season's layer being alone active and distinct, while those of previous seasons are filled up by a new growth of hyphæ from the substance of the sporophore. The recent layer is thin and shows a tendency to turn rusty-brown as age advances. The sterile margin is variously ridged in more or less concentric ridges, marking possibly annual periods of growth, and is dotted with irregular tubercles. The upper surface of the bracket is also brown, roughened, tuberculate and concentrically ridged.

The most striking divergence presented by this fungus when compared with the form on other conifers and in other countries is the possession of *rhizomorphs*. One of these is figured in fig. 5. *Rhizomorphs* are well known in *Agaricus melleus* and *Dematophora necatrix*, two widely differed fungi, but have not been describod in *Fomes annosus*. They are essentially tough bands of fungus-hyphæ converted into definite organs of propagation by a special arrangement of the fibres and by a power of apical growth. To the naked eye the deodar fungus *rhizomorphs* are not unlike the ordinary finer roots of the tree but much blacker and of a different consistence. They are branched, cylindrical or flattened bodies, of uneven diameter not diminishing regularly as roots do, composed of an outer, black, somewhat brittle cortex, and a central, very tough and flexible, whitish medulla. The cortex is often cracked, and where the strand runs along the surface of the stump white sheets of mycelium are often found adhering to it laterally, but not, I think, organically connected. On breaking one of them and teasing out a portion, the true nature of the organ is at once apparent. The medulla may be separated into fine silky filaments, which under the microscope are found to be hyaline hyphæ, while the cortex consists of a tissue of brownish tough hyphæ woven into a pseudoparenchyma.

Numbers of these *rhizomorphs* were found adhering to the diseased stumps. Several of them extended to the base of the sporophores, which, from Mr. Coventry's photographs, are evidently formed just at the level of the surface of the ground. Some were traced under the cortex of the stump and were there found to expand into subcortical *rhizomorphs* of a looser consistence than the external ones and with their cortex intimately connected with the tissues of the deodar. From these subcortical *rhizomorphs* the broad sheets of mycelium above described can be seen to extend.

The occurrence of this form of external subterranean mycelium adds to the probability of the disease being conveyed underground from tree to tree. *Rhizomorphs* are, in fact, organs of vegetative reproduction admirably adapted to life under-ground. Even where the roots of adjacent trees do not come into contact, the *rhizomorph* can bridge over a space of probably many inches to spread the disease. *Fomes annosus*, so far as has hitherto been known in other lands, has relied mainly on actual contact for its extension and in a secondary degree on reproduction by spores. The large quantity of rhizomorphs found on the deodar shows that these must form the chief mode of propagation in India, and the discovery of these organs indicates a greater capacity for damage than in any other instance in which this fungus is known as a forest pest.

Hence treatment is not hopeful. The *rhizomorphs* cannot readily be destroyed. Isolation of diseased trees by trenching is the only method likely to be successful. Such a treatment is advocated in Germany, but it appears to be doubtful if it can be carried out profitably on a large scale. The removal of sporophores from the stem is probably a measure of quite secondary importance.

Although treatment may not be practicable on a large scale in the forest, it is beyond doubt that it might become extremely useful in municipalities or bungalow compounds, where the value of the tree from an ornamental point of view is the chief consideration, and where an outbreak of this disease might cause damage which could not easily be repaired. In such a case early removal of the tree after death to prevent the formation of sporophores, and running a trench a few feet in depth round the stump sufficiently far out to include the larger roots, are measures which could easily be carried out and should serve to prevent the mischief extending.

G. I. C. P. O.—No. 1476 R. & A.— 27-10-1908.—650.—G. R.

EXPLANATION OF THE FIGURES.

FIG. 1. Sporophore of *Fomes annosus* on deodar showing the brown tuberculate incrustation, and bracket-like active portion with white hymenium below, *a a* brown, mostly sterile portion; *b. b.* recent, sporeforming portion.

,, 2. White mycelial sheets under the bark of the collar.

,, 3. Drawing of a portion of the surface of a block of wood cut from a diseased tree, showing the white areas in the wood.

,, 4. Tissue elements modified by the action of the parasite. *a. a.* cells of the wood-parenchyma-bearing starch; *b.* bore-holes of the hyphæ with a filament extending across between two. *c.* spiral cracking of the wall. *d.* pitted vessel with a hypha penetrating it. *e.* network from the crossing of two spirals, the trachea is seen with the upper wall removed, so that the network is made up of the spiral of the lower wall of this trachea and that of the upper wall of the subjacent one. *f.* dissolution of the middle lamella which results in the isolation of the elements.

5. A rhizomorph.

PLATE I



H Hormusji del

FOMES ANNOSUS Fr

[illegible] by A C Chowdhary

Forester (Appendix Series)

PLATE II



2

3



4



5

J Hormusji & E J B del

FOMES ANNOSUS Fr

Lith by S C Mondul

A NOTE

ON THE

PRESERVATION OF BAMBOOS FROM THE ATTACKS OF THE BAMBOO BEETLE OR "SHOT-BORER."

BY

E. P. STEBBING, F.L.S., F.E.S.,

OFFICIATING SUPERINTENDENT, INDIAN MUSEUM.

General Remarks.

THE work of the bamboo beetle or "shot-borer," the *ghoong* of the Natives in many parts of the country, is well known in India. All who have anything to do with bamboos, either with their cutting and export, their use in buildings, or their manufacture into the thousand and one articles to which this most useful commodity is put in the country have to count upon and allow for the ravages of this pest and in many parts a year to a year and a half may be given as the estimated and probable life of a bamboo after cutting.

Description and Life-History of the 'Shot-Borer.'

But although the results of its work are well-known, the real author of the depredations is far from being a well-recognised enemy owing both to its small size and to its secretive habits. The damage is committed by a tiny beetle and its grubs which are just of slightly smaller diameter than the holes with which the bamboos are seen to be riddled. The beetle, which has a black head and thorax and reddish-coloured, shining wing covers, bores its way into the bamboo and lays its eggs in the interior, each beetle laying about 20. From these eggs small, white, roundish dots of grubs issue within a few days of their being deposited. These tiny larvæ burrow up and down in the interior of the bamboo and reduce its structure to powder. About four weeks are spent in this stage and the grubs then enlarge the ends of their burrows and change to pupæ which after some eight days or so turn into the beetles. On becoming mature the beetles bore their way out of the bamboos and thus add further to the tunnels already made in them. On emergence the insects fly off to attack fresh bamboos or they may bore into the one in which they have matured themselves. There are thus three separate forms of attack :—

(*a*) The female beetle bores into the interior of the bamboo and lays its eggs there. This is the first attack on the bamboo

(*b*) From the eggs hatch out little grubs which feed upon the wood of the interior of the bamboo and thus undermine its strength.

(*c*) The beetles on maturing from the grubs bore their way out of the bamboo.

It used to be thought that each of the shot-borers made their way out by a separate tunnel, driven direct from the place where the grub had pupated to the outside. This is not, however, the case as the matured beetles appear to issue either all from the same exit hole or from one or two only, these being often the former entrance holes of the mother beetles which are considerably enlarged. Beetles of the new generation appear to also make use of these old holes to enter the bamboo to egg-lay, boring away from the old gallery when they have got inside. When bamboos are in lengths it will be found that the beetles tunnel in them parallel to the long axis and form galleries which open at one of the ends. The bamboo is thus often completely hollow in parts without there being much outward evidence of its having been badly attacked. This is more especially the case when the beetles have entered and left by the same holes, made at one of the ends of the bamboo. A feature which greatly adds to the insect's power of doing serious damage is to be found in the fact that in the warmer parts of the country it passes through at least five, and perhaps more, generations or life cycles in the year. I have said that the insect lays about 20 eggs and therefore one female beetle may produce the following progeny in the year on the supposition that only five generations are passed through.

1 Female Beetle.

1st generation .	1 × 20 =	20	beetles, say ½ males and ½ females (the latter are, however, usually in excess of former).
2nd „ .	10 × 20 =	200	beetles, say, ½ males and ½ females.
3rd „ .	100 × 20 =	2,000	Ditto.
4th „ .	1,000 × 20 =	20,000	beetles, ½ males and ½ females.
5th „ .	10,000 × 20 =	200,000	Ditto.

If there is a 6th generation the number of females increases to 2,000,000.

Taking only 50 per cent. of the 5th generation beetles as maturing and laying eggs, we still have 100,000 insects as the progeny of the one mother beetle in the spring. This great prolificness easily explains why bamboos suffer so greatly from the shot-borer's attacks throughout the country.

With this brief sketch of the beetle and its mode of attack we will now turn to the consideration of a method of treatment by which the bamboos can be preserved at any rate for a time against the pest.

Experimental Treatment for Preservation.

Towards the end of April of this year Mr. Williams, the Superintendent of the Telegraph Workshops at Calcutta, informed me that bamboos which he was converting into field telegraph posts for use in frontier expeditions and elsewhere were being attacked and riddled by insects. The specimens he sent me I identified as the common bamboo-boring beetle.* As the question of the preservation of bamboos against this insect had been engaging my attention for some time, I immediately paid a visit to the workshops and examined the bamboos. I found that they were being experimentally treated in the following manner before being fitted up as telegraph posts :—

(1) Five days' soaking in river water ;
(2) Five days' soaking in a solution of copper sulphate, after which they were dried in a covered shed for several days ; and then
(3) Soaked for 24 hours in common Rangoon oil.

This latter has the effect of darkening the bamboos and the smell of the oil remains in them for some considerable time, although not so offensively as to prevent their being made use of. The treatment lasted about 14 days upon the expiration of which period the bamboos were at once sent to the workshops to be fitted. Mr. Williams had reported that within three weeks of this treatment some of the bamboos had been again attacked by the borers. As some 9,000 had been through the treatment, many of which had been already fitted, the case afforded a good opportunity for experiment. Having carefully examined all the bamboos and their method of treatment I was able, through the courtesy of the Superintendent, to obtain a number of specimens both untreated and in the various stages of treatment. With them it was my intention to initiate a series of experiments to determine the exact effect of any one or more of these preservative liquids as a deterrent to the attacks of the beetles. The bamboos had been cut in the Garhwal Forests (United Provinces) and were obtained by the Telegraph Department at Najibad near Bareilly having been floated down from the forests. They were, following the usual custom, passed through fire and straightened by the merchants before being sold. The telegraph specification required them to be 8 feet long or over with a diameter at the small end of not less than ⅞ths inch and not more than 1¼ inch. It was known that the bamboos to be obtained were to be cut in the cold weather of 1902-03. Male bamboos, *i.e.*, solid bamboos, only were to be sent. The bamboos were despatched in convenient lots from Bareilly and no especial protection was given to them on the journey down. They arrived in Calcutta mostly in February and March but some in April. They were not subjected to any treatment before the end of February, and consequently some of the bamboos were in the works for nearly a month before being operated upon. The bamboos had therefore either become infested on the way down or in Calcutta itself. When the treatment they were to be subjected to had been decided upon, no time was lost in putting the bamboos through it. It was as the last of the bamboos were being put through the preservative treatment that I visited the works. From previous observations I was of opinion that the beetles then appearing in the works were those of the 1st generation in the year, *i.e.*, they had developed from eggs laid probably at the end of February or beginning of March. I wished to try and find out—

---

* *Dinoderus minutus*, Lesne.

(1) How many more generations of the beetle appeared in the year.
(2) Whether the oil treatment was of any use.

Experiments.

The bamboos I picked to experiment with were good examples of their class of treatment, and on receipt they were placed in boxes constructed of tin foil and provided with close fitting tops of wire gauze. The boxes were so made that there was no chance of anything inside getting out or anything from without getting in and they answered admirably. The whole experiment was personally carried out by myself in order to ensure accuracy in the observations. In each box were placed specimens of differently treated bamboos. The experiments were commenced on the 29th April upon which date four boxes were got ready as follows :—

Experiment I.—Box contained untreated bamboos

Experiment II.—Box contained bamboos which had been through the water process.

Experiment III.—Box contained bamboos which had been through the water and $CuSo_4$ (copper sulphate) processes.

Experiment IV.—Box contained bamboos which had been through the water, $CuSo_4$, and Rangoon oil processes.

A day or two afterwards three more boxes were prepared as follows :—

Experiment V.—Bamboos treated up to and including $CuSo_4$.

Experiment VI.—Fully treated bamboos.

Experiment VII.—Fully treated bamboos.

The idea was to endeavour to ascertain what portion or portions of the treatment were effective against the borer, it being assumed that the bamboos experimented with contained or had contained eggs or grubs or beetles at the time they were put into the boxes. These latter were examined weekly or at lesser intervals. I propose to give *in extenso* the observations noted during the first month, in order that the methods on which the experiments were carried out may be clearly understood, subsequent months being shortly summarised.

During the first month, *i.e.*, up to the 26th May, the following observations were recorded :—

Experiment I.—*Untreated bamboo*—no boring apparent at first. On the 12th May dead beetles, which had issued from the bamboo after egg-laying, found at bottom of box. 18th May—More dead beetles and one living one at bottom of box. A considerable amount of saw-dust, the result of the burrowing operations of beetles and their larvæ, at bottom of box. May 26th—Dead and living beetles taken from box. Considerable heaps of saw-dust present. (I may note that after each inspection all saw-dust was swept up into one corner of the box so as not to interfere with future observations.)

Experiment II.—Water process—This bamboo showed no signs of having been attacked on being placed in the box. No signs were visible up to May 26th.

Experiment III.—$CuSo_4$ process—No signs of attack on April 28th or afterwards up to May 26th.

Experiment IV.—Oil process—The bamboos had been attacked previously to the treatment. No further signs of attack up to May 26th.

Experiment V.—$CuSo_4$ process—Bamboos badly attacked. May 12th—Ten dead beetles found at bottom of box and a large amount of boring was going on inside the bamboos as evidenced by the piles of saw-dust all over the bottom of the box. May 18th—Five beetles at bottom of box, all dead, and a large amount of saw-dust. May 26th—Twenty two beetles, mostly alive, taken from the box. Saw-dust plentiful. (A predaceous beetle and a parasitic ichneumon fly were also taken from the box.)

Experiment VI.—Previous to being treated this bamboo had been badly attacked by the beetles who had bored in to lay eggs, numbers of which must have been deposited within the bamboo. No evidence of any fresh borings in the interior of the bamboo up to May 26th.

Experiment VII.—This bamboo had been slightly attacked before treatment. No subsequent attacks up to May 26th.

On the 18th May I received and examined a very badly riddled bamboo sent by Mr. Williams. He stated that it had been through all the processes: yet it swarmed with the beetles On examination it appeared to me that the bamboo had not been thoroughly subjected to the oil process. It was light coloured, but little greasy to the touch, and smelt but slightly of the oil. As I was becoming convinced that the water and $CuSo_4$ processes alone afforded no protection, I wrote to the Superintendent pointing out that it was possible that some of the bamboos at the top of the heap in the oil tank had probably not been as well soaked as those beneath, and that without this thorough soaking the effects of the oil were soon lost. I had noticed other bamboos in the workshops which showed little traces of the oil although they had been through the complete process. In reply to my letter Mr. Williams agreed that it was possible that the upper bamboos in the oil tanks had not received a sufficient soaking. To make this point more certain I commenced the following further experiments on the 20th May:—

Experiment VIII.—A well oiled bamboo was put into a box and in with it were placed pieces of bamboo completely riddled by the shot-borer and full of living grubs, pupæ and beetles. I examined the box on the 24th and 26th May upon which dates the oil bamboo still remained unattacked.

Experiment IX.—Experiment with bamboos in the open—Bamboos in all stages of treatment were placed in close juxtaposition with badly infested bamboos, lengths of untreated, water, $CuSo_4$ and oil-treated being placed in a row upon a table and covered with split opened out segments of larger-diameter bamboos containing beetles and larvæ, etc.

On the 29th May I paid another visit to the works and found that a large number of the bamboos had been fitted and finished and were stacked in a covered shed open at one side. They were separated in lots by bamboo uprights. These latter had not been treated and were attracting the beetles. The bamboos were exposed to the rays of the hot afternoon sun. I examined the lots carefully and came to the conclusion that the oil treatment had been very uneven. Some bamboos having evidently not been as well treated as others. I could not find a single case of a well-soaked bamboo being attacked by the beetle although I examined a good many. This coincided with the experiments I was conducting at the Museum. I accordingly informed the Superintendent that I was of opinion that the oil treatment was effective if done thoroughly. The beetles had been so numerous during May that I was of opinion that few of the 9,000 bamboos (the number received for conversion into telegraph posts) would have remained unattacked had they not been treated in the manner described.

The following is a summary of the observations recorded for the second month of the experiment to June 23rd :—

Experiment I.—Untreated bamboo—Beetles, both alive and dead, were found at the bottom of the box throughout the month, the number being large on June 23rd. Large amounts of saw-dust. Some predaceous beetles present feeding upon the boring beetle.

Experiment II.—Water—No signs of attack.

Experiment III.—CuSo₄—No signs of attack.

Experiment IV.—Oil—No signs of attack.

Experiments V.—CuSo₄—Number of beetles, both alive and dead, found at bottom of box, the number being largest on June 23rd. A very large amount of saw-dust has been excavated by the beetles and their larvæ. The greater bulk of a new generation of beetles is evidently issuing now (23rd June) from the bamboos. Parasitic beetles and ichneumon flies taken from the box but are not in sufficient numbers to act as an efficient check upon the pest.

Experiment VI.—Oil—No signs of attack.

Experiment VII.—Oil—No signs of attack.

Experiment VIII.—Oil and untreated attacked bamboo—Towards the beginning of the month noted that a beetle had endeavoured to bore into the oil bamboo. It had made a tiny shallow circular depression and then stopped work. Number of dead beetles lying in vicinity of the oil bamboo. A large number of living beetles in box on 23rd June.

Experiment IX.—Experiment with bamboos in the open—The untreated bamboos and the ones soaked in water and CuSo₄ were all attacked during the month by beetles from the infested pieces placed close to them, and on the 23rd June were being freshly riddled by the new generation of beetles then issuing. The oil bamboos although subjected to the same conditions as the others all remained unattacked.

Experiment X. –On the 15th June placed an untreated bamboo in a box with a pair of beetles in order to ascertain the number of eggs laid and the nature of the gallery bored. This latter is generally practically impossible owing to the beetles and larvæ working gregariously in the bamboo with the results that the tunnels all run into one another.

From the above it will be seen that at the end of the second month of the experiment all the bamboos which had gone through the whole process (Experiments IV, VI, VII, VIII, and IX) showed no attack by the beetles. Those which had been infested previously to the oil bath must have had all eggs, larvæ and beetles they may have contained at the time killed off by the oil. It may be contended that the beetles have in all cases had other bamboos to attack and so have left the oiled ones alone. Since, however, this will almost invariably be the case throughout the country, this point would not appear to be an important one.

For the third month up to July 27th the following results were obtained:—

Experiment I.—Untreated bamboo –A large number of beetles taken from the box this month, especially on and after July 21st. From the number found alive between July 21st and 27th it is probable that a new generation of beetles arising from the eggs laid by the June beetles issued at this period: a few predaceous beetles present.

Experiment II.—Water—No signs of attack.

Experiment III.—$CuSo_4$—No signs of attack.

Experiment IV.—Oil—No signs of attack.

Experiment V.—$CuSo_4$—A very large number of beetles taken from this box (mostly alive) towards the end of the month, as many as 106 being taken out on July 21st—evidently a new generation.

Experiment VI.—Oil—No signs of attack.

Experiment VII.—Oil—No signs of attack.

Experiment VIII.—Oil and untreated attacked bamboos—No signs of attacks. Beetles very numerous in the box and in the untreated bamboo.

Experiment IX.—Experiment with bamboos in the open—The attack has been continued in the untreated, water and $CuSo_4$ bamboos, and towards the end of the month a number of new holes were apparent, made by the new generation of beetles. In many cases these latter were watched boring into the bamboos. The paper wrappers tied round the bamboos (on which the number of the particular experiment, etc., was written) showed round holes through them, the result of fresh work on the beetles' part. Numerous beetles were also observed flying about the office between the 21st and 27th of the month.

The oil-treated bamboos were unattacked.

On the 29th June I received a communication from Mr. Williams in which he informed me that he had resoaked all the bamboos (by then mostly converted into field telegraph posts) in oil. Although this was perhaps scarcely necessary in the case of many yet as those in which the oil treatment was not satisfactory were mixed up with those which were fully soaked; this was evidently the safest thing to do. On the 20th July I again paid a visit to the works and inspected the 9,000 bamboos. The Superintendent reported no further attack, and this is the case at the present date (18th August) although at least two generations of the beetles have issued since the treatment was carried out. Under the present plan of soaking, which I was shown during this visit, every bamboo remains well covered by the oil in the tanks for 24 hours before being removed.

For the fourth month up to 21st August the following results were obtained:—

Experiment I.—Untreated bamboo—During the first days of August beetles continued to issue freely from the bamboos. From then onwards only a few were obtained from the box. Heavy boring by grubs was, however, going on inside the bamboos.

Experiment II.—Water—No signs of attack.

Experiment III.—$CuSo_4$—No signs of attack.

Experiment IV.—Oil—No signs of attack.

Experiment V.—Beetles were still issuing freely at beginning of August and they commenced to do so again about the 21st. Predaceous beetles and ichneumon flies fairly numerous.

Experiment VI.—Oil—No signs of attack.

Experiment VII.—Oil—No signs of attack.

Experiment VIII.—Oil and untreated attacked bamboos—Oil bamboo unattacked.

Experiment IX.—Bamboos in the open—Beetles and larvæ plentiful in the untreated, water, and $CuSo_4$ bamboos. The oil-treated bamboos remained unattacked.

The prepared Telegraph posts in the Workshops remained unattacked throughout the month.

For the fifth month up to September 28th the following results were recorded:—

Experiment I.—Untreated bamboo—Between August 21st and September 7th a large number of beetles issued from the bamboos and were found in the box—evidently a new generation. Again at the end of the month the number once more increased, 88 living and 63 dead beetles being taken from the box between September 22nd and 28th. This would be yet another generation—the period from egg to beetle of this one being evidently less than a month.

Experiment II.—Water—No signs of attack.

Experiment III.—$CuSo_4$—No signs of attack.

Experiment IV.—Oil—No signs of attack.

Experiment V.—$CuSo_4$—The generation of beetles which commenced to issue after August 21st continued to issue up to September 7th, as many as 130 beetles being obtained from the box.

Predaceous beetles feeding upon the bamboo-borers fairly numerous. The number of beetles issuing was less during latter part of the month. A large number of half-eaten remains of the shot-borers taken from the box.

Experiment VI.—Oil—No signs of attack.

Experiment VII.—Oil—No signs of attack.

Experiment VIII.—Oil and untreated attacked bamboos—Oil bamboo unattacked.

Experiment IX.—Bamboos in the open—Beetles issued during the first and latter part of the month freely from the untreated, water, and $CuSo_4$ treated bamboos. Of the oil bamboos, one which had not been thoroughly soaked was attacked by two beetles at one end. The other properly soaked oil bamboos remained unattacked.

The Superintendent reported at the end of the month that none of the prepared telegraph posts had been attacked.

For the sixth month up to October 30th the following observations were recorded:—

Experiment I.—Untreated bamboos—The generation of beetles which commenced to issue towards the end of September continued on into October, 150 beetles issuing between September 29th and October 7th. In the latter half of October beetles again issued numerously, over two hundred beetles issuing by the end of the month.

Experiment II.—Water—No signs of attack.

Experiment III.—$CuSo_4$—No signs of attack.

Experiment IV.—Oil—No signs of attack.

Experiment V.—$CuSo_4$—During the month the number of beetles issuing decreased until towards the end of the month the shot-borer beetles entirely stopped coming out. On the other hand, a number of predaceous beetles issued during the latter part of the month they having evidently got the upper hand and practically exterminated all that were left of the bamboo-borers.

Experiment VI.—Oil—No signs of attack.

Experiment VII.—Oil—No signs of attack.

Experiment VIII.—Oil and untreated bamboos—Oil bamboo is still unattacked.

Experiment IX.—During the first part of the month beetles issued in large number from the untreated, water, and $CuSo_4$ bamboos. During the latter part of the month a cold snap occurred between the 24th and 29th and this seems to have put an end to the beetle's work. Oil bamboos unattacked except the badly treated one in which boring continued to a slight extent throughout the month.

I visited the workshops during the month, and inspected the converted bamboos. I could find no signs of attack by the shot-borer although at least four generations of the beetle had issued in Calcutta since they had been treated. For the seventh month up to the 15th November the observations recorded show that the attack of the beetle practically ceased this year at the end of October with the coming of the first cold snap. In warmer years the attacks would probably be carried on up to the middle of November.

Results.

The experiments detailed above show, I think, the following:—

(1) That neither the five days in water nor that followed by a further five days in $CuSo_4$ are of any use as a protection against the beetles. It is true that Experiments II and III seemed at first to prove that these soakings were effective since the bamboos in these boxes have remained unattacked. I attribute this, however, solely to the fact that the pieces of bamboos, selected at haphazard in the Telegraph Workshops, and placed in the closed boxes in April when the beetles were egg-laying, did not happen to have had egg deposited in them and consequently when they were placed in the beetle-proof boxes and protected against the beetles they showed no attacks. All the subsequent experiments with these classes of treatment show that they are no protection against the beetles.

(2) That the bamboos which had gone through all the stages of the treatment and had received a proper soaking in the oil tank remained unattacked and in addition were proof against further attacks by the beetles.

(3) That at least five generations of these beetles issued between the last week in April and the end of

October: the 1st taking about seven weeks, from end of April to the third week in June, to run through all its stages: the 2nd about 4-5 weeks, from the third week in June to near the end of July: the 3rd 4 weeks, from the end of July to the beginning of September: the 4th less than 4 weeks, from 1st week in September to end of the month: the 5th from end of September to end of October. It is probable that many of the beetles of this generation were caught and killed off by the cold snap experienced towards the end of the month.

(4) That bamboos cut in the forests between December and February can, even if not treated till between two and three months after cutting (by which time it is probable that many of them will contain eggs) be preserved by the oil treatment from further attacks of the April, June, July, September, and October generations of beetles, each of which attacks means their subsequent riddling by the larvæ arising from the eggs laid by the beetles.

(5) That the oil treatment therefore considerably prolongs the period of usefulness of the bamboo, this period being, as far as the experiments at present show, at least a year.

Recommendations.

(*a*) I am inclined to recommend that the soaking for five days in water should be continued since a thick shiny gelatinous substance exudes from the bamboos during this process, and this exudation probably enables the bamboo to absorb a larger quantity of oil than would be otherwise the case.

(*b*) That the soaking in the copper sulphate solution be discontinued since the experiments have shown it to have no preservative effect against the beetles.

(*c*) That the bamboos be allowed to dry in a covered shed for several days after the water process.

(*d*) That after drying the bamboos be soaked for 48 hours in common Rangoon oil.

Cost.

The Superintendent of the Telegraph Workshops states that the cost of the treatment as carried through by him, *i.e.*, five days in water, five days in $CuSo_4$ followed by several days drying and then two separate soakings (at an interval of a couple of months) of 24 hours each in Rangoon oil, amounts to R3-5 per 100 6-foot lengths or 6·3 pies per length. This includes the labour.

Omitting the $CuSo_4$ treatment and a second soaking in the oil, together with the additional handling involved, should effect a saving in this price, although of course the longer period of soaking in oil will enable the bamboos to absorb more of this than they would in the shorter one of 24 hours only.

Concluding Remarks.

Although we have yet to see how long the oil-soaked bamboo will remain proof against the attacks of the beetles, I am of opinion that the experiments have advanced sufficiently to render the publication of a note upon the subject of use to those concerned. Bamboos are so largely used that the prolongation of their period of usefulness by even a year only would effect a considerable monetary saving. I trust, however, to be able to show that the treatment will be found to have a yet longer beneficial effect. To the Director General of Telegraphs belongs the credit of having initiated this oil treatment, and to Mr. Williams, to whom my thanks are due for the courtesy with which he has aided me with the specimens and information required to carry on the series of experiments, that of having so efficiently carried it out.

G. I. C. P. O.—No. 2057 R. & A.—19-11-1903—800.—B. M. D.

VIII.—EXTRACTS FROM OFFICIAL GAZETTES.

1.—Gazette of India.—*Nil.*

2.—Madras Gazette.

13th October 1902.—*Transfer.*—N. S Viracharlu, Forest Ranger, 2nd grade, from the Kistna to the Godavari district. To join on relief by Sheikh Rahmatullah Sahib, Forest Ranger, 4th grade.

21st October 1902.—No. 395.—Mr. A. P. Grenfell, Working-plans Officer, Southern Circle, is granted furlough for one year on medical certificate under article 343 of the Civil Service Regulations.

23rd October 1902.—*Leave.*—K. Aswatham Naidu, Ranger, Kurnool district, is granted privilege leave for one month, under Article 291 of the Civil Service Regulations, from 1st January 1903.

23rd October 1902.—*Promotions.*- The following promotions are ordered in the Ranger's class :—

(1) M.R.Ry. T. Arumuga Mudaliyar, Ranger, 2nd grade, acting, sub. *pro tem*, North Arcot district, to be Ranger, 2nd grade, permanent, from 25th April 1902.

(2) M.R.Ry. A. Subba Row, Ranger, 4th grade, North Arcot, to act as Ranger, 3rd grade, sub *pro tem.*, from 25th April 1902.

(3) M.R.Ry. K P. Krishna Aiyar, Ranger, 4th grade (doing duty under the Working-plans Officer, Central Circle), to act as Ranger, 3rd grade, sub *pro tem.*, from 1st May 1902.

(4) M.R Ry. A. N Venkatachalam Chetty, Ranger, 4th grade, acting, sub. *pro tem*, North Salem, to be Ranger, 4th grade, permanent, from 1st July 1902

(5) M.R.Ry. A Venkatanarayaniah, Ranger, 5th grade, North Arcot, to act as Ranger, 4th grade, sub. *pro tem.*, from 1st May 1902.

(6) Mr. H. W. A. Gaudoin, Ranger, 5th grade, acting, sub. *pro tem.*, Cuddapah, to be Ranger, 5th grade, permanent, from 1st May 1902.

(7) M.R.Ry. C. Ramaswami Aiyangar, Ranger, 5th grade, acting, sub. *pro tem.*, Trichinopoly, to be Ranger, 5th grade, permanent, from 1st July 1902.

(8) Mir Jaffir Ali Kirmani Sahib, Ranger, 5th grade, acting, sub. *pro tem.*, Cuddapah, to be Ranger, 5th grade, permanent, from 23rd August 1902.

24th October 1902.—*Promotions*—The following promotions are ordered among Rangers in the Southern Circle :—

Mr. M. S. Noronha, Ranger, 3rd grade, to be Ranger, 2nd grade, acting, sub. *pro tem.*, with effect from 24th March 1902.

Mr. A. F. X. Saldanha, Ranger, 3rd grade, acting, sub. *pro tem.*, to be Ranger, 3rd grade, permanent, with effect from 11th March 1902.

Mr. A. F. X. Saldanha, Ranger, 3rd grade, to be Ranger, 2nd grade, acting, sub. *pro tem.*, with effect from 25th April 1902.

M.R Ry. M Panchapakesa Aiyar, Ranger, 3rd grade, acting, sub *pro tem*, to be Ranger, 3rd grade, permanent, with effect from 25th April 1902.

M R Ry. T. V Arumugam Pillai, Ranger, 4th grade, to be Ranger 3rd grade, acting, sub. *pro tem*, with effect from 11th March 1902.

M.R.Ry. V Raman Menon. Ranger 4th grade, acting sub *pro tem*, to be Ranger, 4th grade, permanent, with effect from 11th March 1902

M R.Ry M. Sreenivasa Aiyangar, Ranger, 4th grade acting, sub *pro tem.*, to be Ranger, 4th grade, permanent, with effect from 25th April 1902.

M R.Ry K. Gajaraja Mudaliar, Ranger, 5th grade, to be Ranger, 4th grade, acting, sub. *pro tem.*, with effect from 11th March 1902.

Mr. B. D'Sa. Ranger. 5th grade, to be Ranger, 4th grade, acting, sub. *pro tem.*, with effect from 25th April 1902

Mr F S. Brito, Ranger, 5th grade, to be Ranger, 4th grade, acting, sub. *pro tem.*, with effect from 1st July 1902.

Mr. G S Lasrado Ranger, 5th grade, acting, sub. *pro tem*, to be Ranger, 5th grade, permanent, with effect from 11th March 1902.

24th October 1902 — *Appointment* —M.R Ry. T. S. Subraman'a Aiyar, Ranger, 6th grade, on probation, Cuddapah district, to be Ranger, 6th grade, with effect from 24th June 1901, *i.e.*, the date of his first appointment.

24th October 1902 — *Promotions.*—The following promotions are ordered:—

(1) Mr G W. Thompson, Ranger, 3rd grade, and Ranger, 2nd grade, acting, sub *pro tem.*, Vizagapatam district, to be Ranger, 2nd grade, from 11th March 1902

(2) M.R Ry S. Eggianarayana Sastri, Ranger, 3rd grade, Bellary district, to be Ranger, 2nd grade, acting, sub. *pro tem.*, from 11th March 1902

(3) M R.Ry. K. Aswatham Naidu, Ranger, 4th grade, and Ranger, 3rd grade, acting, sub. *pro tem.*, to be Ranger, 3rd grade, from 1st May 1902.

(4) M.R Ry. Shaikh Rahamtulla Sahib, Ranger, 5th grade, and Ranger, 4th grade, acting, sub *pro tem.*, Kistna district, to be Ranger, 4th grade, from 1st May 1902.

(5) M R.Ry. S. V. Adinarayana Aiyar, Ranger, 6th grade, and Ranger, 5th grade acting, sub. *pro tem.*, Bellary district, to be Ranger, 5th grade, from 25th April 1902.

26th October 1902.—*Confirmation of Appointment.*—M.R.Ry. K. G. Venkatarama Aiyar, Ranger, 6th grade, on probation, Bellary district, is confirmed in that grade from 17th July 1901.

27th October 1902 —*Transfer.*—M.R Ry. S. Eggianarayana Sastri, Forest Ranger, 2nd grade, acting, sub. *pro tem.*, from the Bellary to the Ganjam district.

28th October 1902 —*Commutation of Leave* —The three months' leave on medical certificate granted to M.R.Ry. S. Eggianarayana Sastri. Ranger, Ganjam district, in this office service order No. 78 of 1902, dated 8th April 1902, is commuted into privilege leave.

1st November 1902.—*Posting*.—M.R Ry. C. M. Maduranayagam Pillai Avargal, Extra-Assistant Conservator of Forests, on return from privilege leave, to the South Arcot district.

3rd November 1902.—*No.* 398.—Mr H. A Gass, Conservator of Forests, is granted privilege leave for three months from or after the 20th November, 1902 and furlough for one year in continuation thereof under Articles 264-A, 291 and 340 (*b*) of the Civil Service Regulations

6th November 1902.—*Transfers.*—M.R.Ry. R. Sama Row, Ranger, 5th grade, from Chingleput to South Arcot.

M R.Ry. K. G. Subba Row, Ranger, 5th grade, from South Arcot to Chingleput, on relief by R. Sama Row.

8th November 1902.—*No* 406.—Mr. C. E. Brasier, Conservator of Forests, to hold charge of the Southern Circle on his return from leave.

3.—BOMBAY GAZETTE.

20th October 1902.—No. 7351.—Messrs H.L Newman, Divisional Forest Officer, Dharwar, and L. S. Koppikar, Sub-Divisional Forest Officer, Satara, passed, on the 18th September 1902 an examination in subjects prescribed in No. VI of the Rules published in Government Notification No. 2, dated 3rd January 1894, for the examination of Officers of the Forest Department.

No. 7401.—His Excellency the Governor in Council is pleased to appoint Mr A. C Robinson, L C E, on return from leave, to be Extra-Assistant Conservator of Forests, Sind Circle.

22nd October 1902.—No. 7420.—His Excellency the Governor in Council is pleased to make the following appointments:—

Mr. W. A. Wallinger, on return to duty, to be Divisional Forest Officer Dharwar.

Mr. H. L. Newman, on relief, to be Divisional Forest Officer, W. D. Kanara.

Mr. T. R D Bell, on return to duty, to be Divisional Forest Officer, West Khandesh.

Mr. H. Murray, on relief, to be Deputy Conservator of Forests, Sind Circle

28th October 1902.—No. 7572.—Mr. Vishnu Mahadeo Tilak, Extra-Assistant Conservator of Forests, 3rd grade, and Divisional Forest Officer, Sholapur, is granted privilege leave of absence for three months in combination with furlough for nine months

No. 2702.—Messrs A G Edie and H. Murray, Deputy Conservators of Forests, respectively delivered over and received charge of the Divisional Forest Office, West Khandesh, on the forenoon of the 19th October 1902.

29th October 1902.—No 7622.—His Excellency the Governor in Council is pleased to appoint Mr. Haripad Mitra, L C E, to act as Divisional Forest Officer, Sholapur, during the absence on leave of Mr. Vishnu Mahadeo Tilak, or pending further orders.

4th November 1902.—No 5402.—Mr. O. H L Napier, Deputy Conservator of Forests, delivered over charge of the Southern Division of Kanara to Mr. W E Copleston, Deputy Conservator of Forests on the forenoon of the 21st October 1902.

4th November 1902.—No. 5403.—Mr. R. S. F Fagan, Acting Conservator of Forests, S. C., delivered over charge of the office of Working plans Division, S. C., to Mr W. E Copleston, Deputy Conservator of Forests, of the afternoon of the 22nd October 1902.

4th November 1902.—No. 7759.—His Excellency the Governor in Council is pleased to appoint Mr Metharam Deumal Jagtiani to act as 4th grade Extra-Assistant Conservator of Forests *vice* Mr. H Mitra, L. C. E., transferred, and to place him under the orders of the Conservator of Forests Northern Circle.

10th November 1902.—No. 5505 —Mr H. L. Newman, Assistant Conservator of Forests, and Mr. W A Wallinger, Extra-Assistant Conservator of Forests, respectively delivered over and received charge of the Divisional Forest Office, Dharwar, on the forenoon of the 3rd instant.

12th November 1902.—No. 7934.—His Excellency the Governor in Council is pleased to appoint Mr. H. Murray to be Divisional Forest Officer, Hyderabad.

15th November 1902 —No. 2904.—Messrs. H. W. Keys and G. R. Duxbury, Deputy Conservators of Forests, respectively delivered over and received charge of the Divisional Forest Office, Satara, on the afternoon of the 3rd November 1902.

17th November 1902 —No. 2609 —Mr. Haripad Mitra, L C.E, Extra-Assistant Conservator of Forests, 1st grade, delivered over charge of the office of the Sub-Division, Central Thana, to Mr G. M. Ryan, Deputy, Conservator of Forests, on the afternoon of the 13th November 1902.

Bombay Castle, 18*th November* 1902.

No 8074 —His Excellency the Governor in Council is pleased to make the following appointments:—

Mr. Vishnu Mahadev Tilak to be 2nd grade Extra-Assistant Conservator, *vice* Mr. Krishnaji Babaji Phadke, deceased.

Mr. Govind Ramchandra Takle to be 3rd grade Extra-Assistant Conservator, *vice* Mr. Tilak, promoted.

Mr. Metharam Deumal Jagtiani to be 4th grade Extra-Assistant Conservator, *vice* Mr. Takle, promoted, and to be under the orders of the Conservator of Forests, Northern Circle.

Mr. Dinkar Narayan Damle to continue to act as 4th grade Extra-Assistant Conservator, *vice* Mr. Haripad Mitra.

Bombay Castle, 19*th November* 1902.

No, 8134.—His Excellency the Governor in Council is pleased to post Mr. J. D. Maitland Kirwan to the Nasik District, and to place him under the orders of the Conservator of Forests, Central Circle.

4.—BENGAL GAZETTE—*Nil.*

5 —UNITED PROVINCES OF AGRA AND OUDH GAZETTE.

12th November 1902.—No. 5319 - II—622 B 1.—The undermentioned Officers have been granted by His Majesty's Secretary of State for India extension of leave

Name.	Service.	Appointment.	Period and nature of leave.
Mr. W.H. Lovegrove.	Imperial Forest Service.	Deputy Conservator of Forests	One day's furlough.

12*th November* 1902.—No. 5321.—II—622 B-1.—The undermentioned Officers have been granted by His Majesty's Secretary of State for India permission to return to duty.

Name.	Service	Appointment.	Date on which permitted to return.
Mr. W.H. Lovegrove.	Imperial Forest Service.	Deputy Conservator of Forests.	Within the period of leave.
*	*	*	*

6.—PUNJAB GAZETTE.

22*nd October* 1902.—No. 565.—*Promotions.*—His Honour the Lieutenant Governor of the Punjab is pleased to order the following promotions with effect from the 1st September 1902 :—

Forest Ranger Jai Kishen, on deputation to Jubbal State, to be Extra-Assistant Conservator of Forests, 4th grade, supernumerary, provisional, on probation in the vacancy caused by the deputation of Lala Sundar Das, Extra-Assistant Conservator of Forests, to the Kotah Native State.

Forest Ranger Imam-ud-din to be Extra-Assistant Conservator of Forests, 4th grade, supernumerary, provisional, on probation, *vice* Lala Jai Kishen, Extra-Assistant Conservator of Forests, on deputation to the Jubbal State.

3*rd November* 1902.—No. 575.—A. L. No. 28.—The following changes have taken place in the list of Forest Officers in the Associated Provinces with effect from the date specified against each :—

Name.	Present grade.	Grade to which promoted or reverted.	With effect from	REMARKS.
Mr. W. Mayes ...	Officiating Deputy Conservator, 3rd grade.	Deputy Conservator, 4th grade.	19th July 1902,	Consequent on the return from privilege leave of Mr. A St. V Beechey on the forenoon of the 19th July 1902.
Mr. O. M. McCrie,	Officiating Deputy Conservator, 3rd grade.	Provisional Deputy Conservator, 4th grade		

12*th November* 1902.—No. 592.—A. L. *No* 29.—*Notification.*—Messrs. A. L. McIntire, Deputy Conservator of Forests, and A. J. Gibson, Officiating Deputy Conservator of Forests, respectively made over and received charge of the Bashahr Forest Division on the afternoon of the 29th October 1902, consequent on the departure of the former on three months' privilege leave.

Mr. Gibson will hold charge of the Bashahr Division in addition to the Simla Division.

7.—CENTRAL PROVINCES GAZETTE.

3*rd November* 1902.—No. 13.—*Corrigendum.*—The following changes have taken place in the list of Forest Rangers in the Central Provinces with effect from the date specified against each.

This is in substitution for those parts of Deparmental Orders Nos. 10 and 11, dated the 12th September 1902, published in *Central Provinces Gazette*, Part II, dated the 27th September 1902, which refer to promotions and confirmations of certain Rangers :—

Name.	Present grade.	Grade to which promoted or confirmed	With effect from.	REMARKS.
K. Rama Rao ...	Ranger, 2nd grade.	Ranger, 1st grade, sub *pro tem.*	1st July 1902...	...
Ditto ...	Ranger, 1st grade, sub *pro tem*	Ranger, 1st grade.	14th July 1902.	...
Bhaya Lal ...	Ranger, 3rd grade, sub *pro tem.*	Ranger, 3rd grade.	Ditto ...	...
Muhamad Ismail..	Ranger, 4th grade, sub *pro tem.*	Ranger, 4th grade.	Ditto ...	...
Surmust Khan ..	Ranger, 5th grade,	Ranger, 4th grade, sub. *pro tem.*	1st July 1902...	*Vice* Tirath Parshad on deputation
Kazim Hussein Khan.	Ditto ..	Ditto ..	14th July 1902	...
Phirozshah R. Katpatia	Ranger, 5th grade, sub. *pro tem.*	Ranger, 5th grade.	Ditto ..	...
Vishnu Vasudeo Sathe.	Ditto ..	Ditto ..	Ditto .	...
Muhammad Hani Siddiqui	Ditto ...	Ditto .	Ditto ..	...

5th November 1902 —No. 6143 —Privilege leave for one month, under Articles 277 and 291 of the Civil Service Regulations, is granted to Mr. C. Somers-Smith. Deputy Conservator of Forests, 2nd grade, with effect from the 21st October 1902, in extension of the one month's privilege leave granted in Revenue Department Order No. 4989, dated the 8th September 1902.

5th November 1902.—No. 6144.—Mr. A. L. Chhatterji, Extra-Assistant Conservator of Forests, 4th grade, Saugor, is directed to continue to hold charge of the Saugor Forest Division, during the absence of Mr. C. Somers-Smith on leave, or until further orders.

8.—BURMA GAZETTE.

10th October 1902.—No. 421.—Mr. F. B. Manson, Conservator of Forests, has been permitted by His Majesty's Secretary of State for India to return to duty within the period of his leave.

10th October 1902.—No 422 —Mr J. Messor, Deputy Conservator of Forests has been permitted by His Majesty's Secretary of State for India to return to duty within the period of his leave.

10th October 1902.—No 423 —Mr A. Rodger, Assistant Conservator of Forests, has been granted by his Majesty's Secretary of State for India extraordinary leave without pay for four days in extension of the leave previously granted to him.

10th October 1902 —No 424.—Mr. A. Rodger, Assistant Conservator of Forests, has been permitted by His Majesty's Secretary of State for India to return to duty within the period of his leave.

11*th October* 1902.—No. 25.—With reference to Revenue Department Notification No 415 (Forests), dated the 7th October 1902, Mr. D. H. Allan, Extra-Assistant Conservator of Forests, assumed charge of the Kado sub-division, relieving Mr. G Cooper, Extra-Assistant Conservator of Forests, on the forenoon of the 26th September 1902.

20*th October* 1902.—No 15.—Mr. H. N. Thompson, Deputy Conservator of Forests, on deputation to Southern Nigeria, was relieved of his duties in the Southern Shan State by the Superintendent and Political Officer of those States on the forenoon of the 7th October 1902.

22*nd October* 1902—No 430.—Under the provisions of Article 366 of the Civil Service Regulations, extraordinary leave without allowances was granted to Mr. H. B. Ward, Deputy Conservator of Forests, for the 27th June 1902.

24*th October* 1902—No. 26—With reference to Revenue Department Notification No 414 (Forests), dated the 7th October 1902, Mr. W. J. G. Cooper, Exta-Assistant Conservator of Forests, availed himself of the two months' leave granted therein on the forenoon of the 26th September 1902.

25*th October* 1902.—No. 16.—With reference to Revenue Department Notifications Nos. 416 and 417, dated the 7th October 1902, Mr. A. Lawrence, Deputy Conservator of Forest, rejoined the Yaw division on the forenoon of the 8th October 1902. Mr. Lawrence relinquished charge of his duties in that division on the forenoon of the 18th October 1902, and on the forenoon of the 25th October 1902, he relieved Mr. G. Cubitt, Deputy Conservator of Forests, of the charge of the Direction division and of the duties of Personal Assistant to the Conservator of Forests, Southern Circle.

28*th October* 1902.—No. 18—Mr. J. Messer, Deputy Conservator of Forests, on his return from the leave granted him in Revenue Department Notification No 132 (Forests), dated the 14th April 1902. received charge of the Katha division from Mr. F. H. Todd, officiating Deputy Conservator of Forests, on the forenoon of the 25th October 1902.

28*th October* 1902.—No. 19.—Mr. W R. French, Extra-Assistant Conservator of Forests, on deputation to the Federated Malay State of Pahang, was relieved charge of his duties in the Tigyaing sub-division, Katha division, by Mr. F. Dalton, Ranger, on the afternoon of the 14th October 1902.

29*th October* 1902.—No 434.—Mr. A. Rodger, Assistant Conservator of Forests, on return from leave, is attached to the Pegu Forest Division for Working-plans duty.

29*th October* 1902—No. 435.—On return from leave Mr. J. J. Rorie, Assistant Conservator of Forests, is attached to the Rangoon Forest Division or Working-plans duty.

30*th October* 1902.—No 436.—Mr. J. Messer, Deputy Conservator of Forests, on return from leave, is posted to the charge of the Katha Forest Division, *vice* Mr. F H. Todd, transferred.

30*th October* 1902.—No. 437—Mr. F. H. Todd, officiating Deputy Conservator of Forests, on relief by Mr. J. Messer, is attached to the Pyinmana Forest Division for Working-plans duty.

30*th October* 1902—No. 438—Mr. H L. P Walsh, officiating Deputy Conservator of Forests, on relief by Mr J C. Hopwood, is attached to the Ruby Mines Forest Division for Working-plans duty.

30*th October* 1902.—No. 439.—Mr. J. C. Hopwood, Assistant Conservator of Forests, attached to the Thayetmyo Forest Division, is transferred to the charge of the Kyauksé Forest sub-division of the Mandalay Forest Division, *vice* Mr. H. L. P. Walsh, transferred.

5th November 1902.—No. 20.—With reference to Revenue Department Notification No. 435 (Forests), dated the 29th October 1902, Mr. J. J Rorie, officiating Deputy Conservator of Forests, assumed charge of the Rangoon Working Plans Division on the afternoon of the 24th October 1902, relieving Mr. S. Carr, Deputy Conservator of Forests.

5th November 1902.—No 17.—With reference to Revenue Department Notification No. 438 (Forests), dated the 30th October 1902, Mr J C. Hopwood, Assistant Conservator of Forests, relieved Mr H. Walsh, Deputy Conservator of Forests, of the charge of the Kyauksé sub-division, Mandalay division, on the afternoon of the 1st November 1902.

6th November 1902.—No. 18.—With reference to Revenue Department Notification No 417 (Forests), dated the 7th October 1902, Mr. G. E. S Cubitt, Deputy Conservator of Forests, joined the Yaw division on the afternoon of the 1st November 1902.

7th November 1902. No 450.—The following alterations in rank are ordered in the Forest Department :—

With effect from the 18th September 1902, consequent on the return from leave of Mr. H. B. Anthony, officiating Deputy Conservator, 1st grade :—

Mr H Calthrop, Deputy Conservator 2nd (officiating 1st) grade, to revert to his substantive appointment.

Mr F. J. Branthwaite, Deputy Conservator, 3rd (officiating 2nd) grade, to revert to his substantive appointment.

Mr. A H. M. Lawson, Deputy Conservator, 4th (officiating 3rd) grade, to revert to his substantive appointment.

Mr. L. C. Davis, Assistant Conservator, 2nd grade (officiating Deputy Conservator, 4th grade), to officiate as Assistant Conservator, 1st grade.

7th November 1902.—No. 451 (Forests)—This department Notification No. 373 (Forests), dated the 9th September 1902, granting privilege leave for three months to Mr. R. C. A. Pinder, Extra-Assistant Conservator of Forests, is cancelled.

10th November 1902.—No. 27.—With reference to Revenue Department Notification No. 418 (Forests), dated the 7th October 1902, Mr. F Ryan, Extra Deputy Conservator of Forests, assumed charge of the South Tenasserim division, relieving Mr. A E. Ross. Deputy Conservator of Forests, on the afternoon on the 4th November 1902

9.—ASSAM GAZETTE.

29th October 1902.—No. 8203G.—Mr. J. L. Pigot, Deputy Conservator of Forests, on return from leave, is appointed to the charge of the Nowgong Forest Division.

6th November 1902.—No. 8373G.—With effect from the 21st October 1902, in consequence of the return from leave of Mr. J. L. Pigot, Deputy Conservator of Forests, 1st grade—

Mr. D. P. Copeland, Officiating Deputy Conservator of Forests, 1st grade, to revert to his substantive appointment of Deputy Conservator, 2nd grade.

Mr. H. G. Young, Officiating Deputy Conservator of Forests, 2nd grade, to revert to his substantive appointment of Deputy Conservator, 3rd grade.

Mr. J. E. Barrett, Officiating Deputy Conservator of Forests, 3rd grade, to revert to his substantive appointment of Deputy Conservator, 4th grade.

10.—HYDERABAD RESIDENCY GAZETTE.—*Nil.*

11.—MYSORE GAZETTE.

10*th November* 1902.—No. 311—2478.—The following promotion and confirmation of Forest Officers are ordered with effect from the 16th November 1902:—

Mr. M. Venkatnarnappa, Assistant Conservator of Forests 1st class, to Deputy Conservator 3rd class, to fill a vacancy.

Mr. B. Heerasingh, Assistant Conservator of Forests, 1st class (supernumerary), is confirmed.

Pioneer Press, No. 1804.—1-1-03.

VIII.—EXTRACTS FROM OFFICIAL GAZETTES.

1.—GAZETTE OF INDIA.

28th November 1902.—No 1123-F—234-4.—In consequence of the death of Mr. C. G. D. Fordyce, Conservator of Forests, 3rd grade, Assam, Mr. E. S Carr, Deputy Conservator, 1st grade, Burma, and Officiating Conservator, 3rd grade, Assam, is confirmed in the latter grade, with effect from the 12th October 1902.

11th December 1902.—No. 1269-F—254-1.—The Governor-General in Council has received, with much regret, intelligence of the death in England on the 7th November, of Mr. Harry Charles Hill, the Inspector-General of Forests to the Government of India.

Mr. Hill entered the Forest Department in December 1872, as Assistant Conservator, and, after officiating on several occasions as Inspector-General of Forests, was finally confirmed in that important post in November 1900. Much of his earlier service was spent in Burma, where the arduous task fell to him of organizing and developing an efficient system of forest administration in the Upper Provinces after their annexation. As Inspector-General his wide experience of Indian forestry was of great value to the Government of India.

Mr Hill's premature death removes one who worthily filled a responsible office, and the Governor-General in Council desires to place on record his sense of the loss which the public service has sustained.

19th December 1902.—No 4242-22—10.—Mr R. C. Wroughton, Conservator of Forests, Bombay, who was appointed in Notification No 959, dated 21st March 1902, to officiate as Inspector-General of Forests, to the Government of India, is confirmed in that appointment, with effect from the 8th November, *vice* Mr. H. C. Hill, *deceased*.

2.—MADRAS GAZETTE.

8th November 1902.—*Leave.*—Mr. L. S. Janes, Ranger, 5th grade, South Coimbatore division, is granted sick leave, under Article 369 of the Civil Service Regulations, for six months and five days from 21st September, 1902.

Notification published on page 948, Part II of *Fort St. George Gazette*, dated 15th July 1902, is hereby cancelled.

15th November 1902.—*Services dispensed with.*—The services of S. G. Joglekar, Probationary Ranger, 6th grade, Godavari district, are dispensed with from 7th November 1902

18th November 1902.—No. 414.—Mr. [illegible] A. Latham, District Forest Officer, South Canara, is granted privilege leave for one month and twenty-two days from or after the 24th instant and furlough for four months and eight days in continuation thereof under Articles 264-A, 291 and 340 (*b*) of the Civil Service Regulations.

23rd November 1902.—*Confirmation of Appointment.*—Mr E. M. Crothers, Ranger, 6th grade, *sub pro tem.*, Kurnool district, is confirmed in that grade from 19th November 1901.

23rd November 1902 —No. 421.—Mr. E C. M. Mascarenhas, Extra-Assistant Conservator of Forests, 4th grade, to act as District Forest Officer, South Canara, during the absence of Mr. H A Latham on leave, or until further orders

28th November 1902. - No 429.—Mr. N M Rego, Extra-Assistant Conservator of Forests, 4th grade, to act as Working Plans Officer under the orders of the Conservator of Forests, Northern Circle.

8th December 1902 – No 449.—Mr. R D Richmond, Assistant Conservator of Forests 2nd grade, to do duty under the District Forest Officer, Tinnevelly

8th December 1902.—*Posting.*—Mr N. M. Rego, Probationary Extra-Assistant Conservator of Forests, Working Plans Office, Northern Circle, is posted to the Godavari district, to work under the orders of the District Forest Officer.

9th December 1902 —No. 445.—

(1) Mr C E Brasier, to act as Conservator of Forests 2nd grade, during the absence of Mr. H. A. Gass on leave.

(2) Mr. H. J. A. Porter, to act as Conservator of Forests 3rd grade, *vice* No. (1).

(3) Mr T P Peake, to act as Deputy Conservator of Forests, 1st grade, *vice* No. (2).

(4) Mr P M Lushington, to act as Deputy Conservator of Forests, 2nd grade *vice* No (3).

(5) Mr H A Latham, to act as Deputy Conservator of Forests, 3rd grade, until the date of expiry of his privilege leave, *vice* No. (4).

(6) Mr. C E C. Fischer, to act as Deputy Conservator of Forests, 3rd grade, from the date of expiry of Mr. Latham's privilege leave, *vice* No. (4).

(7) Mr. C. B. Dawson, to act as Deputy Conservator of Forests, 4th grade, *vice* Nos (5) and (6).

(8) Mr. B H Barlow-Poole to act as Assistant Conservator of Forests, 1st grade, *vice* No (7).

Note.—The foregoing appointments take effect from the date of Mr C. E. Brasier's return to duty.

(9) Mr. H F. A. Wood, to act as Deputy Conservator of Forests, 3rd grade, during the absence of Mr A B Jackson on privilege leave in the months of August and September 1902

(10) Mr. H Tireman, to act as Deputy Conservator of Forests, 3rd grade, during the absence of Mr. A. P. Grentell on leave, or until further orders.

(11) Mr. B H. Barlow-Poole to act as Deputy Conservator of Forests, 4th grade, with effect from 2nd January 1903, during the absence of Mr. S. Cox on leave, or until further orders.

(12) Mr. W. Aitchison, to act as Deputy Conservator of Forests, 4th grade, with effect from 2nd January 1903, during the absence of Mr. C. E. F. Foulkes on leave, or until further orders.

3.—BOMBAY GAZETTE.

24th November 1902.—No. 2740.—Mr. G. M. Ryan, Deputy Conservator of Forests, 3rd grade, delivered over and Mr. Metharam Deumal Jagtiani, Extra-Assistant Conservator of Forests, 4th grade, received charge of the office of the sub division, Central Thana, on the 19th November 1902 in the afternoon.

26th November 1902.—No 2992. Messrs V. M. Tilak and H. Mitra, Extra-Assistant Conservator of Forests, respectively delivered over and received charge of the Divisional Forest Office, Sholapur on the afternoon of the 15th November 1902.

26th November 1902.—No 3024.—Messrs H. Murray and T. R. D. Bell, Deputy Conservators of Forests, respectively delivered over and received charge of the Divisional Forest Office, West Khandesh, on the forenoon of the 10th November 1902.

29th November 1902.—No. 5867.—Messrs. G. P. Millett, Deputy Conservator of Forests, and H. L. Newman, Assistant Conservator of Forests respectively delivered over and received charge of the Divisional Forest Office, W. D. Kanara, on the forenoon of the 10th November 1902.

5th December 1902.—No. 6000.—Mr. H. A. Nadkarni, Extra-Assistant Conservator of Forests who has been appointed as the sub divisional Forest Officer, Belgaum, took over charge of his duties on the afternoon of the 15th November 1902.

17th December 1902. No 8980.—Mr. D. A. Thomson, Deputy Conservator of Forests, 4th grade has been allowed by His Majesty's Secretary of State for India to return to duty within the period of his leave.

4.—BENGAL GAZETTE.

25th November 1902.—No. 4139.—Consequent on the deputation to Foreign service of Mr. A. H. Mee, Extra-Assistant Conservator of Forests, 1st grade the following promotions are ordered, with effect from the 4th October 1902:—

Mr. T. F. Pocock, Extra-Assistant Conservator of Forests, 2nd grade, to be Extra-Assistant Conservator of Forests, 1st grade, sub. *pro tem.*

Mr. R. G. A. Hannah, Extra-Assistant Conservator of Forests, 3rd grade, to be Extra-Assistant Conservator of Forests, 2nd grade, sub. *pro tem.*

Mr. E. R. Comber, Forest Ranger 1st grade, to be Extra-Assistant Conservator of Forests, 4th grade, sub. *pro tem.*, and to be attached to the Chittagong Division.

3rd December 1902.—No. 4375 (Forest).—Mr. J. F. Gregson, Extra-Assistant Conservator of Forests, attached to the Sunderbans Division, is transferred to the Sonthal Parganas Division as an attached officer.

5.—UNITED PROVINCES OF AGRA AND OUDH GAZETTE.

28th November 1902.—No. 6090.—II. 691-1.—Mr. E. A. Courthope, who has been appointed to the Forest Department by the Secretary of State for India, and who reported his arrival in Allahabad on the forenoon of the 28th November 1902, to be an Assistant Conservator of Forests, 3rd grade, and to be attached to the Garhwal Division of the Central Forest Circle.

4th December 1902.—No. 6086.—II. [illegible].—Baba Nand Mal, Extra-Assistant Conservator of Forests, attached to the Naini Tal Forest Division, is granted privilege leave for two months, with effect from the [illegible] December 1902.

18th December 1902.—No 6262.—II 403c.—The following temporary reversions are notified for general information.—

Entry No	With effect from	Consequent on	Name	From	To
1	8th September 1902	The expiry of privilege leave granted to A G Hobart Hampden	Mr T J Campbell	Officiating Deputy Conservator of Forests 1st grade	Deputy Conservator of Forests 2nd grade
			F A Leete	Officiating Deputy Conservator of Forests 2nd grade	Deputy Conservator of Forests, 3rd grade
			H G Billson	Officiating Deputy Conservator of Forests 3rd grade	Deputy Conservator of Forests 4th grade
			F F R Channer	Officiating Deputy Conservator of Forests 4th grade	Assistant Conservator of Forests 1st grade

6.—PUNJAB GAZETTE.

22nd November 1902.—No 606.—*A L No* 30.—*Erratum*.—In Punjab Government Notification No 457—A L No 26 dated 28th July 1902—

	Name	Present grade	Grade to which promoted or reverted	With effect from	REMARKS.
For	Mr W Mayes	Deputy Conservator 4th grade	Officiating Deputy Conservator 3rd grade	6th June 1902	Consequent on the departure of Mr C G Hanson on 24 months privilege leave and concession leave with effect from 7th May 1902.
	Mr A A Dunbar Brander	Provisional Assistant Conservator 1st grade	Officiating Deputy Conservator, 4th grade		
Read	Mr W Mayes	Deputy Conservator 4th grade	Officiating Deputy Conservator, 3rd grade.	7th June 1902	Consequent on the departure of Mr C G Hanson on 24 months' privilege leave and concession leave with effect from the afternoon of the 7th May 1902.
	Mr. A A Dunbar Brander	Provisional Assistant Conservator, 1st grade	Officiating Deputy Conservator 4th grade		

12th *December* 1902.—No. 639.—*Notification*.—Mr A J. Gibson Officiating Deputy Conservator of Forests, is, with effect from the afternoon of [illegible] 1902, appointed Political Assistant to the Superintendent of the Hill States, Simla during the absence on privilege leave of Mr. A. L. McIntire, Deputy Conservator of Forests.

7.—CENTRAL PROVINCES GAZETTE.

12th November 1902.—No. 14.—Ramchandra Tatyaji Kanjrey, Forest Ranger, 6th grade, on Rs 50 per month, in the Raipur Forest Division, is granted two months' sick leave on medical certificate on half pay, with effect from the 21st October 1902.

13th November 1902.—No. 15.—Dinkar Vishnu Paranjpe, Forest Ranger, 4th grade, on Rs. 80 per mensem, attached to the Balaghat Division, is granted fifteen days' privilege leave, with effect from such date as he may be permitted to avail himself of it.

2nd December 1902.—No 6530.—K. Rama Rao, Ranger, 1st grade, is appointed to hold charge temporarily of the Nagpur-Wardha Division until further orders.

5th December 1902.—No 6640.—Mr C. A. Von B Malcolm, Assistant Conservator of Forests, who has been appointed by His Majesty's Secretary of State for India to the Imperial Forest Service, is attached to the Southern Circle, and is deputed to the Balaghat Forest Division, to assist the Forest Divisional Officer in the sleeper operations now in progress there.

5th December 1902.—No. 6641.—Mr. W. G. Morgan, Assistant Conservator of Forests, who has been appointed by His Majesty's Secretary of State for India to the Imperial Forest Service, is attached to the Northern Circle, and is posted to the Hoshangabad Forest Division, under the orders of the Forest Divisional Officer.

10th December 1902.—No. 16.—Ganpati Shanker N. Vaidya, Forest Ranger, 6th grade, on probation in the Bhandara Forest Division, is transferred to the Balaghat Division, for duty on sleeper works, with effect from the 1st December 1902.

11th December 1902.—No. 6774.—Privilege leave for one month, under Articles 277 and 291 of the Civil Service Regulations, is granted to Mr. C. Somers-Smith, Deputy Conservator of Forests, 2nd grade, in extension of the one month's extension of leave granted in Revenue Department Order No. 6143, dated the 5th November 1902.

13th December 1902.—No 6790.—Privilege leave for one month and fifteen days, in combination with furlough on medical certificate for ten months and fifteen days, under Articles 264-A and 343 of the Civil Service Regulations, is granted to Mr C. O. Hanson, Deputy Conservator of Forests, Seoni Forest Division, with effect from the 29th November 1902.

13th December 1902.—No 6791.—Mr. Faiz Bakhsh, Extra-Assistant Conservator of Forests, is appointed to hold charge of the Seoni Forest Division during the absence of Mr. C. O. Hanson on leave, or until further orders.

8.—BURMA GAZETTE.

10th November 1902.—No 21.—Leave on medical certificate for three months is granted to Maung Moh, Forest Ranger, 2nd grade, in extension of the combined leave for six months granted to him.

10th November 1902.—No 19.—With reference to Revenue Department Notification No 487 (Forests), dated the 20th October 1902, Mr. F. H. Todd, Deputy Conservator of Forests, joined the Pyinmana division on the forenoon of the 7th November 1902.

12th November 1902.—No. 470.—Mr. [illegible] Hill, Deputy Conservator of Forests, on return from leave, is posted to the charge of the Southern Shan States division.

18th November 1902.—No 471.—Under the provisions of Article 369 of the Civil Service Regulations Mr. J. L Hefferman, Extra-Assistant Conservator of Forests, is granted six months' leave on medical certificate, with effect from the 11th September 1902.

19th November 1902.—No 472 —Mr. W. J. G. Cooper, Extra-Assistant Conservator of Forests, on return from leave, is posted to the charge of the Kado Forest sub-division, Kado Forest division, *vice* Mr. D H Allan, Extra-Assistant Conservator of Forests, transferred.

19th November 1902.—No. 473.—Mr. D H. Allan, Extra-Assistant Conservator of Forests, on relief by Mr. W. J. G. Cooper, is posted to the charge of the Thaungyin Forest sub-division, *vice* Mr. P. E. Plunkett, Extra-Assistant Conservator of Forests, transferred.

19th November 1902.—No. 474 —Mr P E. Plunkett, Extra-Assistant Conservator of Forests, on relief by Mr D. H. Allen, is posted to the Toungoo Forest division for girdling duty.

19th November 1902.—No. 28 —Mr. H. W. A. Watson, Assistant Conservator of Forests, was relieved of his duties as Personal Assistant to the Conservator of Forests, Tenasserim Circle, on the afternoon of the 18th November 1902. and proceeded on Working-plans duty in the Shwegyin division.

23rd November 1902.—No. 20.—Mr. H. McL Carson, Ranger, 2nd grade. assumed charge of the Myitkyina range on the 22nd October 1902, on his return from six months' leave granted him with effect from the 13th June 1902.

The unexpired portion of the leave is cancelled.

27th November 1902.—No. 23 —With reference to Revenue Department Notification No. 434 (Forests), dated the 29th October 1902, Mr A. Rodgers, Officiating Deputy Conservator of Forests, assumed charge of the Pegu Working-plans division on the afternoon of the 19th November 1902.

2nd December 1902 —No 20 —With reference to Revenue Department Notification No 624 (Forests), dated the 10th October 1902 Mr. F. C. Purkis, Forest Ranger, was relieved of his duties in the Pyinmana division on the 17th November 1902.

2nd December 1902 —No 21 —With reference to Revenue Department Notification No 438 (Forests), dated the 30th October 1902 Mr. H L P. Walsh, Deputy Conservator of Forests, joined the Ruby Mines Division on the forenoon of the 17th November 1902.

3rd December 1902 —No. 520.—Mr. George Reginald Jeffery, who has been appointed by His Majesty's Secretary of State for India to the Imperial Forest Department as Assistant Conservator of Forests, 2nd grade, reported his arrival in Rangoon on the 1st December 1902, before noon.

Mr. Jeffery is posted to the Headquarters of the Mu Forest division of the Northern Circle.

3rd December 1902.—No. 29 —In continuation of this office Notification No 42, dated the 12th September 1902, Maing Kyaing, Ranger, 2nd grade, was granted a further extension of leave for five days, making three months in all, and on return to duty assumed charge of the Bawai range on the 22nd October 1902.

4th December 1902 —No 521 —Mr. G E. S Cubitt, Deputy Conservator of Forests, is transferred from the Yaw division to the charge of the Upper Chindwin division, *vice* Mr. F. Linnell, transferred.

4th December 1902.—No 522.—Mr. F. Linnell, Deputy Conservator of Forests, is transferred from the Upper Chindwin division to the charge of the Myittha division, *vice* Mr C. W. Doveton, transferred.

4th December 1902.—No. 523.—Mr. C. W. Doveton, Deputy Conservator of Forests, is transferred from the Myittha division to the charge of the Lower Chindwin division, *vice* Mr. H. Calthrop proceeding on leave.

6th December 1902.—No. 30.—With reference to Revenue Department Notification No 472 (Forests), dated the 19th November 1902, Mr W. J. G. Cooper, Extra-Assistant Conservator of Forests, on his return from the two months' privilege leave granted to him, took over charge of the Kado sub-division, relieving Mr D H Allan, Extra-Assistant Conservator of Forests, on the forenoon of the 24th November 1902.

8th December 1902.—No. 31.—With reference to Revenue Department Notification No. 473 (Forests), dated the 19th November 1902, Mr. D H. Allan, Extra-Assistant Conservator of Forests, on being relieved of the charge of the Kado sub-division took over charge of the Thaungyin sub division, relieving Mr. P. E Plunkett, Extra Assistant Conservator of Forests, on the forenoon of the 3rd December 1902.

8th December 1902.—No 32.—With reference to Revenue Department Notification No 419 (Forests), dated the 7th October 1902 Mr. A. E. Ross, Deputy Conservator of Forests, assumed charge of his duties as Working Plans Officer for the Taungyin division on the 7th November 1902.

9th December 1902 No 22.—With reference to Revenue Department Notification No. 521 (Forests), dated the 4th December 1902, Mr G Cubitt, Deputy Conservator of Forests, was relieved of his duties in the Yaw division on the afternoon of the 6th December 1902

15th December 1902 - No 33.—With reference to Revenue Department Notification No 474 (Forests), dated the 19th November 1902, Mr. P. E. Plunkett, Extra-Assistant Conservator of Forests, reported himself for girdling duty in the Toungoo division on the forenoon of the 10th December 1902.

16th December 1902.—No. 540.—Mr H Slade, Deputy Conservator of Forests, on being relieved of the charge of the Northern Circle, is posted to special duty in the Arakan (Civil) Division.

9.—ASSAM GAZETTE.

22nd November 1902—No 8765-G.—Babu Kripa Nath De, Extra-Assistant Conservator of Forests, on return from leave, is posted to the Nowgong Forest Division.

22nd November 1902—No. 8766-G.—Mr. J L Pigot, Deputy Conservator of Forests, Nowgong, on relief by Babu Kripa Nath De, is transferred to the Darrang Forest Division.

Pioneer Press, No. [illegible]

VIII.—EXTRACTS FROM OFFICIAL GAZETTES

1.—GAZETTE OF INDIA.

16*th December* 1902.—No. 1285-*F*.—132-22.—The undermentioned officers, who have been appointed by His Majesty's Secretary of State to the Forest Department of India, are appointed to be Assistant Conservators, 2nd grade, with effect from the dates specified opposite their names, and are posted to the provinces named below:—

Mr. V. G. Morgan, Central Provinces, 22nd November 1902.

" C. A. Von B. Malcolm, Central Provinces, 22nd November 1902.

" E. A. Courthope, United Provinces, 22nd November 1902.

" G. M. Townshend, Assam, 28th November 1902.

" G. R. Jeffery, Burma, 1st December 1902.

16*th December* 1902.—No. 1290-*F*.—184-8.—Mr. A. Smythies, Conservator of Forests, 2nd grade, Central Provinces, is permitted to retire from the service of Government, with effect from the 4th December 1902.

From the same date the following promotions are made:—

Mr. F. B. Bryant, Conservator 3rd (officiating 2nd) grade, Punjab, is confirmed in the 2nd grade.

Mr. T. A. Hauxwell, Conservator, 3rd grade, Lower Burma, to officiate as Conservator, 2nd grade.

Mr. A. G. Hobart-Hampden, Deputy Conservator, 1st grade, United Provinces (temporarily transferred to the Central Provinces), to be Conservator 3rd grade, and to hold charge of the Southern Circle, Central Provinces, of which he relieved Mr. Smythies on the afternoon of the 3rd December 1902.

19*th December* 1902.—No. 4242-22 10.—Mr. R. C. Wroughton, Conservator of Forests, Bombay, who was appointed in Notification No. 959, dated 31st March 1902, to officiate as Inspector-General of Forests to the Government of India, is confirmed in that appointmnet with effect from the 5th November, *vice* Mr. H. C. Hill deceased.

24*th December* 1902.—No. 1326-*F*.—On return from furlough, Mr. F. B. Manson, Conservator of Forests, 2nd grade, resumed charge of the Tenasserim Circle, Lower Burma, on the 12th December 1902, relieving Mr. T. A. Hauxwell, Officiating Conservator, 2nd grade.

From the same date Mr. Hauxwell reverted to his substantive appointment of Conservator, 3rd grade, and is posted to the charge of the Northern Forest Circle, Upper Burma.

29*th December* 1902.—No. 1331-*F*.—With reference to the notification of this Department, No. 1326 F., dated the 24th instant, Mr. T. A. Hauxwell, Conservator, 3rd grade, took over charge of the Northern Forest Circle, Upper Burma, in the forenoon of the 22nd December 1902, from Mr. H. Slade, Officiating Conservator, 3rd grade, who then reverted to his substantive appointment of Deputy Conservator, 1st grade, in Burma.

2.—MADRAS GAZETTE.

22nd December 1902.—*Appointment.*—K. Ramaswami Aiyar, Ranger, 6th grade, acting sub. *pro tem.*, Vizagapatam district, is confirmed with effect from 1st April 1902.

26th December 1902.—*Leave*—M. R. Ry V. R Venkataramiah, Ranger, Ganjam district is granted leave without allowances for thirteen days under Article 372 of the Civil Service Regulations from 30th November 1902.

2nd January 1903.—*Transfers*—Mr. H. H Ward, Extra-Assistant Conservator of Forests, from Nellore to Direction Division.

Mr. S C. Moss, Extra-Assistant Conservator of Forests, from North Arcot to Nellore.

15th January 1903—*Transfer*—Mr. H. H Ward. Extra Assistant Conservator of Forests, is transferred from Nellore to North Arcot. This cancels his transfer to Direction Division.

3.—BOMBAY GAZETTE.

5th January 1903.—No 14.—His Excellency the Governor in Council is pleased to appoint Mr D. A. Thomson, Deputy Conservator of the Forests, on return from leave, to be Working Plans Officer, Southern Circle.

6th January 1903—No. 44.—Mr. L. S. Osmaston, Deputy Conservator of Forests, 3rd grade, and Divisional Forest Officer, Nasik, is granted privilege leave of absence for two months and twenty days, in combination with furlough for six months and one day, from or after 11th April 1903.

10th January 1903—No. 134—Mr. N. D Sataravala, Divisional Forest Officer, Satara, passed an examination in Marathi according to the Lower Standard on 15th December 1902

Mr. G. E. Marjoribanks, Divisional Forest Officer, North Thana, passed an examination in Kanarese according to the Higher Standard on 15th December 1902.

10th January 1903.—No. 6925.—Mr. D. A. Thomson, Deputy Conservator of Forests, reported himself for duty to the undersigned on the 8th January 1903, forenoon, and was attached to the Conservator's office until the Working Plans office arrived at Head Quarters at Belgaum, where he took over charge of the same from Mr. W. E. Copleston, Deputy Conservator of Forests, by letter, on the forenoon of the 12th idem.

17th January 1903—No. 301.—His Excellency the Governor in Council is pleased to make the following appointments, *vice* Mr. R. C. Wroughton:—

Mr. T. B. Fry to be Ist grade Conservator of Forests.

Mr. W. A. Talbot to be 2nd grade Conservator of Forests.

Mr. R S. F. Fagan to be 3rd grade Conservator of Forests.

Mr. F. Gleadow to be Ist grade Deputy Conservator of Forests.

17th January 1903.—No. 306.—Mr. Dattatraya Manjunath Bijur, Extra-Assistant Conservator of Forests, 2nd grade and Sub-Divisional Forest Officer, North Thana, is granted privilege leave of absence for two months from or after 22nd January 1903.

17th January 1903—No. 307.—His Excellency the Governor in Council is pleased to appoint Mr Sitaram Hari Vaze to act as 4th grade Extra-

Assistant Conservator of Forests during the absence on leave of Mr. Dattatraya Manjunath Bijur or pending further orders.

20th January 1903.—No. 387.—His Excellency the Governor in Council is pleased to make the following appointments :—

Mr. H. W. Keys to be 2nd grade Deputy Conservator of Forests, *vice* Mr. G. K. Bentham, retired.

Mr. G. P. Millet to be 2nd grade Deputy Conservator of Forests, *vice* Mr. F. Gleadow, promoted.

Mr. W. F. D. Fisher to be 3rd grade Deputy Conservator of Forests, *vice* Mr. H. W. Keys, promoted.

Mr. O. H. L. Napier to be 3rd grade Deputy Conservator of Forests, *vice* Mr. Millet, promoted.

Mr. A. G. Edie to be 4th grade Deputy Conservator of Forests, *vice* Mr. Fisher, promoted.

Mr. E. M. Hodgson to be 4th grade Deputy Conservator of Forests, *vice* Mr. Napier, promoted.

Mr. C. S. McKenzie to be 1st grade Assistant Conservator of Forests, *vice* Mr. Edie, promoted.

Mr. H. L. Newman to be 1st grade Assistant Conservator of Forests, *vice* Mr. Hodgson, promoted.

20th January 1903.—No. 345.—His Excellency the Governor in Council is pleased to appoint Mr. G. E. Marjoribanks to be Assistant Conservator of Forests, 1st grade, with effect from the 7th January 1902.

4.—BENGAL GAZETTE.

26th December 1902.—No. 4920.—Mr. J. P. Haslett, Extra-Assistant Conservator of Forests, is, on return from leave, posted to the charge of the Palamau Forest Division.

Mr. Lalit Mohan Sen, Extra-Assistant Conservator of Forests, on being relieved of the charge of the Palamau Forest Division by Mr. Haslett, is re-attached to the Jalpaiguri Forest Division.

7th January 1903.—No. 14.—Mr. E. P. Stebbing, Deputy Conservator of Forests, is granted privilege leave for three months under Articles 277 and 291 of the Civil Service Regulations, combined with furlough for three months under Articles 264-A and 340 (*b*) of the Civil Service Regulations, with effect from the 5th January 1903.

19th January 1903.—No. 271.—Mr. E. P. Stebbing, Deputy Conservator of Forests, 4th grade, is granted privilege leave for three months combined with furlough for three months, under Articles 264-A and 340 of the Civil Service Regulations, with effect from the 5th January 1903, the date on which his services were replaced at the disposal of this Government by the Government of India.

In consequence of the above, the following changes have effect from the same date :—

Mr. J. W. A. Grieve, Deputy Conservator of Forests, 4th grade, sub. *pro tem.*, to officiate in that appointment.

Mr. E. R. Stevens, Assistant Conservator of Forests, 1st grade, sub. *pro tem.*, to officiate in that appointment.

5.—UNITED PROVINCES OF AGRA AND OUDH GAZETTE.

18th *December* 1902.—No. 6262—II/403c—The following temporary reversions are notified for general information:—

Entry No.	With effect from	Consequent on	Name.	From	To
1	8th September 1902.	The expiry of privilege leave granted to A G Hobart-Hampden.	Mr. T J. Campbell.	Officiating Deputy Conservator of Forests, 1st grade.	Deputy Conservator of Forests, 2nd grade.
			" F. A. Leete.	Officiating Deputy Conservator of Forests, 2nd grade.	Deputy Conservator of Forests, 3rd grade
			" H. G. Billson.	Officiating Deputy Conservator of Forests, 3rd grade	Deputy Conservator of Forests, 4th grade.
			" F F R. Channer.	Officiating Deputy Conservator of Forests, 4th grade.	Assistant Conservator of Forests, 1st grade.

23rd *December* 1902.—No. 6330—II/378c—Mr. R C. Milward, Officiating Deputy Conservator of Forests, on completion of the special duty on which he was placed by Notification No. 3572—II/378c., dated the 31st July 1902. to resume charge of the Dehra Dun Forest Division of the School Circle.

23rd *December* 1902—No. 6331—II/378c.—Lala Gulab Rai, Extra Assistant Conservator of Forests, in charge of the Dehra Dun Forest Division of the School Circle, on being relieved to be attached to that Division.

19th *December* 1902—No. 1118—VII/455B-22—The undermentioned gentlemen are declared to have passed the Departmental Examination of Junior Officers, held on 20th October 1902, and following days in the subjects specified below:—

Forest Officers.

Forest Law.

Mr. H C. Ross.

Land Revenue Systems.

Mr. H. C. Ross.
" H. B. Gawke.

Procedure and Accounts.

Babu Ram Swarup.
Pandit Hari Dutt Joshi.

9th *January* 1903.—No. 15—II/66A-10.—The following temporary promotions are notified for general information :—

Entry No.	With effect from	Consequent on	Name.	From	To
1	4th December 1902	The appointment of Mr A G Hobart Hampden Deputy Conservator of Forests, 1st grade, to be Conservator of Forests, 3rd grade.	Mr T J Campbell	Deputy Conservator of Forests, 2nd grade	Officiating Deputy Conservator of Forests, 1st grade
			Mr F A Leete.	Deputy Conservator of Forests, 3rd grade	Officiating Deputy Conservator of Forests, 2nd grade.
			Mr R. G Millson.	Deputy Conservator of Forests, 4th grade	Officiating Deputy Conservator of Forests, 3rd grade.
			Mr F F R Channer	Assistant Conservator of Forests, 1s grade	Officiating Deputy Conservator of Forests, 4th grade

13th *January* 1903 —No 74—III 1761C —Mr. W H Lovegrove, Deputy Conservator of Forests, on return from leave, to be attached to the Direction Division of the Central Circle.

6.—PUNJAB GAZETTE.

13th *January* 1903 —No 10 —A. L. No. 1 —Mr. W. Mayes, Deputy Conservator of Forests, on return from special leave on urgent private affairs, landed at Bombay on the forenoon of the 6th December 1902, and reported his arrival at Lahore on the forenoon of 9th December 1902, from which date he has been attached to the Direction Division and placed on special duty to inspect and report on the arboricultural work in the Jhang District.

7.—CENTRAL PROVINCES GAZETTE.

15th *December* 1902 —No 2 115 —The following changes among Forest Rangers in the Central Provinces have taken place with effect from the dates specified below :—

Name.	Present grade	Grade in which confirmed.	With effect from
C Alberts ..	6th grade on probation.	6th grade ..	1st April 1902.
Ramchandra Tatyaji Konjrey	Do. ..	Do ..	Do.
Shankar Dayal ..	Do. ..	Do. ..	Do.
[illegible] ..	Do. ..	Do. ..	Do.
Nasir Abbas ..	Do. ..	Do. ..	Do.
Ganpati Shankar N Vaidya.	Do. ..	Do. ..	Do.
Waman Amrit Pandit.	Do. ..	Do.	Do.

24th December 1902—No. 7025—Mr. Ramchandra Krishna, Extra-Assistant Conservator of Forests at present attached to the Direction Division Office, Jubbulpore, is appointed to hold charge of the Damoh Forest Division until further orders.

24th December 1902.—No. 7026—On being relieved by Mr. Ramchandra Krishna of the charge of the Damoh Forest Division Mr S R Parsons, Extra-Assistant Conservator of Forests, is attached to the Nimar Forest Division until further orders.

24th December 1902—No 7027.—On being relieved of the charge of the Saugor Forest Division by Mr. Somers Smith, Mr. A. L Chhatterji, Extra-Assistant Conservator of Forests, is attached to that Division until further orders.

15th January 1903—No 112—Consequent on the return from deputation of Mr. W. G. Gilmore, Extra-Assistant Conservator of Forests, 4th grade, Mr. A. L. Chhatterji, Extra-Assistant Conservator of Forests, 4th grade, sub *pro tem*, is reverted to his substantive appointment of Ranger, 1st grade, with effect from the 20th March 1902.

8.—BURMA GAZETTE.

15th December 1902—No 21—With reference to Revenue Department Notification No. 520 (Forests), dated the 3rd December 1902, Mr. G. R. Jeffery, Assistant Conservator of Forests, assumed charge of his duties in the Mu Forest division on the afternoon of the 4th December 1902.

18th December 1902—No 22—Mr. H Calthrop, Deputy Conservator of Forests, made over charge of the Lower Chindwin division, temporarily to Captain C L O Reid, Deputy Commissioner, Lower Chindwin district, on the afternoon of the 16th December 1902, and proceeded on the leave granted to him.

19th December 1902—No. 23.—With reference to Revenue Department Notification No. 521 (Forests), dated the 4th December 1902, Mr. F Linnell, Deputy Conservator of Forests, made over, and Mr G E. S. Cub tt, Deputy Conservator of Forests, received charge of the Upper Chindwin division on the afternoon of the 13th December 1902.

20th December 1902.—No. 24—With reference to Revenue Department Notification No. 523 (Forests). dated the 4th December 1902, Captain C. L. O. Reid, Deputy Commissioner, made over, and Mr. C. W. Doveton, Deputy Conservator of Forests, received charge of the Lower Chindwin Division on the afternoon of the 17th December 1902.

21st December 1902.—No. 546.—Under the provisions of Articles 277, 291, 340 (*b*) and 246-A of the Civil Service Regulations, Mr H. Calthrop, Deputy Conservator of Forests, is granted privilege leave for three months and furlough in continuation thereof for nine months, with effect from the date on which he may avail himself of the privilege leave.

22nd December 1902—No. 549—Furlough for one day is granted to Mr. H. H. Forteath, Deputy Conservator of Forests, in extension of the leave granted him in this department Notification No. 435 (Forests), dated the 14th November 1901.

29th December 1902—No. 558—This Department Notification No. 519 (Forests), dated the 2nd December 1902, is cancelled.

30th December 1902—No. 23.—With reference to Revenue Department Notification No. 470 (Forests), dated the 17th November 1902, Mr. M. Hill, Deputy Conservator of Forests, assumed charge of the Southern Shan States Division on the forenoon of the 18th December 1902.

31st December 1902.- No 25 – With reference to Revenue Department Notification No 522 (Forests), dated the 4th December 1902 Mr. C. W. Doveton, Deputy Conservator of Forests, made over, and Mr F. Linnell, Deputy Conservator of Forests, received charge of the Myittha Division on the afternoon of the 15th December 1902.

14th January 1903.—No 17.—On being relieved of the charge of the Northern Circle, Mr H Slade, Deputy Conservator of Forests was placed on special duty at Rangoon under the Conservator of Forests, Pegu Circle.

This Department Notification No. 540 (Forests), dated the 16th December 1902, is cancelled

9.—ASSAM GAZETTE.

10th January 1903 —No 221G.—On the report of the Central Examination Committee, the Chief Commissioner directs the publication, for general information, of the results of the Half-yearly Examination of Assistant Commissioners, Extra-Assistant Commissioners and other officers, held on the 10th, 11th, 12th, 13th, and 14th November 1902

Name.	SUBJECTS TAKEN UP BY CANDIDATES.		SUBJECTS IN WHICH PASSED.		SUBJECTS IN WHICH STILL REQUIRED TO PASS.	
	Higher standard.	Lower standard	Higher standard.	Lower standard.	Higher standard	Lower standard.
1	2	3	4	5	6	7
Forest Ranger.						
Babu Ram Nath Mukerji	Forest Law* Procedure and Accounts *		Forest Law Procedure and Accounts.			

10.—HYDERABAD RESIDENCY GAZETTE.

24th December 1902 —No. 347.—The Resident is pleased to invest Mr. N. Narasinga Rao, Forest Ranger of the 3rd grade (on Rs. 100) in the Hyderabad Assigned Districts with the power to compound forest offences under section 33 (3) of the Berar Forest Law 1886, as amended by the Berar Forest Law Amendment Law, 1891.

10th January 1903.—No 2.—Mr R M Williamson, a Deputy Conservator of Forests in the Hyderabad Assigned Districts, has been appointed to the charge of the Ellichpur Forest Division on return from leave

11.—MYSORE GAZETTE.

22nd December 1902.—No 421.—3488.—The privilege leave of absence for one month and a half granted to Mr M. G Rama Rao, Assistant Conservator of Forests, Kadur district, in Notification No 399—3,147 dated the 9th December 1902, is hereby cancelled at his own request.

Pioneer Press, No. 132.—2-3 03.

VIII.—EXTRACTS FROM OFFICIAL GAZETTES.

1.—GAZETTE OF INDIA.

Notification No. 3-1-E, dated 1st January 1903.

It had been the King-Emperor's intention to confer a Companionship of the Most Eminent Order of the Indian Empire on Mr Harry Charles Hill, in recognition of the able manner in which he had conducted his duties, during his long service in the Forest Department in India Mr Hill died on the 7th November, whilst on leave in England He held, at the time, the important post of Inspector-General of Forests.

19th January 1903 —No. 72 24 —2 —Mr. R. C. Wroughton, Inspector-General of Forests to the Government of India, is granted privilege leave for three months combined with furlough up to and including the 14th August 1904, with effect from the 2nd February 1903, or the subsequent date on which he may avail himself of it.

Mr S. Eardley-Wilmot, Conservator of Forests, 1st grade, Burma, is appointed to officiate as Inspector-General of Forests during the absence on leave of Mr. R C Wroughton or until further orders.

21st January 1903.—No. 32 F.—160 3 —With reference to the Notification of this Department, No 156-F.—41-2, dated 30th January 1901, the services of Mr. E P. Stebbing, Deputy Conservator of Forests, on special duty as Forest Entomologist, are replaced at the disposal of the Government of Bengal, with effect from the 5th January 1903.

2.—MADRAS GAZETTE.

20th January 1903 —M. R Ry. C. Seenayya, Acting Ranger, Kurnool district, is granted leave on medical certificate for three months from 10th December, 1902, under Article 373 of the Civil Service Regulations.

24th January 1903 —M R. Ry K. Ramaswami Aiyar, Forest Ranger, is transferred from Vizagapatam to Ganjam district.

24th January 1903 —*Leave.*—Mr. L. S. Janes, Ranger, 5th grade, South Coimbatore division, is granted privilege leave for two months and twenty-nine days from 21st September 1902, and sick leave for three months and six days in continuation thereof under Article 264-A of the Civil Service Regulations.

Notification published on page 1414, Part II of *Fort St. George Gazette*, dated 18th November 1902 is hereby cancelled.

26th January 1903.—*Promotions* —The following Deputy Rangers are promoted temporarily to the Rangers' class from 1st January 1903 :—

S Thambu Naidu
K. Venkata Subba Row.
Saiyid Yassim Saib.
H. Rama Row.

30th January 1903.—*Leave.*—Under Article 291 of the Civil Service Regulations, the Board of Revenue has granted privilege leave for one month to Mr. J. A. Daly. Extra-Assistant Conservator of Forests, with effect from the 12th January 1903.

2nd February 1903.—*Reversion* —M. R. Ry. V. R. Venkataramiah, Acting 4th grade Ranger, Ganjam district, will revert to his permanent appointment of Ranger, 5th grade, from 1st February 1903.

5th February 1903.—*Leave.*—M R. Ry. P. Anantha Row, Ranger, Kurnool district, is granted privilege leave for one day, *i.e.*, 9th January 1903, under Article 291 of the Civil Service Regulations.

6th *February* 1903 —*Cancelment of Transfer* —This office Service order No 7 of 1903, dated 24th January 1903, transferring M R Ry K Ramaswami Aiyar Ranger from Vizagapatam to Ganjam is cancelled

8th *February* 1903 —*Leave* —M R Ry S Eggia Narayana Sastri, Forest Ranger 2nd grade Ganjam district is granted leave on medical certificate for three months and ten days from 6th January 1903

12th *February* 1903 —*Departmental Test* —The following Subordinates have passed the Departmental test in parts noted against each of section 69 of the Forest Code, at the examination held on the 23rd January 1903 –

Name and Designation	In parts (*a*) or (*b*)
T Swaminatha Pillai, Probationary Forester 3rd grade	(*a*) & (*b*)
P K Venkatanaras Aiyar, Minor Produce Supervisor	(*a*) & (*b*)
Mr S Nicholas, Probationary Deputy Ranger, 3rd grade	(*a*) & (*b*)
S S Venkatarama Aiyangar, Deputy Ranger, 3rd grade	(*a*) & (*b*)
B S Venkataramaniah, Range Clerk	(*a*)
T M Parthasarathy Naidu, Acting Forester, 1st grade	(*a*)
S Gopalayya Forester, 2nd grade ...	(*a*)

3.—BOMBAY GAZETTE

28th *January* 1903 – No 615 – Mr E G Oliver Deputy Conservator of Forests, 3rd grade has been allowed by His Majesty's Secretary of State for India to return to duty within the period of his leave

4th *February* 1903 —No 3632 —Messrs L S Koppikar, Extra Assistant Conservator of Forests, and G R Duxbury Deputy Conservator of Forests respectively delivered over and received charge of the Sub Division Forest Office Satara on the afternoon of the 19th January 1903

16th *February* 1903 —No 1127 —Mr G E Marjoribanks Assistant Conservator of Forests 1st grade, is allowed privilege leave of absence for three months, in combination with leave on urgent private affairs for three months from or after 2nd May 1903

16th *February* 1903 —No 1131 —Mr W A Talbot Conservator of Forests 2nd grade is allowed privilege leave of absence for one month and two days in combination with furlough for eighteen months, from or after 4th May 1903

18th *February* 1903 —No 1176 —Mr Lakshman Shamrao Koppikar, Extra Assistant Conservator of Forests, 4th grade and Sub Divisional Forest Officer Satara is granted leave on private affairs for one month from 20th January 1903

4 —BENGAL GAZETTE

31st *January* 1903 —No 509 —On return from the leave granted in Notification No 794 F dated the 4th February 1902, Mr J P Haslett, Extra Assistant Conservator of Forests 2nd grade, is promoted to be Extra-Assistant Conservator of Forests, 1st grade, sub *pro tem*, with effect from the 22nd January 1903 From the same date Mr T I Pocock Extra-Assistant Conservator of Forests, 1st grade sub *pro tem*, reverted to his substantive appointment of Extra Assistant Conservator of Forests, 2nd grade.

17th *February* 1903 —No 900 —Consequent on the return of Mr. T H. Monteath, Assistant Conservator of Forests, 1st grade, from the leave granted in Notification No 1070 T R, dated the 16th June 1902, Mr J L Baker, Officiating Assistant Conservator of Forests, 1st grade, reverted to his substantive appointment of Assistant Conservator of Forests, 2nd grade, with effect from the 20th October 1902

5.—UNITED PROVINCES OF AGRA AND OUDH GAZETTE.

26th January 1903.—No. 266—II/86A-11.—The following temporary reversions are notified for general information :—

Entry No.	With effect from	Consequent on	Name	From	To
1	11th January 1903.	The return from leave of Mr. W. H. Lovegrove, Deputy Conservator of Forests, 2nd grade.	Mr. F. A. Leete.	Officiating Deputy Conservator of Forests, 2nd grade	Deputy Conservator of Forests, 3rd grade.
			" H. B. Billson	Officiating Deputy Conservator of Forests, 3rd grade.	Deputy Conservator of Forests, 4th grade.
			" F. F. R. Channer.	Officiating Deputy Conservator of Forests, 4th grade.	Assistant Conservator of Forests, 1st grade.

5th February 1903.—No. 394—II/665B-4.—The following promotions are notified for general information :—

Entry No.	With effect from	Consequent on	Name.	From	To
1	4th December 1902.	The promotion of Mr. A. G. Hobart-Hampden, Deputy Conservator of Forests, 1st grade, to be Conservator of Forests, 3rd grade.	Mr. T. J. Campbell.	Deputy Conservator of Forests, 2nd grade	Deputy Conservator of Forests, 3rd grade.
			Mr. W. H. Lovegrove.	Deputy Conservator of Forests, 2nd grade, prov. sub.	Deputy Conservator of Forests, 2nd grade.
			Mr. P. H. Clutterbuck	Deputy Conservator of Forests, 3rd grade.	Deputy Conservator of Forests, 2nd grade, prov. sub.
			Mr. F. A. Leete.	Deputy Conservator of Forests, 3rd grade, prov. sub.	Deputy Conservator of Forests, 3rd grade.
			Mr. J. C. Tulloch.	Deputy Conservator of Forests, 4th grade.	Deputy Conservator of Forests, 3rd grade, prov. sub.
			Mr. H. G. Billson.	Deputy Conservator of Forests, 4th grade, prov. sub.	Deputy Conservator of Forests, 4th grade.
			Mr. R. C. Milward.	Assistant Conservator of Forests, 1st grade.	Deputy Conservator of Forests, 4th grade, prov. sub.
			Mr. F. F. R. Channer.	Assistant Conservator of Forests, 1st grade, prov. sub.	Assistant Conservator of Forests, 1st grade.
			Mr. E. H. B. M. Dobree.	Assistant Conservator of Forests, 2nd grade.	Assistant Conservator of Forests, 1st grade, prov. sub.

17*th February* 1903.—No. 607—II/378c—Mr. R. C. Milward, Deputy Conservator of Forests, in charge of the Dehra Dun Division, School Circle, privilege leave for such period as may be due to him, combined with furlough for a total period of one year, with effect from the 15th March 1903, or subsequent date.

6.—PUNJAB GAZETTE.

7*th February* 1903—No 57—A L No. 2—Mr A L. McIntire, Deputy Conservator of Forests, on return from leave, took over charge of the Bashahr Forest Division, on the afternoon of the 26th January 1903, relieving Mr A. J Gibson, Officiating Deputy Conservator of Forests, who will on and from that date remain in charge of the Simla Forest Division.

7*th February* 1903.—No. 61—A. L. No. 3.—With reference to Notification No. 639, dated 11th December 1902, Mr. A L. McIntire. Deputy Conservator of Forests, on return from leave, took over charge of the duties of the Political Assistant to the Superintendent, Hill States, Simla, on the afternoon of the 26th January 1903, relieving Mr. A. J. Gibson, Officiating Deputy Conservator of Forests.

7.—CENTRAL PROVINCES GAZETTE.

21*st January* 1903.—No. 17.—Laiq Singh, Forest Ranger, 6th grade, on Rs 50 per mensem, attached to the Chanda Forest Division, is granted one month's privilege leave with effect from the 6th instant.

27*th January* 1903—No. 18.—The following transfers are ordered in the interests of the public service:—

(1) Ramchandra Tatyaji Konjrey, Forest Ranger, 6th grade, from the Raipur to the Seoni Division.

(2) Mr. E A. Rooke, Forest Ranger, 2nd grade, from the Seoni to the Raipur Division.

27*th January* 1903.—No. 19.—The two months' sick leave, on medical certificate, on half pay, granted to Ramchandra Tatyaji Konjrey, Forest Ranger, 6th grade, in Departmental Order No. 14, of the 12th November last, is hereby cancelled.

27*th January* 1903.—No 20—Waman Amrit Pandit, Forest Ranger, 6th grade, in the Balaghat Forest Division, is granted six months' sick leave, on medical certificate, on half pay, with effect from the 3rd instant.

8.—BURMA GAZETTE.

21*st January* 1903.—No. 35.—The following alterations in rank are ordered in the Imperial Forest Department, Burma:—

(1) With effect from the 2nd June 1902—
    Mr R. E Marsden, Assistant Conservator, 2nd grade, to officiate as Deputy Conservator 4th grade.

(2) With effect from the 15th August 1902—
    Mr. R. E. Marsden, Assistant Conservator, 2nd grade (officiating Deputy Conservator. 4th grade,) to officiate as Assistant Conservator, 1st grade.

(3) With effect from the 1st October 1902, consequent on the departure on leave of Mr. C. R Dun, Deputy Conservator of Forests, 4th (officiating 3rd) grade—
    Mr A. H. M. Lawson, Deputy Conservator, 4th grade, to officiate as Deputy Conservator, 3rd grade.
    Mr. L C. Davis, Assistant Conservator, 2nd (officiating 1st) grade, to officiate as Deputy Conservator, 4th grade.

(4) With effect from the 7th October 1902, consequent on the deputation of Mr H N. Thompson, Deputy Conservator of Forests, 3rd grade, to Southern Nigeria—

Mr S. Carr, Deputy Conservator, 4th (officiating 3rd) grade to be Deputy Conservator, 3rd grade, *prov. sub.*

Mr. C. W. Doveton, Deputy Conservator, 4th grade, to officiate as Deputy Conservator, 3rd grade.

Mr. R. S. Troup, Assistant Conservator, 1st grade (officiating Deputy Conservator, 4th grade,) to be Deputy Conservator, 4th grade, *prov sub.*

Mr. H. C. Walker, Assistant Conservator, 2nd grade (officiating Deputy Conservator. 4th grade,) to be Assistant Conservator, 1st grade, *prov sub.*, and to continue to officiate as Deputy Conservator, 4th grade.

Mr. R. E. Marsden, Assistant Conservator, 2nd (officiating 1st) grade, to officiate as Deputy Conservator, 4th grade.

(5) With effect from the 8th October 1902, consequent on the return from leave of Mr A. Lawrence, Assistant Conservator, 1st grade *prov. sub.*—

Mr R E. Marsden Assistant Conservator, 2nd grade (officiating Deputy Conservator, 4th grade,) to officiate as Assistant Conservator, 1st grade

(6) With effect from the 12th October 1902, consequent on the confirmation of Mr. E S Carr as Conservator of Forests—

Mr J. Copeland, Deputy Conservator, 2nd grade. to be Deputy Conservator 1st grade.

Mr. H. Jackson, Deputy Conservator, 3rd grade, to be Deputy Conservator, 2nd grade, and to continue to be seconded.

Mr. G. F. R Blackwell, Deputy Conservator, 3rd (officiating 2nd) grade, to be Deputy Conservator, 2nd grade, *prov. sub.*

Mr. C. W. Doveton, Deputy Conservator, 4th (officiating 3rd) grade, to revert to his substantive appointment.

Mr. L. C. Davis, Assistant Conservator, 2nd (officiating Deputy Conservator. 4th) grade, to officiate as Assistant Conservator, 1st grade.

(7) With effect from the 25th October 1902, consequent on the return from leave of Mr J Messer, Deputy Conservator, 3rd grade, and of Mr. J. Rorie, Assistant Conservator, 1st grade:—

Mr. A. H. M Lawson, Deputy Conservator, 4th (officiating 3rd) grade, to revert to his substantive appointment.

Mr. J Rorie, Assistant Conservator, 1st grade, to officiate as Deputy Conservator, 4th grade.

Mr. H. C. Walker, Assistant Conservator, 1st grade, *prov. sub.* (officiating Deputy Conservator 4th grade), to revert to his *prov. sub.* appointment.

Mr H. L. P. Walsh, Assistant Conservator, 1st grade, *prov. sub.* (officiating Deputy Conservator, 4th grade), to revert to his *prov. sub.* appointment.

(8) With effect from the 20th November 1902, consequent on the return from leave of Mr. A. Rodger, Assistant Conservator 1st grade, *prov sub.*

Mr. A. Rodger, Assistant Conservator, 1st grade, *prov. sub.*, to officiate as Deputy Conservator, 4th grade

Mr. A. Lawrence. Assistant Conservator, 1st grade, *prov. sub.* (officiating Deputy Conservator, 4th grade), to revert to his *prov. sub.* appointment.

(9) With effect from the 13th December 1902, consequent on the return from leave of Mr. M. Hill, Deputy Conservator, 3rd grade—

Mr. M. Hill, Deputy Conservator, 3rd grade, to officiate as Deputy Conservator 2nd grade.

Mr H. Carter, Deputy Conservator, 3rd (officiating 2nd) grade, to revert to his substantive appointment.

Mr C. B Smales, Deputy Conservator, 4th (officiating 3rd) grade to revert to his substantive appointment.

Mr A Rodger, Assistant Conservator, 1st grade, *prov. sub.* (officiating Deputy Conservator, 4th grade) to revert to his *prov. sub.* appointment.

(10) With effect from the 17th December 1902 consequent on the departure on leave of Mr. H. Calthrop, Deputy Conservator, 2nd grade.

Mr. H. Carter, Deputy Conservator, 3rd grade, to officiate as Deputy Conservator, 2nd grade.

Mr. C. B. Smales, Deputy Conservator, 4th grade, to officiate as Deputy Conservator, 3rd grade.

Mr. A. Rodger, Assistant Conservator, 1st grade, *prov. sub.*, to officiate as Deputy Conservator, 4th grade

(11) With effect from the 22nd December 1902, consequent on the reversion of Mr. H Slade to his substantive appointment of Deputy Conservator, 1st grade—

Mr. H B. Anthony, Deputy Conservator, 2nd (officiating 1st) grade, to revert to his substantive appointment

Mr. H Carter, Deputy Conservator (officiating 2nd) grade, to revert to his substantive appointment.

Mr. C. B. Smales, Deputy Conservator, 4th (officiating 3rd) grade, to revert to his substantive appointment.

Mr. A. Rodger, Assistant Conservator 1st grade, *prov. sub.* (officiating Deputy Conservator, 4th grade) to revert to his *prov. sub.* appointment.

21st January 1903—No. 10.—At the departmental examination held at Bassein, Akyab Sandoway, Moulmein, Mergui, Minbu, Pakôkku, Meiktila, Mandalay, Mogôk, Myitkyina, Mônywa, Kindat, Lashio, Taunggyi, Kêngtûng and Falam on the 3rd and 4th November 1902, the following officers passed the examination in Burmese by the standards specified below :—

HIGHER STANDARD.

Mr. H. McL. Carson, Forest Ranger.

LOWER STANDARD.

Mr. F. C. Purkis, Forest Ranger.

22nd January 1903—No. 31—(ADDENDUM)—In this Department Notification No 288 (Forests), dated the 18th July 1900, *for* the words "Extra Assistant Conservator of Forests" *read* "Extra Assistant Conservator of Forests, *prov. sub.*"

22nd January 1903.—No. 32.—The following alterations in rank are ordered in the Provincial Forest Service :—

(1) With effect from the 23rd February 1902, consequent on the transfer of Mr. C. W. B. Anderson, Extra Assistant Conservator of Forests, 1st grade, to the Port Blair Commission—

Mr. D. H. Allan, Extra-Assistant Conservator, 1st grade, *prov. sub.*, to be confirmed in that grade.

Mr. C. E. Allen, Extra-Assistant Conservator, 2nd grade, *prov. sub.*, to be confirmed in that grade.

Mr. G. T. Wrafter, Extra-Assistant Conservator, 3rd grade, *prov. sub*, to be confirmed in that grade.

Mr. A. S. Rencontre, Extra-Assistant Conservator, 4th grade, *prov. sub*, to be confirmed in that grade.

(2) With effect from the 14th March 1902, consequent on the return from deputation of Mr S. A. Wood, Extra-Assistant Conservator, 3rd grade—

Mr. P. E. Plunkett, Extra-Assistant Conservator, 3rd grade, *prov. sub*. to revert to his substantive appointment of Extra Assistant Conservator, 4th grade.

Mr. W. J Cooper, Extra Assistant Conservator, 4th grade, *prov sub*., to revert to his substantive appointment of Ranger, 1st grade

(3) With effect from the 7th July 1902—

Mr. J. W. Ryan, Extra-Assistant Conservator, 1st grade, *prov sub*., to be confirmed in that grade

Maung Yaing Extra Assistant Conservator, 2nd grade, to be Extra-Assistant Conservator, 1st grade, *prov. sub*.

This Department Notification No. 304, dated the 31st July 1902, is hereby cancelled.

(4) With effect from the 23rd September 1902, consequent on the deputation of Mr W. H Craddock, Extra-Assistant Conservator of Forests, 2nd grade, to the Federated Malay States—

Maung Tha Ka Do, Extra-Assistant Conservator, 3rd grade, to be Extra-Assistant Conservator, 2nd grade, *prov sub*.

Mr. P. E Plunkett Extra-Assistant Conservator, 4th grade, to be Extra Assistant Conservator, 3rd grade, *prov. sub*.

Mr. W. T Cooper, Ranger, 1st grade, to be Extra-Assistant Conservator, 4th grade, *prov. sub*.

27th January 1903—No 42—On his arrival in Burma, Mr A. R. Brown, probationary 6th grade Ranger, Madras Presidency, is appointed to be Forest Ranger, 3rd grade, and is attached to the Pyinmana Forest division.

29th January 1903.—No. 43—Mr D. A. Allan, Forest Ranger, 2nd grade, is transferred from the Maymyo Range, Mandalay division, to the charge of the Mergui Range, South Tenasserim division.

9th February 1903—No 63—Mr B. R Hutchins, 4th grade Ranger, is promoted to the 3rd grade, with effect from the 1st February 1903

9.—ASSAM GAZETTE.

22nd January 1903—No 373G.—Mr. G. M. Townshend, Assistant Conservator of Forests, who was posted temporarily to the Kamrup Forest Division from the 3rd December 1902, the date of his arrival, is transferred and attached to the Darrang Forest Division, until further orders.

10.—HYDERABAD RESIDENCY GAZETTE.

26th January 1903.—No. 28. The following transfers among the Divisional Forest Officers in Berar have been made by the Resident:—

Mr. Pandurang Narayan, Extra-Assistant Conservator of Forests, from Basim to Wun.

Mr. S. L. Kenny, Deputy Conservator of Forests, from Ellichpur to Basim.

Rai Bahadur Mansukh Rai, Extra-Assistant Conservator of Forests, is appointed to hold charge of the Basim Forest Division, in addition to his own duties, pending the arrival of Mr. S. L. Kenny.

7th February 1903.—No. 46.—On being relieved of the charge of the Wun Division by Mr. Srinivasalu Naidu, Mr. Pandurang Narayan, Extra-Assistant Conservator of Forests, is transferred and attached to the Ellichpur Division.

11.—MYSORE GAZETTE.

20th-21st January 1903.—No 454—4277.—Under Article 188 of the Mysore Service Regulations, Mr M. Venkatnarnappa, Deputy Conservator of Forests, Kolar District, has been granted privilege leave of absence for one month, with effect from the 16th January 1903. Mr G. E Ricketts, Head-Quarter Assistant to the Conservator of Forests, will be in charge of the Kolar District Forest Office, in addition to his own duties, during the absence of Mr. Venkatnarnappa on leave or until further orders.

9th February 1903.—No 481—4814.—Mr. M. Venkatnarnappa, Deputy Conservator of Forests, Kolar District, having availed himself of the leave granted to him in Notification No. 454—4277, dated 21st January 1903, on the afternoon of 15th January 1903, and returned to duty on the afternoon of 2nd February 1903, the unexpired portion of the leave, *viz.*, twelve days, is hereby cancelled.

Pioneer Press, No. 285.—1-4-03.

VIII.—EXTRACTS FROM OFFICIAL GAZETTES.

1.—GAZETTE OF INDIA.

20th February 1903.—No 214-F—36-3.—With reference to the Notification of this Department, No 72—24-2 (General), dated the 19th January 1903, Mr. S Eardley-Wilmot, Conservator, 1st grade, Lower Burma, assumed charge of the office of Inspector-General of Forests from Mr. R. C Wroughton, in the forenoon of the 4th February 1903.

From the same date, the following promotions are made during the absence of Mr Wroughton on leave, or until further orders:—

Mr E E Fernandez, Conservator, 2nd grade, Berar, to officiate as Conservator, 1st grade.

Mr. T A Hauxwell, Conservator, 3rd grade, Upper Burma, to officiat[illegible] Conservator, 2nd grade

Mr H Slade, Deputy Conservator, 1st grade, Burma, to officiate as Conservator, 3rd grade in charge of the Pegu Forest Circle, of which he relieved Mr. S. Eardley-Wilmot in the afternoon of the 24th January 1903.

2.—MADRAS GAZETTE.

18*th February* 1903 – *Departmental Test*.—The following candidates have passed the Departmental Test prescribed in Forest Code, paragraph 69, at the examination held in January 1903, in the subjects specified opposite their names:—

B. Jogeswara Rao, Probationary Deputy Ranger, Bellary—Forest Act and Rules and Code and Accounts.

A Bastian, Forester, Vizagapatam—Forest Act and Rules.

20th February 1903.—The officers mentioned below have been declared by the Board of Examiners to have passed at the half-yearly examination held in January 1903, in the subjects mentioned:—

F.L. ... Forest Law.
F.R. ... Forest Revenue.
O.P.A. ... Office Procedure and Accounts.

M.R.Ry. P. Annappa, Forest Ranger, 6th grade, in O P.A.

Mr. James Tapp, Extra-Assistant Conservator of Forests, 4th grade, in O P.A.

Mr. E. M. Crothers, Forest Ranger, 6th grade, in F.R.

M R Ry. V. Subramaniya Aiyar, Ranger, 4th grade (supernumerary), in F.L., F.R. and O P.A.

Mr. [illegible] M. Rego, Probationary Extra Assistant Conservator, 4th [illegible]de, in F.R.

[illegible] Ry T. M Parthasarathy Naidu, Acting Forester, 1st grade, in O P.A.

M.R.Ry. S Gopaliah, Forester, 2nd grade, in O.P A.

" K. S. Narayana Aiyangar, Ranger, 6th grade, in F.R.

" C. Seshagiri Rao, Forester, 3rd grade, in F.R.

27th February 1903.—No. 83 —In modification of the furlough for one year granted in notification No 395 and published at page 1096 of Part I of the *Fort St. George Gazette*, dated 28th October 1902, Mr. A P. Grenfell, Deputy Conservator of Forests, is granted privilege leave for 25 days combined with furlough on medical certificate for one year under Articles 264-A and 291 of the Civil Service Regulations (3rd edition)

4th March 1903 —No. 103 —Mr C J. Wouterez, Extra-Assistant Conservator of Forests, is granted privilege leave for 2 months and 15 days from the date of his relief under Article 260 of the Civil Service Regulations.

5th March 1903.—No 104.—Under Articles 260, 308(*b*) and 283 of the Civil Service Regulations, Mr. H. J. A Porter, Acting Conservator of Forests, Northern Circle, is granted privilege leave for 2 months and 15 days from or after the 11th April 1903, and furlough without medical certificate for 1 year 9 months and 15 days in continuation thereof

10th March 1903. - No. 105.—

(1) Mr. R. D Richmond to act as District Forest Officer, Tinnevelly.

(2) Mr. P. M. Lushington, to act as Working Plans Officer, Southern Circle, on relief by Mr. Richmond

(3) Mr. A. W. Lushington, to act as Conservator of Forests, 3rd grade, and to hold charge of the Northern Circle during the absence of Mr. H J. A. Porter on leave or until further orders.

(4) Mr. P M Lushington to be District Forest Officer, North Coimbatore, *vice* Mr. A. W Lushington.

16th March 1903 —No. 106.—Under Article 336 of the Civil Service Regulations (4th edition), Mr. H H. Ward, Extra-Assistant Conservator of Forests, is granted leave on medical certificate for 5 months and 11 days with effect from the 21st January 1903

3.—BOMBAY GAZETTE.

17th February 1903 —No. 3729 —Messrs G. R Duxbury and H. W. Keys, Deputy Conservators of Forests respectively delivered over and received charge of the Divisional Forest Office, Satára, on the 4th February 1903, in the forenoon.

17th February 1903.—No. 3730 —Messrs G. R. Duxbury and W. H. Keys, Deputy Conservators of Forests, respectively delivered over and received charge of the Sub-Division Forest Office, Satára, on the forenoon of the 4th February 1903.

9th February 1903.—No. 3401.—Mr. Dattatraya Manjunath Bijoor, Extra-Assistant Conservator of Forests, 2nd grade, delivered over and Mr Shitaram Hari Vaze, Ranger, 1st grade, received charge of the office of the Sub-Division Forest Office, North Thána, on the 11th February 1903, in the afternoon.

20th February 1903 —No 3757.—Messrs. H W. Keys, Deputy Conservator of Forests, and L. S. Koppikar respectively delivered over and received charge of the Sub-Division Forest Office, Satára, on the afternoon of the 4th February 1903.

3rd March 1903.—No 1471.—His Excellency the Governor in Council is pleased to appoint Mr. E. G Oliver, on return to duty, to be attached to the office of Conservator of Forests, Central Circle, as a temporary measure.

4th March 1903.—No. 1481.—His Excellency the Governor in Council is pleased to make the following appointments:

> Mr. A. G. Edie to be Divisional Forest Officer, Nasik, *vice* Mr. L. S. Osmaston proceeding on leave.
>
> Mr. T. R. D. Bell to hold charge of the office of Divisional Forest Officer, East Khandesh, in addition to his own duties, pending further orders.

17th March 1903.—No. 1856.—Mr. F Gleadow, Deputy Conservator of Forests 1st grade, is granted privilege leave of absence for three months in combination with furlough for fifteen months.

No 1857.—His Excellency the Governor in Council is pleased to appoint Mr H. Murray to act as Deputy Conservator of Forests, 1st grade, and to hold charge of the Sind Circle, *vice* Mr. F. Gleadow, pending further orders.

No. 1868.—Mr. J. Dodgson, Deputy Conservator of Forests, 4th grade, is allowed such privilege leave as may be due to him on the date he avails himself of it, in combination with special leave on urgent private affairs for such period as may bring the combined period of absence up to six months.

4.—Bengal Gazette.

24th February 1903.—No 1041 For.—Consequent on the death of Mr. J. P. Gregson, Extra-Assistant Conservator of Forests, 4th grade, Mr. E R Comber, Extra-Assistant Conservator of Forests, 4th grade, *sub. pro tem.* is confirmed in that grade.

21st February 1903.—No. 977 For.—The services of Mr E P. Stebbing, Deputy Conservator of Forests, are placed at the disposal of the Government of India, Department of Revenue and Agriculture, for employment as Officiating Superintendent of the Indian Museum.

23rd February 1903.—No 1019F.—Mr C. C Hatt, Deputy Conservator of Forests, is placed on special duty in connection with the preparation of a Working-plan for the forests of the Buxa Division, with effect from the 23rd January 1903—the date on which he completed the Working-plan for the Kurseong Division.

23rd February 1903.—No 1020 For.—On return from the leave granted in Notifications Nos 2192 For. and 2342T R., dated the 7th April 1902 and 10th October 1902, respectively, Mr. Guru Das Chatterjee, Extra-Assistant Conservator of Forests, 3rd grade, is promoted to be Extra-Assistant Conservator of Forests, 2nd grade, sub *pro tem*, with effect from the 26th January 1903. From the same date Mr. R. G. A. Hannah, Extra-Assistant Conservator of Forests, 2nd grade, *sub-pro tem*, reverted to his substantive appointment of Extra-Assistant Conservator of Forests, 3rd grade.

5.—United Provinces of Agra and Oudh Gazette.

4th March 1903.—No. 880 II-165C.—Babu Raghu Nath Pat'ak, Extra-Assistant Conservator of Forests in charge of the Saharanpur Forest Division of the School Circle to hold charge of the Dehra Dún Forest Division of that Circle in addition to his other duties, as a temporary measure.

4th March 1903.—No. 881-II-378C.—Mr R. H. B. M Dobree, Assistant Conservator of Forests, from the charge of the Ganges Forest Division of the Central Circle to that of the Dehra Dun Forest Division of the School Circle.

4th March 1903—No. 882.—II-378C.—Mr. W. H. Lovegrove, Deputy Conservator of Forests, attached to the Direction Forest Division of the Central Circle, to the charge of the Ganges Forest Division of that Circle.

18th March 1903—No 1083—II-114C.—Mr. P. H. Clutterbuck, Deputy Conservator of Forests in charge of the Kheri Forest Division, Oudh Circle, is granted furlough combined with such privilege leave as may be due to him for a total period of six and a half months, with effect from the 7th April 1903.

18th March 1903.—No. 1085—II-114C.—Mr. R. St G. Burke, Assistant Conservator of Forests, attached to the Kheri Forest Division, to the charge of the Gorakhpur Forest Division, Oudh Circle, *vice* Mr Billson transferred.

18th March 1903—No. 1084.—II-114C.—Mr. H. G. Billson. Deputy Conservator of Forests, from the charge of the Gorakhpur Forest Division, to that of the Kheri Forest Division of the Oudh Circle, *vice* Mr. P. H. Clutterbuck granted leave.

6.—PUNJAB GAZETTE.

19th February 1903—No. 89—A L No. 4—Mr. W. Mayes, Deputy Conservator of Forests on return from special duty in the Jhang District, took over charge of the Simla Forest Divison on the afternoon of the 7th February 1903, relieving Mr. A. J. Gibson, Officiating Deputy Conservator of Forests, who will until further orders remain attached to that Division.

6th March 1903.—No 109.—Consequent on the return from leave of Mr. C. F. Rossiter. Extra Deputy Conservator of Forests Munshi Fazal Din (I), Khan Bahadur, Officiating Extra Deputy Conservator of Forests, 4th grade, reverted to Extra-Assistant Conservator of Forests, 1st grade, with effect from the 17th September 1902:

7.—CENTRAL PROVINCES GAZETTE.

31st January 1903.—*Corrigendum.*—In Departmental Order No. 2-115, dated the 15th December 1902, *for* "1st April 1902" in column 4 against Waman Amrit Pandit, *read* "24th April 1902" as the date from which he was confirmed as Forest Ranger.

23rd February 1903.—No 21.—Ranger Ganpat Shanker Vaidya having completed the special duty upon which he was employed in the Balaghat Division, is re-transferred to the charge of the Bhawanthari Range, Bhandara Division, from the date of relief.

3rd March 1903—No 1105.—Privilege leave for eleven days, under Article 199(*a*) of the Civil Service Regulations, is granted to Mr. B. Inamati Shama Rao, Extra-Assistant Conservator of Forests, Chanda, with effect from the 9th to the 19th January 1903, both dates inclusive.

4th March 1903.—No 1108—On being relieved by Mr J. J. Hobday, Extra-Assistant Conservator of Forests of the charge of the Sambalpur Forest Division, Mr. B. Inamati Shama Rao, Extra-Assistant Conservator of Forests, is posted to the charge of the Moharli Sub-Division, Chanda.

4th March 1903—On being relieved by Mr. B. Inamati Shama Rao, Extra-Assistant Conservator of Forests, of the charge of the Moharli Sub-Division, Chanda, Mr. Dhanji Shah Nasarwanji Awasia, Extra-Assistant Conservator of Forests, is posted to the charge of the Pranhita-Godavery Sub-Division, Chanda.

8.—BURMA GAZETTE.

13th February 1903.—No. 1.—Leave on medical certificate for three months is granted to Maung Moh, Forest Ranger, 2nd grade, in extension of the leave granted to him in Notification No. 21, dated the 10th February 1902.

16th February 1903.—No. 63.—Mr. A. S. Rencontre, Extra-Assistant Conservator of Forests, is transferred from the Toungoo Forest Division to the Railway (Revenue) Range of the Tenasserim Circle, with headquarters at Toungoo.

18th February 1903.—No. 67.—Mr. C. E. Muriel, Deputy Conservator of Forests, is transferred from Pyinmana to the charge of the Upper Chindwin Forest Division, *vice* Mr. G. F. S. Cubitt, transferred.

18th February 1903.—No. 68.—On relief by Mr. Muriel, Mr. G. E. S. Cubitt, Deputy Conservator of Forests, is transferred from Kindat to the charge of the Pyinmana Forests Division.

19th February 1903.—No. 69.—Under the provisions of Article 366 of the Civil Service Regulations, extraordinary leave without allowances was granted to Mr. A. Rodger, officiating Deputy Conservator of Forests, for the 15th November 1902.

19th February 1903.—No. 70.—Mr. C. V. Ryan, Extra-Assistant Conservator of Forests, was temporarily placed in charge of the Southern Shan States Forest Division from the 7th to the 13th December 1902.

23rd February 1903.—No. 2.—Maung Po Ta, Ranger, 3rd grade, on being transferred from the Northern Circle, was posted to the Bassein range of the Bassein Division, and took over charge of the same on the afternoon of the 15th February 1903.

25th February 1903.—No. 3.—With reference to Revenue Department Notification No. 42 (Forests), dated 27th January 1903, Mr. A. R. Brown, Forest Ranger, joined the Pyinmana Division on the afternoon of 31st January 1903.

25th February 1903.—No. 4.—The headquarters of the Mandalay Forest Division have been transferred from Mandalay to Maymyo with effect from 10th January 1903.

5th March 1903.—No. 90.—Mr. W. H. Craddock, Extra Assistant Conservator of Forests, returned from the privilege leave granted him in Revenue Department Notification No. 271 (Forests), dated the 9th July 1902, on the 18th September 1902.

5th March 1903.—No. 91.—Mr. S. A. Wood, Extra-Assistant Conservator of Forests, is granted privilege leave for three months under the provisions of Article 260 of the Civil Service Regulations, with effect from the date on which he may avail himself of it.

7th March 1903.—No. 1.—With reference to Revenue Department Notification No. 63 (Forests), dated the 16th February 1903, Mr. A. S. Rencontre, Extra-Assistant Conservator of Forests, assumed charge of the Railway Revenue Range, with Headquarters at Toungoo, with effect from the 1st February 1903.

9.—ASSAM GAZETTE.

19th February 1903.—No. 1189G.—In consequence of the return to duty of Babu Kripa Nath De, Extra-Assistant Conservator of Forests, 2nd grade, *provisionally substantive*, Babu Ram Nath Mukharji, Officiating Extra-Assistant Conservator of Forests, 4th grade, to revert to his appointment of Forest Ranger, 1st grade, *provisionally substantive*, with effect from the 11th December 1902.

19th February 1903.—No. 1190G—Mr. J. L Pigot, Deputy Conservator of Forests, who was appointed to the charge of the Nowgong Forest Division, by Notification No 8203G, dated the 29th October 1902, was attached to that Division from the 18th to the 20th October 1902, previous to his taking over charge from Mr A R. Dicks.

19th February 1903 —No. 1191G.—In General Department Notification No 8878G, dated the 6th November 1902, ordering reversions in consequence of the return from leave of Mr J. L Pigot, Deputy Conservator of Forests, *for* "21st October 1902" *read* "18th October 1902."

10.—HYDERABAD RESIDENCY GAZETTE.—*Nil.*

11.—MYSORE GAZETTE.

20th February 1903.—No 514—5091 —The following transfers of Forest Officers are ordered in the public interests:—

(1) Mr. S A. Bapu Rao, Deputy Conservator of Forests, from the Shimoga District to the Kolar District.

(2) Mr M. Venkatnaranappa, Deputy Conservator of Forests, from the Kolar District to the Shimoga District.

VIII.-EXTRACTS FROM OFFICIAL GAZETTES.

1.—GAZETTE OF INDIA.—*Nil.*

2.—MADRAS GAZETTE.

20th March 1903.—No 114—Under Articles 233, 260 and 308(*b*) of the Civil Service Regulations, Mr. C. DuPré Thornton, Deputy Conservator of Forests, is granted privilege leave for two months and twenty days with effect from the 14th April 1903, and furlough without medical certificate for five months in continuation thereof.

20th March 1903—*Leave*—Under Article 260 of the Civil Service Regulations, 4th edition, the Board of Revenue has granted Mr. S. C. Moss, Extra-Assistant Conservator of Forests, Nellore, privilege leave for one month with effect from 22nd February 1903.

27th March 1903—*Leave.*—Mr A B Myers, Ranger, 2nd grade, South Coimbatore division, is granted two months' privilege leave from or after 1st April 1903 under Article 291 of the Civil Service Regulations.

28th March 1903—*Extension of Leave.*—The three months' leave on medical certificate granted to M R Ry. C Seenayya, Acting Ranger, Kurnool district, in this office S O. No. 4 of 1903, dated 20th January 1903, is extended by three months.

28th March 1903.—*Leave.*- Sheik Rahimatullah Sahib, Ranger, Kistna district, is granted leave without allowances for one month from 14th March 1903, under Article 372 of the Civil Service Regulations.

28th March 1903—*Transfer*—M R Ry. C. M. Maduranayakam Pillai Avargal, Extra-Assistant Conservator of Forests, 2nd grade, from the South Arcot district to the North Arcot district.

1st April 1903.—No. 139.—M. R Ry. V. S Gurunatha Pillai Avargal, Extra-Assistant Conservator of Forests, to act as District Forest Officer, Chingleput, without prejudice to his duties as Special Working-plans Officer, Central Circle, during the absence of Mr. C. J. Wouters on leave or until further orders.

9th April 1903—*Leave.*—M R. Ry. T. V. Arumugam Pillai, Ranger, 3rd grade, North Coimbatore division, is granted privilege leave for two months under Article 260 of the Civil Service Regulations, 4th edition, from the date of relief by Deputy Ranger K. R. Venkatramana Aiyar from Dehra Dun.

14th April 1903.—*Leave.*—Mr. G S. Lasrado, Ranger, 5th grade, North Malabar, is granted privilege leave for six weeks in continuation of Easter holidays under Article 260 of the Civil Service Regulations.

15th April 1903.—*Extension of Leave.*—The one month's leave on loss of pay granted to Sheik Rahimatullah Sahib, Ranger, Kistna district, in this office Service Order No. 56 of 1903, dated 28th March 1903, is extended by a fortnight.

16th April 1903—No. 153.—In modification of the leave granted to him in notification No. 114, published at page 364 of Part I of the *Fort St. George Gazette,* dated 24th March 1903, Mr. C. DuPré Thornton

Deputy Conservator of Forests, is granted privilege leave for two months and eighteen days with effect from 26th March 1903, and in continuation thereof furlough without medical certificate for five months under Articles 233, 260 and 308 (*b*) of the Civil Service Regulations.

16*th April* 1903.—No. 158.—M R Ry C. M Maduranayagam Pillai Avargal, Extra-Assistant Conservator of Forests to act as District Forest Officer, North Arcot, *vice* Mr C. D. P. Thornton on leave or until further orders.

3.—BOMBAY GAZETTE.

25*th March* 1903.—No. 2102.—His Excellency the Governor in Council is pleased to make the following appointments, *vice* Mr. Vishun Mahadev Tilak, deceased :—

Mr. Chuni Lal Gulab Chand Dalia, L C E, to be 2nd grade Extra Assistant Conservator of Forests

Mr. Bajibhai Jadhavbhai Patel, L. C E, to be 3rd grade Extra-Assistant Conservator of Forests.

Mr. Dinkar Narayan Damle to be 4th grade Extra-Assistant Conservator of Forests.

No 2103.—His Excellency the Governor in Council is pleased to make the following appointments :—

Mr H Murray to act as Conservator of Forests, *vice* Mr W A. Talbot proceeding on leave, and to continue to hold charge of the Sind Circle.

Mr G P. Millett to act as 1st grade Deputy Conservator of Forests, *vice* Mr. Murray, and to hold charge of the Northern Circle during the absence of Mr. Talbot, or pending further orders.

Mr E. G Oliver to be Divisional Forest Officer, Dharwar.

Mr W. A. Wallinger to be Divisional Forest Officer, Kolaba.

Mr W. E Copleston to hold charge of the office of Divisional Forest Officer N. D. Kanara, in addition to his own duties, *vice* Mr. Millett, pending further orders.

Mr G. M. Ryan to hold charge of the office of Divisional Forest Officer, North Thana, in addition to his own duties, *vice* Mr. G. E. Marjoribanks proceeding on leave, pending further orders.

The Conservator of Forests, Central Circle, to hold charge of the Working Plans Office, Central Circle, *vice* Mr. J. Dodgson, proceeding on leave.

Mr J. D Maitland-Kirwan to be attached to the office of the Conservator of Forests, Central Circle.

23*rd March* 1903.—No 2028.—Mr. A. D. Wilkins, Deputy Conservator of Forests, 2nd grade, is allowed such privilege leave as may be due to him on the date he avails himself of it, in combination with special leave for such period as may bring the combined period of absence up to six months.

23*rd March* 1903.—No 2028-*A*.—His Excellency the Governor in Council is pleased to appoint Mr. G R. Duxbury to act as Divisional Forest Officer, Poona, *vice* Mr. A. D. Wilkins proceeding on leave, pending further orders.

28*th March* 1903.—No. 8751.—Mr. E. G. Oliver, Deputy Conservator of Forests, reported himself for duty to this office on the forenoon of the 24th March 1903.

8th April 1903.—No. 2448.—Mr. C. S. McKenzie, Divisional Forest Officer, Jerruck, Sind Circle, passed an examination in Sindhi according to the Higher Standard on the 16th March 1903.

16th April 1903.—No. 145.—Messrs L. S. Osmaston and A. G. Edie, Deputy Conservators of Forests, respectively delivered over and received charge of the Divisional Forest Office, Nasik, on the afternoon of the 10th April 1903.

21st April 1903.—Mr. K. B. Gokhale, Sub-Divisional Forest Officer, S. D. Kanara, passed an examination in Kanarese according to the Lower Standard on the 18th March 1903.

21st April 1903.—No. 2622.—The leave on private affairs granted to Mr. Lakshman Shamrao Koppikar, Extra-Assistant Conservator of Forests, 4th grade, and Sub-Divisional Forest Officer Satara, in Government Notification No. 1176, dated 18th February 1903, is commuted into privilege leave for 16 days.

4.—BENGAL GAZETTE.—*Nil.*

5.—UNITED PROVINCES OF AGRA AND OUDH GAZETTE.

26th March 1903.—No. 1229.-II-868C.—Babu Nand Mal, Extra-Assistant Conservator of Forests in charge of the Ranikhet Sub-Division of the Naini Tal Forest Division, Central Circle, to the charge of that Division, *vice* Mr. T. J. Campbell on deputation.

28th March 1903.—No. 1276—II-378C.—Mr. R. C. Milward, Deputy Conservator of Forests, in charge of the Dehra Dun Forest Division of the School Circle, was on special duty in connection with the Working Plan of that Division, from the forenoon of the 16th March to the afternoon of the 24th March 1903.

28th March 1903.—No. 1304.—II-429C.—Lala Gulab Rai, Extra-Assistant Conservator of Forests, in charge of the Deoban Range, Jaunsar Forest Division, School Circle, to the charge of the Saharanpur and Dehra Dun Forest Divisions of that Circle, as a temporary measure, *vice* Babu Raghu Nath Pathak.

28th March 1903.—No. 1315—II-761C.—In supersession of Notification No. 74—II-761C, dated the 13th January 1903, Mr. W. H. Lovegrove, Deputy Conservator of Forests, on return from leave, was placed on special duty in the Bhabar and Tarai estates in the Naini Tal district, for the purpose of drawing up a scheme of management for the forest areas.

6.—PUNJAB GAZETTE.

20th March 1903.—No. 123.—His Honour the Lieutenant-Governor of the Punjab is pleased to order the following promotion with effect from the 1st March 1903:—

> Sardar Bishen Singh, Extra-Assistant Conservator of Forests 4th grade, to be Extra Assistant Conservator of Forests, 3rd grade, provisional, *vice* Lala Sundar Das, Extra-Assistant Conservator of Forests, on deputation to the Kotah State.

7th April 1903.—No. 164.—Messrs. J. C. Carroll and A. D. Blascheck, Assistant Conservators of Forests, respectively made over and received charge of the Direction Division and the duties of Personal Assistant to the Conservator of Forests, Punjab, on the afternoon of the 25th March 1903, consequent on the former's transfer to the Kulu Forest Division.

7th April 1903.—No. 166.—Messrs. H. A. Hoghton and W. Shakespear, Deputy Conservators of Forests, respectively made over and received charge of the Rawalpindi Forest Division on the afternoon of the 25th March 1903, consequent on the former's transfer from the Punjab.

7.—CENTRAL PROVINCES GAZETTE.

15th April 1903.—No. 1540.—Under section 67 of the Indian Forest Act (VII of 1878), the Officiating Chief Commissioner is pleased to invest Forest Ranger Ghanshyam Parshad with the powers described in that section.

8.—BURMA GAZETTE.

11th March 1903.—No. 5.—With reference to Revenue Department Notification No. 43 (Forests), dated the 29th January 1903, Mr. D. A. Allan, Forest Ranger, was relieved of his duties in the Mandalay division on the afternoon of the 2nd March 1903.

27th March 1903.—No. 112.—Under the provisions of Article 200 of the Civil Service Regulations, Mr. H. N. Thompson, Deputy Conservator of Forests, is granted privilege leave for the period from the 7th October 1902 to the 28th November 1902.

1st April 1903.—No. 116.—Mr. J. L. Heffernan, Extra-Assistant Conservator of Forests, has been granted by His Majesty's Secretary of State for India an extension of leave on medical certificate for six months.

1st April 1903.—No. 117.—Mr. C. M. Hodgson, Deputy Conservator of Forests, has been granted by His Majestys Secretary of State for India an extension of furlough for six months.

1st April 1903.—No. 118.—Mr. E. M. Buchanan, Extra Deputy Conservator of Forests, has been permitted by His Majesty's Secretary of State for India to spend the remainder of his leave in India.

1st April 1903.—No. 124.—The following alterations in rank are ordered in the Imperial Forest Department, Burma :—

With effect from the 4th February 1903, consequent on the appointment of Mr. H. Slade as officiating Conservator.

Mr. H. B. Anthony, Deputy Conservator, 2nd grade, to officiate as Deputy Conservator, 1st grade.

Mr. H. Carter, Deputy Conservator, 3rd grade, to officiate as Deputy Conservator, 2nd grade.

Mr. C. B. Smales, Deputy Conservator, 4th grade, to officiate as Deputy Conservator, 3rd grade.

Mr. A. Rodger, Assistant Conservator, 1st garde, *prov. sub.*, to officiate as Deputy Conservator, 4th grade.

Mr. H. C. Walker, Assistant Conservator, 1st grade, *prov. sub.*, to be Assistant Conservator, 2nd grade, and to officiate as Assistant Conservator, 1st grade.

1st April 1903.—No. 125.—(*Forests*).—The following alterations in rank are ordered in the Provincial Forest Department, Burma :—

(1) With effect from the 12th October 1902 :—

Mr. C. W. Allan, Extra Deputy Conservator, 4th grade, to be Extra Deputy Conservator, 3rd grade.

Mr. W. A. Hearsey, Extra-Assistant Conservator, 1st grade, to be Extra Deputy Conservator, 4th grade.

Maung Yaing, Extra-Assistant Conservator, 1st grade, *prov. sub.*, to be confirmed in that grade.

Mr R. L Pocock, Extra-Assistant Conservator, 2nd grade, to be Extra-Assistant Conservator, 1st grade, *prov sub.*

Mr. T. W. Forster, Extra-Assistant Conservator, 2nd grade, *prov. sub.*, to be confirmed in that grade.

Mr. J. L Hefferman, Extra-Assistant Conservator, 3rd grade, to be Extra-Assistant Conservator, 2nd grade, *prov. sub.*

Mr. C. V. Ryan, Extra-Assistant Conservator, 3rd grade, *prov sub.*, to be confirmed in that grade.

Mr. S E. F. Jenkins, Extra-Assistant Conservator, 4th grade, to be Extra-Assistant Conservator, 3rd grade, *prov. sub.*

Mr. W. R French, Extra-Assistant Conservator. 4th grade, *prov sub.* (on deputation to the Federated Malay State of Pahang), to be confirmed in that grade

(2) With effect from the 4th February 1903 :—

Mr. W. H Craddock, Extra-Assistant Conservator, 2nd grade (on deputation to the Federated Malay States), to be Extra-Assistant Conservator, 1st grade, *prov sub.*

Mr. C. E Allen, Extra-Assistant Conservator, 2nd grade, to be Extra-Assistant Conservator, 1st grade, *prov. sub.*

Mr. S. A. Wood, Extra-Assistant Conservator, 3rd grade, to be Extra-Assistant Conservator, 2nd grade, *prov. sub.*

Mr. B. P. Kelly, Extra-Assistant Conservator, 4th grade, to be Extra-Assistant Conservator, 3rd grade, *prov. sub.*

1st April 1903 —No. 126 —(*Forests*) —(*Corrigendum*).—In item No. (4) of this Department Notification No. 32 (Forests), dated the 22nd January 1903, *for* "23rd September" *read* "19th September."

1st April 1903.—No. 6.—With reference to Revenue Department Notification No. 67 (Forests), dated the 18th February 1903, Mr C E. Muriel, Deputy Conservator of Forests, was relieved of the charge of the Pyinmana division by Mr. F. H. Todd, Deputy Conservator of Forests, on the afternoon of the 25th March 1903.

2nd April 1903.—No 184.—The following promotions are ordered in the Subordinate Forest Service with effect from the 1st April 1903 :—

Maung San E, Ranger, 2nd grade, to be Ranger, 1st grade

Maung Aung Thu, Ranger, 4th grade, to be Ranger, 3rd grade, sub. *pro tem.*

Maung Pan U, Ranger, 4th grade, to be Ranger, 3rd grade, sub. *pro tem.*

6th April 1903.—No. 2.—Maung San E, Forest Ranger, 2nd grade, on return from the Forest School, Tharrawaddy, took charge of the Northern Range in the West Salween division, on the forenoon of 3rd January 1903, with headquarters at Papun.

15th April 1903 —No. 135 —Under the provisions of Article 260 of the Civil Service Regulations privilege leave for one month and fourteen days is granted to Mr. C. E Muriel, Deputy Conservator of Forests, with effect from the date on which he availed himself of it.

Mr. Muriel is permitted to overstay his leave by 15 days under Article 251 (ii) of the Civil Service Regulations.

15th April 1903 —No 136 —Revenue Department Notifications Nos 67 and 68 (Forests), dated the 18th February 1903, are hereby cancelled.

16th April 1903.—No. 143.—The following alterations in rank are ordered in the Imperial Forest Department, Burma, in supersession of the alterations published in items (4), (5), (6), (7) and (8) of this department Notification No. 35 (Forests), dated the 21st January 1903 :—

(1) With effect from the 8th October 1902, consequent on the return from leave of Mr. A. Lawrence, Assistant Conservator, 1st grade, *prov. sub.*

Mr. L. C. Davis, Assistant Conservator, 2nd grade (officiating Deputy Conservator, 4th grade), to officiate as Assistant Conservator, 1st grade.

(2) With effect from the 12th October 1902, consequent on the confirmation of Mr. E. S. Carr as Conservator of Forests :

Mr. J Copeland, Deputy Conservator, 2nd grade, to be Deputy Conservator, 1st grade.

Mr. H. Jackson, Deputy Conservator, 3rd grade, to be Deputy Conservator, 2nd grade, and to continue to be seconded.

Mr. G. F. R. Blackwell, Deputy Conservator, 3rd (officiating 2nd) grade, to be Deputy Conservator, 2nd grade, *prov. sub.*

Mr. A. H. M. Lawson, Deputy Conservator, 4th (officiating 3rd) grade, to revert to his substantive appointment.

Mr. H C. Walker, Assistant Conservator, 2nd grade (officiating Deputy Conservator, 4th grade), to officiate as Assistant Conservator, 1st grade.

(3) With effect from the 25th October 1902 consequent on the return from leave of Mr. J. Messer, Deputy Conservator, 3rd grade, and of Mr. J. Rorie, Assistant Conservator, 1st grade, *prov. sub.:*

Mr. C. B. Smales, Deputy Conservator, 4th (officiating 3rd) grade, to revert to his substantive appointment

Mr. J. Rorie, Assistant Conservator, 1st grade, *prov. sub.*, to officiate as Deputy Conservator, 4th grade.

Mr. A. Lawrence, Assistant Conservator, 1st grade, *prov. sub.* (officiating Deputy Conservator, 4th grade), to revert to his *prov. sub* appointment.

Mr. H. L P Walsh. Assistant Conservator, 1st grade, *prov. sub.* (officiating Deputy Conservator, 4th grade), to revert to his *prov. sub.* appointment.

(4) With effect from the 29th November 1902, consequent on the deputation of Mr H N. Thompson, Deputy Conservator of Forests, 3rd grade, to Southern Nigeria :

Mr. S. Carr, Deputy Conservator, 4th (officiating 3rd) grade to be Deputy Conservator, 3rd grade, *prov. sub.*

Mr. C. B. Smales, Deputy Conservator, 4th grade, to officiate as Deputy Conservator, 3rd grade.

Mr. R. S. Troup, Assistant Conservator, 1st grade (officiating Deputy Conservator, 4th grade), to be Deputy Conservator, 4th grade, *prov sub.*

Mr. A. Rodger, Assistant Conservator, 1st grade, *prov. sub.*, to officiate as Deputy Conservator, 4th grade.

Mr. H. C. Walker, Assistant Conservator, 2nd (officiating 1st) grade, to be Assistant Conservator, 1st grade, *prov. sub.*

16th April 1903—No 144.—This Department Notification No. 379, dated the 11th September 1902, is hereby cancelled.

9.—ASSAM GAZETTE.

31st March 1903.—No. 2722G.—In consequence of the deputation to Ceylon of Mr. J. L. Pigot, Deputy Conservator of Forests, 1st grade, the following promotions are made with effect from the 12th January 1903:

Mr. D. P. Copeland, Deputy Conservator of Forests, 2nd grade, to be Deputy Conservator of Forests, 1st grade, sub *pro tem*

Mr. H. G. Young, Deputy Conservator of Forests, 3rd grade, to be Deputy Conservator of Forests, 2nd grade, sub. *pro tem*

Mr. A. R. Dicks, Deputy Conservator of Forests, 4th grade, to be Deputy Conservator of Forests, 3rd grade, sub. *pro tem.*

Mr. W. A. R. Doxat, Officiating Deputy Conservator of Forests, 4th grade, to be sub *pro tem.* in that grade.

10.—HYDERABAD RESIDENCY GAZETTE.—*Nil.*

11.—MYSORE GAZETTE.

24th March 1903.—No. 586-5854.—The following promotions of Forest Rangers are ordered with effect from 14th March 1903 to fill up existing vacancies among Sub-Assistant and Extra-Assistant Conservators:

1. M. Srinivasa Rao, Ranger, 1st grade, to be Sub-Assistant Conservator, on the minimum pay of Rs 100.

2. H. Ramaiya, Ranger, 1st grade, to be Sub-Assistant Conservator, on the minimum pay of Rs 100.

3. V. Narasinha Murti Rao, Ranger, 2nd grade, to be Sub-Assistant Conservator, on Rs 100.

4. K. Muthaiya, Ranger, 2nd grade, to be Sub-Assistant Conservator, on Rs.100.

13th April 1903.- No.734-6.—Under Article 188 of the Mysore Service Regulations Mr. B. Heerasingh, Assistant Conservator of Forests and District Forest Officer, Tumkur District, is granted privilege leave of absence for three months with effect from the 15th April 1903 or such subsequent date as he may be permitted to avail himself of the same.

Mr M. Srinivasa Rao, Sub-Assistant Conservator, Shimoga, will be in charge of the Tumkur District Forest Office during the absence of Mr. Heerasingh on leave or until further orders.

Pioneer Press, No. 595.—1 6 03.

VIII.—EXTRACTS FROM OFFICIAL GAZETTES.

1.—Gazette of India.

30th April 1903.—No. 454—241-12-*F.*—Mr. J. W Oliver, Conservator of Forests, 1st grade, in charge of the School Circle, United Provinces, and Director of the Imperial Forest School, Dehra Dun, is granted privilege leave for three months, combined with furlough for one year five months and five days, with effect from the 6th April 1903

From the same date, the following arrangements are made during Mr. Oliver's absence, or until further orders:—

(*i*) Mr. F B. Manson, Conservator, 2nd grade, Lower Burma, to officiate as Conservator, 1st grade

(*ii*) Mr. J H. Lace, Conservator, 3rd grade, Bengal, to officiate as Conservator, 2nd grade.

(*iii*) Mr. A. G Hobart-Hampden, Conservator of Forests, 3rd grade, in charge of the Southern Circle, Central Provinces, is appointed to the charge of the School Circle, United Provinces, and Director of the Imperial Forest School, Dehra Dun, of which he relieved Mr. Oliver on the forenoon of the 6th April 1903.

Mr. H. A. Hoghton, Deputy Conservator of Forests, 2nd (officiating 1st) grade Punjab, is appointed to officiate as Conservator, 3rd grade, in charge of the Southern Circle, Central Provinces, of which he relieved Mr. Hobart-Hampden on the afternoon of the 4th April 1903.

30th April, 1903 - No. 460—53-5-*F*—Mr. J. H. Lace, Conservator, 3rd (officiating 2nd) grade, Bengal, is granted privilege leave for three months, combined with furlough for fifteen months, with effect from the 15th April 1903.

From the same date the following promotions are made:—

(*i*) Mr. E. S. Carr, Conservator, 3rd grade, Assam, to officiate as Conservator, 2nd grade.

(*ii*) Mr. A. L. McIntire, Deputy Conservator of Forests, 1st grade, *pron. sub*, Punjab, is appointed to officiate as Conservator, 3rd grade, in charge of the Bengal Forest Circle, of which he relieved Mr. Lace on the afternoon of the 14th April 1903.

30th April 1903.—No. 465—75-4-*F.*—Mr. F. B Dickinson, Conservator of Forests, 1st grade, in charge of the Central Circle, United Provinces, is granted privilege leave for three months, with effect from the 17th April 1903.

From the same date the following promotions are made:—

(*i*) Mr. E G. Chester, Conservator, 2nd grade, Central Provinces, to officiate as Conservator, 1st grade.

(*ii*) Mr. A. G. Hobart-Hampden, Conservator, 3rd grade, United Provinces, and Director of the Imperial Forest School, to officiate as Conservator, 2nd grade.

(*iii*) Mr. L. Mercer, Deputy Conservator of Forests, 2nd grade, United Provinces (on deputation to the Government of India), to officiate in the 3rd grade of Conservators until further orders, but to remain *seconded* as Assistant Inspector-General of Forests and Superintendent of Working-Plans.

(*iv*) Mr. T. J Campbell, Deputy Conservator of Forests, 1st grade, United Provinces, to officiate as Conservator, 3rd grade, in charge of the Central Circle, United Provinces, during the absence of Mr. Dickinson on leave or until further orders.

1st May 1903.—No 471—36-5-*F.*—*Erratum.*—In the Notification of this Department No 214F—36 3, dated the 20th February 1903, *substitute*, in the second paragraph, *for* the words "From the same date" the words "From the 25th March 1903"

13th May 1903.—No 516—66-4-*F.*—The services of Mr. J. L. Pigot, Deputy Conservator of Forests, 1st grade, Assam, are placed at the disposal of the Government of Ceylon, with effect from the 11th January 1903.

13th May 1903.—No 521—36 7-*F.*—*Erratum.*—In the Notification of this Department No 471—36 5-F, dated the 1st May 1903, *for* "25th March 1903," *substitute* "25th January 1903."

2 —MADRAS GAZETTE.—

22nd April 1903—No. 162—Under articles 233, 260 and 338 of the Civil Service Regulations, Mr T. G A. Gaudoin, Extra-Assistant Conservator of Forests, is granted, with effect from the date of his relief, privilege leave for two months and eight days, and in continuation thereof furlough up to and inclusive of 1st March 1904.

24th April 1903—M. R Ry. H Rama Rao, Acting Ranger, Kistna district, is granted privilege leave for seven weeks under article 260 of the Civil Service Regulations.

25th April 1903.—M.R Ry A.P. Ramachandra Mudaliar, Forest Ranger, 2nd grade, sub *pro tem*, from the Tanjore district to the Nellore district.

26th April 1903—Mr. E. M Crothers and M. R. Ry K. G. Venkatarama Aiyar, Rangers, 6th grade, are promoted to 5th grade, acting sub. *pro tem.*, with effect from 1st March 1903.

29th April 1903.—The following men, who have obtained the Higher Standard certificates of the Forest School are appointed as Rangers, 6th grade, sub *pro. tem*, on probation for six months from 1st April 1903:—

(1) M.R Ry V.S. Subramania Aiyar, Deputy Ranger, 2nd grade.

(2) M.R Ry M. Sreenivasa Rao, Forester, 2nd grade, and Acting Deputy Ranger, 2nd grade

(3) M. R. Ry. B Krishna Rao, Forester, 3rd grade, and Acting Deputy Ranger, 2nd grade.

(4) M R.Ry. K. Chengappa, Stipendiary student.

Appointment.—B. Sanniah, who has obtained the Dehra Dun Ranger's certificate, is appointed Deputy Ranger, 2nd grade, and to act as Ranger, 6th grade, and he is posted to the Anantapur District.

29th April 1903—The following promotions in the Southern Circle have been ordered by the Board:—

(1) M. P. Govindan, acting sub. *pro. tem.* Ranger, 5th grade, to be Ranger, 5th grade, permanent, with effect from 28th November 1902, *vice* S V. Audinarayana Aiyar, deceased.

(2) S. V. Venkatarama Aiyar, Ranger 6th grade, to be acting sub. *pro tem.* 5th grade, from 1st March 1903, to fill existing vacancy.

(3) K. S. Narayana Aiyangar, Ranger, 6th grade, to be acting sub. *pro tem.* 5th grade, from 1st March 1903, to fill existing vacancy.

1st May 1903.—The following is the result of the Government students deputed from the Southern Circle to the Dehra Dun Forest School for training in 1901:—

Rank.		Name.
1 out of 31 who passed	..	K. R. Venkatarama Aiyar, Acting Deputy Ranger, 1st grade, obtained Higher Standard certificate with honors. Awarded bronze medal in Forestry; the Campbell-Walker prize for the best student from Madras.
4 out of 31 who passed	..	A. M. C. Littlewood, Acting Deputy Ranger, 1st grade, obtained Higher Standard certificate with honors. Awarded bronze medal in Surveying and Drawing; Prothero Thomas prize for best student of the year in Practical Forestry: for the best note-book in Forestry and Engineering.
7 Do.	..	J. Sadasiva Aiyar, Acting Deputy Ranger, 1st grade, obtained Higher Standard certificate
12 Do.	..	A. H. Simpson, Acting Deputy Ranger, 1st grade, obtained Higher Standard certificate.

The following promotions are ordered with effect from 1st April 1903:—

(1) K. R. Venkatarama Aiyar, Acting Deputy Ranger, 1st grade, to be Ranger, 6th grade, to fill a vacancy.

(2) A. M. C. Littlewood, Acting Deputy Ranger, 1st grade, to be Ranger, 6th grade, to fill a vacancy.

(3) J. Sadasiva Aiyar, Acting Deputy Ranger, 1st grade, to be Ranger, 6th grade, to fill a vacancy.

(4) A. H. Simpson, Deputy Ranger, 3rd grade, and Acting Deputy Ranger, 1st grade, to be Ranger, 6th grade sub *pro. tem.*, *vice* Mr. H. O. Neill as probationary Extra-Assistant Conservator.

3.—BOMBAY GAZETTE.

19th February 1903.—No. 522.—Mr. Ganpat Ramji Mane, Extra-Assistant Conservator of Forests and Sub-Divisional Forest Officer, N. D., Kanara, is allowed thirty days' famine concession privilege leave with effect from such date as he may avail himself of it.

23rd April 1903.—No. 203.—Mr. Shitaram Hari Vase, Acting Extra-Assistant Conservator of Forests, 4th grade, delivered over, and Mr. Dattatraya Manjunath Bijoor, Extra-Assistant Conservator of Forests, 2nd grade, received charge of the office of the Sub-Divisional Forest Officer, North Thana, on the 11th April 1903, in the afternoon.

23rd April 1903.—No. 573.—Mr. W. A. Wallinger, Extra-Assistant Conservator of Forests, handed over, and Mr. E. G. Oliver, Deputy Conservator of Forests, received charge of the Dharwár Division on the forenoon of the 14th April 1903.

2. Mr. W. A. Wallinger also assumed charge of his duties as Sub-Divisional Forest Officer, Dhârwar, on the same date in the forenoon.

1st May 1903.—No. 292.—Messrs. A. G. Edie and T. R D. Bell, Deputy Conservators of Forests, respectively delivered over and received charge of the Divisional Forest Office, East Khandesh, on the afternoon of the 8th April 1903.

8th May 1903.—No 386.—Mr. G. E. Marjoribanks, Acting Deputy Conservator of Forests, 4th grade, delivered over, and Mr. G. M. Ryan, Acting Deputy Conservator of Forests, 2nd grade, received charge of the Office of the Divisional Forest Officer, North Thana, on the 1st May 1903, in the afternoon.

8th May 1903.—No. 1087.—Mr Ganpat Ramji Mane, Extra-Assistant Conservator of Forests and Sub-Divisional Forest Officer, N. D., Kanara, who was allowed thirty days' famine concession privilege leave in this Office Notification No 522, dated the 22nd ultimo, availed himself of the same on the afternoon of 1st May 1903, handing over charge of the Sub-Divisional Forest Office to Mr. G. P. Millett, Divisional Forest Officer, N. D. Kanara.

4.—BENGAL GAZETTE.

28th April 1903—No. 279 T R—Mr. J. W. A. Grieve, Officiating Deputy Conservator of Forests, in charge Tista Forest Division, is granted combined leave for seven months, *viz.*, privilege leave for three months under Article 233 of the Civil Service Regulations, with effect from the 15th May 1903, and furlough for the remaining period under Article 308 (*b*) of the Regulations.

Mr. T. H. Monteath, Assistant Conservator of Forests, in charge, Buxa Forest Division, is appointed to hold charge of the Tista Forest Division, during the absence, on leave, of Mr. Grieve, or until further orders

Mr. C C Hatt, Deputy Conservator of Forests, at present employed in making a working-plan for the Buxa Forests, is placed in charge of the Buxa Forest Division, *vice* Mr. Monteath.

14th May 1903.—No. 570 T. R.—Mr. J. L. Baker, Assistant Conservator of Forests, attached to the Singhbhum Forest Division, is transferred and temporarily placed in charge of the Sonthal Parganas Forest Division, during the absence, on deputation, of Mr. H. D. D. French, Deputy Conservator of Forests, or until further orders.

14th May 1903—No. 579 T. R.—The services of Mr. H. D. D. French, Deputy Conservator of Forests, are placed at the disposal of the Government of India in the Department of Revenue and Agriculture, for employment as Officiating Conservator of Forests, Oudh Circle, United Provinces, with effect from the date he is relieved of the charge of the Sonthal Parganas Forest Division.

5.—UNITED PROVINCES GAZETTE.

21st April 1903—No. 1583—II-665-B.—4.—With effect from the 28th March 1903, consequent on the death of Babu RaghuNath Pathak, Extra-Assistant Conservator of Forests, 1st grade :—

Lala Harswarup, Extra-Assistant Conservator of Forests, 2nd grade, to be Extra-Assistant Conservator of Forests, 1st grade.

Mr. E. L. Haslett, Extra-Assistant Conservator of Forests, 3rd grade, provisionally substantive, to be Extra-Assistant Conservator of Forests, 2nd grade.

Lala Permeshwari Din, Extra-Assistant Conservator of Forests, 4th grade, to be Extra-Assistant Conservator of Forests, 3rd grade, provisionally substantive.

Lala Gulab Rae, Extra-Assistant Conservator of Forests, 4th grade, provisionally substantive, to be confirmed in that appointment.

Munshi Medi Husain, Forest Ranger, 1st grade, to be Extra-Assistant Conservator of Forests, 4th grade, provisionally substantive.

18*th April* 1903.—No. 1561-II-85—A-11—The following temporary promotions and reversions are notified for general informations :—

Entry No.	With effect from	Consequent on	Name	From	To
1	25th March 1903.	The departure on leave of Mr R. C Milward	Mr F F. R. Channer	Assistant Conservator of Forests, 1st grade	Officiating Deputy Conservator of Forests, 4th grade.
2	7th April 1903.	The departure on leave of Mr. F H Clutterbuck.	,, F. A. Lecte	Deputy Conservator of Forests, 3rd grade.	Officiating Deputy Conservator of Forests, 2nd grade.
			,, H. G Billson.	Deputy Conservator of Forests, 4th grade.	Officiating Deputy Conservator of Forests, 3rd grade.
			,, R.H B.M. Dobree.	Assistant Conservator of Forests, 1st grade	Officiating Deputy Conservator of Forests, 4th grade.
3	17th April 1903.	The assumption by Mr. T. J. Campbell of the office of Conservator of Forests, Central Circle.	,, L Mercer. ,, W H Lovegrove.	Deputy Conservators of Forest, 2nd grade	Officiating Deputy Conservator of Forests, 1st grade.
			,, J C Tulloch.	Deputy Conservator of Forests, 3rd grade.	Officiating Deputy Conservator of Forests, 2nd grade.
			,, R. C. Milward on privilege leave.	Deputy Conservator of Forests, 4th grade.	Officiating Deputy Conservator of Forests, 3rd grade
			,, F. F. R. Channer.	Officiating Deputy Conservator of Forests, 4th grade.	Officiating Deputy Conservator of Forests, 3rd grade.

6.—PUNJAB GAZETTE.

2*nd May* 1903.—No. 186.—A. L. No. 5.—Mr. A. J. Gibson, Officiating Deputy Conservator of Forests, was transferred from the Simla *Division* and attached to the Bashahr Division with effect from the forenoon of the 2nd April 1903.

2*nd May* 1903.—No. 190—A. L No. 6—Mr. W. Shakespear, Deputy Conservator of Forests, and Pandit Gokal Das, Extra-Assistant Conservator of Forests, respectively made over and received charge of the Jhelum Forest Division on the forenoon of the 24th March 1903, consequent on the former's transfer to the Rawalpindi Forest Division.

Pandit Gokal Das will temporarily hold charge of the Jhelum Forest Division in addition to the Chenab Division.

2nd May 1903.—No 194—Pandit Gokal Das and Pandit Thakur Das, Extra-Assistant Conservators of Forests, respectively made over and received charge of the Chenab Forest Division on the afternoon of the 26th March 1903, on and from which date the former will hold charge of the Jhelum Division only.

2nd May 1903.—No. 197—A. L. No. 7.—Mr. E. M. Coventry, Deputy Conservator of Forests, and Mr. J. C. Carroll, Assistant Conservator of Forests, respectively made over and received charge of the Kulu Division on the afternoon of the 31st March 1903, consequent on the former's transfer to the Kangra Division.

2nd May 1903.—No. 201—A. L. No. 8.—Messrs G. S. Hart and E. M. Coventry, Deputy Conservators of Forests, respectively made over and received charge of the Kangra Division on the forenoon of the 1st April 1903, consequent on the former's transfer to the Bashahr Division.

2nd May 1903—No. 204—A. L. No. 9.—Messrs. A. L. McIntire and G S Hart, Deputy Conservator of Forests, respectively made over and received charge of the Bashahr Division on the afternoon of the 6th April 1903, consequent on the former's transfer to Bengal.

7.—CENTRAL PROVINCES GAZETTE.

14th March 1903—No. 9.—With the approval of the Honourable the Officiating Chief Commissioner, Central Provinces, Gulam Nabi Khan, Ranger, 4th grade, temporarily reduced to 5th grade, is permanently reduced to Forester, 1st grade, with effect from the 1st April 1903.

18th April 1903.—No 1.—Dinker Vishnu Paranjpe, Forest Ranger, reduced by the orders of the Honourable the Chief Commissioner. Central Provinces from the 3rd to the 4th grade for one year, is now restored to his place in the 3rd grade of Rangers on Rs 100, with effect from the 13th March 1903.

24th April 1903.—No 2.—Under the authority conferred by Article 31, clause (1), of the Forest Department Code, Diwaker Balwant Burhanpurai, Stipendiary Student who was deputed to the Imperial Forest School, Dehra Dun, under Rule 8 of the Admission Rules, in March 1901, and who has duly obtained the Higher Standard certificate of the school, is appointed Ranger, 6th grade on Rs 50 per mensem, on probation for six months, with effect from the 1st April 1903, and is posted to the Raipur Forest Division.

23rd April 1903.—No. 1702.—On return from the combined leave granted him by Order No. 2474, dated the 23rd May 1901, and Orders Nos. 5406 and 5408, dated the 25th September 1902, Mr. H E Bartlett, Deputy Conservator of Forests 4th grade, reported his arrival in Bombay on the forenoon of the 4th April 1903, and is attached to the Direction Division, Southern Circle, Central Provinces, from the forenoon of the 8th instant.

29th April 1903.—No. 1782.—Mr. L G. Smith, Deputy Conservator of Forests, has been granted, by His Majesty's Secretary of State for India, six months' leave on medical certificate, in extension of the leave granted him by Revenue Department Order No. 5255, dated the 17th September 1902.

29th April 1903—No 1789.—Mr. H. E. Bartlett, Deputy Conservator of Forests, attached temporarily to the Direction Division, Southern Circle, Central Provinces, is posted to the charge of the Nagpur-Wardha Division.

1st May 1903.—No. 3.—Sarmast Khan, Forest Ranger, Nagpur-Wardha Division, is transferred to the charge of the Laon Range, Raipur Division, from the date he is relieved.

4th May 1903.—No 1868—Privilege leave for three months, under Article 260 of the Civil Service Regulations (4th edition), is granted to Mr. A L Chatterji Extra-Assistant Conservator of Forests, with effect from the 4th May 1903, or the subsequent date on which he may avail himself of it.

8.—BURMA GAZETTE.

22nd April 1903—No. 3.—With reference to Revenue Department Notification No. 91 (Forests), dated the 5th March 1903, Mr. S A. Wood, Extra-Assistant Conservator of Forests, availed himself of the three months privilege leave on the afternoon of the 15th April 1903.

27th April 1903.—No. 3.—Maung Moh, Ranger, 2nd grade, assumed charge of the Railway Range, Tharrawaddy Division, on the afternoon of the 19th April 1903, on his return from 12 months' leave granted him with effect from the 18th May 1902. The unexpired portion of the leave is cancelled.

No 4—With reference to Revenue Department Notification No. 43 (Forests), dated the 29th January 1903, Mr. D. A. Allan, Forest Ranger, 2nd grade, assumed charge of the Mergui Range on the forenoon of the 18th March 1903.

7th May 1903—No 164—Under the provisions of Articles 260, 233 and 308 (*b*) of the Civil Service Regulations, Mr. C. B. Smales, Deputy Conservator of Forests, is granted privilege leave for three months and furlough in continuation thereof for one year and five months, with effect from the date on which he may avail himself of the privilege leave.

7th May 1903.—No 165—Under the provisions of Articles 260, 233 and 308 (*b*) of the Civil Service Regulations, Mr. A. H. M. Lawson, Deputy Conservator of Forests, is granted privilege leave for three months and furlough in continuation thereof for three months, with effect from the 25th May 1903, or such subsequent date as he may avail himself of the privilege leave.

7th May 1903—No. 166.—Mr. J. J Rorie, Officiating Deputy Conservator of Forests, is transferred from Working Plans duty in the Rangoon Division to the charge of the Prome Division, *vice* Mr. A. H. M. Lawson, Deputy Conservator of Forests, proceeding on leave.

(*Forests.*)—No. 167.—Mr. A. Rodger, Officiating Deputy Conservator of Forests, is transferred from Working Plans duty in the Pegu Division to the charge of the Thayetmyo Division, *vice* Mr. C. B. Smales, Deputy Conservator of Forests, proceeding on leave.

7th May 1903.—No. 4—(*Corrigendum*).—In this office Notification No. 3, dated the 27th April 1903, *for* the words "the Railway Range" *read* "special duty in or about Railway Depôts."

11th May 1903.—No. 169—The following alterations in rank are ordered in the Forest Department:—

With effect from the 26th March 1903, consequent on the departure on leave of Mr. C. E. Muriel, Deputy Conservator of Forests, 2nd grade:

Mr. F. J. Branthwaite, Deputy Conservator, 3rd grade, to officiate as Deputy Conservator, 2nd grade.

Mr. A. H. M. Lawson, Deputy Conservator, 4th grade, to officiate as Deputy Conservator, 3rd grade.

Mr. A. Lawrence, Assistant Conservator, 1st grade, *prov. sub.*, to officiate as Deputy Conservator, 4th grade.

11*th* *May* 1903.—No. 170.—Under the provisions of Articles 293, 260 and 336 of the Civil Service Regulations, Mr G. K Parker, Deputy Conservator of Forests, is granted privilege leave for three months and leave on medical certificate for six months in continuation thereof with effect from the date on which he may avail himself of the privilege leave.

11*th* *May* 1903—No. 171—Mr. A. E. Ross, Deputy Conservator of Forests, is posted to the charge of the West Salween Division, *vice* Mr. G. K. Parker, Deputy Conservator of Forests, proceeding on leave.

12*th* *May* 1903—No 172—The furlough for one year granted to Mr. E. M Buchanan, Extra Deputy Conservator of Forests, in this Department Notification No 129 (Forests), dated the 2nd April 1902, has been commuted by His Majesty's Secretary of State for India into leave on medical certificate and extended by two months. This Department Notification No 118 (Forests), dated the 1st April 1903, is hereby cancelled.

9.—ASSAM GAZETTE.—*Nil.*

10.—HYDERABAD RESIDENCY GAZETTE.—*Nil.*

11.—MYSORE GAZETTE.

17*th* *April* 1903—C. No. 747—10—Under Article 188 of the Mysore Service Regulations, Mr H. Srinivasa Rao, Assistant Conservator of Forests, Mysore District, is granted privilege leave of absence for eight days, with effect from the 20th April 1903, or such other date as he may avail himself of the same.

12*th* *May* 1903.—No. 1709—6995—In modification of Notification No. 254—1887, dated the 17th October 1902, the Government of His Highness the Maharaja of Mysore are pleased to direct that Mr. B Ramaswami Iyer, Forest Settlement Officer, Kadur and Chitaldrug Districts, be also appointed Settlement Officer in respect of forests of the Hassan District, which have been notified under Section 4 of the Mysore Forest Regulation

Pioneer Press, No. 761.—1-7-03.

VIII.—EXTRACTS FROM OFFICIAL GAZETTES.

1.—GAZETTE OF INDIA.

29th May 1903.—No. 577—258 6-F.—Mr. A. M. Reuther, Conservator, 2nd grade, Upper Burma, is granted privilege leave for three months combined with furlough for fifteen months, with effect from the 21st May 1903.

Mr J. Copeland, Deputy Conservator of Forests, 1st grade, Burma, is appointed to officiate as Conservator, 3rd grade, until further orders, and to hold charge of the Southern Circle, Upper Burma, of which he relieved Mr. Reuther on the afternoon of the 20th May 1903.

11th June 1903.—No 636—80-7 F.—Mr J. A. McKee, Conservator of Forests, 1st grade, United Provinces, is granted privilege leave for three months with effect from the 28th May 1903, combined with furlough extending to the 8th December 1903.

From the former date, the following appointments are made:—

(*i*) Mr. A. M. Reuther, Conservator, 2nd grade, Upper Burma, on privilege leave, to officiate as Conservator, 1st grade.

(*ii*) Mr. F. Beadon Bryant, Conservator, 2nd grade, Punjab, to officiate as Conservator, 1st grade, *vice* Mr A. M. Reuther.

(*iii*) Mr. H. D. D French, Deputy Conservator, 2nd grade, Bengal, to officiate as Conservator, 3rd grade, in charge of the Oudh Forest Circle, United Provinces, of which he relieved Mr. McKee on the afternoon of the 27th May 1903.

15th June 1903.—No. 656–119-8-F.—Privilege leave for three months, under Articles 246 and 260 of the Civil Service Regulations, combined with furlough for five months, under Articles 233 and 308 (*b*), is granted to Mr. B O Coventry, Instructor at the Imperial Forest School, Dehra Dun, with effect from the 1st July 1903, or the subsequent date on which he may avail himself of it.

2.—MADRAS GAZETTE.—

20th May 1903.—Under Article 260 of the Civil Service Regulations, (4th edition), the Board of Revenue has granted Mr. E. C. M. Mascurenhas, Extra-Assistant Conservator of Forests, privilege leave for one month with effect from or after 24th May 1903.

22nd May 1903.—*Transfers.*—The following transfers are ordered:—

Mr. L S. Janes, Ranger, 5th grade, from South Coimbatore division to Tinnevelly district, to relieve Mr. J. P. Nasareth, Ranger, 5th grade, who is transferred to North Coimbatore division.

M. R. Ry. T. V. Arumugam Pillai, Ranger, 3rd grade, acting, sub. *pro tem.*, North Coimbatore division, is, on return from leave, transferred to Tinnevelly district to relieve M. R. Ry. A. R Rama Row, Ranger, 4th grade, who is transferred to Madura district

23rd May 1903.—*Transfers.*—The following transfers are ordered:—

(1) M. R. Ry. Shaik Rahmatullah Sahib, Ranger, 4th grade, from Kistna district to Kurnool district, to join forthwith.

(2) M. R Ry. C. Seenayya, Acting Ranger, 6th grade, from Kurnool district to Vizagapatam district.

(3) M. R. Ry. N. Swaminatha Aiyar, Ranger, 5th grade, from Vizagapatam district to Kurnool district on relief by Acting Ranger C. Seenayya.

29th May 1903.—M. R. Ry. K. G. Venkatrama Aiyar, Ranger, Bellary district, is granted privilege leave for one month and twenty days from 4th May 1903, under Article 260 of the Civil Service Regulations.

29th May 1903.—Mr. T. N. Hearsey, Extra-Assistant Conservator of Forests, 1st grade, on return from Coorg, is posted to North Coimbatore to work under the orders of the District Forest Officer.

4th June 1903.—M. R. Ry. R. Sundram Pillai, Forest Ranger, 2nd grade, the Nilgiri district, is granted privilege leave, under Articles 260 and 345 of the Civil Service Regulations, for thirty days from 5th June 1903.

12th June 1903.—No. 233.—Mr. J. L. MacC. O'Leary, Assistant Conservator of Forests, is granted furlough for eighteen months with effect from the 15th June 1903.

16th June 1903.—No. 243.—The service of Mr. E. C. M. Mascarenhas, Extra-Assistant Conservator of Forests, 4th grade, on probation, are placed at the disposal of the Chief Commissioner of Coorg on the expiry of his leave.

2.—BOMBAY GAZETTE.

23rd May 1903—No. 592.—Messrs. A. D. Wilkins and G. R. Duxbury, Deputy Conservators of Forests, respectively delivered over and received charge of the Divisional Forest Office, Poona, on the afternoon of the 15th May 1903.

25th May 1903—No. 1839.—Messrs G. P. Millett and W. E. Copleston, Deputy Conservators of Forests respectively delivered over and received charge of the Northern Forest Division of Kanara on the afternoon of the 14th May 1903

Mr. G. P. Millett also delivered over charge of the Sub Divisional Forest Office, N. D., Kanara, to Mr. W. E. Copleston on the same date in the afternoon.

27th May 1903—No. 627.—Messrs J Dodgson, Deputy Conservator of Forests, and T B. Fry, Conservator of Forests, respectively delivered over and received charge of the Divisional Forest Office, Working-Plans, C. C., on the afternoon of 22nd May 1903.

30th May 1903—No. 3510.—In modification of Government Notification No. 1131, dated 16th February 1903, Mr. W. A. Talbot, Conservator of Forests, 2nd grade, is allowed privilege leave of absence for one month and three days, in combination with furlough for eighteen months.

1st June 1903—No. 677.—Mr. J. D. Maitland-Kirwan, Assistant Conservator of Forests, reported himself for duty in the undersigned's office on the 20th May 1903, before noon, as per Government Notification No. 2103, dated 25th March 1903, Revenue Department.

15th June 1903—No. 1914.—Mr G. R. Mane, Extra-Assistant Conservator of Forests, returned from the thirty days' privilege leave and received charge of the Sub-Divisional Forest Office, N. D., Kanara, from Mr. W. E. Copleston, Divisional Forest Officer, N. D., Kanara, on the forenoon of 1st instant.

16th June 1903—No. 3887.—Mr. H. Murray, Acting Conservator of Forests, 3rd grade, is allowed such privilege leave as may be due to him on the date he avails himself of it, in combination with special leave on urgent private affairs for such period as may bring the combined period of absence up to six months.

18th June 1903—No 3888.—His Excellency the Governor in Council is pleased to make the following appointments:—

Mr. G. P. Millett to act as Conservator of Forests, *vice* Mr. W. A. Talbot and during the absence on leave of Mr. H. Murray, continuing to hold charge of the Northern Circle pending further orders.

Mr. T. R. D. Bell to act as 1st grade Deputy Conservator of Forests *vice* Mr. Millett and to hold charge of the Sind Circle during the absence of Mr. H. Murray, or pending further orders.

Mr A C Robinson, L C. E, to act as Divisional Forest Officer, West Khandesh, *vice* Mr Bell, pending further orders.

Mr A G Edie to hold charge of the office of Divisional Forest Officer, East Khandesh, in addition to his own duties, as a temporary measure, pending further orders.

4.—BENGAL GAZETTE.

26th May 1903—No 748 T R.—In supersession of portion of Notification No 271 For., dated 19th January 1903, and in consequence of the changes notified in Notification No 1286 For, dated 10th March 1903, and No 977 For, dated 21st February 1903, the following reversions and promotions are ordered —

Mr. J. W A. Grieve, Deputy Conservator of Forests, 4th grade, sub. *pro tem*, reverted to Assistant Conservator of Forests, 1st grade, from 5th January 1903, was promoted to officiate as Deputy Conservator of Forests, 4th grade, on 9th January 1903 and to be Deputy Conservator of Forests, 4th grade, sub. *pro tem*, on the 19th February 1903.

Mr. E R Stevens, Assistant Conservator of Forests, 1st grade, sub. *pro tem.* reverted to Assistant Conservator of Forests, 2nd grade, from 5th January 1903, and was promoted to officiate as Assistant Conservator of Forests, 1st grade, on 9th January 1903, and to be Assistant Conservator of Forests, 1st grade, sub. *pro tem.*, on the 19th February 1903.

28th May 1903—No 764 T R—Mr E E Slane, Extra-Assistant Conservator of Forests, attached to the Sunderbans Forest Division, is granted privilege leave, under Article 260 of the Civil Service Regulations, for one month, with effect from the 21st May 1903, or from such subsequent date as he may be relieved of his duties.

5th June 1903—No. 914 T R—Sir Henry A. Farrington, Bart., Deputy Conservator of Forests, in charge Jalpaiguri Forest Division, is granted combined leave for eight months, *viz*, privilege leave for one month and twenty-four days, under Article 233 of the Civil Service Regulations, and furlough for the remaining period under Article 308 (*b*) of the Regulations, with effect from the 1st July 1903, or from such subsequent date as he may avail himself of it.

Mr. W. M Green, Deputy Conservator of Forests, in charge Kurseong Forest Division, is appointed to hold charge of the Jalpaiguri Forest Division in addition to his present duties, as a temporary measure, during the absence on leave of Sir H A Farrington, or until further orders.

5.—UNITED PROVINCES OF AGRA AND OUDH GAZETTE.

21st May 1903—No. 2085—II. 2370.—Lala Gulab Das, Extra-Assistant Conservator of Forests, in charge of the Saharanpur Forest Division of the School Circle, to hold charge of the Dehra Dun Forest Division of the same circle in addition to his other duties.

23rd May 1903—No 2112—II. 36C.—Babu Nand Mal, Extra-Assistant Conservator of Forests, in charge of the Ranikhet Sub-Division of the Naini Tal Forest Division, was on special duty in the Bhabar and Tarae estates in the Naini Tal district for the purpose of drawing up a scheme of management for the forest areas, from the 8th April to 11th May 1903, inclusive.

10th June 1903—No 2365—II 237C.—Munshi Mehdi Husain, Extra-Assistant Conservator of Forests, attached to the Garhwal Forest Division of the Central Circle, to hold charge of the Dehra Dun Forest Division of the School Circle, *vice* Lala Gulab Rai.

17th June 1903—No. 2491 - II —237C—In Notification No 2365—II 237C, dated 10th June 1903, appointing Munshi Medhi Hasan to the charge of a Forest Division, *for* "Dehra Dun Forest Division" *read* "Saharanpur Forest Division."

15th June 1903—No. 661—VII 455B-23.—The undermentioned gentlemen, other than Deputy Collectors, are declared to have passed the Departmental examination of Junior officers held on the 14th April 1903 and following days in the subjects specified below :—

Forest Officers.

Forest Law.

Mr. E. A. Courthope.

Land Revenue Systems.

Mr E. A. Courthope.

Procedure and Accounts.

Mr. E. A. Courthope.

6.—PUNJAB GAZETTE.

28th May 1903—No. 252—A. L. No. 10.—Errata to Punjab Government Notifications Nos. 238—A. L. No. 10, dated 7th April 1902, 297—A. L. No. 14, dated 7th May 1902, and 457—A L. No. 26, dated 28th July 1902:—

Name.	Present grade.	Grade to which promoted or reverted.	With effect from.	REMARKS.
Omit the following entries in No. 238—A. L. No. 10, dated 7th April 1902 :—				
Mr. J. C. Carroll ...	Provisional Assistant Conservator, 1st grade.	Assistant Conservator, 1st grade, and Officiating Deputy Conservator, 4th grade.	3rd March 1902.	Mr. Carroll having become permanent Assistant Conservator, 1st grade, resumes his place above Mr. Gibson, according to seniority.
Mr. A. P. Percival	Officiating Deputy Conservator, 4th grade.	Assistant Conservator, 1st grade.		
Instead of— Mr. A. J. Gibson ...	Officiating Deputy Conservator, 4th grade	Assistant Conservator, 1st grade.	4th March 1902.	Consequent on Mr. Fisher's return from leave.
Read— Mr. A. P. Percival	Officiating Deputy Conservator, 4th grade	Assistant Conservator, 1st grade.		

Name.	Present grade.	Grade to which promoted or reverted.	With effect from.	REMARKS.
Instead of—				
Mr. A. J. Gibson ...	Assistant Conservator, 1st grade.	Officiating Deputy Conservator, 4th grade.	4th March 1902.	Consequent on the retirement of Mr. Minniken.
Read—				
Mr A. P. Percival	Assistant Conservator, 1st grade.	Officiating Deputy Conservator, 4th grade		
Omit—				
Appointment No. 32 (Classified List for July 1901)	Provisional Assistant Conservator, 1st grade.	Assistant Conservator, 1st grade.	4th March 1902.	
In Notification No. 297, dated 7th May 1902.				
Instead of—				
Mr. A P. Percival	Assistant Conservator, 1st grade	Officiating Deputy Conservator, 4th grade	20th March 1902.	Consequent on Mr. Gisborne Smith proceeding on 7½ months' furlough.
Read—				
Mr J C. Carroll ..	Provisional Assistant Conservator, 1st grade	Officiating Deputy Conservator, 4th grade.		
In Notification No. 457 dated 28th July 1902				
Instead of—				
Mr A. P. Percival	Officiating Deputy Conservator, 4th grade.	Assistant Conservator, 1st grade,	15th May 1902.	Consequent on the return of Mr A W. Blunt from deputation to Rewah State.
Read—				
Mr J C. Carroll.	Officiating Deputy Conservator, 4th grade.	Provisional Assistant Conservator, 1st grade		
Instead of—				
Mr A. P. Percival.	Assistant Conservator, 1st grade.	Officiating Deputy Conservator, 4th grade.	1st June 1902.	Consequent on the departure of Mr R. A. Hole on three months' privilege leave with effect from the afternoon of 1st May 1902.
Read—				
Mr J. C. Carroll,	Provisional Assistant Conservator, 1st grade.	Officiating Deputy Conservator, 4th grade.		

28*th May* 1903—No 256—A. L. No. 11.—The following changes have taken place in the List of Forest Officers in the Associated Provinces with effect from the date specified against each :—

Name.	Present grade.	Grade to which promoted or reverted.	With effect from.	REMARKS.
Mr. A. W. Blunt ...	Deputy Conservator, 3rd grade.	Officiating Deputy Conservator, 2nd grade.	31st September 1902.	Consequent on the departure of Mr. C. Somers-smith on two months' privilege leave with effect from the afternoon of the 30th September 1902.
Mr. C. M. McCrie,	Provisional Deputy Conservator, 4th grade.	Officiating Deputy Conservator, 3rd grade.		
Mr. A. E. Lowrie ...	Deputy Conservator, 2nd grade.	Officiating Deputy Conservator, 1st grade.	30th October 1902.	Consequent on the departure of Mr. A. L. McIntire on three months' privilege leave with effect from the afternoon of the [illegible] October 1902.
Mr. A. M. F. Caccia	Deputy Conservator, 3rd grade.	Officiating Deputy Conservator, 2nd grade		
Mr. S. L. Kenny ...	Provisional Deputy Conservator, 4th grade.	Officiating Deputy Conservator, 3rd grade.		

28th May 1903—No. 960.—A. L. No. 12.—The following changes have taken place in the List of Forest Officers in the Associated Provinces with effect from the date specified against each :—

Name.	Present grade.	Grade to which promoted or reverted.	With effect from.	REMARKS.
Mr. R. S. Hole ...	Assistant Conservator, 1st grade.	Officiating Deputy Conservator, 4th grade.	8th November 1902.	Consequent on his return from privilege and special leave on the afternoon of the 7th November 1902.
Mr. A. A. Dunbar Brander.	Provisional Assistant Conservator, 1st grade.	Officiating Deputy Conservator, 4th grade.	29th November 1902.	Consequent on his return from privilege and special leave on the forenoon of 29th November 1902
Mr. R. S. Hole ...	Officiating Deputy Conservator, 4th grade	Officiating Deputy Conservator, 3rd grade.	29th November 1902	Consequent on the departure of Mr C O. Hanson on 1½ months' privilege leave and 10½ months' furlough on the afternoon of the 28th November 1902
Mr W Mayes ...	Deputy Conservator, 4th grade.	Officiating Deputy Conservator, 3rd grade.	9th Decr 1902	Consequent on the return of Mr Mayes from leave on the forenoon of the 9th December 1902.
Mr. R. S Hole ...	Officiating Deputy Conservator, 3rd grade	Officiating Deputy Conservator 4th grade.		
Mr. S. L. Kenny.	Officiating Deputy Conservator, 3rd grade.	Provisional Deputy Conservator, 4th grade.	18th Decr. 1902.	Consequent on the return of Mr. Williamson from leave on the forenoon of the 18th December 1902.
Mr. A. D. Blascheck	Officiating Deputy Conservator, 4th grade.	Provisional Assistant Conservator, 1st grade.		
Mr. A. M. F. Caccia.	Officiating Deputy Conservator, 2nd grade.	Deputy Conservator, 3rd grade	31st Decr. 1902.	Consequent on the return of Mr. C. Somers-Smith from leave on the afternoon of the 30th December 1902.
Mr. C. M. McCrie.	Officiating Deputy Conservator, 3rd grade.	Provisional Deputy Conservator, 4th grade.		
Mr. A. A. Dunbar Brander.	Officiating Deputy Conservator, 4th grade.	Provisional Assistant Conservator, 1st grade.		
Mr. A. E. Lowrie...	Officiating Deputy Conservator, 1st grade.	Deputy Conservator, 2nd grade.	27th Jan. 1903.	Consequent on the return from leave of Mr. A. L. McIntire on the afternoon of the [illegible] January 1903.
A. W. Hunt..	Officiating Deputy Conservator, 2nd grade.	Deputy Conservator, 3rd grade.		
Mr. W. Mayes ...	Officiating Deputy Conservator, 3rd grade.	Deputy Conservator, 4th grade.		
Mr. J. C. Cassell...	Officiating Deputy Conservator, 4th grade.	Provisional Assistant Conservator, 1st grade.		

28*th May* 1903—No 264—A L. No 13—The following changes have taken place in the List of Forest Officers in the Associated Provinces with effect from the date specified against each —

Name	Present grade	Grade to which promoted or reverted	With effect from	REMARKS.
Mr. H B. Bartlett	Deputy Conservator, 4th grade	Officiating Deputy Conservator, 3rd grade	4th April 1903	Consequent on his return from combined leave on the forenoon of the 4th April 1903.
Mr A St V Beechey	Officiating Deputy Conservator, 3rd grade	Deputy Conservator, 4th grade	4th April 1903.	Consequent on Mr H B. Bartlett's return from combined leave on the forenoon of the 4th April 1903
Mr. A. P Percival	Officiating Deputy Conservator, 4th grade	Assistant Conservator 1st grade		
Mr A E Lowrie	Deputy Conservator 2nd grade	Officiating Deputy Conservator, 1st grade	5th April 1903	Consequent on Mr H. A. Hoghton's appointment to officiate as Conservator on the afternoon of the 4th April 1903.
Mr A W Blunt	Deputy Conservator, 3rd grade	Officiating Deputy Conservator, 2nd grade.		
Mr A St V. Beechey	Deputy Conservator, 4th grade	Officiating Deputy Conservator, 3rd grade		
Mr. A P Percival	Assistant Conservator, 1st grade	Officiating Deputy Conservator, 4th grade		

28*th May* 1903—No 268—A L No 14—The following changes have taken place in the List of Forest Officers in the Associated Provinces with effect from the date specified against each :—

Name.	Present grade	Grade to which promoted or reverted.	With effect from	REMARKS.
Mr G S. Hart	Deputy Conservator, 2nd grade	Officiating Deputy Conservator, 1st grade.	16th April 1903.	Consequent on Mr A. L. McIntire's appointment to officiate as Conservator from the afternoon of the 15th April 1903.
Mr. A. M F. Caccia	Deputy Conservator, 3rd grade	Officiating Deputy Conservator, 2nd grade.		
Mr W. Mayes ..	Deputy Conservator, 4th grade	Officiating Deputy Conservator, 3rd grade.		
Mr. J. C. Carrell...	Provisional Assistant Conservator, 1st grade.	Officiating Deputy Conservator, 4th grade.		

28*th May* 1903—No. 249—*Appointment.*—Mr. G. S. Hart, Deputy Conservator of Forests, is, with effect from the afternoon of the 6th April 1903, appointed Political Assistant to the Superintendent of Hill States, Simla, vice Mr A. L McIntire, Deputy Conservator of Forests, transferred.

7.—CENTRAL PROVINCES GAZETTE.

21st May 1903—No. 2086.—Privilege leave for three months, under Article 260 of the Civil Service Regulations (4th edition), combined with special leave on urgent private affairs for three months, is granted to Mr. A. P Percival, Officiating Deputy Conservator of Forests, with effect from the 28th May or the subsequent date on which he may avail himself of it.

21st May 1903—No. 2087.—Mr. A. A. Dunbar-Brander, Officiating Deputy Conservator of Forests, Mandla Division, is posted to the charge of the Seoni Forest Division and will relieve Mr. Faiz Bakhsh.

21st May 1903—No. 2088.—Mr. Faiz Bakhsh, Forest Divisional Officer, Seoni, is transferred to the Balaghat Forest Division and will relieve Mr. Percival.

27th May 1903—No. 2233.—Mr. W. G. Morgan, Assistant Conservator of Forests, attached to the Hoshangabad Forest Division, is transferred to Jubbulpore, and will be attached to the Direction Division until further orders.

3rd June 1903—No. 2312.—Mr. C. A. Von B. Malcolm, Assistant Conservator of Forests, attached to the Balaghat Division, is transferred to Nagpur and will be attached to the Direction Division, Southern Circle, until further orders

8—BURMA GAZETTE.

28th May 1903—No. 10.—With reference to Revenue Department Notification No. 178 (Forests), dated the 18th May 1903, Mr. F. H. Todd, Officiating Deputy Conservator of Forests, received charge of the Yaw Division from Mr. F. J. Branthwaite, Deputy Conservator of Forests, on the afternoon of 20th May 1903.

30th May 1903—No. 7.—With reference to Revenue Department Notification No 184 (Forests), dated the 20th May 1903, Mr. W R. French, Extra-Assistant Conservator of Forests, reported his arrival in the Tharrawaddy Division on the forenoon of the 21st April 1903.

3rd June 1903—No. 197.—Under the provisions of Articles 264 and 260 of the Civil Service Regulations, privilege leave for three months is granted to Mr. H L P. Walsh, Assistant Conservator of Forests, with effect from the date on which he may avail himself of it.

Mr. Walsh is permitted to overstay his leave by 15 days under Article 251, Exception (1), of the Civil Service Regulations.

No 198.—Under the provisions of Articles 246 and 260 of the Civil Service Regulations, privilege leave for three months is granted to Mr. R C. A Pinder, Extra-Assistant Conservator of Forests, with effect from the date on which he availed himself of it.

4th June 1903—No. 199.—Under the provisions of Articles 246, 260, 233 and 308 (*b*) of the Civil Service Regulations, Mr. C. B. Smales, Deputy Conservator of Forests, is granted privilege leave for three months and furlough in continuation thereof for one year and nine months, with effect from the date on which he may avail himself of the privilege leave.

This Department Notification No. 164, dated the 7th May 1903, is hereby cancelled.

5th June 1903—No. 203.—Under the provisions of Articles 260, 233 and 308 (*b*) of the Civil Service Regulations, Mr. E. H. Powell, Extra-Assistant Conservator of Forests, is granted privilege leave for three months and furlough in continuation thereof for one year with effect from the 1st June 1903 or such subsequent date as he may avail himself of the privilege leave

5th June 1903 —No 8 – In continuation of this office Notifications Nos 5 and 6 dated the 22nd May 1903 Maung Moh Forest Ranger, 2nd grade assumed charge of the Railway Range, Rangoon Division on the forenoon of 1st June 1903 relieving Maung Po Tu, Forest Ranger, 1st grade

9th June 1903 No 9 – With reference to Revenue Department Notification No 166 (Forests) dated the 7th May 1903 Mr J J Rorie, Officiating Deputy Conservator of Forests assumed charge of the Prome Division on the afternoon of 3rd June 1903 relieving Mr A H M Lawson Deputy Conservator of Forests

10th June 1903 – No 212 —This department Notification No 188 date the 22nd May 1903 is hereby cancelled

16th May 1903—No 5 —With reference to Revenue Department Notification No 171 (Forest) dated the 11th May 1903 Mr A E Ross, Deputy Conservator of Forests assumed charge of the West Salween Division, relieving Mr G K Parker, Deputy Conservator of Forests, on the afternoon of the 11th May 1903

16th May 1903—No 7 —Mr C E Muriel, Deputy Conservator of Forests, received charge of the Pyinmana Division from Mr F H Todd, Deputy Conservator of Forests on the forenoon of the 14th May 1903

18th May 1903—No 176 —Under the provisions of Articles 233 260 and 308 (*b*) of the Civil Service Regulations Mr F J Branthwaite, Deputy Conservator of Forests, is granted privilege leave for three months and furlough in continuation thereof for one year two months and eight days, with effect from the 20th May 1903, or subsequent date on which he may avail himself of the privilege leave

18th May 1903—No 177 —On return from leave, Mr C E Muriel, Deputy Conservator of Forests, is posted to the charge of the Pyinmana Forest Division *vice* Mr F H Todd, Officiating Deputy Conservator of Forests, transferred

18th May 1903– No 178 —On relief by Mr C E Muriel, Mr F H Todd Officiating Deputy Conservator of Forests is transferred from Pyinmana to the charge of the Pakokku Forest Division, *vice* Mr F J Branthwaite, Deputy Conservator of Forests, proceeding on leave

20th May 1903 –No 181 —Mr A. Lawrence, Officiating Deputy Conservator of Forests, is transferred from his duties as Personal Assistant to the Conservator of Forests Southern Circle and posted to the charge of the Mandalay Forest Division, *vice* Mr J Copeland, Deputy Conservator of Forests, transferred

20th May 1903—No 184 —On his return from deputation to the Federated Malay States, Mr W R French, Extra Assistant Conservator of Forests, is posted to the Tharrawady Forest Division

21st May 1903—No. 6 – Mr J Copeland, Officiating Conservator of Forests, received charge of the Direction Division, Southern Circle, from Mr A Lawrence, Officiating Deputy Conservator of Forests, on the afternoon of the 20th May 1903

22nd May 1903 – No 183 —Mr P E, Plunket, Extra-Assistant Conservator of Forests, is transferred from girdling duty in the Toungoo Division to the West Salween Division, *vice* Mr S A Wood, proceeding on leave.

22nd May 1903—No. 5.—Under the provisions of section 338 of the Civil Service Regulations, furlough for one year is granted to Maung Po Tu, Forest Ranger, 1st grade, with effect from the date on which he is relieved of his duties.

22nd May 1903—No 6—Maung Mo, Ranger, 2nd grade, is transferred from the Tharrawaddy Division to the charge of the Railway Range, Rangoon Division, in place of Maung Po Tu, Ranger, 1st grade, proceeding on furlough.

9.—ASSAM GAZETTE.

25th May 1903—No. 4617G.—The following Notification by the Government of India, Department of Revenue and Agriculture, is republished: —

Forests—*No.* 516—66-4*F.*—*Dated Simla, the* 18*th May* 1903—The services of Mr. J L. Pigot, Deputy Conservator of Forests, 1st grade, Assam, are placed at the disposal of the Government of Ceylon, with effect from the 11th January 1903.

5th June 1903—No. 5036G—The following is published:

The undermentioned officer has been granted by His Majesty's Secretary of State for India extension of leave as advised in list dated the 8th May 1903:

Name.	Service.	Appointment.	Period and nature of extension.
Mr. J. E. Barrett ...	...	Deputy Conservator of Forests, Assam.	Two months on medical certificate.

10th June 1903—No. 5165G—On the report of the Central Examination Committee, the Officiating Chief Commissioner directs the publication, for general information, of the results of the half-yearly Examination of Assistant Commissioners, Extra-Assistant Commissioners and other Officers, held on the 4th, 5th, 6th, 7th, and 8th May 1903:—

Name.	Subjects taken up by candidates.		Subjects in which passed.		Subjects in which still required to pass.	
	Higher standard.	Lower standard.	Higher standard.	Lower standard.	Higher standard.	Lower standard.
1	2	3	4	5	6	7
Extra-Assistant Conservator of Forests.						
Babu Jnanada Charan Sen.	Land Revenue		Land Revenue ...		...	...

10.—HYDERABAD RESIDENCY GAZETTE—*Nil.*

11—MYSORE GAZETTE.

12th May 1903—No. 709—6995.—In modification of Notification No. 254—1867, dated the 17th October 1902, the Government of His Highness the Maharaja of Mysore are pleased to direct that Mr. B. Ramaswami Iyer, Forest Settlement Officer, Kadur and Chitaldrug Districts, be also appointed Settlement Officer in respect of forests of the Hassan District, which have been notified under Section 4 of the Mysore Forests Regulation.

25th May 1903—No. 785—7451.—The eight days' privilege leave of absence granted to Mr. H. Srinivasa Rao, Assistant Conservator of Forests, Mysore District, in Notification No. C. 747—10, dated the 17th April 1903, is hereby extended by two days.

6th June 1903—No. 806—7685.—Mr. B. Ramaswami Iyer, B.A., Forest Settlement Officer, Kadur and Chitaldrug Districts, was granted privilege leave of absence from 1st to 21st March 1903, under Article 188 of the Mysore Service Regulations.

Pioneer Press, No. 985.—1-8-03.

VIII.—EXTRACTS FROM OFFICIAL GAZETTES.

1.—GAZETTE OF INDIA.

10th July 1903.—No. 772—119-10-*F.*—Mr. R. S. Hole, Officiating Deputy Conservator of Forests, 4th grade, Central Provinces, is appointed to officiate as Instructor at the Imperial Forest School, Dehra Dun, with effect from the afternoon of the 15th June 1903, until further orders.

2.—MADRAS GAZETTE.

16th June 1903.—No. 251.—*Appointments.*

(1) Mr. H. F. Arbuthnot to act as Deputy Conservator of Forests, 3rd grade, *vice* Mr. C. Du Pre Thornton on leave, until the return of Mr. F. C. L. Cowley-Brown from leave.

(2) Mr. F. C. L. Cowley-Brown to act as Deputy Conservator of Forests, 3rd grade, from the date of his return to duty, *vice* Mr. C. D. P. Thornton on leave.

(3) Mr. J. S. Scott to act as Deputy Conservator of Forests, 4th grade, *vice* No. (2).

(4) Mr. F. A. Lodge to act as Deputy Conservator of Forests, 1st grade, during the absence of Mr. H. J. A. Porter on leave or until further orders.

(5) Mr. C. D. McArthy to act as Deputy Conservator of Forests, 2nd grade, *vice* No. (4).

(6) Mr. H. A. Latham to act as Deputy Conservator of Forests, 3rd grade, with effect from the date of his return to duty, *vice* No. (5).

(7) Mr. B. H. Barlow Poole to act as Deputy Conservator of Forests, 4th grade, with effect from 5th July 1902, during the absence of Mr G. F. F. Foulkes on leave or until further orders.

(8) Mr. W. Aitchison to act as Deputy Conservator of Forests, 4th grade, with effect from 6th July 1902, during the absence of Mr. S. Cox on leave or until further orders.

Note.—The above two appointments will modify so much of Notification No. 445, published at page 1286 of Part I of the *Fort St. George Gazette*, dated 9th December 1902, as related to the acting promotions of Messrs. Barlow Poole and Aitchison.

16th June 1903.—No. 252.—*Posting.*—Mr. H. B. Bryant to be District Forest Officer, Madura *vice* Mr. H. J. A. Porter.

25th June 1903.—*Leave.*—Under Article 260 of the Civil Service Regulations (4th edition), the Board of Revenue has granted privilege leave for three weeks to M. R. Ry. M. Rama Rao Avargal, District Forest Officer, North Salem Division, with effect from 9th July 1903.

30th June 1903.—*Transfer.*—M. R. Ry. V. R. Venkatrama Aiyar, Ranger 5th grade, is transferred from Ganjam to Kurnool.

6th July 1903.—*Promotions.*—The following promotions are ordered with effect from 31st March 1903, the date of passing with honours the final examination at the Forest School course of 1901-1903:—

(1) K R Venkatarama Aiyar, Ranger, 6th grade, North Coimbatore Division, to be supernumerary Ranger 4th grade.

(2) Mr. A. M C Littlewood, Ranger, 6th grade, South Coimbatore Division, to be Supernumerary Ranger, 4th grade

9th July 1903. -*Confirmation of Appointment.*—M. R. Ry. C. Sinayya, acting sub *pro tem.* Ranger, 6th grade, Vizagapatam District, is confirmed with effect from 10th June 1903.

Promotions—The following Deputy Rangers are promoted temporarily to the 6th grade of the Rangers' class from 1st July 1903:—

(1) K. Venkatasubbarow, Deputy Ranger, 2nd grade, and sub. *pro tem.* 1st grade.

(2) Saiyed Yassim Saib, Deputy Ranger, 3rd grade, and sub. *pro tem.* 1st grade

(3) H. Rama Row, Deputy Ranger, 3rd grade, and sub. *pro tem* 1st grade.

12th July 1903.—*Leave.*—M. R. Ry. K Ramaswami Aiyar, Ranger, Vizagapatam District, is granted privilege leave for one month from 5th August 1903, under Article 260 of the Civil Service Regulations.

3.—BOMBAY GAZETTE.

30th June 1903.—No. 2309.—Mr. W. A. Wallinger, Extra-Assistant Conservator of Forests, delivered over and Mr. E. G Oliver, Divisional Forest Officer, Dharwar, received charge of the Sub-Divisional Forest Office, Dharwar, on the afternoon of the 17th June 1903.

1st July 1903.—No. 1035 —Messrs. T. R D. Bell, Deputy Conservator of Forests, 4th grade, and R. E A. Elliott, Assistant Collector, respectively delivered over and received charge of the Divisional Forest Offices, East and West Khandesh, on the afternoon of the 20th June 1903.

3rd July 1903.—No. 1056.—Messrs. R E A Elliott, Assistant Collector, and A G. Edie, Deputy Conservator of Forests, 4th grade, respectively delivered over and received charge of the Divisional Forest Office, East Khandesh, on the afternoon of the 23rd June 1903.

4th July 1903.—No. 2494.—Messrs. N. D. Satarawala, L.C.E., and W. A Wallinger, Extra-Assistant Conservators of Forests, respectively delivered over and received charge of the Kolaba Division on the forenoon of the 24th June 1903.

15th July 1903.- No 1238.—Messrs. R E. A Elliott, Assistant Collector, and A. C. Robinson, Extra-Assistant Conservator of Forests, 1st grade, respectively delivered over and received charge of the Divisional Forest Office, West Khandesh, on the forenoon of the 3rd July 1903.

4.—BENGAL GAZETTE.

17th June 1903.—No. 1122 T. R.- Consequent on the departure of Mr. J. W. A. Grieve, Deputy Conservator of Forests, 4th grade, substantive *pro tempore*, on the afternoon of the 17th May 1903, on the three months' privilege leave, combined with four months furlough, granted to him in Notification No 279T R, dated the 28th April 1903, the following temporary promotions are ordered with effect from the 16th May 1903 —

Mr T H Monteath, Assistant Conservator of Forests, 1st grade, to officiate as Deputy Conservator of Forests, 4th grade

Mr J L Baker, Assistant Conservator of Forests, 2nd grade, to officiate as Assistant Conservator of Forests, 1st grade.

17th June 1903 — No 1163T. R — The following temporary promotions are ordered, with effect from the 20th May 1903, *vice* Mr H D D French, Deputy Conservator of Forests, 2nd grade, temporarily transferred to the Oudh Circle United Provinces, as Officiating Conservator of Forests, 3rd grade —

Mr. B B Osmaston, F C H. Deputy Conservator of Forests, 3rd grade, to officiate as Deputy Conservator of Forests, 2nd grade.

" C C Hatt, Deputy Conservator of Forests, 4th grade, to officiate as Deputy Conservator of Forests, 3rd grade.

" E R Stevens, Assistant Conservator of Forests, 1st grade, substantive *pro tempore*, to officiate as Deputy Conservator of Forests, 4th grade.

20th June 1903 — No 1156 T R — Mr E R Comber, Extra Assistant Conservator of Forests attached to the Chittagong Forest Division, is transferred and attached to the Sunderbans Forest Division.

6th July 1903 — No. 1859A D — The Report of the Central Examination Committee having been received, the result of the first half yearly Departmental Examination of Assistant Magistrates and others, held on the 4th May 1903 and the two following days, is published for general information :—

III—FOREST OFFICERS.

The following Forest Officers have passed in the subject or subjects mentioned against them .—

1.	Mr. H. K Robinson	...	Forest Law, Land Revenue systems, and Hindustani by the Lower Standard.
2.	Babu Lalit Mohan Sen	...	Land Revenue systems.

5.—UNITED PROVINCES OF AGRA AND OUDH GAZETTE.

2nd July 1903 — No 2739 - II-578C — Pandit Sada Nand Gairola, Extra-Assistant Conservator of Forests, in charge of the Pilibhit Forest Division of the Oudh Circle, on being relieved, priviledge leave for three months, combined with furlough, for a total period of fifteen months.

2nd July 1903 — No. 2738—II-237C — Mr. T. J. Campbell, Officiating Conservator of Forests, in charge of the Central Circle, on being relieved, to revert to his substantive appointment as Deputy Conservator of Forests and to be posted to the charge of the Naini Tal Forest Division of that Circle

2nd July 1903. — No. 2740— II-578C. — Babu Nand Mal, Extra-Assistant Conservator of Forests, on being relieved from the charge of the Naini Tal Forest Division of the Central Circle, to that of the Pilibhit Forest Division in the Oudh Circle.

6.—PUNJAB GAZETTE.

8th July 1903.—*No.* 324—*A. L. No.* 15.—The following changes have taken place in the list of Forest Officers in the Associated Provinces with effect from the date specified against each :—

Name.	Present grade.	Grade to which promoted or reverted.	With effect from	REMARKS.
Mr. A. A. Dunbar Brander.	Provisional Assistant Conservator, 1st grade.	Provisional Assistant Conservator, 1st grade, and Officiating Deputy Conservator, 4th grade.	28th May 1903.	Consequent on Mr. Percival proceeding on three months' privilege leave, combined with three months' leave on private affairs, on the afternoon of the 27th May 1903.
Mr. A. A. Dunbar Brander.	Provisional Assistant Conservator, 1st grade, and Officiating Deputy Conservator, 4th grade.	Ditto	7th June 1903.	Consequent on Mr. Hole's deputation as Instructor to the Forest School, Dehra Dun, on the afternoon of the 6th June 1903. Mr. Dunbar Brander will officiate in this vacancy and Mr. Blascheck will officiate in the vacancy caused by Mr. Percival proceeding on leave.
Mr. A. D. Blascheck	Provisional Assistant Conservator, 1st grade.	Ditto	Ditto	

17th July 1903.—*No.* 333.—*Examination.*—Lala Mulraj, Extra-Assistant Conservator of Forests, passed the following Departmental Examinations as laid down in Section 72, Forest Code, on the dates noted :—

Procedure and Accounts .. .. 7th May 1903.
Land Revenue } .. .. 8th May 1903.
Forest Law }

7.—CENTRAL PROVINCES GAZETTE.

1st July 1903.—No. 4.—Y. M. Wadikar, Ranger, 4th grade, attached to the Raipur Division, is granted one month's privilege from the 10th June 1903.

1st July 1903.—No 5.—Laiq Singh, Ranger, 6th grade, attached to the Chanda Division, is temporarily transferred to the Balaghat Division in connection with the sleeper works.

1st July 1903.—No. 6.—Sakharam Vinayak Bhagwat, Ranger, 4th grade, attached to the Chanda Division, is granted privilege leave for two-and-a-half months, from the 1st July 1903, or from the date on which he may be permitted to avail himself of it.

2nd July 1903.—No. 2740.—Consequent on the transfer of Mr. R. S. Hole, Forest Divisional Officer, Jubbulpore, to the Imperial Forest School, Dehra Dun, the following transfers are ordered:—

Mr Punaswamy Mudliar, Extra-Assistant Conservator of Forests, in charge of the Narsinghpur Forest Division, to the Jubbulpore Forest Division, and to take charge of that division.

Mr. P. Shankarnath, Extra-Assistant Conservator of Forests, sub. *pro tem.*, attached to the Damoh Forest Division, to the Narsinghpur Forest Division, and to take charge of that division.

15th July 1903.—No. 2999.—Privilege leave for one month, under Article 260 of the Civil Service Regulations (4th edition), is granted to Mr. A St V Beechey, Deputy Conservator of Forests in charge of the Nimar Forest Division, with effect from the 6th instant, or the subsequent date on which he may avail himself of it.

Mr. S. R. Parsons, Extra-Assistant Conservator of Forests now attached to the Nimar Forest Division, is placed in charge of the division during the absence of Mr. Beechey, or until further orders.

8.—BURMA GAZETTE

11th June 1903.—No 214—Under the provisions of Articles 246 and 260 of the Civil Service Regulations, privilege leave for two months and 21 days is granted to Mr. H C. Walker, Assistant Conservator of Forests, with effect from the date on which he availed himself of it.

Mr. Walker is permitted to overstay his leave by 15 days under Article 251, Exception (1) of the Civil Service Regulations.

22nd June 1903—No. 10—With reference to Revenue Department Notification No. 214 (Forests), dated the 11th June 1903, Mr H C. Walker, Assistant Conservator of Forests, made over, and Mr. W. R. French, Extra-Assistant Conservator of Forests, received charge, of the South Tharrawaddy Sub-division, on the afternoon of the 27th May 1903.

17th June 1903—No 222.—Under the provisions of Articles 246, 260 and 251 of the Civil Service Regulations Mr J. G F. Marshall, Extra Deputy Conservator of Forests, is granted privilege leave for three months and 15 days with effect from the date on which he may avail himself of the leave.

18th June 1903—No. 223.—Under the provisions of Articles 246 and 260 of the Civil Service Regulations, privilege leave for three months is granted to Mr. A. H. M. Lawson Deputy Conservator of Forests, with effect from the date on which he may avail himself of the leave.

Mr Lawson is permitted to overstay his leave by 15 days under Article 251 (1) of the Civil Service Regulations.

This Department Notification No. 165, dated the 7th May 1903, is hereby cancelled

25th June 1903.—No. 242.-Mr. R. E. Marsden, Assistant Conservator of Forests, is transferred from the Yamethin Sub-division of the Pyinmana Division to the charge of the Magwe Sub-division of the Minbu Division, *vice* Mr. J. G. F. Marshall, Extra-Deputy Conservator of Forests, proceeding on leave.

27th June 1903.—No. 244.—Under the provisions of Articles 246, 260, 233 and 338 of the Civil Service Regulations, privilege leave for two months and twenty-eight days, and furlough in continuation thereof for one year, is granted to Mr. A S. Rencontre, Extra-Assistant Conservator of Forests, with effect from the date on which he may avail himself of the privilege leave.

27th June 1903.—No. 245.—Under the provisions of Article 260 of the Civil Service Regulations, privilege leave for three months is granted to Mr. W. E. Johnson, Superintendent of Land Records, with effect from the date on which he avails himself of the leave.

2nd July 1903.—No. 11.—Mr. H. L. P. Walsh, Assistant Conservator of Forests, relinquished charge of his duties in the Ruby Mines Division on the afternoon of the 20th June 1903 and availed himself of the three months and 15 days privilege leave granted him in Revenue Department Notification No. 197 (Forests), dated the 3rd June 1903.

9th July 1903.—No. 12.—Mr. R. C. A. Pinder, Extra-Assistant Conservator of Forests, relinquished charge of his duties in the Shweli Sub division, Ruby Mines Division, and availed himself of the three months' privilege leave granted him in Revenue Department Notification No. 198 (Forests), dated 3rd June 1903, on the afternoon of the 4th July 1903.

9th July 1903.—No. 369.—The following Forest Rangers are appointed to be Extra-Assistant Conservators of Forests, 4th grade, *prov. sub.*, with effect from the 4th February 1903:—

Mr. Hatim Tai, Ranger, 1st grade.
Mr. F. C. Purkis, Ranger, 2nd grade.

9th July 1903.—No. 370.—The following promotions are ordered in the Subordinate Forest Service with effect from the 4th February 1903:—

Maung Kyaing, Ranger, 2nd grade, to be Ranger, 1st grade, *prov. sub.*
Maung Po Ta, Ranger, 3rd grade to be Ranger, 2nd grade, *prov. sub.*

10th July 1903.—No. 269.—The following alterations in rank are ordered in the Forest Department:—

(1) With effect from the 12th May 1903, consequent on the departure on leave of Mr. G. K. Parker, Deputy Conservator, 4th grade, *prov. sub.*,

Mr. H. L. P. Walsh, Assistant Conservator, 1st grade, *prov. sub.*, to officiate as Deputy Conservator, 4th grade.

(2) With effect from the 14th May 1903, consequent on the return from leave of Mr. C. E. Muriel, Deputy Conservator, 2nd grade:

Mr. F. J. Branthwaite, Deputy Conservator, 3rd grade, officiating 2nd grade, to revert to his substantive appointment.

Mr. A. H. M. Lawson, Deputy Conservator, 4th grade, officiating 3rd grade, to revert to his substantive appointment.

Mr. H. L. P. Walsh, Assistant Conservator, 1st grade, *prov. sub.*, officiating Deputy Conservator, 4th grade, to revert to his *prov. sub.* appointment.

(3) With effect from the 21st May 1903, consequent on the appointment of Mr. J. Copeland as Officiating Conservator and the departure on leave of Mr. F. J. Branthwaite, Deputy Conservator, 3rd grade:

Mr. C. E. Muriel, Deputy Conservator, 2nd grade, to officiate as Deputy Conservator, 1st grade.

Mr. G. R. Long, Deputy Conservator, 3rd grade, to officiate as Deputy Conservator, 2nd grade.

Mr. A. H. M. Lawson, Deputy Conservator, 4th grade, to officiate as Deputy Conservater, 3rd grade.

Mr. C. W. Doveton, Deputy Conservator, 4th grade, to officiate as Deputy Conservator, 3rd grade.

Mr. H L. P. Walsh, Assistant Conservator, 1st grade, *prov. sub*, to officiate as Deputy Conservator, 4th grade.

Mr. H C Walker, Assistant Conservator, 2nd grade, Officiating Assistant Conservator, 1st grade, to officiate as Deputy Conservator, 4th grade.

(4) With effect from the 28th May 1903, consequent on the departure on leave of Mr H. C. Walker, Assistant Conservator, 2nd grade:

Mr L C. Davis, Assistant Conservator, 2nd grade, *prov. sub.*, officiating Assistant Conservator, 1st grade, to officiate as Deputy Conservator, 4th grade.

10th July 1903 – No 11.—With reference to the Revenue Department Notification No. 199 (Forests) dated 4th June 1903, Mr A. Rodger, Deputy Conservator of Forests, assumed charge of the Thayetmyo Division on the afternoon of the 4th July 1903, relieving Mr. C. B. Smales, Deputy Conservator of Forests.

10th July 1903 —No. 5 —Mr H W. A. Watson, Officiating Deputy Conservator of Forests, assumed charge of his duties as Personal Assistant to the Conservator of Forests Tenasserim Circle, in addition to his other duties, on the forenoon of the 9th July 1903.

16th July 1903 —No. 6 —With reference to Revenue Department Notification No. 244, dated 27th June 1903, Mr. A S Recontre, Extra-Assistant Conservator of Forests, availed himself of the leave granted therein on the afternoon of the 7th July 1903.

16th July 1903 —No. 7.—Mr. P. E Plunkett, Extra-Assistant Conservator of Forests, assumed charge of the Railway Revenue Range, with headquarters at Toungoo. releiving Mr. A S. Rencontre, Extra-Assistant Conservator of Forests, proceeding on leave, on the afternoon of the 7th July 1903.

11th July 1903.—No. 271.—Mr. H. W. A. Watson, Officiating Deputy Conservator of Forests, is transferred from Working Plans duty in the Shwegyin Division and is appointed to be Personal Assistant to the Conservator of Forests, Tenasserim Circle.

9.—ASSAM GAZETTE.—*Nil.*

10.—HYDERABAD RESIDENCY GAZETTE—*Nil.*

11—MYSORE GAZETTE.

27th June 1903.—No. 845—8522.—Under Article 188 of the Mysore Service Regulations. Mr. M. G. Rama Rao, Assistant Conservator of Forests, Kadur District, is granted privilege leave of absence for ten days, with effect from the 1st July 1903 or such other date as he may avail himself of the same The District Treasury Officer at Chikmagalur will be in charge of the current duties of the District Forest Office, during Mr. Rama Rao's absence on leave or until further orders.

Pioneer Press, No. 1071.—1-9-03.

Advertisements.

ESTABLISHED 1891.

THE "TROPICAL AGRICULTURIST"

Circulates in India, Ceylon, the Straits, Burma, Japan, Borneo, Northern Australia, Fiji, East and South Africa, Central and South America, Florida, California, West Indies, &c.

A Monthly Magazine of Information specially all about Tea, regarding tropical and sub-tropical products.

Edited by J. Ferguson, of the *Ceylon Observer, &c.*

RATES OF SUBSCRIPTION INCLUDING POSTAGE,

STRICTLY IN ADVANCE.

For Ceylon.	Yearly ... Rs.12	For Europe, India, &c.	Yearly ...	£1-6s.	or Rs. 14
	Half-yearly „ 9		Half-yearly ...	15s.	„ „ 8

Single Copies, Re.1; Back Copies, Re.1-5-0.

Publishers:—A. M. & J. Ferguson, Colombo, Ceylon. *Agents:*—Thacker Spink & Co., Calcutta.

"INDIAN PLANTING AND GARDENING."

Published Weekly. Illustrated.

Circulates all over India, Burma, Ceylon, Straits, East and South Africa, Mexico, California, Central America, Mauritius, Zanzibar &c., &c.

Contains the most reliable information on all matters regarding Tea, Coffee and other tropical and sub-tropical products.

The only Horticultural Paper in the East.

A guide to Amateur Gardeners.

Edited by H. St. John Jackson, F.L.S., F.R.H.S.

Subscription:— Indian, Rs. 20 yearly and Rs. 11 half-yearly, including postage; Rs.6 quarterly, including postage. Foreign, £2 yearly and £1-1 half-yearly, including postage.

Apply to—

Manager, 5/1, Council House Street, Calcutta.

FOR SALE

A MANUAL OF FOREST ENGINEERING FOR INDIA

— BY —

C. G. ROGERS, DEPUTY CONSERVATOR OF FORESTS, BENGAL.

Volumes I and II, Rs. 4 per Volume.

May be obtained from the Superintendent of Government Printing, India; or Messrs. Thacker, Spink & Co., Calcutta.

SALE OF MR. BADEN-POWELL'S BOOKS.

Land Revenue of British India and its Administration ...	Rs. 3 15
Forest Law	„ 5 14
Land Tenures and Systems of India	„ 27 4

The above may be obtained from Messrs. Thacker & Co. and Combridge & Co. Booksellers, Bombay.

VIII.—EXTRACTS FROM OFFICIAL GAZETTES.

1.—GAZETTE OF INDIA.

5th August 1903.—No. 870—119-12-F.—With reference to the notification of this Department, No. 656-F., dated the 15th June 1903, Mr. B. O. Coventry, Deputy Conservator of Forests, 4th (officiating 3rd) grade, proceeded on the leave granted therein, from the afternoon of the 13th July 1903, on which date he was relieved of his duties as Instructor at the Imperial Forest School. From the same date Mr. Coventry reverted to the Punjab Forest List.

Mr. R. S. Hole, officiating Instructor at the Imperial Forest School, is confirmed in that appointment, with effect from the afternoon of the 13th July 1903.

6th August 1903.—No. 875—173-4-F.—Mr. H. Slade, officiating Conservator of Forests, 3rd grade, Burma, is granted privilege leave for three and a half months, with effect from the 5th August 1903, or the subsequent date on which he may avail himself of it.

12th August 1903.—No. 892—173-7-F.—With reference to the Notification of this Department, No. 875-F., dated the 6th instant, Mr. A. F. Gradon, Deputy Conservator of Forests, 2nd grade, Burma, is appointed to officiate as Conservator, 3rd grade, and to hold charge of the Pegu Circle, Lower Burma, of which he relieved Mr. H. Slade on the afternoon of the 4th August 1903.

2.—MADRAS GAZETTE.

19th July 1903.—M.R.Ry. V. R. Venkatrama Aiyar, Ranger, 5th grade, is transferred from Kurnool to Godavari district, to join on relief by Ranger Sheik Rahimatullah Sahib.

6th August 1903.—The following candidates have passed the Departmental test held in July 1903 in parts noted against each:—

Name.		Designation.	Part (*a*) or (*b*).
(1) T. M. Parthasarathy Naidu	...	Forester, 1st grade, the Nilgiri district	(*b*)
(2) M. V. Subramania Mudali	...	Forester, 2nd grade, Madura district	(*a*)
(3) S. Nagappa Iyer	...	Clerk, District Forest Office, the Nilgiris	(*a*)

3.—BOMBAY GAZETTE. *Nil.*

4.—BENGAL GAZETTE.

25th July 1903.—No. 2303.—Mr. J. L. Baker, Assistant Conservator of Forests, 2nd grade, officiating in the 1st grade, is promoted to officiate as Deputy Conservator of Forests, 4th grade, with effect from the 1st July 1903, *vice* Sir Henry A. Farrington, Deputy Conservator of Forests, 4th grade, on leave, or until further orders.

3rd August 1903.—No. 2452.—The services of Mr. E. R. Stevens, Assistant Conservator of Forests, 1st grade, and Officiating Deputy Conservator of Forests, 4th grade, are placed at the disposal of the Government of India in the Revenue and Agricultural Department, for employment in the United Provinces, with effect from the date on which he is relieved of the charge of the Singhbhum Forest Division.

3rd August 1903.—No. 2453.—Mr. H. K. Robinson, Assistant Conservator of Forests, attached to the Darjeeling Forest Division, is transferred and placed in charge of the Singhbhum Forest Division, during Mr. Stevens's absence on deputation to the United Provinces, or until further orders.

18th August 1903.—No. 2710.—Mr L. M. Sen, Extra Assistant Conservator of Forests, 4th grade, is promoted to be Extra-Assistant Conservator of Forests, 3rd grade, sub *pro tem.*, with effect from the 5th May 1903.

5.—UNITED PROVINCES GAZETTE.

16th July 1903.—No. 2995—II/578C.—In Notification No 2739—II/578C., dated the 2nd July 1903, granting leave to Pandit Sada Nand Gairola, Extra-Assistant Conservator of Forests in charge of the Pilibhit Division of the Oudh Circle *for* "for a total period of fifteen months" *read* "for a total period of eighteen months."

20th July 1903.—No 3020—II/578C.—In supersession of Notification No. 2740—II/578C., dated 2nd July 1903, Babu Nand Mal, Extra-Assistant Conservator of Forests in charge of the Naini Tal Forest Division of the Central Circle, on being relieved, to be temporarily attached to that Division.

20th July 1903.—No. 3033—II/578C.—Babu Nand Mal, Extra-Assistant Conservator of Forests, attached to the Naini Tal Forest Division of the Central Circle, to the charge of the Pilibhit Forest Division of the Oudh Circle, *vice* Pandit Sada Nand Gairola, granted leave.

5th August 1903.—No. 3240—II/152C.—The following temporary romotions and reversions are notified for general information:—

Entry No.	With effect from	Consequent on	Name.	From	To
1	20th July 1903.	Reversion of Mr T. J Campbell as Deputy Conservator, 1st grade.	Mr W. H. Lovegrove.	Officiating Deputy Conservator of Forests, 1st grade.	Deputy Conservator of Forests, 2nd grade.
			Mr. J. C. Tulloch	Officiating Deputy Conservator of Forests, 2nd grade	Deputy Conservator of Forests, 3rd grade.
			" F. F. R. Channer.	Officiating Deputy Conservator of Forests, 3rd grade.	Officiating Deputy Conservator of Forests, 4th grade.

6.—PUNJAB GAZETTE.

7th August 1903.—No. 359.—Lala Mul Raj, Extra-Assistant Conservator of Forests (Provisional on probation), was transferred from the Chamba Forest Division on the forenoon of the 1st July 1903, and joined the Bashahr Division, to which he has been attached, on the forenoon of the 15th idem.

7th August 1903.—No. 362.—Lala Jawala Pershad, Extra Assistant Conservator of Forests, and Mr. C. F. Rossiter, Extra Deputy Conservator of Forests, respectively made over and received charge of the Montgomery Forest Division on the afternoon of the 20th July 1903, consequent on the former proceeding on 2½ months' privilege leave.

Mr. Rossiter will hold charge of the Montgomery Forest Division in addition to the Mooltan Forest Division.

7th August 1903.—No. 365—A. L. No. 16.—Mr. A. J. Gibson, Officiating Deputy Conservator of Forests, attached to the Bashahr Forest Division, was transferred on the forenoon of the 10th July 1903, and took over charge of the Hazara Forest Division on the afternoon of the 21st idem, relieving Mr. A. V. Monro, Deputy Conservator of Forests, proceeding on 2 months and 27 days' privilege leave.

7th August 1903.—No. 369—A. L. No. 17.—*Erratum.*—In Punjab Government Notification No. 324—A. L. No. 15, dated 8th July 1903—

Name.	Present grade.	Grade to which promoted or reverted.	With effect from	REMARKS.
For—				
Mr. A. A. Dunbar Brander.	Provisional Assistant Conservator, 1st grade, and Officiating Deputy Conservator, 4th grade	Provisional Assistant Conservator, 1st grade, and Officiating Deputy Conservator, 4th grade.	7th June 1903	Consequent on Mr. Mole's deputation as Instructor to the Forest school, Dehra Dun, on the afternoon of the 6th June 1903, Mr. Dunbar Brander will officiate in this vacancy and Mr. Blascheck will officiate in the vacancy caused by Mr. Percivall proceeding on leave.
Mr. A. D. Blascheck.	Provisional Assistant Conservator, 1st grade	Ditto ditto	Ditto	
Read—				
Mr. A. A. Dunbar Brander.	Provisional Assistant Conservator, 1st grade, and Officiating Deputy Conservator, 4th grade.	Provisional Assistant Conservator, 1st grade, and Officiating Deputy Conservator, 4th grade.	16th June 1903	Consequent on Mr. Mole's deputation as Instructor to the Forest School, Dehra Dun, on the afternoon of the 15th June 1903, Mr. Dunbar Brander will officiate in this vacancy and Mr. Blascheck will officiate in the vacancy caused by Mr. Percivall proceeding on leave.
Mr. A. D. Blascheck.	Provisional Assistant Conservator, 1st grade.	Ditto ditto	Ditto	

7.—CENTRAL PROVINCES GAZETTE.

22nd July 1903.—No. 3109.—Privilege leave for three months, under Article 260 of the Civil Service Regulations (4th edition), is granted to Mr. Ganga Parshad Khatri, Extra-Assistant Conservator of Forests, with effect from the 30th August 1903, or the subsequent date on which he may avail himself of it.

22nd July 1903.—No. 3110.—On return from the privilege leave granted him by Order No. 1888, dated the 4th May 1903, Mr. A. L. Chatterji, Extra-Assistant Conservator of Forests, is posted to the charge of the Betul Forest Division.

24th July 1903.—No. 82.—Under the authority conferred by Article 81, clause (1), of the Forest Department Code, Mahadeo Krishna Dandekar, a private student of the Imperial Forest School, Dehra Dun, who has duly obtained the Higher Standard Certificate of the School, is appointed, on probation, as Ranger, 6th grade, with effect from the date he reports himself for duty to the Divisional Forest Officer, Hoshangabad.

25th July 1903.—No. 7.—Prabhakar Narayan Joshi, Ranger, 5th grade, attached to the Chanda Division, is granted privilege leave for one month and fifteen days, from the 10th August 1903.

25th July 1903.—No. 8.—K. Rama Rao, Ranger, 1st grade, attached to the Nagpur-Wardha Division, is granted privilege leave for two months, with effect from the 15th August 1903, or from the date on which he may be permitted to avail himself of it.

27th July 1903.—No. 9.—The one month's privilege leave granted to Y. M. Wadikar, Ranger, 4th grade, attached to the Raipur Division, by Departmental Order No. 50, dated the 1st June 1903, is extended by ten days.

4th August 1903.—No. 85.—The following Forest Rangers, sub. *pro tem.* in the grades mentioned against them, are confirmed in those grades with effect from the 1st July 1903 :—

Pandit V. C. Phagwat	..	..	..	2nd grade
Pandit Chintaman V. Sarvate		..	..	3rd „
Pandit Matadin Dube	..	..	..	3rd „
Ilahdad Khan	..	..	..	4th „
Tirath Prashad	..	..	..	4th „
Sarmast Khan	..	..	..	4th „
A. D. Bhote	..	..	..	4th „

5th August 1903.—No. 87.—The following changes among Forest Rangers in the Central Provinces have taken place with effect from the dates specified below :—

Name.	Present grade.	Grade to which promoted.	With effect from
Mr. Phirozshah Rustamji Kotpitia.	5th grade .	4th grade, sub *pro tem.*	1st August 1903
Pandit Vishnu Vasudeo Sathe.	Do. ..	Do ..	Do
Babu I. Kandaswamy Pillay	Do. sub. *pro tem.*	5th grade ...	14th July 1903.
Babu Lalk Singh ...	6th grade ...	Do. ..	1st August 1903.
Muhammad Yasin Khan	Do. ...	Do. ...	Do.
Thakur Arjun Singh ...	Do. ..	Do. ..	Do.
Mr. C. Alberts ...	Do. ...	Do. ...	Do.
Pandit Ramchandra Tatiyaji Konjrey.	Do. ...	Do. ...	Do.
Pandit Shankar Dayal ...	Do. ...	Do. sub. *pro tem.*	Do.

8.—BURMA GAZETTE.

9th July 1903.—No. 276.—The following Forest Rangers are appointed to be Extra-Assistant Conservators of Forests, 4th grade, *prob. sub.*, with effect from the 4th February 1903 :—

Mr. Hatim Tai, Ranger, 1st grade.
Mr. F. C. Purkis, Ranger, 2nd grade.

21st July 1903.—No 280.—On return from leave Mr. S A. Wood, Extra-Assistant Conservator of Forests, is posted to the charge of the Bampôn subdivision, Southern Shan States Division, *vice* Mr. C. V. Ryan, transferred

21st July 1903.—No. 281.—On relief by Mr. S. A. Wood, Mr. C V. Ryan, Extra-Assistant Conservator of Forests, is transferred from Bampôn to the charge of the Kado subdivision, Kado Division, *vice* Mr. W. J G. Cooper, transferred.

21st July 1903.—No. 282.—On relief by Mr. C. V. Ryan, Mr. W J G. Cooper, Extra-Assistant Conservator of Forests, is transferred from Kado and is posted to duty in the West Salween Division, with headquarters at Papun.

22nd July 1903.—No 284.—Mr. E M Buchanan, Extra Deputy Conservator of Forests, has been granted by His Majesty's Secretary of State for India an extension of leave on medical certificate for two months.

23rd July 1903.—No. 12.—With reference to Revenue Department Notification on No. 203, dated the 5th June 1903, Mr. E B Powell, Extra-Assistant Conservator of Forests, availed himself of privilege leave for three months, and furlough in continuation thereof for one year, with effect from the 11th July 1903.

25th July 1903.—No 290.—The following alterations in rank are ordered in the Forest Department :—

With effect from the 4th June 1903, consequent on the departure, on leave, of Mr. A. H. M. Lawson, Deputy Conservator, 4th grade—

Mr. A E. Ross, Deputy Conservator, 4th grade, *prov. sub.*, to officiate as Deputy Conservator, 3rd grade.

Mr. R. E. Marsden, Assistant Conservator, 2nd grade, *prov. sub.*, officiating Assistant Conservator, 1st grade, to officiate as Deputy Conservator, 4th grade.

27th July 1903.—No. 178.—At the departmental examination held at Bassein, Akyab, Moulmein, Mergui, Minbu, Pakokku Meiktila, Mandalay, Mogok, Myitkyina, Monywa, Kindat, Lashio, Taunggyi and Falam on the 1st, 2nd and 3rd June 1903, the following officers passed the examination in Burmese by the standards specified below :—

* * * * * * *

Mr. G. R Jeffery, Assistant Conservator of Forests.
Mr. C. C. Chill, Forest Ranger.

29th July 1903.—No 296.—Under the provisions of Articles 246 and 260 of the Civil Service Regulations, privilege leave for two months and fifteen days is granted to Mr. S. E. F Jenkins, Extra-Assistant Conservator of Forests, with effect from the date on which he may avail himself of the leave.

30th July 1903.—No 406.—Mr. J. D Hamilton, Forest Ranger, 2nd grade, is transferred from the Shwegyin Division and is attached to the Depôt and Agency Division, Rangoon.

3rd August 1903.—No 13.—Mr. S. E. F. Jenkins, Extra-Assistant Conservator of Forests, relinquished charge of his duties as Sub-divisional Officer of the Gangaw subdivision, Yaw Division, on the afternoon of the 1st August 1903, and availed himself of the two months and fifteen days privilege leave granted him in Revenue Department Notification No. 296 (Forests), dated the 29th July 1903, from the same date.

3rd August 1903.—No. 14.—With reference to Revenue Department Notification No. 242 (Forests), dated 25th June 1903, Mr. R E. Marsden, Assistant Conservator of Forests, relinquished charge of the Yamethin subdivision, Pyinmana Division, on the afternoon of the 11th July 1903 and received charge of the Magwe subdivision, Minbu Division, from Mr. J. G. F Marshall, Extra Deputy Conservator of Forests, on the afternoon of the 24th July 1903

3rd August 1903 —No. 15.—Mr J G F Marshall, Extra Deputy Conservator of Forests, availed himself, on the afternoon of the 24th July 1903, of the three months and fifteen days' privilege leave granted him in Revenue Department Notification No. 22 (Forests), dated the 17th July 1903

4th August 1903.—No. 8.—Mr H. W. A Watson, officiating Deputy Conservator of Forests, was relieved of his duties as Personal Assistant to the Conservator of Forests, Tenasserim Circle, on the forenoon of the 1st August 1903, and proceeded to the Henzada Division on transfer.

5th August 1903 —No 304 —Mr. H. W. A. Watson, officiating Deputy Conservator of Forests, is transferred from his duties as Personal Assistant to the Conservator of Forests, Tenasserim Circle, to the charge of the Henzada-Thongwa division, *vice* Mr. A. F. Gradon, Deputy Conservator of Forests, transferred.

10th August 1903 —No. 13.—With reference to Revenue Department Notification No 304 (Forests), dated the 5th August 1903, Mr A. F. Gradon, Deputy Conservator of Forests, made over charge of the Henzada-Thongwa Division on the afternoon of the 1st August 1903, temporarily, to Mr N. S. Field, Deputy Commissioner, and Mr. H W. A. Watson Officiating Deputy Conservator of Forests, assumed charge of the Division on the afternoon of 3rd August 1903, relieving Mr. N. S. Field, Deputy Commissioner.

9.—ASSAM GAZETTE.—

24th July 1903.—No. 6594G.—Privilege leave of absence for one month and three weeks, under Article 260 of the Civil Service Regulations, is granted to Babu Jnanada Charan Sen, Extra-Assistant Conservator of Forests attached to the Goalpara Forest Division, with effect from the date on which he may avail himself of it.

10.—HYDERABAD RESIDENCY GAZETTE—*Nil.*

11.—MYSORE GAZETTE.

29th July 1903 —No. 72—879.—The casual leave of absence for five days granted to Mr. G E. Ricketts, Head-quarter Assistant to the Conservator and Assistant Secretary to Government, Forest Department, in Government Proceedings No. 44-5—374-5, dated the 11th July 1903, is hereby extended by two days, and the whole period, *viz.*, seven days, will be treated as privilege leave under Article 188 of the Mysore Service Regulations.

5th August 1903.—No. 84—1007.—Under Article 188 of the Mysore Service Regulations, Mr. P. E. Benson, Sub-Assistant Conservator of Forests, Mysore District, has been granted privilege leave of absence for forty-one days, with effect from the 1st July 1903.

Pioneer Press, No. 1221.—1-10-03.

Advertisements.

ESTABLISHED 1891.

THE "TROPICAL AGRICULTURIST"

Circulates in India, Ceylon, the Straits, Burma, Japan, Borneo, Northern Australia, Fiji, East and South Africa, Central and South America, Florida, California, West Indies, &c.

A Monthly Magazine of Information specially all about Tea, regarding tropical and sub-tropical products.

Edited by J. FERGUSON, of the *Ceylon Observer, &c.*

RATES OF SUBSCRIPTION INCLUDING POSTAGE,

STRICTLY IN ADVANCE.

For Ceylon	Yearly	Rs 12	For Europe, India, &c.	Yearly ...	£1-6s. or Rs.14
	Half-yearly	„ 9		Half-yearly ...	15s. „ „ 8

Single Copies, Re.1; Back Copies, Re.1-5-0.

Publishers:—A. M. & J. Ferguson, Colombo, Ceylon. *Agents:*—Thacker Spink & Co., Calcutta.

"INDIAN PLANTING AND GARDENING."

PUBLISHED WEEKLY. ILLUSTRATED.

Circulates all over India, Burma, Ceylon, Straits, East and South Africa, Mexico, California, Central America, Mauritius, Zanzibar &c., &c.

Contains the most reliable information on all matters regarding Tea, Coffee and other tropical and sub-tropical products.

THE ONLY HORTICULTURAL PAPER IN THE EAST.

A guide to Amateur Gardeners.

Edited by H. St. John Jackson, F.L.S., F.R.H.S.

SUBSCRIPTION:- Indian, Rs. 20 yearly and Rs. 11 half-yearly, including postage; Rs.6 quarterly, including postage. Foreign, £2 yearly and £1-1 half-yearly, including postage.

Apply to—

MANAGER, 5/1, Council House Street, CALCUTTA.

FOR SALE

A MANUAL OF FOREST ENGINEERING FOR INDIA

BY —

C. G. ROGERS, DEPUTY CONSERVATOR OF FORESTS, BENGAL.

VOLUMES I and II, Rs. 4 per VOLUME

May be obtained from the Superintendent of Government Printing, India; or Messrs Thacker, Spink & Co., Calcutta.

SALE OF MR. BADEN-POWELL'S BOOKS.

Land Revenue of British India and its Administration ...	Rs.	3	10
Forest Law	„	5	14
Land Tenures and Systems of India	„	47	4

The above may be obtained from Messrs. THACKER & Co. and COMBRIDGE & Co., Booksellers, Bombay.

VIII.—EXTRACTS FROM OFFICIAL GAZETTES.

1.—GAZETTE OF INDIA.

28th August 1903.—No 1034—136-II *F.*—Mr. E. R. Stevens, Assistant Conservator of Forests, 1st grade, and officiating Deputy Conservator of Forests, 4th grade, Bengal, is transferred to the United Provinces in the interests of the public service.

28th August 1903.—No. 1039—75-9-*F.* Mr F. B Dickinson, Conservator of Forests, 1st grade, on return from the privilege leave granted to him in the Notification of this Department, No 465-F, dated the 30th April 1903, having resumed charge of the Central Circle, United Provinces, from Mr. T. J Campbell, the following reversions took effect from the 20th July 1903:—

(*i*) Mr. A. M. Reuther, officiating Conservator, 1st grade, Burma, on leave, to Conservator, 2nd grade.

(*ii*) Mr. F Beadon Bryant, officiating Conservator, 1st grade, Punjab, to Conservator, 2nd grade.

(*iii*) Mr L. Mercer, officiating Conservator, 3rd grade, to Deputy Conservator, 2nd grade, United Provinces, but to remain *seconded* as Assistant Inspector-General of Forests and Superintendent of Working-Plans.

(*iv*) Mr T. J. Campbell, officiating Conservator, 3rd grade, to Deputy Conservator, 1st grade, United Provinces.

28th August 1903.—No. 1044—75-10-*F*—Mr. J. H. Lace, Officiating Conservator, 2nd grade, Bengal, on furlough, reverted to the 3rd grade of Conservator, with effect from the 15th July 1903, on expiry of the privilege leave granted to him in the notification of this Department, No. 460-F., dated the 30th April 1903.

24th September 1903.—No. 1176—144-4-*F.*—The following transfers are made in the interests of the public service:—

(*i*) Mr. C. A Von B. Malcolm, Assistant Conservator of Forests, from the Central Provinces to Berar.

(*ii*) Mr. S. L. Kenny, Deputy Conservator of Forests, from Berar to the Central Provinces.

2.—MADRAS GAZETTE.

10th August 1903.—The following subordinates are declared to have passed the following examinations in accordance with Forest Code paragraph 69:—

(*a*) *Keeping of Forest Accounts and Returns*—
Deputy Ranger K. Ramachendra Aiyar.
Deputy Ranger P. Gopala Sankara.
Forester A Kuppuswami Aiyar.

(*b*) *Forest Act and Rules of the District*—
Deputy Ranger K. Ramachendra Aiyar (with credit).
Deputy Ranger P. Gopala Sankara.
Forester A Kuppuswami Aiyar,

• • • •

18th August 1903.—*Leave.*—Under Article 260 of the Civil Service Regulations, P. Venkatakrishnama Naidu, Acting Ranger, 4th grade, South Coimbatore Division, is granted privilege leave for two months and twenty days from 21st July 1903.

19th August 1903 —*Examinations.*—The following is the result of the Departmental Test held at the examinations in July 1903 :—

No.	Name.	Designation.	Subjects passed.
1	M. V. Ramaswami Aiyar ..	Probationary Deputy Ranger, 3rd grade, North Salem.	Forest Act and Rules and Forest Accounts and Returns.
2	A. Penchal Reddy ...	Forester, 3rd grade, Cuddapah.	Forest Accounts and Returns.
3	M. Kuppuswami Naidu ..	Forester, 3rd grade, South Salem.	Forest Act and Rules and Forest Accounts and Returns.
4	P. M. Krishnaswami Naidu.	Forester, 2nd grade, Nellore.	Forest Act and Rules.

24th August 1903.—*Transfers* —The following transfers are ordered :—

(1) M.R.Ry. P. Annappa, Ranger, from Ganjam to Kistna.

(2) * * * * *

(3) M.R.Ry K. Rama Row Ranger, from Anantapur to Kurnool.

(4) M.R.Ry P. Anantha Row, Ranger, from Kurnool to Bellary.

(5) M.R.Ry. V Kalyanarama Iyer, Extra Assistant Conservator of Forests, from Bellary to Ganjam

27th August 1903 —*Leave.*—Under Article 260 Civil Service Regulations, the Board of Revenue has granted Mr. A. B Jackson, District Forest Officer, South Coimbatore, privilege leave for one month with effect from or after 1st September 1903

31st August 1903 —*Transfer* —M.R.Ry. T Bapu Rao. Extra Assistant Conservator of Forests, from the Cuddapah district to Direction Division, Central Circle, from 1st October as a temporary measure.

11th September 1903 —*No* 361.—Mr. Francis Cowley Loftus Cowley Brown, Deputy Conservator of Forests, will on return from leave join duty at Madras and proceed to the Ganjam district to complete the preparation of working-plans for the Surada and Bugudi ranges. He will thereafter join as Special Working Plans Officer, Southern Circle.

3.—BOMBAY GAZETTE.

1st September 1903.—No 5998.—Mr. W. E. Copleston, Divisional Forest Officer, S. D. Kanara, is allowed privilege leave of absence for two months and twenty-six days

1st September 1903.—No 5999.—His Excellency the Governor in Council is pleased to make the following appointments :—

Mr. H. L. Newman to hold charge of the office of Divisional Forest Officer, S. D. Kanara, in addition to his own duties, during the absence on leave of Mr. W. E. Copleston, or pending further orders.

Mr. O H. L Napier to hold charge of the office of Divisional Forest Officer, N. D. Kanara, in addition to his own duties, pending further orders.

2nd September 1903.—No 6033—Mr. G. E. Marjoribanks, Assistant Conservator of Forests, 1st grade, has been allowed by His Majesty's Secretary of State for India to return to duty within the period of his leave.

9th September 1903—No. 6235.—Mr. H. Murray, Deputy Conservator of Forests, 2nd grade, has been allowed by His Majesty's Secretary of State for India to return to duty within the period of his leave.

14th September 1903—No. 4645.—Mr. W. E. Copleston, Deputy Conservator of Forests, delivered over and Mr. H. L. Newman, acting Deputy

Conservator of Forests, received charge of the Southern Forest Division of Kanara on the afternoon of the 3rd September 1903.

17th September 1903.—No. 6433.—Mr A. D. Wilkins, Deputy Conservator of Forests, 2nd grade, has been allowed by His Majesty's Secretary of State for India to return to duty within the period of his leave

No 4672.—Messrs W E. Copleston and O. H L Napier, Deputy Conservators of Forests, respectively delivered over and received charge of the Northern Forest Division of Kanara on the afternoon of the 3rd September 1903.

23rd September 1903.—No. 6578.—Mr Harihar Anant Nadkarni, L. C. E., Extra Assistant Conservator of Forests, 3rd grade, and Sub-Divisional Forest Officer, Belgaum, is allowed privilege leave of absence for three months.

23rd September 1903.—No. 6579.—His Excellency the Governor in Council is pleased to appoint Mr. Jehangir Hormasji Irani to act as Fourth Grade Extra-Assistant Conservator of Forests, Belgaum, during the absence on leave of Mr. Harihar Anant Nadkarni, L C E., or pending further orders.

23rd September 1903.—No. 6609.—Mr. J Dodgson Deputy Conservator of Forests, Fourth Grade, has been allowed by His Majesty's Secretary of State for India to return to duty within the period of his leave.

4.—BENGAL GAZETTE.

28th August 1903.—No 1830 T. R.—Mr J. L. Baker, Assistant Conservator of Forests, 2nd grade, Officiating as Deputy Conservator of Forests, 4th grade, is appointed to be Assistant Conservator of Forests 1st grade, substantive *pro tempore*, with effect from the 14th August 1903, *vice* Mr. E R Stevens, transferred to the United Provinces. Mr. Baker will continue to officiate as Deputy Conservator of Forests, 4th grade

18th September 1903.—No. 2214 T. R.—Mr T I. Pocock, Extra-Assistant Conservator of Forests, attached to the Sundarbans Division, is allowed leave for one month, under Articles 246 and 260 of the Civil Service Regulations, with effect from the 1st September 1903, or any subsequent date on which he availed himself of it.

5.—UNITED PROVINCES OF AGRA AND OUDH GAZETTE.

26th August 1903.—No. 3620.—II-622B-1.—The undermentioned officer has been granted by His Majesty's Secretary of State for India permission th return to duty :—

Name.	Service.	Appointment *	Date on which permitted to return.
Mr. P. H. Clutterbuck...	Forest.	Deputy Conservator.	Within the period of leave.

2nd September 1903.—No. 3716—II-851-1.—Mr. E R. Stevens, Assistant Conservator of Forests, whose services have been transferred to these Provinces by the Government of India, Department of Revenue and Agriculture, is hereby posted to the charge of the Dehra Dun Forest Division of the School Circle :—

31st August 1903.—No. 36-2.—II-429-C.—Mr. E A. Courthope, Assistant Conservator of Forests, attached to the Garhwal Division of the Central Circle, to be attached temporarily to the Naini Tal Division in the same Circle.

2nd September 1903.—No. 3717—II 851-1.—Lala Gulab Rai Extra-Assistant Conservator of Forests, on being relieved from the charge of the Dehra Dun Forest Division of the School Circle, to that of the Saharanpur Forest Division of the same circle.

2nd September 1903.—No 3718—II-851-1—Munshi Mahdi Hasan, Extra Assistant Conservator of Forests, in charge of the Saharanpur Forest Division of the School Circle, on being relieved, to be attached to the Garhwal Forest Division of the Central Circle.

3rd September 1903—No 3771.—II-720-C—Mr. H. G. Billson, Deputy Conservator of Forests, in charge of the Kheri Forest Division of the Oudh Circle, to hold charge of the current duties of the office of Conservator of Forests of that Circle in addition to his own, *vice* Mr. H. D. D. French, deceased.

16th September 1903.—No. 3922—II-86A-11.—The following temporary promotion is notified for general information :—

Entry No.	With effect from	Consequent on	Name.	From	To
1	22nd August 1903.	His arrival in these Provinces.	Mr E. R. Stevens.	Assistant Conservator of Forests, 1st grade.	Officiating Deputy Conservator of Forests, 4th grade.

6.—PUNJAB GAZETTE.

8th September 1903.—No. 407—A L. No. 18.—The following changes have taken place in the list of Forest Officers in the Associated Provinces with effect from the date specified against each :—

Name.	Present grade.	Grade to which promoted or reverted.	With effect from	REMARKS.
Mr. C. M McOrie.	Provisional Deputy Conservator, 4th grade.	Officiating Deputy Conservator, 3rd grade.	7th July 1903	Consequent on Mr. A. St. V Beechey's departure on one month's privilege leave on the afternoon of the 6th July 1903.
Mr. S. L. Kenny	Provisional Deputy Conservator, 4th grade.	Officiating Deputy Conservator, 4th grade.	14th July 1903	Consequent on Mr. B O. Coventry's return from deputation and departure on combined leave on the afternoon of the 13th July 1903.
Mr. B. M. Coventry.	Deputy Conservator, 3rd grade.	Officiating Deputy Conservator, 2nd grade.	22nd July 1903	Consequent on Mr. A V. Monro's departure on two months and 27 days' privilege leave on the afternoon of the 21st July 1903.
Mr. S. L. Kenny	Officiating Deputy Conservator, 4th grade.	Officiating Deputy Conservator, 3rd grade		
Mr. S. L. Kenny	Officiating Deputy Conservator, 3rd grade.	Officiating Deputy Conservator, 4th grade.	7th August 1903.	Consequent on Mr. A. St.V. Beechey's return from privilege leave on the forenoon, of the 7th August 1903.

7.—CENTRAL PROVINCES GAZETTE.

3rd September 1903 —No. 3906.—Privilege leave for two months and twenty-three days, under Article 260 of the Civil Service Regulations (4th edition), is granted to Mr J. J Hobday, Extra Assistant Conservator of Forests, with effect from the date on which he is relieved by Mr. Faiz Bakhsh.

12th September 1903 —No. 4099.—Mr. L. G Smith, Deputy Conservator of Forests, has been granted by His Majesty's Secretary of State for India two months' leave on medical certificate in extension of the leave granted him by Revenue Department Order No. 1782, dated the 29th April 1903.

8.—BURMA GAZETTE.

19th August 1903 —No 9.—Mr. J D. Hamilton, Forest Ranger, was relieved of the charge of the Sittang River Range on the afternoon of the 11th August 1903, by Mr. W. A Hearsey, Extra Deputy Conservator of Forests, Shwegyin Division.

21st August 1903.—No 331.—Under the provisions of Articles 246 and 260 of the Civil Service Regulations, privilege leave for three months is granted to Mr. R L. Pocock, Extra Assistant Conservator of Forests, with effect from the date on which he may avail himself of it.

26th August 1903.—No 342.—In this Department Notification No. 289 (Forests), dated the 2nd August 1901, make the following modifications :—

Cancel the following reversions ordered in item (2) :—

Mr W. T. T. McHarg, Deputy Conservator, 3rd grade, *prov. sub.* (on leave), to revert to his substantive appointment in the 4th grade of Deputy Conservator.

Mr. C. B. Smales, Deputy Conservator, 4th grade, *prov. sub* (officiating 3rd grade) to be Assistant Conservator, 1st grade, and to continue to officiate as Deputy Conservator, 3rd grade.

Mr. H. W. A. Watson, Assistant Conservator, 1st grade, *prov. sub.*, (officiating Deputy Conservator, 4th grade), to be Assistant Conservator, 2nd grade, and to continue to officiate as Deputy Conservator, 4th grade.

For item (14) substitute the following :—

(14) With effect from the 5th March 1901, consequent on the confirmation of Mr. A. Reuther, Deputy Conservator, 1st grade, as Conservator :

Mr. A. Weston, Deputy Conservator, 1st grade, *prov. sub.*, to be confirmed in his appointment.

Mr. J Murray, Deputy Conservator, 2nd (officiating 1st) grade, to be Deputy Conservator, 1st grade, *prov. sub.*

Mr. C. E. Muriel, Deputy Conservator, 2nd grade, *prov. sub.*, to be confirmed in his appointment.

Mr. A. F. Gradon, Deputy Conservator, 3rd grade (on leave), to be Deputy Conservator, 2nd grade, *prov. sub.*

Mr. G. R Long, Deputy Conservator, 3rd grade, *prov. sub.*, to be confirmed in his appointment.

Mr. C. W. A. Bruce, Deputy Conservator, 4th grade (on leave), to be Deputy Conservator, 3rd grade, *prov. sub.*

Mr. F. Linnell, Deputy Conservator, 4th grade, *prov. sub.* (officiating 3rd grade), to be confirmed in his appointment and to continue to officiate in the 3rd grade of Deputy Conservators.

Mr. A. H. M. Lawson, Assistant Conservator, 1st grade (officiating Deputy Conservator, 3rd grade), to be Deputy Conservator, 4th grade *prov. sub.*, and to continue to officiate as Deputy Conservator, 3rd grade.

Mr. R. S. Troup, Assistant Conservator, 1st grade, *prov. sub.*, (officiating Deputy Conservator, 4th grade), to be confirmed in his appointment and to continue to officiate as Deputy Conservator, 4th grade

Mr. J. J. Rorie Assistant Conservator 2nd grade (officiating Deputy Conservator, 4th grade), to be Assistant Conservator, 1st grade, *prov. sub.*, and to continue to officiate as Deputy Conservator, 4th grade.

26th *August* 1903.—No. 343.—In this department Notification No 153, (Forests) dated the 24th April 1902, as amended by this Department Notifications Nos 217 and 354 (Forests), dated the 16th June 1902 and the 1st September 1902, respectively, make the following modifications:—

Substitute the following for item (3):—

(3) With effect from the 30th August 1901, consequent on the death on the 29th August 1901, of Mr. C L Toussaint, Deputy Conservator, 3rd grade:—

Mr. W T. T McHarg, Deputy Conservator, 3rd grade, *prov. sub.*, to be confirmed in that grade, and to continue to officiate as Deputy Conservator, 2nd grade.

Mr. J. Messer, Deputy Conservator, 4th (officiating 3rd) grade, to be Deputy Conservator, 3rd grade, *prov. sub* and to officiate as Deputy Conservator, 2nd grade.

Mr. C B Smales, Deputy Conservator, 4th grade, *prov sub*, to be confirmed in that grade, and to continue as Deputy Conservator, 3rd grade.

Mr. C. W. Doveton, Assistant Conservator, 1st grade, to be Deputy Conservator, 4th grade, *prov sub*; and to continue to officiate as Deputy Conservator 3rd grade.

Mr. H. W A. Watson, Assistant Conservator, 1st grade, *prov. sub.*, to be confirmed in that grade.

Mr. H L. P. Walsh, Assistant Conservator, 2nd grade (officiating Deputy Conservator, 4th grade), to officiate as Deputy Conservator, 3rd grade.

Substitute the following for item (4):—

(4) With effect from the 12th September 1901, consequent on the return from deputation of Mr. H. Slade, Deputy Conservator 1st grade—

Mr. J. Murray, Deputy Conservator, 1st grade, *prov sub.*, to be Deputy Conservator, 2nd grade, and to officiate as Deputy Conservator, 1st grade

Mr. G. F. R Blackwell, Deputy Conservator, 3rd (officiating 1st) grade, to officiate as Deputy Conservator, 2nd grade.

Mr. A. F. Gradon, Deputy Conservator, 2nd grade, *prov. sub.*, to be Deputy Conservator, 3rd grade.

Mr. J. Messer, Deputy Conservator, 3rd grade, *prov. sub.*, officiating Deputy Conservator, 2nd grade, to be Deputy Conservator, 4th grade, and to officiate as Deputy Conservator, 3rd grade.

Mr. C. W. Doveton, Deputy Conservator, 4th grade, *prov. sub.*, to be Assistant Conservator, 1st grade, and to continue to officiate as Deputy Conservator, 3rd grade.

Mr H. L P. Walsh, Assistant Conservator, 2nd grade (officiating Deputy Conservator, 3rd grade), to officiate as Deputy Conservator, 4th grade.

Cancel the following promotions ordered in item (6):—

Mr C. W A Bruce, Deputy Conservator, 4th grade, to be Deputy Conservator, 3rd grade, *prov sub.*

Mr. A H. M Lawson, Assistant Conservator, 1st grade, to be Deputy Conservator 4th grade, *prov. sub.*, and to continue to officiate as Deputy Conservator, 3rd grade.

Mr. J J. Rorie, Assistant Conservator, 2nd grade, to be Assistant Conservator, 1st grade, *prov sub.*, and to continue to officiate as Deputy Conservator, 3rd grade.

No 348 —Mr C. M. Hodgson, Deputy Conservator of Forests, has been permitted by His Majesty's Secretary of State for India to return to duty within the period of his leave.

3rd September 1903 —No. 353 —In this Department Notification No. 344, dated the 27th August 1903, in the seventh line, *for* "24th June 1900" *read* "24th June 1903."

3rd September 1903 —No 354 —Under the provisions of Articles 246 and 260 of the Civil Service Regulations, privilege leave for two months and seven days is granted to Mr J. W. Ryan, Extra Assistant Conservator of Forests, with effect from the date on which he may avail himself of it.

3rd September 1903 —No. 355 —Mr J. L. Hefferman, Extra Assistant Conservator of Forests, has been granted by His Majesty's Secretary of State for India an extension of leave on medical certificate for two months.

3rd September 1903 —No 467 —Mr. D. A. Allan, Forest Ranger, 2nd grade, is transferred from the Mergui Range. South Tenasserim Division, and is posted to the charge of the Mergui Rubber Plantation, *vice* Mr. J. W. Ryan, Extra Assistant Conservator of Forests, proceeding on leave.

3rd September 1903 —No. 1.—Mr. R. L. Pocock, Extra Assistant Conservator of Forests, made over charge of the Shwegu Sub-division, Bhamo Division, to Mr G F. R Blackwell, Deputy Conservator of Forests, on the afternoon of the 30th August 1903, and proceeded on the leave granted him in Revenue Department Notification No 331 (Forests), dated the 21st August 1903.

5th September 1903 —No 497.—Mr C. H. Hearsey, Ranger, 3rd grade, is promoted to the 2nd grade, *prov. sub.*, with effect from the 22nd August 1903.

9th September 1903.—No. 14 —With reference to Revenue Department Notification No. 406 (Forests), dated the 30th July 1903, Mr. J D. Hamilton, Forest Ranger, 2nd grade, assumed charge of his duties in the Depot and Agency Division, Rangoon, on the forenoon of the 17th August 1903.

10th September 1903. No. 367.—On return from leave Mr. H. C. Walker, Assistant Conservator of Forests, is posted to the Tenasserim Circle as Personal Assistant to the Conservator.

10th September 1903 —No. 10.—With reference to Revenue Department Notification No. 381 (Forests), dated the 31st July 1903, Mr. C. V. Ryan, Extra Assistant Conservator of Forests, reported his arrival at the office of the Deputy Conservator of Forests, Kado Division, on the forenoon of the 4th September 1903.

11th September 1903.—No 11.—Mr. H. C. Walker, Assistant Conservator of Forests, assumed charge of his duties as Personal Assistant to the Conservator of Forests, Tenasserim Circle, on the forenoon of the 7th day of September 1903.

16th September 1903.—No. 12.—With reference to Revenue Department Notification No. 467 (Forests), dated the 3rd September 1903, Mr D. A. Allan, Forest Ranger, assumed charge of the Meigui Rubber Plantation, relieving Mr. J. W. Ryan, Extra Assistant Conservator of Forests, on the afternoon of the 8th September 1903.

9.—ASSAM GAZETTE.—

3rd September 1903.—No 7685G.—The following is published :—

The undermentioned officers have been granted by His Majesty's Secretary of State for India extension of leave or permission to return to duty, as advised in list dated the 7th August 1903 :—

Name.	Service.	Appointment	Period and nature of extension.
Mr. W. F. Perrée ...	...	Deputy Conservator of Forests	Furlough extended on the 27th November 1903
Name.	**Service**	**Appointment.**	**Date on which permitted to return.**
Mr J. E. Barret ...	...	Deputy Conservator of Forests.	Within period of leave.
"	"	"	"
"	"	"	"
Mr. W. F. Perrée ...	...	Deputy Conservator of Forests.	Do Do.

10.—HYDERABAD RESIDENCY GAZETTE—*Nil.*

11.—MYSORE GAZETTE.

14th August 1903.—No. 96.—1213.—The five days' casual leave of absence granted to Mr. P. E. Benson, Sub-Assistant Conservator of Forests, Mysore District, in Government Proceedings No 627-8—6327-8, dated the 15th April 1903, is hereby commuted to privilege leave under Article 188 of the Mysore Service Regulations.

14th August 1903.—No. 99—1216.—The forty-one days' privilege leave of absence granted to Mr P. E. Benson, Sub-Assistant Conservator of Forests, Mysore District, in Government Notification No. 84—1007, dated 5th August 1903, is hereby extended by ten days.

Pioneer Press, No. 1309.—1-11-03.

Advertisements.

ESTABLISHED 1881.

THE "TROPICAL AGRICULTURIST"

Circulates in India, Ceylon, the Straits, Burma, Japan, Borneo, Northern Australia, Fiji, East and South Africa, Central and South America, Florida, California, West Indies, &c.

A Monthly Magazine of Information specially all about Tea, regarding tropical and sub-tropical products.

Edited by J. FERGUSON, of the *Ceylon Observer, &c.*

RATES OF SUBSCRIPTION INCLUDING POSTAGE,

STRICTLY IN ADVANCE.

For Ceylon.	Yearly ...	Rs.12	For Europe, India, &c.	Yearly ...	£1 6s.	or Rs.14
	Half-yearly	" 9		Half-yearly ...	15s.	" " 8

Single Copies, Re.1; Back Copies, Re.1-5-0.

Publishers:—A. M. & J. Ferguson, Colombo, Ceylon. *Agents:*—Thacker, Spink & Co., Calcutta.

"INDIAN PLANTING AND GARDENING."

PUBLISHED WEEKLY. ILLUSTRATED.

Circulates all over India, Burma, Ceylon, Straits, East and South Africa, Mexico, California, Central America, Mauritius, Zanzibar, &c., &c.

Contains the most reliable information on all matters regarding Tea, Coffee and other tropical and sub-tropical products.

THE ONLY HORTICULTURAL PAPER IN THE EAST.

A guide to Amateur Gardeners.

Edited by H. St. John Jackson, F.L.S., F.R.H.S.

SUBSCRIPTION:—Indian, Rs. 20 yearly and Rs. 11 half-yearly, including postage; Rs.6 quarterly, including postage. Foreign, £2 yearly and £1 1s. half-yearly, including postage.

Apply to—

MANAGER, 5/1, Council House Street, CALCUTTA.

FOR SALE

A MANUAL OF FOREST ENGINEERING FOR INDIA

— BY —

C. G. ROGERS, DEPUTY CONSERVATOR OF FORESTS, BENGAL.

VOLUMES I and II, Rs. 4 per VOLUME

May be obtained from the Superintendent of Government Printing, India; or Messrs. Thacker, Spink & Co., Calcutta.

SALE OF MR. BADEN-POWELL'S BOOKS.

Land Revenue of British India and its Administration ...	Rs 8	10
Forest Law	" 5	14
Land Tenures and Systems of India	" 47	4

The above may be obtained from Messrs THACKER & Co and COMBRIDGE & Co., Booksellers, Bombay

FOR SALE

1. ***The Indian Forester***, complete in 28 Volumes, bound in half green Calf: in excellent condition. Cost Rs.15 per vol.
2. ***Encyclopædia Britannica***, 9th Edition, in 25 Vols., half morocco' in original condition, with a revolving book case, cost Rs. 420. What offers? Apply FORESTER, care of Manager, Pioneer Press.

CORRIGENDA

TO

TABLES

Showing the Cubic Contents of Round and Squared timber in feet and decimals of a foot, and the values of the same at various rates

ARRANGED BY

L. MERCER,

Deputy Conservator of Forests, N.-W. P. and Oudh.

Contents of Round Timber.

Page.	Length.	Girth.	Correction.
7	36	3′-11″	For 24·5 read 34·5
10	18	5′-1″	For 39·1 read 29·1
13	33	6′-11″	For 110·6 read 113·6
14*	20	7′-1″	For 26·7 read 62·7
18	20	9′-0″	For 169·2 read 101·2
21	36	10′-7″	For 256·0 read 252·0

Contents of Sawn Timber.

Page.	Length.	Breadth and thickness.	Correction.
6	15	20″ × 1½″	For 3·3 read 3·1
17	10	23″ × 7″	For 1·2 read 11·2
32	19	17″ × 14″	For 31·6 read 31·4
34†	16	11″ × 15″	For 28·3 read 18·3
„ †	17	16″ × 15″	For 18·3 read 28·3

* Correction required in 1st edition only.
† Do. do. in both editions.
Other corrections required in 2nd edition only.

Spare copies of this slip can be obtained from the Deputy Conservator of Forests, Garhwal Division, Naini Tal.

تصحیح

جنتریوں کا

گول و چوکور لکڑی کے فٹ مکعب و مختلف درفی فٹ مکعب کے حساب سے
لکڑی کے دام نکلنے کی
جسکو
ایل مرسر صاحب ڈپٹی کنسرویٹر نے تیار کیا

جنتری مکعب فٹ گول لکڑی کی

ورق	لمبائی فٹ	بیچ کی گولائی انچوں میں	صحیح کیا ہوا
۱۵	۲۲	۷'—۹"	۸۶٫۵۶ کے بدلے ۸۲٫۵۶ پڑھو
۲۰	۳۳	۱۰'—۴"	۲۲۴٫۵۲ کے بدلے ۲۲۰٫۵۲ پڑھو

جنتری مکعب فٹ چری ہوئی لکڑی کی

ورق	لمبائی فٹ	چوڑائی و موٹائی انچوں میں	صحیح کیا ہوا
۳۴	۱۱	۵" × ۱۵"	۵٫۵ کے بدلے ۵٫۷ پڑھو
۳۶	۱۴	۱۴" × ۱۶"	۸٫۲۱ کے بدلے ۲۱٫۸ پڑھو

جنتری مکعب فٹ کے دام نکالنے کی

ورق	مقدار فٹ	شرح فی فٹ مکعب	صحیح کیا ہوا
۹	۸۰	۵	صــ صــ کے بدلے عــ صــ پڑھو

جنتری کے زاید پارچے ڈپٹی کنسرویٹر صاحب بہادر محکمہ جنگلات گڑھوال ڈویژن مقام نینی تال سے دستیاب ہوسکتے ہیں

VIII.—EXTRACTS FROM OFFICIAL GAZETTES.

1.—GAZETTE OF INDIA.

24th September 1903.—No. 1176—144-4-*F*.—The following transfer are made in the interests of the public service:

(i) Mr. C. A. Von B. Malcolm, Assistant Conservator of Forests, from the Central Provinces to Berar.

(ii) Mr. S. L. Kenny, Deputy Conservator of Forests, from Berar to the Central Provinces.

19th *October* 1903.—No 49.—Mr. Harswarup, Extra-Assistant Conservator of Forests of Ajmer-Merwara, is granted privilege leave for three months, with effect from the date of his relief by Mr. Nand Mal, Extra-Assistant Conservator of Forests, whose services have been temporarily placed by the Government of the United Provinces of Agra and Oudh at the disposal of the Hon'ble the Chief Commissioner of Ajmer-Merwara.

On return from leave Mr. Harswarup will revert to his substantive employment under the Government of the United Provinces of Agra and Oudh.

2.—MADRAS GAZETTE.

21st September 1903.—No.—386.—Mr. George Frederick Fischer Foulkes to be District Forest Officer, Godavari, to join on return from leave.

21st September 1903.—No 387.—Mr. Hugo Francis Andrew Wood to be District Forest Officer, Kurnool, to join on relief by Mr. Foulkes.

21st September 1903.—No 388.—Mr. John Sinclair Battie to be District Forest Officer, North Arcot, to join on relief by Mr. Wood.

5th October 1903.- *Erratum*.—In notification relating to the promotions to the Rangers' class of four students who returned with certificates from the Dehra Dun Forest School, published on page 698 of Part II of the *Fort St. George Gazette* of 12th May 1903, *for* "1st April 1903" *read* "31st March 1903."

15th October 1903.—No. 415.—Mr. James Stewart Scot, District Forest Officer, Cuddapah, is granted privilege leave for one month and seven days, with effect from 20th October 1903 or date of relief, under Article 260 of the Civil Service Regulations.

3.—BOMBAY GAZETTE.

9th October 1903.—No 7071.—Mr. R. S. F. Fagan, Conservator of Forests, Southern Circle, is granted privilege leave of absence for three months in combination with furlough for fifteen months.

Mr. J. Dodgson, on return to duty, to be Divisional Forest Officer in charge Working plans, Central Circle.

Mr. J. D. Maitland-Kirwan to be Divisional Forest Officer, Ea Khandesh.

10th October 1903.—No. 7107.—His Excellency the Governor in Council is pleased to appoint Mr. A. A. Zuzarte to act as Daftardar to the Collector of Khandesh during the absence of Mr. Shalom Bapuji on leave, or pending further orders.

13th October 1903.—No. 7150.—His Excellency the Governor in Council is pleased to make the following appointments :—

- Mr. H. Murray, on return to duty, to be Divisional Forest Officer, S. D Kanara, and on the departure of Mr. R. S F. Fagan on leave, to act as Conservator of Forests, Southern Circle, holding the Office of Divisional Forest Officer, S. D. Kanara, in addition, pending the return of Mr. W. E. Copleston.
- Mr. G E Marjoribanks, on return to duty, to be Divisional Forest Officer, N. D Kanara.
- Mr. A. D Wilkins, on return to duty, to be Divisional Forest Officer, Poona.
- Mr. G. R Duxbury, on relief, to be Divisional Forest Officer in charge Working-plans, Northern Circle.
- Mr. V. D. P. Rebeiro, L C E, on relief to be Extra-Assistant Conservator of Forests, Sind Circle.

13th October 1903 —No. 5460.—Messrs. H. A. Nadkarni, Extra-Assistant Conservator of Forests, delivered over, and J. H. Irani, Forest Ranger, received charge of the Sub-Divisional Forest Office, Belgaum Division, on the forenoon of 2nd October 1903.

21st October 1903 —No 7322.—Mr E M Hodgson, Divisional Forest Officer, Surat, is allowed privilege leave of absence for six weeks.

21st October 1903.—No. 7323.—His Excellency the Governor in Council is pleased to appoint Mr. Chunilal Gulabchand Dalal, L. C. E, to hold charge of the office of the Divisional Forest Officer, Surat. in addition to his own duties, during the absence on leave of Mr. E. M. Hodgson, or pending further orders.

4.—BENGAL GAZETTE.

22nd September 1903 —No. 2285 T. R --In continuation of this Department Notification No. 1163 T. R, dated the 17th June 1903, Mr. J. L. Baker, Assistant Conservator of Forests, 2nd grade, is promoted to officiate as Assistant Conservator of Forests, 1st grade, with effect from the 20th May 1903, *vice* Mr. H. D D. French, temporarily transferred to the Oudh Circle, United Provinces, as Officiating Conservator of Forests, 3rd grade.

The portion of Notification No 1122 T. R., dated the 17th June 1903, which refers to Mr. J. L. Baker, is cancelled.

5.—UNITED PROVINCES GAZETTE.

29th September 1903.—No. 4104 II—665B.—Mr. E. R. Stevens, Assistant Conservator of Forests, 1st grade, provisionally substantive, with effect from 22nd August 1903, to fill an existing vacancy.

6th October 1903.—No. 4227—II/ 651B.—Saiyid Mahdi Hasan, Extra-Assistant Conservator of Forests, attached to the Garhwal Forest Division of the Central Circle, to be temporarily in charge of the Pilibhit Forest Division of the Oudh Circle, *vice* Babu Nand Mal, on deputation.

6th October 1903 —No. 4228.—II/651B.—Notification No. 4018—II/267C, dated 23rd September 1903, granting Saiyid Mahdi Hasan, Extra-Assistant Conservator of Forests, privilege leave for one month from the 15th September 1903, is hereby cancelled.

6th October 1903.--No. 4226—II/651B.—The services of Babu Nand Mal, Extra-Assistant Conservator of Forests in charge of the Pilibhit Forest Division of the Oudh Circle, are hereby temporarily placed at the disposal of the Chief Commissioner of Ajmer-Merwara.

10th October 1903 —No 4315—II/595C —Mr F F R Channer, officiating Deputy Conservator of Forests in charge of the Bahraich Forest Division of the Oudh Circle, privilege leave for twenty-eight days from 27th October 1903.

10th October 1903 —No 4317—II/595C —Mr P H. Clutterbuck, Deputy Conservator of Forests, on return from leave, to the charge of the Kheri Forest Division of the Oudh Circle

14th October 1903 —No 4454 —II/866C —Mr T J Campbell, Deputy Conservator of Forests, Naini Tal Forest Division, Central Circle, to hold charge of the current duties of the office of Conservator of Forests of that Circle in addition to his own, *vice* Mr F B Dickinson, deceased

10th October 1903 —No 4316—II 595C – Mr H G Billson, Deputy Conservator of Forests, on being relieved from the charge of the Kheri Forest Division of the Oudh Circle, to that of the Gorakhpur Forest Division of the same Circle, and to hold, in addition, the charge of the Bahraich Forest Division during the absence of Mr Channer on leave.

16th October 1903 —No 4512 - II/835C — Babu Karuna Nidhan Mukerji, Extra Deputy Conservator of Forests in charge of the Gonda Forest Division of the Oudh Circle, on being relieved, privilege leave for one month and fifteen days

16th October 1903 —4513 —II 835C – Mr R St G Burke, Assistant Conservator of Forests, on being relieved from the charge of the Gorakhpur Forest Division of the Oudh Circle, to that of the Gonda Forest Division of the same Circle, *vice* Babu Karuna Nidhan Mukerji, granted leave

6.—PUNJAB GAZETTE.

21st October 1903 – No 461 —Mr C. F Rossiter, Extra Deputy Conservator of Forests, and Lala Jowala Pershad, Extra-Assistant Conservator of Forests, respectively made over and received charge of the Montgomery Forest Division on the forenoon of the 5th October 1903, consequent on the latter's return from privilege leave.

On and from the said date Mr C. F. Rossiter will remain in charge of the Mooltan Forest Division only

7.—CENTRAL PROVINCES GAZETTE.

28th September 1903 —No 4402 – Privilege leave for twenty days, under Articles 246 and 260 of the Civil Service Regulations, is granted to Mr. G. F. Taylor, Deputy Conservator of Forests, Chhindwara, with effect from the 10th August 1903, or the subsequent date on which he may avail himself of it.

9th October 1903 —No. 10.—K. Rama Rao, Ranger, 1st grade, attached to the Nagpur-Wardha Division, is granted privilege leave for a fortnight in extension of the two months' privilege leave already granted him by Departmental Order No 80, dated the 22nd July 1903.

8.—BURMA GAZETTE.

16th September 1903 —No 16 —With reference to Revenue Department Notification No. 280 (Forests), dated the 21st July 1903, Mr C. V. Ryan, Extra-Assistant Conservator of Forests, made over, and Mr S. A. Wood Extra-Assistant Conservator of Forests, received charge of the Bampon subdivision, Southern Shan States Division, on the forenoon of the 14th August 1903.

16th September 1903.—No. 2.—Mr. B. R. Hutchins, Forest Ranger, 3rd grade, has been granted privilege leave for one month and eight days, with effect from the 29th August 1903.

18th September 1903.—No. 3.—Mr C. A. Clerk, Ranger, 2nd grade, on transfer, relinquished charge of his duties in the Depôt Division on the afternoon of the 28th August 1903, and assumed charge of the Mawku and Yu Ranges in the Upper Chindwin Division on the afternoon of the 3rd September 1903.

18th September 1903.—No. 13.—With reference to Revenue Department Notification No 354 (Forests), dated the 3rd September 1903, Mr. J. W. Ryan, Extra-Assistant Conservator of Forests, availed himself of the privilege leave on the afternoon of the 8th September 1903.

18th September 1903.—No 384.—Mr R. E Marsden, officiating Deputy Conservator of Forests, is transferred from the Magwe subdivision, Minbu Division, to the charge of the Pyinmana Division, *vice* Mr C. E. Muriel, Deputy Conservator of Forests, transferred.

18th September 1903.—No 385.—Mr C. R Dun, Deputy Conservator of Forests, has been granted by His Majesty's Secretary of State for India an extension of furlough for six months.

24th September 1903.—No. 386.—The following alterations in rank are ordered in the Forest Department :—

With effect from the 5th August 1903, consequent on the appointment of Mr. A. F. Gradon as officiating Conservator—

Mr. W. T. T McHarg, Deputy Conservator of Forests, 3rd grade, to officiate as Deputy Conservator, 2nd grade.

Mr. R. S Troup, Deputy Conservator of Forests, 4th grade *prov. sub.*, to officiate as Deputy Conservator, 3rd grade.

29th September 1903.—No. 14.—With reference to Revenue Department Notification No. 282 (Forests), dated the 21st July 1903, Mr. W. J G. Cooper, Extra Assistant Conservator of Forests, reported himself for duty in the West Salween Division on the afternoon of the 17th September 1903.

1st October 1903.—No. 388.—On return from leave Mr. A. H. M. Lawson, Deputy Conservator of Forests, is posted to the charge of the Prome Division, *vice* Mr. J. J. Rorie, officiating Deputy Conservator of Forests, transferred.

1st October 1903.—No. 389.—On relief by Mr. A. H. M. Lawson, Deputy Conservator of Forests, Mr. J J. Rorie, officiating Deputy Conservator of Forests, is attached to the Rangoon Forest Division for Working-plans duty.

1st October 1903.—No. 390.—On return from leave Mr. H. L. P. Walsh, officiating Deputy Conservator of Forests, is attached to the Ruby Mines Division for Working-plans duty.

3rd October 1903.—No. 391.—Mr. L. C. Davis, officiating Deputy Conservator of Forests, is transferred from the North Tharrawaddy subdivision, Tharrawaddy Division, to the charge of the Bassein Division.

3rd October 1903.—No. 392.—On relief by Mr. Davis, Mr. H. B. Ward, Deputy Conservator of Forests, is transferred from the Bassein Division to the charge of the Rangoon Division.

3rd October 1903.—No. 393.—On relief by Mr. Ward, Mr. S. Carr, Deputy Conservator of Forests, is transferred from the Rangoon Division to the charge of the Pyinmana Division.

3rd October 1903.—No. 394.—On relief by Mr. S. Carr, Mr. R. E. Marsden, officiating Deputy Conservator of Forests, is transferred from Pyinmana to the charge of the North Tharrawady subdivision, Tharrawaddy Division.

3rd October 1903.—No. 395.—Mr. G. R. Jeffery, Assistant Conservator of Forests, is transferred from the Mu Division to the charge of the Myadaung subdivision, Katha Division.

3rd October 1903.—No. 396—Mr. J. C. Hopwood, Assistant Conservator of Forests, is transferred from the Kyaukse subdivision, Mandalay Division, to the charge of the South Tharrawaddy subdivision, Tharrawaddy Division, *vice* Mr. French, transferred.

3rd October 1903—No. 397.—On relief by Mr. Hopwood, Assistant Conservator of Forests, Mr. W. R. French, Extra-Assistant Conservator of Forests, is transferred from the charge of the South Tharrawaddy subdivision to the charge of the Revenue Range, Tharrawaddy Division.

5th October 1903.—No. 15.—With reference to Revenue Department Notification No. 388 (Forests), dated 1st October 1903, Mr. A. H. M. Lawson, Deputy Conservator of Forests, assumed charge of the Prome Division on the forenoon of the 19th September 1903, relieving Mr. J. J. Rorie, officiating Deputy Conservator of Forests.

5th October 1903.—No. 16.—With reference to Revenue Department Notification No. 389 (Forests), dated 1st October 1903, Mr. J. J Rorie, officiating Deputy Conservator of Forests, assumed charge of Working-plans in the Rangoon Division on the forenoon of the 22nd September 1903.

15th October 1903—No. 406.—On return from leave Mr. E. M. Buchanan, Extra Deputy Conservator of Forests, is posted to the charge of the Henzada-Thongwa Division, *vice* Mr. H. W. A. Watson, transferred.

17th October 1903.—No. 409.—Mr. C. V. Ryan, Extra-Assistant Conservator of Forests, was placed on special duty at the Kado timber depôt from the 5th to the 14th September 1903.

17th October 1903.—No. 17.—With reference to Revenue Department Notification No. 396 (Forests), dated 3rd October 1903, Mr. J. C. Hopwood, Assistant Conservator of Forests, made over, and Mr. A. Lawrence, Deputy Conservator of Forests, received, charge of the Kyaukse subdivision, Mandalay Division, on the afternoon of the 12th October 1903.

17th October 1903.—No. 18.—Mr. C E. Muriel, Deputy Conservator of Forests, made over charge of the Pyinmana Forest Division temporarily to Mr T. W Forester, Extra-Assistant Conservator of Forests, on the afternoon of the 17th September 1903.

17th October 1903—No 19.—With reference to Revenue Department Notification No. 384 (Forests), dated 24th September 1903, Mr. R E. Marsden, officiating Deputy Conservator of Forests, relinquished charge of his duties in the Magwe subdivision, Minbu Forest Division, on the afternoon of the 8th October 1903, and relieved Mr. T. W. Forester, Extra-Assistant Conservator of Forests, of the charge of the Pyinmana Forest Division on the afternoon of the 15th October 1903.

22nd October 1903.—No 414—On relief by Mr. E. M. Buchanan, Extra Deputy Conservator of Forests, Mr. H W. Watson, officiating Deputy Conservator of Forests, is attached to the Shwegyin Forest Division for Working-plans duty.

9.—ASSAM GAZETTE.—

22nd October 1903.—No. 9059G.—Mr. E. S. Barker, Assistant Conservator of Forests, is transferred from the Sibsagar Forest Division to the Darrang Forest Division and attached to the latter division.

10 —HYDERABAD RESIDENCY GAZETTE.

The following extract from the Punjab Gazette is republished —

8th September 1903 —No 407 —A *L* No 18 —The following changes have taken place in the list of Forest Officers in the Associated Provinces with effect from the date specified against each —

Name	Present grade	Grade to which promoted or reverted	With effect from	REMARKS
* *	* *	* *	* *	* *
Mr S L Kenny	Provisional Deputy Conservator 4th grade	Officiating Deputy Conservator 4th grade	14th July 1903	Consequent on Mr B O Coventry's return from deputation and departure on combined leave on the afternoon of the 13th July 1903
* *	* *	* *	* *	* *
Mr S L Kenny	Officiating Deputy Conservator 4th grade	Officiating Deputy Conservator 3rd grade	22nd July 1903	Consequent on Mr A V Monro's departure on two months and 27 days privilege leave on the afternoon of the 21st July 1903
Mr S L Kenny	Officiating Deputy Conservator 3rd grade	Officiating Deputy Conservator 4th grade	7th August 1903	Consequent on Mr A St V Beechey's return from privilege leave on the forenoon of the 7th August 1903

11 —MYSORE GAZETTE.

14th October 1903 —No 175—2498 —Mr P E Benson, Sub Assistant Conservator of Forests, Mysore District, who was granted ten days' extension of leave in Notification No 99—1216, dated the 14th August 1903, in continuation of the forty one days' privilege leave sanctioned in Notification No 84—1007, dated the 5th idem, having returned and reported himself for duty on the forenoon of the 17th idem, the unexpired portion of the leave, namely four days is hereby cancelled

2nd October 1903 —No 164—2293 —Under Article 188 of the Mysore Service Regulations Mr G E Ricketts, Assistant Conservator of Forests and *ex-officio* Assistant Secretary to Government, Forest Department, was granted privilege leave of absence for nine days, with effect from the 12th September 1903

Pioneer Press, No.1478.—1-12-03

Advertisements.

. ESTABLISHED 1881.

THE "TROPICAL AGRICULTURIST"

Circulates in India, Ceylon, the Straits, Burma, Japan, Borneo, Northern Australia, Fiji, East and South Africa, Central and South America, Florida, California, West Indies, &c.

A Monthly Magazine of Information specially all about Tea, regarding tropical and sub-tropical products.

Edited by J. FERGUSON, of the *Ceylon Observer, &c.*

RATES OF SUBSCRIPTION INCLUDING POSTAGE,

STRICTLY IN ADVANCE.

For Ceylon.	Yearly ...	Rs.12	For Europe, India, &c.	Yearly ...	£1 6s. or Rs.14
	Half-yearly „	9		Half-yearly ...	15s. „ „ 8

Single Copies, Re.1 ; Back Copies, Re.1-5-0.

Publishers:—A. M. & J. Ferguson, Colombo, Ceylon. *Agents:*—Thacker, Spink & Co., Calcutta

"INDIAN PLANTING AND GARDENING."

PUBLISHED WEEKLY. ILLUSTRATED.

Circulates all over India, Burma, Ceylon, Straits, East and South Africa, Mexico, California, Central America, Mauritius, Zanzibar, &c., &c.

Contains the most reliable information on all matters regarding Tea, Coffee and other tropical and sub-tropical products.

THE ONLY HORTICULTURAL PAPER IN THE EAST.

A guide to Amateur Gardeners.

Edited by H. St. John Jackson, F.L.S., F.R.H.S.

SUBSCRIPTION :—Indian, Rs. 20 yearly and Rs. 11 half-yearly, including postage; Rs.6 quarterly, including postage. Foreign, £2 yearly and £1 1s. half-yearly, including postage.

Apply to—

MANAGER, 5/1, Council House Street, CALCUTTA.

FOR SALE

A MANUAL OF FOREST ENGINEERING FOR INDIA

— BY —

C G. ROGERS, DEPUTY CONSERVATOR OF FORESTS, BENGAL.

— VOLUMES I and II, Rs. 4 per VOLUME.

May be obtained from the Superintendent of Government Printing, India ; or Messrs. Thacker, Spink & Co., Calcutta.

SALE OF MR. BADEN-POWELL'S BOOKS.

Land Revenue of British India and its Administration ...	Rs. 3 10
Forest Law	„ 5 14
Land Tenures and Systems of India	„ 47 4

The above may be obtained from Messrs. THACKER & Co. and COMBRIDGE & Co., Booksellers, Bombay

FOR SALE

1. ***The Indian Forester***, complete in 28 Volumes, bound in half green Calf : in excellent condition. Cost Rs.15 per vol.

2. ***Encyclopædia Britannica***, 9th Edition, in 25 Vols., half morocco, in original condition, with a revolving book case, cost Rs. 420. What offers? Apply FORESTER, care of Manager, Pioneer Press.

CORRIGENDA

TO

TABLES

Showing the Cubic Contents of Round and Squared timber in feet and decimals of a foot, and the values of the same at various rates

ARRANGED BY

L. MERCER,

Deputy Conservator of Forests, N.-W. P. and Oudh.

Contents of Round Timber.

Page.	Length.	Girth.	Correction.
7	36	3′-11″	For 24·5 read 34·5
10	18	5′-1″	For 39·1 read 29·1
13	38	6′-11″	For 116·6 read 113·6
14*	20	7′-1″	For 26·7 read 62·7
18	20	9′-0″	For 169·2 read 101·2
21	36	10′-7″	For 256·0 read 252·0

Contents of Sawn Timber.

Page.	Length.	Breadth and thickness.	Correction.
6	15	20″×1½″	For 3·3 read 3·1
17	10	23″×7″	For 1·2 read 11·2
32	19	17″×14″	For 31·6 read 31·4
34†	16	11″×15″	For 28·3 read 18·3
,, †	17	16″×15″	For 18·3 read 28·3

* Correction required in 1st edition only.
† Do. do. in both editions.
Other corrections required in 2nd edition only.

Spare copies of this slip can be obtained from the Deputy Conservator of Forests, Garhwal Division, Naini Tal.

تصحیح
جنتریوں کا

گول و چوکور لکڑی کے فٹ مکعب و مختلف در فی فٹ مکعب کے حساب سے
لکڑی کے دام نکالنے کی
جسکو
ایل مرسر صاحب ڈپٹی کنسرویٹر نے تیار کیا

جنتری مکعب فٹ گول لکڑی کی

ورق	لمبائی فٹ	بیچ کی گولائی انچوں میں	صحیح کیا ہوا
۱۵	۲۲	۷'—۹"	۸۹٫۶ کے بدلے ۸۲٫۶ پڑھو
۲۰	۳۳	۰'—۴"	۲۲۴٫۳ کے بدلے ۲۲۰٫۲ پڑھو

جنتری مکعب فٹ چری ہوئی لکڑی کی

ورق	لمبائی فٹ	چوڑائی و موٹائی انچوں میں	صحیح کیا ہوا
۳۴	۱۱	۵"×۱۵"	۵٫۵ کے بدلے ۵٫۷ پڑھو
۳۶	۱۴	۱۳"×۱۶"	۸٫۲۱ کے بدلے ۲۱٫۸ پڑھو

جنتری مکعب فٹ کے دام نکالنے کی

ورق	مکعب فٹ	شرح فی فٹ مکعب	صحیح کیا ہوا
۹	۸۰	۵	[illegible] کے بدلے [illegible] پڑھو

جنتری کے زاید پارچے ڈپٹی کنسرویٹر صاحب بہادر محکمہ جنگلات گڑھوال ڈویژن مقام نینی تال سے دستیاب ہوسکتی ہیں